

# BASIC ASSESSMENT REPORT DRAFT

THE PROPOSED UPGRADE OF
NATIONAL ROAD R574 (DISTRICT
ROAD D1547) SECTION 1 FROM R33 AT
GROBLERSDAL (KM 0.0) TO THE R579
AT MORWANENG (KM 38.9)

Prepared for the South African National Roads Agency Soc Limited

18 March 2022









## THE PROPOSED UPGRADE OF NATIONAL ROAD R574 (DISTRICT ROAD D1547) SECTION 1 FROM R33 AT GROBLERSDAL (KM 0.0) TO THE R579 AT MORWANENG (KM 38.9)

#### **APPLICANT**

The South African National Roads Agency Soc Limited Head Office P O Box 415 Pretoria 0001

Tel: +27(0)12 844-8000 Fax: +27(0)12 844-8200

Environmental coordinator: Mr Mogole Mphahlele

E-mail: mphahlelem@nra.co.za



#### **ENVIRONMENTAL ASSESSMENT PRACTITIONER**

Chameleon Environmental cc PO Box 11788 Silver Lakes 0054

Tel: +27(0)82 571 6920 Fax: +27(086)6855080 E-Mail:ce.j@mwebbiz.co.za



#### **Document Status**

Title	THE PROPOSED UPGRADE OF NATIONAL ROAD R574	
	(DISTRICT ROAD D1547) SECTION 1 FROM R33 AT	
	GROBLERSDAL (KM 0.0) TO THE R579 AT MORWANENG (KM	
	38.9)	
Author	Dr Jenine Bothma	
Status	Draft Report	
Date	18 March 2022	

Reason for Circulation
Document submitted for comments

Nature of Comments Required
Any inaccurate observations

#### **Table of Contents**

Li	st of Ta	ıbles	5
Α	CRONY	MS	6
1	. DE	TAILS OF EAP AND EXPERTISE	7
2	. LO	CATION OF THE ACTIVITY	8
3	. DE	SCRIPTION OF THE SCOPE OF THE PROPOSED ACTIVITY	8
	Phase	4: Open both carriageways to traffic	8
	3.1	Technical Details	9
	3.2	Facilities and Construction Activities	12
	a. C	Construction Materials	13
	b. F	Rock Quarries and Borrow Pits	14
	c. C	Crushing Plants	14
	3.3	Additional Project Infrastructure	14
	a.	Site Camps	14
	b.	Electricity and Diesel Supply	14
	c.	Concrete Batching and Mixing Plants	15
	d.	Excavators, Motor Graders and Road Rollers	15
	e.	Asphalt Mixing Plants	15
	f.	Forklift Truck and Wheel Loader	15
	g.	Water Supply and Sewage Treatment	15
4	. LIS	TED ACTIVITIES	16
5	. AP	PLICABLE LEGISLATION, POLICIES AND/OR GUIDELINES	18
6	. NE	ED AND DESIRABILITY OF PROJECT	21
7.	DET	AILS OF PUBLIC PARTICIPATION PROCESS FOLLOWED	28
	7.1	Summary of issues raised by I&APs	30
	7.2	The Environmental Attributes Associated With Alternatives	35
	7.2.	1 Baseline Environment	35
8.	Pos	sible Project Benefits	39
	8.1	Economic Benefits	39
	8.2	Social Benefits	40
	8.3	Transport Benefits	40
9.	Pos	sible Impacts and Risks Identified	40
	9.1	Methodology Used in Determining Impacts	41
	9.2	Positive and Negative Impacts and Assessment	44

10.	ALTERNATIVES CONSIDERED	57
10.2	1 Site Selection Matrix	57
10.2	2 Advantages and Disadvantages of Alternatives Considered	58
10.3	3 Sustainable Development	59
10.4	4 Socio-Economic Parameters	59
11.	SUMMARY OF SPECIALIST REPORTS	61
12.	ENVIRONMENTAL IMPACT STATEMENT	
10.1		
10.2		
ider	ntified alternatives	66
13. MAN <i>A</i>	PROPOSED IMPACT MANAGEMENT OBJECTIVES AND THE IMPACT AGEMENT OUTCOMES FOR INCLUSION IN THE EMPR	67
14.	ASPECTS FOR INCLUSION AS CONDITIONS OF AUTHORISATION	71
15. KNOV	DESCRIPTION OF ANY ASSUMPTION, UNCERTAINTIES AND GAPS IN VLEDGE	71
	REASONED OPINION AS TO WHETHER THE PROPOSED ACTIVITY SHOU	
17.	PERIOD FOR WHICH THE ENVIRONMENTAL AUTHORISATION IS REQUII	RED72
18.	UNDERTAKING	73
LIST O	F APPENDICES	74
**.		
	of Tables 1: Existing structures on project	10
	1: Existing structures on project	
	3: Intersections required	
Table	4: Construction Facilities	12
Table	5: List of Construction Activities	12
	6: Listed activities applicable to project	
	7: Legislation, policies and/or guidelines are applicable to the application	
	8: Summary of Issues raised by I&APs	
	9: Vegetation classification of the study site (Flori Scientific Services, 2021)	
	10: Potential Impacts and Risks Identified	
	11: Positive and Negative impacts and Assessment	
	13: Summary of Specialist Reports	

#### **ACRONYMS**

BID Background Information Document

CV Curriculum Vitae

DFFE Department of Forestry, Fisheries and the Environment

EAP Environmental Assessment Practitioner

EAPASA Environmental Assessment Practitioner Association of SA

EMPr Environmental Management Programme

I&APs Interested and Affected Parties

IBA Important Bird Area(s)
IRR Internal Rate of Return
PPP Public Participation Process

NEMA National Environmental Management Act

NEM:AQA National Environmental Management: Air Quality Act

NFEPA National Freshwater Ecosystem Priority Area

PLO Project Liaison Officer

SANRAL South African National Roads Agency Soc Limited

#### 1. DETAILS OF EAP AND EXPERTISE

This report was prepared by Dr Josephine Bothma from Chameleon Environmental.

• Tel No.: 012 809-1704 or 082 571 6920

• Fax No.: 086 6855 080

• E-mail address: ce.j@mwebbiz.co.za

#### a. The qualifications of the EAP

Dr Josephine Bothma has a PhD in Environmental Management. Please find a CV of the EAP and proof of qualifications included in Appendix A.

#### b. Summary of the EAP's past experience

The Environmental Assessment Practitioner (EAP) has the appropriate skills and experience to undertake the required studies for the proposed project. Dr Bothma has:

- Experience in environmental studies for linear project and borrow pits and quarries.
- The EAP is registered as an Environmental Assessment Practitioner with EAPASA with registration number 2019/246.
- Proven ability to timeously produce thorough, readable and informative documents.
- Adequate recording and reporting systems to ensure the preservation of all data gathered.
- A good working knowledge of all relevant and applicable policies, legislation, guidelines, norms and standards.
- The EAP does not have any links to engineering firms, construction companies, or financial institutions, and would be able sign the required declarations of independence to be submitted to the relevant environmental authorities.

Dr Bothma has a PhD in Environmental Management with extensive experience in the environmental field. Dr Bothma is a founder member of Chameleon Environmental since August 2006, a specialist environmental consulting company based in Pretoria, South Africa but operates nationwide. The company provides a broad range of environmental consulting services to the public and private sectors.

#### She has:

- » Thirty-two (32) years' experience in the environmental field
- » Twenty-two (22) years' experience in Project Management
- » Project management of large environmental assessment and environmental management projects.

#### 2. LOCATION OF THE ACTIVITY

The project is located on National Road R574 (District Road D1547) Section 1 from the R33 at Groblersdal (Km 0.0) at the intersection of R579/R33 to the intersection of the R574/R579 at Morwaneng (Km 38.9). This project consists of a total length of approximately 38.9 km and is situated in the province of Limpopo within the Elias Motsoaledi Local Municipality and the Sekhukhune District Municipality. A locality plan is included as Appendix B.

The coordinates for the project are the following:

•	Starting point of the activity
	(km 0.0)

- Middle point of the activity (km 19.5)
- End point of the activity (km 87.4)

Latitude (S): Longitude (E):			
25°	08'48.71"	29°	26'15.11"
25°	00'56.25"	29°	33'05.93"
25°	00'33.28"	29°	44'38.64"

Please see locality plan of the project attached as Appendix B.

#### 3. DESCRIPTION OF THE SCOPE OF THE PROPOSED ACTIVITY

It is the intention of the South African National Roads Agency Soc Ltd (SANRAL) to upgrade the National Road R574 (District Road D1547) Section 1 from the R33 at Groblersdal (Km 0.0) to the R579 at Morwaneng (Km 38.9)) in the Limpopo Province. The scope of works will include the following:

- Widening of the existing road cross section to a new single and dual carriageway cross-section,
- Vertical and horizontal geometric improvements,
- Vertical and horizontal realignments,
- Improvements of minor and major intersections.
- Widening of river bridges and major and minor culverts,
- Clearing of vegetation outside road reserve for stockpile areas.

The traffic accommodation will be implemented in phases as follows:

Phase 1: Widen the outer edge on the Southbound portion of the carriageway with final earthworks and temporary layer works while accommodating traffic on the existing carriageway.

Phase 2: Divert and accommodate traffic on the Southbound portion of the carriageway. Rehabilitate the existing carriageway and construct the new widenings on the Northbound portion of the carriageway.

Phase 3: Divert and accommodate traffic on the completed Northbound carriageway. Rehabilitate the existing carriageway and construct the new widenings on the southbound portion of the carriageway.

Phase 4: Open both carriageways to traffic.

#### 3.1 Technical Details

The R574 is currently a single carriageway which consists of one lane in each direction from km0.0 to km38.8. The road generally consists of two 3.7m lanes and 2 x 2.5m gravel shoulders. There is also some sections which have a paved shoulder varying from 0.3m to 0.5m. There is an existing climbing lane northbound between km6.9 to km10.1. The width of the lane is  $\pm 3.7m$ . The road has a camber and is generally 2 %.

The road generally consists of three typical cross-sections:

#### Cross-section 1 (km 0 to km 6.9)

- 2 x 3,7m lanes,
- 2 x 2.5m gravel shoulders, (varying from 2m to 2,5m),
- Camber 2%.

#### Cross-section 2 (km 6.9 to km 10.1)

- 2 x 3,5m lanes (climbing),
- 1 x 3,5m lane
- 1 x 0.5m paved edge, (varying from 0.3m to 0.5m)
- Rock wall protection works 0.7m high
- · Camber 2%,
- Earth lined box drain in cut condition ±2m.

#### Cross-section 3 (km 10.1 to km 38.8)

- 2 x 3,7m lanes,
- 2 x 2m gravel shoulder, (varying from 1.5m to 2m),
- 2 x 0.5m paved edge, (varying from 0.3m to 0.5m)
- Camber 2%.

There are a number of gravel and paved intersections along the route. There are 17 major intersections which consists of 2 x 3,5m lanes, and mountable/semi mountable kerb and channel combinations. Painted refuge islands are located at km6.2, km10.2 and km15.6. Limited Taxi lay-byes and pedestrian crossings have been observed at intersections. All intersections are stop controlled. A new gravel intersection has been constructed by Roads Agency Limpopo at km24.0 (D4311-D4310).

It is proposed to upgrade the road to the following:

- km 0.0 km 1.0: Dual carriageway with 2 x 3.5m lane per direction, a 2.8m median and shoulders, and walkways where required.
  - km 1.0 km 6.9: Dual carriageway with 2 x 3.5m lanes per direction, a 2.8m median and a 2.5 m walkway where required and an unsurfaced shoulder on the opposite side.
- km 6.9 km 10.1: Dual carriageway with 2 x 3.5m lanes per direction, a 2.8m median and a 2.5 m walkway where required.

- km 10.1 km 18.2: Dual carriageway with 2 x 3.5m lanes per direction, a 2.0m median and a 2.5 m walkway on either side where required.
- km 18.2 km 21.9: Dual carriageway with 2 x 3.5m lanes (lane + climbing lane) and a 2.5m walkway on either side where required, a 2.0 median and a 3.7 m lane and a 1.5 m surfaced shoulder on the opposite carriageway.
- km 21.9 km 33.4: Dual carriageway with 1 x 3.7m lane per direction, 1.5m surfaced outer shoulders either side, a 2.0m median and 2.5m walkway either side.
- km 33.4 km 34.2: Dual carriageway on one side with 2 x 3.5m lane in one direction and a 2.5 m walkway, a 2.0 m median, a 1 x 3.7m lane and 1.5 m shoulder on the opposite carriageway.
- km 34.2 km 34.4: Dual carriageway with 2 x 3.5m lanes per direction, a 2.0m median and 2.5m walkway on either side.
- km 34.4 km 37.85: Dual carriageway with 2 x 3.5m lanes (lane + climbing lane) and a 2.5m walkway where required, a 2.0 median and a 3.7 m lane with a 1.5 m surfaced shoulder on the opposite carriageway.
- km 37.85 km 38.80: Dual carriageway with 1 x 3.7m lane per direction, a 2.0m median and 1.5 outer shoulders and 2.5 m walkways on both sides.

No new bridge or culvert structures will be required on the project. The project road currently has two bridges and four major culverts and several smaller culverts. Based on the upgrading proposals, two bridges, eight major culverts, eighteen lesser culverts, and forty-eight nominal culverts were to be engineered. The following existing structures will either be demolished and replaced or upgraded on the project:

Table 1: Existing major bridge and culvert structures on project

Existing Bridge / Major Culvert Nr	Bridge / Culvert Name	Action Required at Existing Structure	Section and km Distance	Area outside road reserve m <sup>2</sup>
B3187	Bloed River Bridge	Retained and Widened	0.99	39.9
C9561	Rulokwane River Culvert	Retained and Widened	6.075	55.73
C9061	Rulokwane River Culvert	Retained and Widened	12.42	232.11
C9062	Rulokwane River culvert	Retained, widened and rehabilitated	12.45	513.3
C9563	Puleng River Culvert	Retained and widened	17.2	55.00
C9063	Ramogwerane River culvert	Retained and the end structures raised	20.20	404.47

Existing Bridge / Major Culvert Nr	Bridge / Culvert Name	Action Required at Existing Structure	Section and km Distance	Area outside road reserve m <sup>2</sup>
B261	Gamakatle River bridge	Retained, widened, provided with new end structures and rehabilitated	26.26	3.5
B262	Gemsbokspruit Tributary culvert	Replaced by a new Major Culvert	31.78	50
C9064	Gemsbokspruit River culvert	Retained, widened, the end structures raised and rehabilitated	34.2	2267.01

The following table provides a list of the intersections that will be required on the project:

**Table 2: Intersections required** 

Intersection	Туре	KM
Nr.		
1	Leeuwfontein	2.60
2	Motetema	6.20
3	Unknow	6.5
4	Tafelkop	10.2
5	Entrance	13.0
6	Access	15.6
7	Access	19.7
8	Access	21.00
9	Access	23.6
10	High School	23.8
11	Legolaneng	24.00
12	Caltex	24.4
13	Access	25.6
14	Access	27.3
15	Access	28.08
16	Ga-Phadi	31.00
17	Access	36.9

The water uses (crossing streams/rivers or within 500m of a wetland) will be applied for at the Department of Water and Sanitation in accordance with the National Water Act, (Act No. 36 of 1998).

#### 3.2 Facilities and Construction Activities

A list of possible facilities and construction activities associated with the project are summarised in Tables 3 and 4.

**Table 3: Construction Facilities** 

REFERENCE	FACILITIES
Construction site camp	Access Roads
	Offices and site laboratory
	Storage Tanks
	Topsoil stockpiles
	Work shops
	Wash bays
	Laydown areas
	Store rooms
	Fuel storage facilities
	Cement silos
	Batching plants
	Temporary spoil stockpile
	Toilets and sanitation
	Oil traps
	Oil recycling facilities
	Storage of hazardous materials (oil, paint etc)
	Storage of gas
	Refuelling area
	Site security post
Pre-cast yard	Batching plant
	Cement Silos
	Settlement ponds
	Concrete washing facilities
	Curing areas
	Workshops

**Table 4: List of Construction Activities** 

No	CONSTRUCTION ACTIVITIES
1	Earthworks: Excavation
2	Earthworks: Blasting
3	Cleaning and grubbing and bulldozing activities
4	Concrete work
5	Construction and use of temporary access roads
6	Construction employment (appoint labourers)
7	Control of weeds and invasive species
8	Spoil material generation and management
9	Domestic solid waste collection and disposal
10	Locate spoil disposal sites

No	CONSTRUCTION ACTIVITIES
11	Explosive magazines (to be determined)
12	Handling and disposal of contaminated water
13	Handling, storage and disposal of hazardous material
14	Horticultural activities
15	Parking bay for trucks
16	Lighting activities
17	Managing construction site (labourers)
18	Managing spoil dump sites
19	Managing topsoil stockpiles
20	Mixing of concrete
21	Ongoing consultation with affected parties
22	Overhead work and signalling
23	Painting
24	Provision and operation of water washing and toilet facilities
25	Refuelling of construction vehicles and machinery
26	Slope stabilisation and erosion control
27	Construction solid waste collection and disposal
28	Storage and disposal of empty containers
29	Topsoil stripping
30	Transportation of hazardous substances
31	Transportation of spoil material
32	Use of electricity generators
33	Welding

#### a. Construction Materials

The following construction materials could be required by the Project:

- Gravel material
- Cement
- Structural Steel
- Reinforcement Steel
- Sand
- Bituminous material/asphalt
- Paints and chemicals, mineral products
- Fixtures and fittings

The construction material such as cement, structural steel, reinforcement steel, rock bolts and paints will be procured directly from sources. The fine and coarse aggregate required for the preparation of concrete is planned to be made available from suitable quarry sites located and/or spoil from excavations.

#### b. Rock Quarries and Borrow Pits

A survey to identify suitable quarry and borrow pit locations was undertaken. The aim of the survey was to identify sites which could potentially provide the quantity and quality of aggregates required at a location as close to the major project components as possible, in order to reduce transportation costs and minimise environmental impacts. A separate environmental study was undertaken for the quarry and borrow pit sites and submitted to the Department of Mineral Resources and Energy for approval.

#### c. Crushing Plants

A crushing plant is planned at the identified quarry sites, with a spoils area at the quarry.

#### 3.3 Additional Project Infrastructure

#### a. Site Camps

The final location of the construction camp sites, including offices during the construction phase, will be determined by the Contractor that is appointed for the construction of the road by the applicant (South African National Roads Agency Soc Limited), following the tender process. The appointed contractor usually identifies land that is already disturbed or makes use of an old farm house. However, it is acknowledged that should any listed activity be triggered in terms of the EIA Regulations, 2014, as amended, in the setting up of the construction camp site, the contractor would have to undertake the necessary environmental studies before the camp site can be erected.

The following could potentially be construction camp sites, including offices during the construction phase:

- Disturbed, open land.
- On farmland.

Both options will have to be discussed with the various landowners by the appointed Contractor for the project.

It is envisioned that the staff would stay in Groblersdal.

The options to have the camp sites dismantled after construction work is completed or to sign it over to the respective landowner, will also be negotiated with the Contractor and the respective landowner.

#### b. Electricity and Diesel Supply

The power demand is expected to be 1000 kW per day, and will be supplied from two 800 kW diesel generators on site. Buried electrical cables will distribute power around the site.

Diesel fuel for generators and construction equipment will be stored in a secure area in suitable above ground steel tanks at the identified camp sites, supplied and maintained by the fuel suppliers. An adequate bund wall (110% volume) will be provided for fuel and diesel areas to accommodate any spillage or overflow of these substances. Approximately 300,000 tonnes of diesel is expected to be supplied over the three years of operation.

#### c. Concrete Batching and Mixing Plants

At this stage the location and number of concrete batching and mixing plants and stores and workshops for the project is unknown. It is envisaged that there will be construction facilities at various sections along the alignment and that each of these sections will include a concrete batching and mixing plant, main stores and a workshop.

#### d. Excavators, Motor Graders and Road Rollers

Various excavators and motor graders will also be used for the construction of the road. The graders are used to create an even flat surface to lay the asphalt on. The road roller is basically a compactor which makes use of soil, gravel, and asphalt during the construction of roads. Road rollers are also used for compacting the land before the asphalt can be laid after the graders have done their work. The rollers are used to press the asphalt in place and bind the various layers of the road together.

#### e. Asphalt Mixing Plants

Asphalt mixing plants are machines that are used to manufacture road stone like asphalt, cement and rock stones to make the top layer of the roads. The operation of a temporary asphalt plant is exempted from applying for an Atmospheric Emission License as per NEM:AQA, 2004 Section 23 Notice 201. The definition of a temporary asphalt plant is the following: "An asphalt plant that is used for the sole purposes of supplying asphalt for a specific road paving contract not exceeding a period of 24 months". New and existing temporary asphalt plants must comply with the standards and limits as noted in Notice 201.

#### f. Forklift Truck and Wheel Loader

Forklift truck is a powered industrial vehicle that can be used to pick an object on or below the ground level and raised to move the object. Wheel loaders are also known as front-end loaders. It is a machine that is used to move a pile of material from the ground and load it onto a dump truck. It consists of front mounted square wide bucket joined to the end of two arms used to scoop up materials from the ground without spreading it out.

#### g. Water Supply and Sewage Treatment

The appointed Contractor will be responsible to source water for the project. It is presumed that potable water will initially be supplied by road from Municipal water. Water could also be sourced from existing boreholes, fountains and farm dams in close proximity to the project

site. The necessary permits will be obtained by the appointed Contractor for any new abstractions.

Water for use in construction processes (eg concrete production) and dust control will be sourced from existing boreholes and farm dams.

Firefighting water will be held in tanks to provide a sustained flow rate of 250 000 litres per hour, for up to four hours.

During the construction stage, sewage will be treated using portable chemical treatment units on the construction site and at the site camps. The potable toilets will be serviced regularly by a reputable service provider (at least once a week).

#### 4. LISTED ACTIVITIES

The following listed activities are applicable to this project:

Table 5: Listed activities applicable to project

Listed activity	Reason	Reason					
triggered							
GN R. 983, Item	The follow	The following structures extend beyond the current road reserve:					
12 (as amended):							
The development of ii). infrastructure of structures with a physical footprint of	Km Distance	Structure Nr.	Latitude	Longitude	Area beyond existing road reserve (m²)		
100 square metres	0.99	B3187	25°08'18.49"S	29°26'15.95"E	39.9		
or more;	6.075	C9561	25°3'29.81"S	29°30'20.35"E	55.73		
or more,	12.42	C9061	25°08'30.27"S	29°30'19.11"E	232.1		
	12.45	C9062	25°08'30.27"S	29°30'19.11"E	513.3		
	17.2	C9563	25°0'44.63"S	29°33'38.96"E	55.0		
	20.20	C9063	25°00'44.43"S	29°33'27.95"E	404.47		
	26.26	B261	25°00'41.43"S	29°37'14.01"E	3.50		
	31.86	B262	25°00'31.86"S	29°40'30.96"E	50.0		
	34.20	C9064	25°00'19.04"S	29°41'58.72"E	2267.0		
ON P. 000 Hors	Th	S-1 (b-1 (120)	ha na mila di fan	in Cilliana and an a	-20 20 b -		
GN R. 983, Item	The material that will be required for infilling or depositing will be more than 10 m <sup>2</sup> for the project.						
19 (as amended):	more man	io iii iort	ne project.				
The infilling or depositing of any material of more than 10 cubic							

metres into, or removal or moving				
of soil from a				
watercourse.				
GN R. 983, as				
amended in GN R. 327: Item 24 (as amended)	The road reserve widened by 21.8m.	varies between 40m	to 84m and the	road will be
,				
The development				
of a road				
(ii) with a reserve				
wider that 13.5 m				
or where no reserve exists				
where the road is				
wider than 8 m				
GN R. 983, as amended in GN R.	The following struc	tures will be demoli	shed and replac	ed:
327: Item 31 (as amended)	Structure Nr	Name	Action	km
	NC1	Unknown	Structure to	60.535
The			be	
decommissioning			demolished	
of existing facilities,	B2490	Tributary to	and replaced Structure to	61.520
structures or	BZ+30	Sandspruit 1	be	01.020
infrastructure for		Bridge	demolished	
(i) Any development			and replaced	
and related	B2489	Sandspruit	Structure to	61.820
operation		Tributary Bridge	be demolished	
activity or		Diluge	and replaced	
activities listed				
in this Notice	B1421	River Bridge	Structure	62.970
			upgraded	
	D2400	Cond Divor	Structure to	64 300
	B2488	Sand River Bridge	be demolished	64.390
		Dilage	and replaced	
		Tributary	Structure to be	
	C03	Sandspruit 3	extended to	66.503
		Culvert	accommodate	
			new road cross	
	B2479	Vaal River Bridge	section Structure to	78.840
	DZ413	vaai Nivei Diluge	be	10.040
			demolished	
			and replaced	

GN R. 983, as amended in GN R.	B2 <sup>2</sup> The followi		Witpunt River Bridge es will be expar	Structure to be demolished and replaced	87.240 nan 100sq m:
327: Item 48 (as amended)  The expansion of	Km Distance	Structure Nr.	Latitude	Longitude	Area beyond existing road reserve (m²)
infrastructure or	58.41	C04	26°43'57.35"S	30°18'0.71"E	TBC*
structures where	60.50	NC01	26°43'53.26"S	30°16'53.23"E	
the physical footprint is	61.57	B2490	26°43'52.66"S	30°16'13.32"E	350.897
expanded by 100	61.73	B2489	26°43'52.52"S	30°16'2.74"E	523.344
sq m or more	62.96	B1421	26°43'51.89"S	30°15'20.79"E	875.427
(a) Inside a	64.36	B2488	26°44'0.90"S	30°14'31.29"E	538.458
watercourse	66.49	C03	26°43'52.93"S	30°13'15.59"E	111.382
Wateroodroo	78.82	B2479	26°38'53.71"S	30° 9'4.32"E	1033.593
	83.94	CC01	26°36'40.37"S	30° 7'22.72"E	42.460
GN R. 983, Item 56 (as amended):	The road r		es between 40n	n to 84m and th	ne road will be
The widening of a road by more than 6 m where the existing reserve is wider than 13.5 m					

#### 5. APPLICABLE LEGISLATION, POLICIES AND/OR GUIDELINES

The following legislation, policies and/or guidelines are applicable to the application:

Table 6: Legislation, policies and/or guidelines are applicable to the application

Title of legislation, policy	Applicability to the	Administering	Date
or guideline	project	authority	
EIA Regulations 2014 as	Listed activities triggered	Department of	4
amended	in terms of the EIA	Environment al	December
GN R. 983 as amended	Regulations, 2014 as	Affairs	2014
in GN R. 327	amended		
Activities 12, 19, 24 and			
56			
Department of	Guidance with regard to	Department of	2010
Environmental Affairs	the execution of the	Environmental	
Departmental Guidelines	Environmental Impact	Affairs	

Title of legislation, policy or guideline	Applicability to the project	Administering authority	Date
under	Assessment process	additionity	
www.environment.gov.za	Assessment process		
National Environmental	General objectives of	The National	1998
Management Act, 1998	Integrated Environmental	Department of	1990
(Act No. 107 of 1998)	Management as set out in	Environmental	
The National	section 23 of NEMA taken	Affairs	
Environmental	into account	Allalis	
	into account		
Management Act, 1998			
(Act No. 107 of 1998):			
[NEMA] was enacted in November 1998. NEMA			
provides for cooperative			
governance by			
establishing principles for			
decision-making on matters affected the			
environment, institutions			
•			
that will promote co-			
operative governance and procedures for			
coordinating			
environmental functions,			
public participation and			
sustainable development.			
National Environmental	Ecological study	Department of	2004
Management:	Red data and protected	Agriculture,	2004
Biodiversity Act (Act No.	species listed in the Act	Forestry and	
10 of 2004)	will need to be assessed	Fisheries (permit	
10 01 2004)	will fleed to be assessed	application, if	
Red data and protected		necessary)	
species listed.		i iicocosaiy <i>j</i>	
The National Water Act	Aquatic Study	Department of	2016
(Act No. 36 of 1998) for	Stream crossings and	Water and	2010
water uses as defined in	application of a general	Sanitation	
section 21 (c) and	authorization or WUL at	Januarion	
section 21 (i).	the Department of Water		
(1).	and Sanitation		
The application for a	and Jamadon		
General Authorisation or			
Water Use License (WUL)			
in terms of the National			
Water Act, 1998.			
1.2017.00, 1000.			

Title of legislation, policy	Applicability to the	Administering	Date
or guideline	project	authority	
National Heritage	Construction of road, or	South African	1999
Resource Act 1999 (Act	other linear form of	Heritage	
No. 25 of 1999) and	development or barrier	Resources	
KwaZulu-Natal Heritage	exceeding 300m in length	Agency (SAHRA)	
Act (Act 4 of 2008)	Construction of bridge or		
Standards and	similar structure exceeding		
Regulations	50m in length		
South African Heritage	Development exceeding		
Resources Agency	5000 sq m required		
(SAHRA) Minimum	approval from SAHRA.		
Standards;			
Association of Southern	Heritage and		
African	Palaeontological study		
Professional			
Archaeologists (ASAPA)			
Constitution and Code of			
Ethics;			
Anthropological			
Association of			
Southern Africa			
Constitution and Code of			
Ethics.			
International Best			
Practise and Guidelines			
ICOMOS Standards			
(Guidance			
on Heritage Impact			
Assessments for			
Cultural World Heritage			
Properties); and			
The UNESCO			
Convention			
In terms of the National			
Heritage Resources Act,			
1999 (Act No. 25 of 1999)			
comment will be obtained			
from SAHRA. Permits will			
be obtained if necessary.			
Concerning the Protection			
of the World Cultural and			
Natural Heritage (1972).			

Title of legislation, policy	Applicability to the	Administering	Date
or guideline	project	authority	
Regulation 15 of the	Ecological study	Department of	1983
Conservation Act of	Alien vegetation	Agriculture	
Agricultural Resources	identification on site		
Act, 1983 (Act 43 of			
1983)			
The Conservation of	Land capability and	Department of	1983
Agricultural Resources	Agricultural Potential Study	Agriculture	
Act, 1983 (Act No. 43 of			
1983).			
Disaster Management	Directions issued for PPP	DAFF	2020
Act, 2002 (Act 57 of			
2002)			

#### 6. NEED AND DESIRABILITY OF PROJECT

The following provide a motivation for the need and desirability of the activity:

1. Is the activity permitted in terms of the property's YES X NO	
existing land use rights?	explain

The project is undertaken in terms of the South African National Roads Agency Soc Limited (SANRAL's) mandate in terms of the South African National Roads Agency Limited and National Roads Act, 1998. The declaration of the R574 as a national road under section 40(1) of the Act creates the land use right within the declared road reserve.

#### 2. Will the activity be in line with the following?

(a) Provincial Spatial Dovolonment Framework (PSDE)	VEQV	NO	Please
(a) Provincial Spatial Development Framework (PSDF)	1123 x	INO	explain

The SANRAL is given the power to perform all strategic planning, as well as the planning, design, construction, operation, management, control, maintenance and rehabilitation of all national roads in South Africa in terms of the South African National Roads Agency Limited and National Roads Act, 1998. The R574 is a national road and falls within the jurisdiction of the SANRAL and the development is not bound by the Municipality's PSDF in order to continue.

(h) Urban adas / Edge of Built anvironment for the area	VECV	NO	Please		
(b) Urban edge / Edge of Built environment for the area	I EO X	NO	explain		
The SANRAL is given the power to perform all strategic planning, as well as the planning,					
design, construction, operation, management, control, maintena	nce and	l rehab	ilitation of all		
national roads in South Africa in terms of the South African Nation	nal Roa	ads Ag	ency Limited		
and National Roads Act, 1998. The R574 is a national road and		•	•		
of the SANRAL and the development is not bound by the Munici			•		
order to continue as it is not a residential development or munici			•		
(c) Integrated Development Plan (IDP) and Spatial			•		
Development Framework (SDF) of the Local			6.		
Municipality (e.g. would the approval of this	YES x	NO	Please		
application compromise the integrity of the existing			explain		
approved and credible municipal IDP and SDF?).					
The SANRAL is given the power to perform all strategic planning	ı, as we	ll as th	e planning,		
design, construction, operation, management, control, maintenant					
national roads in South Africa in terms of the South African Nation					
and National Roads Act, 1998. The R574 is a national road and		•	•		
of the SANRAL and the development is not bound by the Munici			•		
continue as it is not a residential development or municipal roads					
			Please		
(d) Approved Structure Plan of the Municipality	YES x	NO	explain		
The SANRAL is given the power to perform all strategic planning	, as we	ll as th	e planning,		
design, construction, operation, management, control, maintenant					
national roads in South Africa in terms of the South African Nation					
and National Roads Act, 1998. The R574 is a national road and		_			
of the SANRAL and the development is not bound by the Munici			•		
plan in order to continue as it is not a residential development or					
development.	•				
(e) An Environmental Management Framework (EMF)					
adopted by the Department (e.g. Would the					
approval of this application compromise the	\/=0		Please		
integrity of the existing environmental management	YES	NO x	explain		
priorities for the area and if so, can it be justified in			•		
terms of sustainability considerations?)					
The approval of this application will not compromise the integrity	of the	existing	<b>j</b>		
environmental management priorities for the area and it can it be		_			
sustainability considerations. No significant long term impact is foreseen as a result of the					
project.					
	VEO	NO -	Please		
(f) Any other Plans (e.g. Guide Plan)	YES	NO x	explain		
	<u> </u>		•		

No significant long term impact is foreseen as a result of the project.

3. Is the land use (associated with the activity being applied for) considered within the timeframe intended by the existing approved SDF agreed to by the relevant environmental authority (i.e. is the proposed development in line with the projects and programmes identified as priorities within the credible IDP)?	YES x	NO	Please explain
The SANRAL is given the power to perform all strategic planning	as we	ll as th	e planning
design, construction, operation, management, control, maintenant			. •
national roads in South Africa in terms of the South African Nation			
		_	-
and National Roads Act, 1998. The R574 is a national road and			-
of the SANRAL. The development is not bound by the Municipal			
order to continue as it is not a residential development or munici	pal roac	ls deve	elopment.
4. Does the community/area need the activity and the associated land use concerned (is it a societal priority)? (This refers to the strategic as well as local level (e.g. development is a national priority, but within a specific local context it could be inappropriate.)			Please explain
The area is in dire need of this project and it is a societal priority	as num	erous	accidents
occur on the R574 in this area every year with associated loss of	f lives.		
5. Are the necessary services with adequate capacity currently available (at the time of application), or must additional capacity be created to cater for the development?	YES x	NO	Please explain
The contractor, once appointed through the tender process with	SANRA	L, will	decide on
the water, sewage and waste disposal services during the time of	of constr	uction	The
relevant contractor will negotiate with the relevant local Municipa	lity for p	orovisio	on of these
services.	, ,		
6. Is this development provided for in the infrastructure			
planning of the municipality, and if not what will the			
	YES x	NO	Please
	ILSX	INO	explain
municipality (priority and placement of services and			
opportunity costs)?			
The SANRAL is given the power to perform all strategic planning			
design, construction, operation, management, control, maintenant			
national roads in South Africa in terms of the South African Nation		•	•
and National Roads Act, 1998. The R574 is a national road and	falls wit	hin the	jurisdiction
of the SANRAL. The development is not bound by the Municipa	lity's inf	rastruc	ture
planning in order to continue.			
7. Is this project part of a national programme to address	VEC	NO	Please
an issue of national concern or importance?	YES x	NO	explain
The upgrade of the R574/34 is part of the wider R574 corridor up	grades	betwe	•
border and Camden which in turn forms part of the strategic rout	•		
Gauteng and Richards Bay and Durban harbours.	. 0		

8. Do location factors favour this land use (associated				
with the activity applied for) at this place? (This relates	YES x	NO	Please	
to the contextualisation of the proposed land use on	I E S X	NO	explain	
this site within its broader context.)				
The R574 is an existing national road and will be widened in tern	ns of SA	NRAL	's mandate	
in terms of the South African National Roads Agency Limited and	d Nation	al Roa	ads Act,	
1998.				
9. Is the development the best practicable environmental	YES x	NO	Please	
option for this land/site?	ILSX	INO	explain	
The upgrade of the R574 will be conducted within the R574 road	reserve	. The	potential	
impacts related to the activity were assessed together with speci	alist eng	jineeri	ng and	
environmental input and the best practicable environmental optic	n and m	nitigati	on	
measures recommended in the report.				
10. Will the benefits of the proposed land use/development	YES x	NO	Please	
outweigh the negative impacts of it?	ILOX	INO	explain	
The benefits of the proposed development will outweigh the negative	ative imp	acts a	as the local	
communities and road users are in dire need of this project as a	result of	the s	evere safety	
risk if the R574 is not upgraded with associated loss of lives. The	R574 v	vill, the	erefore, be	
upgraded with a low impact to the environment but a high positiv	e impac	t to the	e community	
and traveling public.				
11. Will the proposed land use/development set a			Please	
precedent for similar activities in the area (local	YES	NO x	explain	
municipality)?			•	
The SANRAL is given the power to perform all strategic planning	, as wel	l as th	e planning,	
design, construction, operation, management, control, maintenar				
national roads in South Africa in terms of the South African Natio		-	•	
and National Roads Act, 1998. The R574 is a national road and			•	
of the SANRAL. This development will therefore not set a precede				
it is not bound by the Municipality's infrastructure planning in ord	er to cor	ntinue.		
12. Will any person's rights be negatively affected by the	YES	NO x	Please	
proposed activity/ies?			explain	
It is not foreseen that any person's rights will be negatively affect	•			
activity as no community displacement will take place. A public participation process was				
followed and the comments and concerns taken into account dur	ing the	enviro	nmental	
process.		T		
13. Will the proposed activity/ies compromise the "urban	YES	NO x	Please	
edge" as defined by the local municipality?			explain	
The SANRAL is given the power to perform all strategic planning, as well as the planning,				
design, construction, operation, management, control, maintenance and rehabilitation of all				
national roads in South Africa in terms of the South African National Roads Agency Limited				
and National Roads Act, 1998. The R574 is a national road and falls within the jurisdiction				
of the SANRAL and the development is not bound by the Municipality's urban edge in				
order to continue as it is not a residential development or municipal road development.				
14. Will the proposed activity/ies contribute to any of the	YES	NO x	Please	
17 Strategic Integrated Projects (SIPS)?			explain	
This project is not included in any of the SIP projects.				

## 15. What will the benefits be to society in general and to the local communities?

Please explain

The upgrade of the R574 offer several benefits to society in general, including:

- Decrease accidents due to decreasing possibility of head-on collisions;
- Safer driving conditions for the road users as the road will provide opportunities to pass heavy vehicles.
- With the upgrade of the road, less maintenance on vehicles are anticipated;
- Improved traffic flow, particularly during peak periods;
- Reduced congestion;
- Improved drainage and other services.

The following community involvement goals will form part of the construction works:

- Minimum of 30% of the Final Contract Value by the end of the contract to Targeted Enterprises in the form of subcontracting works;
- Minimum of 8% of the Final Contract Value by the end of the contract to Targeted Labour; and
- An amount still to be determined will also be allocated for a Community Development (CD) type project within the main contract. The CD component to be executed by CIDB 1 to 4 Targeted Enterprise contractors, utilising labour enhanced construction methods.

## 16. Any other need and desirability considerations related to the proposed activity?

Please explain

- Employment opportunities for the local residents during construction.
- Less accidents and associated loss of lives.
- Improved drainage and other services.
- Drainage channels will be improved.

## 17. How does the project fit into the National Development Plan for 2030?

Please explain

The SANRAL is given the power to perform all strategic planning, as well as the planning, design, construction, operation, management, control, maintenance and rehabilitation of all national roads in South Africa. The R574 is a national road and falls within the jurisdiction of the SANRAL in terms of the South African National Roads Agency Limited and National Roads Act, 1998.

## 18. Description of how the general objectives of Integrated Environmental Management as set out in section 23 of NEMA have been taken into account.

The following general objectives of integrated environmental management have been taken into account:

- a) Identified, predicted and evaluated the actual and potential impact on the environment as a result of the upgrade of the R574 as well as the socio-economic conditions and cultural heritage,
- b) Investigated alternatives and options for mitigation of activities, with a view to minimizing negative impacts.
- c) Maximizing benefits to the environment as a result of the upgrade of the R574;
- d) Ensured that the effects of activities on the environment received adequate consideration before actions are taken in connection with them;
- e) Ensured adequate and appropriate opportunity for public participation in decisions that may affect the environment;
- f) Ensured the consideration of environmental attributes in management and decision-making which may have a significant effect on the environment; and
- g) Identified and employed the modes of environmental management best suited to ensuring that a particular activity is pursued in accordance with the principles of environmental management set out in section 2 of the NEMA.

## 19. Description of how the principles of environmental management as set out in section 2 of NEMA have been taken into account.

The following have been taken into account:

- Identified all potential activities and associated environmental risks associated with the proposed project;
- Consideration of all relevant ecological, social and economic factors in development;
- Minimised adverse environmental impacts, pollution or degradation of the environment;
- Avoiding or minimising the disturbance to ecosystems;
- That pollution and degradation of the environment are avoided, or, where they cannot be altogether avoided, are minimised and remedied;
- That the disturbance of landscapes and sites that constitute the nation's cultural heritage is avoided, or where it cannot be altogether avoided, is minimised and remedied:
- That waste is avoided, or where it cannot be altogether avoided, minimised and reused or recycled where possible and otherwise disposed of in a responsible manner;
- That the use and exploitation of non-renewable natural resources is responsible and equitable, and takes into account the consequences of the depletion of the resource;
- That the development, use and exploitation of renewable resources and the
  ecosystems of which they are part do not exceed the level beyond which their
  integrity is jeopardised;
- That a risk-averse and cautious approach is applied, which takes into account the limits of current knowledge about the consequences of decisions and actions;
- That negative impacts on the environment and on people's environmental rights be anticipated and prevented, and where they cannot be altogether prevented, are minimised and remedied.
- Promotion of community participation through an extensive and open public participation process with I&APs;
- Delivery of high quality information to government and other decision-makers in order to enable them to make informed decisions regarding the project and avoid unnecessary project delays.

#### 7. DETAILS OF PUBLIC PARTICIPATION PROCESS FOLLOWED

A public participation process was undertaken in accordance with the EIA Regulations, 2014, as amended and the Directions regarding measures to address, prevent and combat the spread of COVID-19 relating to National Environmental Management Permits and Licenses dated 05 June 2020.

The public participation and communication process aims to identify issues in order to maximise the social and environmental benefits, and to minimise the social and environmental costs of the proposed project.

Interested and affected parties (I&APs) were consulted and afforded the opportunity to participate. The I&APs were informed and involved in the project from the outset in order to promote participation and transparency.

The aim of this public participation process is to achieve the following broad goals:

- Identification of all key I&APs and stakeholders;
- The active involvement of all I&APs with respect to decision making;
- An exchange of information relevant to the proposed project through Background Information Documents (BID), consultations and newspaper advertisements.
- The development of an understanding with regards to the broader project objectives and goals and knowledge of the project; and
- The identification of issues and concerns with regards to all potential alternatives associated with the proposed development.

The following approach was followed in undertaking the public participation process:

#### a. Identification of and Consultation with I&APs

The first step in the public participation process was to identify the key I&APs. A list of the registered I&APs is attached as Appendix D.

#### b. Advertising

In accordance with the EIA Regulations, 2014, as amended an advertisement was placed requesting I&APs to register their interest in the project. An advertisement was placed in the Sekhukhune Times of 17 June 2021. A copy of the advertisement is included in Appendix D.

#### c. Site Notice

Site notifications in English in A2 format requesting comments or objections were placed on site and at the Groblersdal public Library on 11 June 2021. Photographs of the site notices are included in Appendix G.

#### d. Notification Letter and Background Information Document

Notification letters about the project and a Background Information Document were sent out to the particular Ward Councillors, Government Departments that would be relevant to this project and the affected landowners are included in Appendix D.

#### e. Comments and Response Report

A comments and response report was drafted that included all the issues raised by the Interested and/or Affected Parties as well as the responses to the issues raised. The Comments and Response report is included in Appendix D.

#### f. Local Authority Involvement

Letters were forwarded to the Elias Motsoaledi Local Municipality and the Sekhukhune District Municipality. The letters are included in Appendix D.

#### g. Review of Draft Basic Assessment Report

The Draft Basic Assessment Report will be made available to the public for review and comment, within an allocated 30-day period.

#### 7.1 Summary of issues raised by I&APs

 Table 7: Summary of Issues raised by I&APs

Interested and Affected Parties	Date Comments Received	Issues raised	EAPs response to issues as mandated by the applicant	Section and Paragraph Reference in This report Where the Issues and or Responses were incorporated.
AFFECTED PARTIES				
Landowner/s				
The South African National Roads Agency Soc Limited	No comments received	No issues raised	No response necessary	None required
Lawful Occupier/s of the Land				
There are no lawful occupiers of the R574 road reserve	No comments received	No issues raised	No response necessary	None required
Landowners or Lawful Occupiers on				
Adjacent Properties				
Mr Sam Moloko Bakone Batubatse Tribal Authority	23 August 2021	Any projects and developments that is taking place to our constituency is as the legal entity, we are obliged to provide our inputs for the good running of that process.	Thank you for the comments submitted on 23 August 2021.  Chameleon Environmental was appointed to undertake the environmental studies for the project only. A Basic Assessment	None required.
		Doing this, we are admonished by the Constitution of our country Government plan action include	is undertaken for the project that will be submitted to the National Department of Forestry, Fisheries	

the integrated development plan.
The provision permits society to participate in food faith and be given a platform by those stakeholders in charge to provide those services as stipulated by the Business Act of our country.

Our inputs are driven by the following exercise inside:

- We got full people that are registered with the Department of Trade and Industry;
- The company and civil constitution are run by well experienced business minded people.
- All the company workers are skilled workers, qualified qualified officials and with qualifications to some positions.
- Some of the company have their own employed consultants.
- The company has a good record in the field of civil and construction.
- In terms of grades we are a good company that have level 4,6,7,8 and 9 at this post in terms of our data system.
- Our proposal sustainability is driven by the State facts and aspects. We are also prepared to meet with you

and the Environment (DFFE) for authorisation.

The project will be put out to tender once the authorisation is received from DFFE. You need to consult the SANRAL website (www.nra.co.za) for the tender and tender process. Any enquiries regarding the tender or employment opportunities should be directed to the applicant (SANRAL).

		for more discussion.  The proposal is mainly for the road from Groblersdal to Nebo.		
Municipal Councillors				
Cllr Mokwane Magdeline Kubane Ward 27	No comments received	No issues raised	No response necessary	None required.
Cllr Mokganyetji Thomas Mareme Ward 24	No comments received	No issues raised	No response necessary	None required.
Cllr Malatji Meriam Nape Ward 29	No comments received	No issues raised	No response necessary	None required.
Cllr Msiza Mothibe Rhodes Ward 29	No comments received	No issues raised	No response necessary	None required.
Municipality				
Mr Meshack Kgwale Municipal Manager Elias Motsoaledi Local Municipality	No comments received	No issues raised	No response necessary	None required
Ms Maureen Ntshudisane Municipal Manager Sekhukhune District Municipality	No comments received	No issues raised	No response necessary	None required
Organs of State				
Mr Vusi Maluleke Department of Economic Development, Environment and Tourism	No comments received	No issues raised	No response necessary	None required
Ms Ramatsimele Jacqueline Maisela Head of Department Limpopo Department of Agriculture	No comments	No issues raised	No response necessary	None required

	received			
Mr Dawid Nethengwe (Water Licenses) Department of Water and Sanitation	No comments received	No issues raised	No response necessary	None required
Mr. Sello Maleka The Chief Executive Officer The Limpopo Tourism Agency	No comments received	No issues raised	No response necessary	None required
Services				
Mr Fana Hlathi Manager Head Planner for JHB Liquid Telekoms	09 February 2022	Liquid Services are not affected by this project.	Thanks for letting us know.	None required.
Communities				
Mr Sam Moloko Bakone Batubatse Tribal Authority	23 August 2021	Any projects and developments that is taking place to our constituency is as the legal entity, we are obliged to provide our inputs for the good running of that process.  Doing this, we are admonished by the Constitution of our country Government plan action include the integrated development plan. The provision permits society to participate in food faith and be given a platform by those stakeholders in charge to provide those services as stipulated by the Business Act of our country.  Our inputs are driven by the following exercise inside:  • We got full people that are	Thank you for the comments submitted on 23 August 2021.  Chameleon Environmental was appointed to undertake the environmental studies for the project only. A Basic Assessment is undertaken for the project that will be submitted to the National Department of Forestry, Fisheries and the Environment (DFFE) for authorisation.  The project will be put out to tender once the authorisation is received from DFFE. You need to consult the SANRAL website (www.nra.co.za) for the tender and tender process. Any enquiries regarding the tender or employment opportunities should	None required.

registered with the Department of Trade and Industry;  The company and civil constitution are run by well experienced business minded people.  All the company workers are skilled workers, qualified qualified officials and with qualifications to some positions.  Some of the company
consultants.  The company has a good record in the field of civil and construction.  In terms of grades we are a good company that have level 4,6,7,8 and 9 at this post in terms of our data system.  Our proposal sustainability is driven by the State facts and aspects. We are also
prepared to meet with you for more discussion.  The proposal is mainly for the road from Groblersdal to Nebo.

#### 7.2 The Environmental Attributes Associated With Alternatives

The environmental attributes described below include socio-economic, social, heritage, cultural, geographical, physical and biological aspects.

#### 7.2.1 Baseline Environment

#### a. Topography

The topography of the region is that of undulating plains and hills. The lowest point along the R574 is at Bloed River, near the start of the study site, at an elevation above average sea level of 915m. From the start of the route at KM 0,0 the road continues to climb ever higher, while undulating up and down small hills and eventually onto a large plateau. The highest point is at Morwaneng, at the end of the route, where the elevation is about 1 632m. The average slope across the study site is approximately 3,4% (Flori Scientific Services, 2022).

#### b. Climate

The study site is situated within the summer rainfall region of South Africa and within the medium rainfall region of 401 mm to 600 mm per annum. The average annual rainfall for the nearby Town of Groblersdal is approximately 497 mm (en.climate-data.org). The average annual rainfall across the Sekhukhune District Municipality is typically below 600 mm. Sekhukhune district is characterised by relatively poor and unreliable rainfall, frequent droughts and periodic flooding (<a href="https://www.researchgate.net">www.researchgate.net</a>).

The climate is warm to hot during the summer months, with some days becoming very hot, while temperatures are typically moderate to cold, but seldom very cold, in winter. The warm summers are long, while the winters are usually short, dry and with mostly clear skies. There are always winter days of colder temperatures with light frost in the early morning hours, especially in the low lying areas around streams and between mountains. The study site is situated within the Temperate Interior Climatic Zone of South Africa, but close to the outer edge of the Cold Interior (Flori Scientific Services, 2022).

#### c. Land cover

The landuse or landcover of the study site is that of an existing hard surface asphalt road (R574), along with the road reserve. The landcover of the greater area in which the study site is situated is that of open bushveld, commercial farmlands, small plots of subsistence farming and scattered rural villages / townships. The biggest landuse or landcover across the area is that of large and medium sized villages / townships that have tended to extend and merge into each other (Flori Scientific Services, 2022).

#### d. Vegetation

South Africa is divided up into nine major Biomes. The study site and the surrounding area are within the Savanna Biome and the Grassland Biome. The Savanna (Bushveld) Biome is

typically characterised by a lower layer of grasses, middle layer of shrubs and an upper layer of trees, while the Grassland Biome is characterised by the mostly absent upper layer of trees and scattered middle layer of shrubs, except in rocky areas or rocky outcrops (koppies).

Mucina & Rutherford (2010) divided the Savanna Biome (Bushveld Biome) into six bioregions, namely: Central Bushveld, Mopane, Lowveld, Sub-Escarpment Savanna, Eastern Kalahari Bushveld; and Kalahari Duneveld. The Grassland Biome is divided into four bioregions, namely: Drakensberg Grassland, Dry Highveld Grassland, Mesic Highveld Grassland, and Sub-Escarpment Grassland.

The eastern and middle sections of the study site (about 2/3) are within the Central Bushveld Bioregion of the Savanna Biome and the eastern section (about 1/3) is in the Mesic Highveld Grassalnd Bioregion of the Grassland Biome. Within these bioregoins the study site (R574) is within the original extent of the veldtypes of Central Sandy Bushveld, Loskop Thornveld and Rand Highveld Grassland (Flori Scientific Services, 2022).

Table 8: Vegetation classification of the study site (Flori Scientific Services, 2022)

Category Description	Classification
Biome	Savanna & Grassland
Bioregion	Central Bushveld & Mesic Highveld Grassland
Veldtype	Central Sandy Bushveld, Loskop Thornveld & Rand
	Highveld Grassland
Status	Central Sandy Bushveld – Least Concern / Least
	Threatened
	Loskop Thornveld – Least Concern / Least Threatened
	Rand Highveld Grassland - Vulnerable

Central Sandy Bushveld is characterised by low undulating areas, sometimes between mountains, and sandy plains and catenas supporting tall, deciduous *Terminalia sericea* and *Burkea africana* woodland on deep sandy soils (with the former often dominant on the lower slopes of sandy catenas) and low, broad-leaved *Combretum* woodland on shallow rocky or gravelly soils. Species of Vachellia (*Acacia*), *Ziziphus* and *Euclea* are found on flats and lower slopes on eutrophic sands and some less sandy soils. *Vachellia* (*Acacia*) *tortilis* may dominate some areas along valleys. Grass-dominated herbaceous layer with relatively low basal cover is found on dystrophic sands (Mucina & Rutherford, 2010).

Loskop Thornveld is characterised by valleys and plains of parts of the upper Olifants River catchment. The veldtype tends to be open, deciduous to semi-deciduous, tall, thorny woodland, usually dominated by thorn trees (Vachellia / *Acacia*) species (Mucina & Rutherford, 2010).

Rand Highveld Grassland is characterised by highly variable landscape with extensive sloping plains and a series of ridges slightly elevated over undulating surrounding plains. The vegetation is species-rich, wiry, sour grassland alternating with low, sour shrubland on rocky outcrops and steeper slopes. Most common grasses on the plains belong to the genera *Themeda*, *Eragrostis*, *Heteropogon* and *Elionurus*. High diversity of herbs, many of

which belong to the Asteraceae, is also a typical feature. Rocky hills and ridges carry sparse (savannoid) woodlands with *Protea caffra* subsp. *caffra*, *Protea welwitschii*, *Vachellia* (=*Acacia*) *caffra* and *Celtis africana*, accompanied by a rich suite of shrubs among which the genus *Searsia* (especially *Searsia* (=*Rhus*) *magalismonata*) is most prominent (Flori Scientific Services, 2022).

# e. Vegetation of the study area

The vegetation of the study site is mostly transformed and highly degraded. The vegetation present in the study site is within the road reserve and consists mainly of grasses and a few forbs. The road reserve is routinely cut and burnt thereby altering and degrading the natural vegetation. Most of the study site runs through villages and townships where the natural environment has been totally transformed and highly degraded.

There are no areas of pristine vegetation present within the study site itself. The areas of good vegetation are confined to patches and are typically not within the study site itself, but in nearby fields, or on nearby hills (Flori Scientific Services, 2022).

# g. Priority Floral Species

No Red Data Listed (RDL) species (endangered, threatened or vulnerable) were observed during field investigations in the study area (Flori Scientific Services, 2022).

#### h. Protected Species

Only one protected tree, namely the Marula (*Sclerocarya birrea*), was found to be present within the study site. There are a few scattered trees along the road in the road reserve (Flori Scientific Services, 2022).

### i. Fauna

No large- or medium-sized mammals were observed during field investigations. A few small burrows were found occasional within the road reserve, which appear to be used by small field mice and other rodents such as rock mouse (*Aethomys namaquensis*), striped mouse (*Rhabdomys pumilio*), multimate mouse (*Mastomus natalensis*) and bushveld gerbil (*Tatera leucogaster*). In open, less populated areas outside of the study area some evidence was found of scrub hare (*Lepus sacatilis*) and possibly yellow mongoose (*Cynictis penicillata*). There are many common species of wild animals and mammals present in the area of the greater Sekhukhune District, and many more with a historical distribution in the area, but these are more and more restricted to less accessible areas such as mountains, rocky ravines, etc. The study site is within a mostly densely populated area with numerous settlements and villages where the presence of large and medium sized mammals are scarce (Flori Scientific Services, 2022).

# j. Watercourses

There are eight main watercourses (rivers or streams) that the study site (R574) crosses over. Starting from KM 0,0, near Groblersdal these are: Bloed, Rulokwane, Puleng, Puleng

tributary, Ga-Makatle, Gemsbokspruit tributary, Gemsbokspruit and Malekani. In general the watercourses in the study area (those that are crossed) are all small, mostly semi-perennial / intermittent streams and seasonal drainage lines. The crossings are also small and narrow with only two actual bridges crossings over the Bloed River and Ga-Makatle River. The streams have no distinctive riparian zones or vegetation, except for the Bloed River, which only has a narrow zone of a few metres wide.

The only wetlands present in the study site are valley bottom or floodplain wetlands associated with the eight small rivers and streams already mentioned. There are no large or distinctive 'stand alone' wetlands in the study area such as pans, valley bottom wetlands without mainstream channels, etc. The national wetland map only shows one valley bottom wetland associated with the Gemsbokspruit (Flori Scientific Services, 2022).

# k. Air Quality

The project occurs in rural areas and the air quality is considered good apart from the air pollution that emanates from the R574.

#### l. Noise

The current noise levels are high due to the presence of heavy traffic on the R574.

#### m. Visual

The countryside through which the R574 road passes is largely one of rural agriculture on an undulating landscape. The widening of the road will have little visual effect as the existing road will be widened.

## n. Sites of Archaeological and Cultural Interests

There are no sites of archaeological or cultural interests that were identified in the area.

#### o. Socio-Economic Aspects

The project could have a positive impact on the regional socio-economic structure through its support of the development industry, profit generation contributing to tax revenue, employment creation and the skills development of its employees.

# p. Sensitive Landscapes

There are eight main watercourses (rivers or streams) that the study site (R574) crosses over. Starting from KM 0,0, near Groblersdal these are: Bloed river, Rulokwane, Puleng, Puleng tributary, Ga-Makatle, Gemsbokspruit tributary, Gemsbokspruit and Malekani Please find a sensitivity plan included in Appendix B.

# q. Cumulative Impacts

The cumulative impacts associated with the upgrade of the road could be the following (based on experience with regard to other major road upgrade projects):

- Additional traffic on the local roads during construction;
- Possible time delays as a result of construction period;
- Possible influx of people searching for employment opportunities in the area during construction.

# 8. Possible Project Benefits

#### 8.1 Economic Benefits

#### a. Short term Employment Creation

New employment opportunities will be created during the construction of the road. This includes much needed employment for existing industry, i.e. contractors (especially local Small, Medium and Micro Enterprises from the previously disadvantaged communities), consultants and suppliers.

The construction of the road could take place over several years, requiring a potentially large workforce and possible employment opportunities could be created in the project area. The benefits to the local community from employment could be dependent on the extent of local recruitment.

During the operational phase, the roads project could improve the well-being of populations in the area, and potentially improve the economy as a result of improved transport infrastructure.

# b. Long Term Employment Creation

Sustainable employment opportunities will be created for industry (contractors, consultants) during operation and maintenance of the road. Periodic upgrading, maintenance and rehabilitation of the road will be conducted over the next 20 years.

# c. Enhance Tourism

The road could enhance tourism through improved accessibility and a continuous route offering an improved, safer road for all road-users.

#### 8.2 Social Benefits

#### a. Employment

The road could provide long and short term employment opportunities, especially employment for industry. The development could provide employment to unskilled labour in both road and associated developments especially local Small, Medium and Micro Enterprises from the previously disadvantaged communities.

#### b. Improve Safety

The possibility of head-on collisions will be lowered with the upgrade of the road which will be much safer for all road users, especially heavy vehicles.

#### c. Skills Development

With the construction of the road, skills development could occur with practical training in management and technical skills. This could also include unskilled labour training and the use of small and medium enterprises.

# 8.3 Transport Benefits

#### a. Improved Accessibility:

Improved road networks could encourage business, industry and investment for South Africa and assist in alleviating the high unemployment in the region as a whole.

# b. Relieve Traffic Congestion

Traffic congestion occurs in the pass as a result of queueing of heavy vehicles. The upgrade would alleviate these issues.

# 9. Possible Impacts and Risks Identified

The **potential** impacts associated with the project and the degree to which these impacts can be reversed or may cause irreplaceable loss of resource and can be avoided, managed or mitigated are the following:

Table 9: Potential Impacts and Risks Identified

Potential Impact	Reversed Y/N or n/a	Irreplaceable	Avoided, Managed,
		loss	Mitigated
Dust Nuisance	Yes	No	Mitigated
Soil Erosion	Yes	Yes	Avoided, Mitigated
Loss of topsoil	Yes	No	Avoided
Noise Impact	Yes	No	Avoided, Mitigated
Water Pollution	Yes	No	Avoided, Mitigated

Visual Impact	Yes	No	Avoided, Mitigated
Clearing of protected	Yes	No	Mitigated
trees			
Mammals and snakes	Yes	No	Managed, Mitigated
in road reserve			
Uncovered heritage	Yes	No	Managed, Mitigated
sites and graves			
Contamination of site	Yes	No	Avoided, Managed
due to hydrocarbon			
spillage			
Emissions from heavy	Yes	No	Avoided, Managed
vehicles			
Infestation of weeds	Yes	No	Managed, Mitigated
and alien vegetation			
Possible pollution of	Yes	No	Managed, Mitigated
solid waste			
Possible sewage	Yes	No	Managed, Mitigated
pollution			
Possible pollution of	Yes	No	Managed, Mitigated
fuels and gas as a			
result of inadequate			
storage			
Possible pollution by	Yes	No	Managed, Mitigated
cement or concrete			

# 9.1 Methodology Used in Determining Impacts

Potential environmental impacts on the environment will be determined in terms of the following in order to determine the significance of each impact:

#### Nature:

A brief description of the environmental aspect being impacted upon by a particular action or activity is presented. Also:

- Probability (how likely is it that the impact will occur?)
- Magnitude (how severe will the impact be?)
- Duration (how long will the impact last?)
- Scale of the impact (what size of the area will be affected?)

Thereafter, mitigation measures will be proposed in order to reduce or eliminate negative impacts and enhance positive impacts. The impact of the proposed activity on the environment will be considered for the pre- construction, construction and operational phases. The necessary mitigation measures will be consolidated in the form of an Environmental Management Programme (EMPr).

Assessment of significance – method:

The significance of every environmental impact identified will be determined using the following approach:

In assessing the potential significance of an impact two aspects will be considered:

- i) Occurrence
- ii) Severity

Occurrence will be sub-divided into:

- Probability of occurrence
- Duration of occurrence

Severity will be sub-divided into:

- Magnitude (severity) of impact
- Scale/extent of impact

In order to assess each of these factors for each impact, ranking scales were employed as follows:

Probability:	Duration:
5 - Definite/don't know	5 - Permanent
4 - Highly probable	4 - Long-term*
0 14 11 1 1 1114	0 14 11 4

3 - Medium probability
2 - Low probability
1 - Improbable
3 - Medium-term (5-15 years)
2 - Short-term (0-5 years)
1 - Immediate

0 – None 0 - None

Scale: Magnitude:

5 – International 10 - Very high/don't know

4 - National
 3 - Regional
 2 - Local
 1 - Site only
 2 - Minor
 - None
 - None

Once the above factors had been ranked for each impact, the overall risk (environmental significance) of each impact will be assessed using the following formula: SP = (magnitude (M) + duration (D) + scale(S)) x probability (P). The maximum value is 100 significance points (SP). Environmental impacts will be rated as either of High, Moderate or Low significance on the following basis:

SP greater or the same as 60 indicates high environmental significance; SP 31 greater or the same as 59 indicates moderate environmental significance;

 $SP \le 30$  indicates low environmental significance.

<sup>\*</sup>impact ceases after operational life of the activity

Risks associated with alternatives: The risks associated with the alternatives are deemed to be low.

# 9.2 Positive and Negative Impacts and Assessment

The following table provides the positive and negative impacts associated with the project and the impact assessment undertaken. The mitigation measures are also included in the table.

**Table 10: Positive and Negative Impacts and Assessment** 

POTENTIAL ENVIRONMENTAL	ACTIVITY			SIGN	IFIC	ENTAL ANCE IGATION		RECOMMENDED MITIGATION MEASURES/  ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION	ı
IMPACT		М	D	S	Р	TOTAL	SP	REMARKS M D S P TOTA	L S P
AIR AND DUST POLLUTIO	N								
Possible air and dust pollution	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area	6	2	2	4	40	M	<ul> <li>Dust will be suppressed through a watering management programme, especially during windy conditions.</li> <li>Dust generated will be carefully monitored by the DEO and should be suppressed by means of watering regularly.</li> <li>Access roads will be watered regularly, especially in the dry winter months and in periods of high wind.</li> <li>Vegetation will not be unnecessary stripped.</li> <li>Domestic fires will be prohibited on site.</li> <li>Heavy vehicle will be serviced regularly to ensure emission control.</li> <li>All heavy vehicles, excavators and generators used on site will be in good working condition and will be serviced regularly.</li> </ul>	L

POTENTIAL ENVIRONMENTAL	ACTIVITY		;	SIGN	IFIC	ENTAL ANCE IGATION		RECOMMENDED MITIGATION  MEASURES/  ENVIRONMENTAL  SIGNIFICANCE  AFTER MITIGATION
IMPACT		M	D	s	Р	TOTAL	SP	REMARKS  M D S P TOTAL S P
								Should a vehicle have a break down, it will be serviced immediately.
SOIL EROSION								
Possible soil erosion	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area	4	2	2	2	16	L	<ul> <li>Topsoil will be removed over the section to be widened and stored in a perimeter berm. The height of the topsoil berm will not exceed 3m.</li> <li>The topsoil berm will be inspected for erosion daily.</li> <li>Minimal amounts of topsoil shall be lost due to erosion, either by wind or water. This can be facilitated through the grassing of topsoil stockpiles.</li> <li>Condition of soil in walk or drive areas should be checked daily for erosion.</li> <li>Access road condition will be checked daily.</li> <li>If erosion is noted at walk and drive areas, access road or topsoil berms, the erosion channel will be fixed by placing cut vegetation, sandbags or rocks within the erosion channel and the cause of the erosion will be</li> </ul>

POTENTIAL ENVIRONMENTAL	ACTIVITY		5	SIGN	IFIC	IENTAL ANCE IGATION		RECOMMENDED MITIGATION MEASURES/	ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION						
IMPACT		M	D	s	Р	TOTAL	SP	REMARKS	М	D	s	Р	TOTAL	S P	
								mitigated through the creation of runoff channels.							
NOISE															
Possible Noise Impact	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area	6	2	2	5	50	M	<ul> <li>The working hours shall be limited to between 07:00 hrs and 18:00 hrs on weekdays, and 07:00 hrs and 16:00 hrs on Saturdays, or as per contract documentation.</li> <li>Vehicles must be driven at a moderate speed (50 kph) on private roads.</li> <li>Noise generated from heavy vehicles shall only be carried out during normal working hours.</li> <li>Extended working hours will be in accordance with contract documentation.</li> <li>SANRAL shall be obligated to maintain vehicles used at the site in a good condition;</li> <li>SANRAL will be obliged to ensure that all personnel on site apply occupational health and safety requirements with respect to hearing protection.</li> </ul>	2	2	2	5	30	L	

POTENTIAL ENVIRONMENTAL	ACTIVITY		5	SIGN	IFIC	IENTAL ANCE IGATION		RECOMMENDED MITIGATION MEASURES/		ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION							
IMPACT		M	D	s	Р	TOTAL	SP	REMARKS	М	D	s	Р	TOTAL	S P			
VISUAL																	
Possible visual impacts	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area	2	2	2	3	18	L	<ul> <li>Where areas are going to be disturbed through the destruction of vegetation, use appropriate indigenous and endemic plants to replace screening vegetation lost.</li> <li>If practically possible, locate construction camps in areas that are already disturbed or where it isn't necessary to remove established vegetation.</li> <li>Keep the construction sites and camps neat, clean and organised (i.e. no littering) in order to portray a tidy appearance.</li> <li>In visually sensitive areas screen the construction camp and lay-down yards by enclosing the entire area with a dark green or black shade cloth of no less than 2 m height.</li> <li>Maintain natural vegetation where possible.</li> <li>Rehabilitate disturbed areas as soon as practically possible after construction. This should be done to restrict extended periods of exposed soil.</li> </ul>	2	2	2	2	12	L			

POTENTIAL ENVIRONMENTAL	ACTIVITY		9	SIGN	IFIC	ENTAL ANCE IGATION		RECOMMENDED MITIGATION MEASURES/	ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION						
IMPACT		М	D	s	Р	TOTAL	SP	REMARKS	M	D	s	Р	TOTAL	S P	
								<ul> <li>Utilise existing screening features such as dense vegetation stands or topographical features to place the construction camps and lay-down yards out of the view of sensitive visual receptors.</li> <li>Where vegetation clearance must be done for safety reasons, this should be kept to a minimum.</li> <li>Hydro-seeding must be undertaken as soon as possible after rehabilitation has commenced.</li> <li>The success of hydro-seeding must be monitored over a period of 1 year and be repeated in areas of low success.</li> </ul>							
AQUATIC AND TERRESTR	IAL ECOLOGY										'				
Possible impacts on watercourses and terrestrial ecology	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping	6	2	2	4	40	М	<ul> <li>No watercourses (streams, drainage lines, rivers) may be impeded or impounded during the construction phase or at any stage of the project.</li> <li>Work at watercourse crossings and on stormwater culverts should preferably be carried out during the dry, winter season when water flow is at its lowest or non-existent.</li> <li>The main flow of watercourses at</li> </ul>	4	2	2	2	16	L	

POTENTIAL ENVIRONMENTAL	ACTIVITY		9	SIGN	IFIC/	ENTAL ANCE IGATION		RECOMMENDED MITIGATION  MEASURES/  ENVIRONMENTAL  SIGNIFICANCE  AFTER MITIGATION
IMPACT		M	D	S	Р	TOTAL	SP	REMARKS  M D S P TOTAL S P
	and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area							crossings must not be altered or rerouted during the construction phase.  • Preferably any major upgrades and construction of water crossings, and stormwater culverts should be done during the dry, winter period when water flow is at its' lowest.  • Erosion and potential siltation of watercourses must be monitored at all times during the construction phase of the project.  • Any temporary storage, lay-down areas or accommodation facilities to be setup in existing disturbed areas only.  • Ensure small footprint during construction phase.  • 32m Buffer zones, from the edge of the banks of all watercourses need to be implemented. These are 'No-Go' zones in terms movement of vehicles and contractors. The only areas of exception are the work areas and footprints at the road crossings of watercourses.  • No temporary site offices or lay-down areas are allowed within 50m of the

POTENTIAL ENVIRONMENTAL	ACTIVITY		9	SIGN	IFIC/	ENTAL ANCE IGATION		RECOMMENDED MITIGATION  MEASURES/  ENVIRONMENTAL  SIGNIFICANCE  AFTER MITIGATION
IMPACT		М	D	S	Р	TOTAL	SP	REMARKS  M D S P TOTAL S P
								edge of any watercourses.  No temporary site offices or lay-down areas are allowed on top of any rocky hills or along any steep hill slopes. All laydown areas must be on flat, plains / surfaces and must be within disturbed areas as far as possible. No areas of trees may be specifically cleared for a laydown area or temporary office site.  All hazardous materials must be stored appropriately to prevent these contaminants from entering the water environment;  All excess materials brought onto site for construction must be removed after construction.  No open trenches or mounds of soils to be left.  A rehabilitation plan for disturbed areas to be compiled and implemented as part of the construction phase of the project. This includes access roads and temporary laydown / site office areas.  There are a few marula trees within the road reserve. These are protected trees and a permit will be required if any need to be removed. However, it

POTENTIAL ENVIRONMENTAL	ACTIVITY		5	SIGN	IFIC	ENTAL ANCE IGATION		RECOMMENDED MITIGATION  MEASURES/  ENVIRONMENTAL  SIGNIFICANCE  AFTER MITIGATION
IMPACT		М	D	S	Р	TOTAL	SP	REMARKS  M D S P TOTAL S P
								seems unlikely that any will need to be removed.  A General Authorisation (GA) process will be required for work on the stream crossings.  There are a few protected trees (Marulas) within the study area. All efforts must be made to avoid these trees, along with other any other large, well-established trees.  The study site is within a transformed and degraded environment and therefore impact on natural vegetation will be low.  Any priority species encountered must be identified and rescue prior to any excavation or construction activities. However, it is unlikely that any are present within the study site or the road and road reserve.  A weed control programme should be implemented. This can form part of the routine maintenance programme for the road.  Care must be taken not to interact directly with any wild life encountered.  Any bird nests encountered in the grass, trees or on the ceilings of

POTENTIAL ENVIRONMENTAL	ACTIVITY		5	SIGN	IFIC/	ENTAL ANCE IGATION		RECOMMENDED MITIGATION MEASURES/		ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION							
IMPACT		М	D	S	Р	TOTAL	SP	REMARKS	M	D	s	Р	TOTAL	S P			
								culverts must not be interfered with. If encountered must first be discussed with specialist as how best to proceed. This also applies to any active animal burrows encountered.  Care must be taken with heavy machinery used on the project. All access roads used during construction must be monitored for erosion and maintained.  Soils and stones excavated may be used on site as backfill, fixing of roads, filling of dongas, etc.  Excavated soils and rocks may not be simply dumped in any open veld or even on site.  All temporary access roads, laydown areas, temporary camps, site offices, etc. must be fully rehabilitated by the contractors prior to final signing off of the construction phase of the project.  Maintenance phase (to be implemented in defect liability period for 1 year)  Mechanical control of alien plants around disturbed areas to be implemented within three months of completion of construction. Thereafter									

POTENTIAL ENVIRONMENTAL	ACTIVITY	ENVIRONMENTAL SIGNIFICANCE BEFORE MITIGATION			SIGNIFICANCE RECOMMENDED MITIGATION SIGNIFIC SIGNIFIC MEASURES/ AFTER MIT								ICANCE		
IMPACT		М	D	s	Р	TOTAL	SP	REMARKS	М	D	s	Р	TOTAL	S	
HYDROCARBON SPILLAG								every six months. Mechanical control to be of such a nature as to allow local, indigenous grasses and other pioneers to colonise the previously disturbed areas, thereby keeping out alien invasives.  No chemical control (herbicides) of alien plants to be used within 100m of any watercourses.  Areas around foundations, culverts, gabions, etc. need to be check before and after the summer rainy season for signs of soil erosion due to stormwater run-off. Such sites need to be modified and rehabilitated to prevent ongoing erosion. These sites need to be monitored more closely than other sites which show no or minimal signs of erosion.  Inspection of road shoulders in areas of steep topography to be inspected after the summer rainy season for signs of erosion and rehabilitated and rectified as required.							

POTENTIAL ENVIRONMENTAL	ACTIVITY	ENVIRONMENTAL SIGNIFICANCE RECOMMENDED MITIGATION BEFORE MITIGATION MEASURES/		SIGNIFICANCE					MEASURES/ AFTER MITIGATION
IMPACT		M	D	s	Р	TOTAL	SP	P REMARKS  M D S P TOTAL S P	
Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material  Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area		6	3	2	3	27	L	<ul> <li>All heavy vehicles, excavators and generators used for the project will be in good working condition.</li> <li>A drip tray will be available to place underneath heavy vehicles while the vehicles are parked at night.</li> <li>Should a vehicle have a break down, it will be serviced immediately. If soil contamination with diesel and oils occurred, the spill will be cleared up promptly. If the spill is small, it will be cleaned with a spill kit. if the spill is large, a spill clean-up company will be used to clean-up the spill;</li> <li>Proper functioning of heavy vehicles will be ensured.</li> </ul>	
ALIEN VEGETATION							-		
Possible alien vegetation infestation	Construction Phase: Vegetation, stripping, stripping and stockpiling of topsoil, subsoil, overburden and spoil  Operational Phase: Excavations, Stockpiling and Transporting of gravel material	6	2	2	4	40	М	<ul> <li>Every 3 months casual labour will be employed to circumnavigate the site to hand pull out known alien vegetation that may have established in the disturbed area.</li> <li>Casual labour will be provided with photographs of the alien vegetation that could establish.</li> </ul>	

POTENTIAL ENVIRONMENTAL	ACTIVITY	ENVIRONMENTAL SIGNIFICANCE BEFORE MITIGATION			SIGNIFICANCE RECOMMENDED MITIGATE FORE MITIGATION MEASURES/				ENVIRONMENTAL SIGNIFICANCE AFTER MITIGATION					
IMPACT		M	D	s	Р	TOTAL	SP	REMARKS	M	D	s	Р	TOTAL	S P
	Decommissioning Phase: Sloping and Landscaping during rehabilitation, Replacing the topsoil and revegetating the disturbed area													
SANITATION FACILITIES														
Provision and management of sanitation facilities	All phases	8	2	2	4	48	M	<ul> <li>Chemical toilet facilities shall preferably be used on site. The toilets shall be services every second week by a service provider.</li> </ul>	4	2	2	3	24	L
HERITAGE, ARCHAEOLOG	SICAL AND PALEONTOLOGICAL IS	SSUE	S											
Possible archaeological sites and graves to be affected	Construction phase	6	5	1	5	60	Н	<ul> <li>If an artefact or grave on-site is uncovered, work in the immediate vicinity shall be stopped immediately and it should immediately be reported to a heritage practitioner so that an investigation and evaluation of the finds can be made. The Contractor</li> </ul>		5	1	2	24	L

POTENTIAL ENVIRONMENTAL	ACTIVITY	ENVIRONMENTAL SIGNIFICANCE BEFORE MITIGATION						SIGNIFICANCE RECOMMENDED MITIGATION		S	IGNI	FICA	NTAL NCE ATION	
IMPACT		М	D	s	Р	TOTAL	SP	REMARKS	М	D	s	Р	TOTAL	S P
								<ul> <li>shall take reasonable precautions to prevent any person from removing or damaging any such article.</li> <li>The South African Heritage Resources Agency (SAHRA) shall be contacted such that an archaeological/heritage resources consultant can be appointed to record the site and excavate if necessary. Work may only resume once clearance is given in writing by the archaeologist/heritage resources consultant.</li> </ul>						
SAFETY														
Safety of sloped areas and safety of employees	All phases – employees Decommissioning phase – sloped areas	6	5	1	5	60	Η	<ul> <li>Appropriate safety clothing will be worn at all times i.e. head gear, shoes, ear plugs.</li> </ul>		5	1	2	24	L

#### 10. ALTERNATIVES CONSIDERED

Motivation for preferred site: The R574 is an existing road that will be upgraded and site alternatives are therefore, not relevant.

The alternatives that were investigated are different design alternatives for the proposed road.

## a) Preferred design alternative

From km 0.0 – km 1.0: Dual carriageway with 2 x 3.5m lane per direction.

# b) Design Alternative 1

From km 0.0 – km 1.0: Single carriageway with 1 x 3.7m lane per direction.

#### c) No-go Alternative

Should the project not proceed the traffic on the R574 could experience increasingly unsafe driving conditions. This project will accommodate the predicted increase in traffic volume and avoid high driver frustration. The cost of maintenance could be very high with this alternative.

The current high volumes of heavy vehicle traffic on the R574 are a major safety and capacity concern. The volume of heavy vehicles is expected to increase significantly over the next 20 years. Traffic volumes and design principals determine that the road needs to be upgraded to ensure the safety of the traveling public. If this is not done, it is anticipated that accidents on this road will increase in future.

Please see facility illustrations in Appendix C.

#### 10.1 Site Selection Matrix

The following table provides a site selection matrix of the alternatives considered:

**Table 11: Site Selection Matrix** 

Criteria	Preferred Design	Design Alternative 1
	Alternative	
Cost	R690 585 000	R694 924 000
Level of Service (LOS)	Dueling km0 - km1 improve	No duelling of section and the
	the Level of Service (LOS)	LOS will remain at E.
	from LOS E to LOS A	
Choking of traffic	Prevent choking of traffic	Choking of traffic will continue
	between R33 and Bloed river	
	bridge at km 1	
Internal Rate of Return	21.6	21.5
(IRR)		

# 10.2 Advantages and Disadvantages of Alternatives Considered

## a. Preferred design alternative

From km 0.0 – km 1.0: Dual carriageway with 2 x 3.5m lane per direction.

#### Advantages

The advantages of the preferred alternative are the following:

- This is the most cost effective option.
- Duelling km0 km1 improve the Level of Service (LOS) from LOS E to LOS A.
- Prevent choking of traffic between R33 and the Bloed river Bridge km1.
- No additional tapers required at the R33/R574 intersection.
- Future cost saving by constructing the portion of dual carriageway and Bloed river Bridge.
- The Internal Rate of Return for this option is 21,6.
- The safety to the traveling public will be significantly improved as the traffic will be flowing optimally.
- The road could be upgraded to acceptable horizontal and vertical geometric requirements.
- This option drastically lowers the possibilities of head-on collisions.
- It is anticipated that the traffic accidents that occur on this road will be reduced with this option.
- It is anticipated that the road upgrade will cater for future traffic demand and will support economic growth. This will benefit the communities in the area including local residents, motorists, the road freight industry and its customers. The upgrade of the road will, therefore, ensure safer driving conditions for the traveling public by enabling vehicles to travel more efficiently and smoothly with less congestion.
- Improved traffic flow, particularly during peak periods.
- Reduced congestion is anticipated.
- The environmental impact of the upgrade of the road is deemed to be low.

#### Disadvantages

The disadvantages of this alternative are the following:

Additional material will be required for this option, considering the implied pavement
and fill widening. The existing sources currently being acquired will however be
sufficient in size to address the additional material requirements. In some cases,
borrow pit depth of excavation will be amended slightly.

#### b. Design Alternative 1

From km 0.0 – km 1.0: Single carriageway with 1 x 3.7m lane per direction. *Advantages* 

The advantages of this alternative are the following:

- Improved traffic flow, particularly during peak periods.
- Reduced congestion is anticipated.
- The environmental impact of the upgrade of the road is deemed to be low.

#### Disadvantages

The disadvantages of this alternative are the following:

- This is the most expensive option.
- The Level of Service (LOS) from will remain at a LOS E.
- The Internal Rate of Return for this option is 21,5 which is lower than the preferred alternative.
- No choking of traffic is prevented between R33 and the Bloed river Bridge km1.
- Additional tapers are required at the R33/R574 intersection,
- No future cost saving is anticipated with this option.
- The Internal Rate of Return for this option is 21,6.

# **10.3** Sustainable Development

It will be attempted to implement the following:

- · Compact fluorescent lights will be installed in the site offices;
- All solid waste will be separated in different containers to make recycling possible;
- Where new toilets will be installed dual flush device toilets will be installed;
- Storm water will be managed and improved to reduce erosion by installing gabion boxes;
- Where new grassing is done, it will be done by using locally indigenous vegetation;
- Training of staff will be done to implement good housekeeping. This will be done during toolbox talks.
- An ECO will address the staff on good housekeeping actions.

#### **10.4** Socio-Economic Parameters

The value of the project is approximately R690 585 000 million. Employment opportunities that will accrue to previously disadvantaged individuals are the following:

- a. A minimum of 30% of the Final Contract Value by the end of the contract will accrue to Targeted Enterprises;
- b. A minimum of 8% of the Final Contract Value by the end of the contract will accrue to Targeted Labour; and
- c. An amount still to be determined will also be allocated for a Community Development type project within the main contract. The Community Development component to be executed by CIDB 1 to 4 Targeted Enterprise contractors, utilising labour enhanced construction methods. A sub-target of 36% are to be black women owned sub-contractors and 36% are to be black youth owned sub-contractors (Note that a particular sub-contractor ownership may contribute to both the women and the youth

criteria. Hence, 36% black women – and 36% black youth ownership does not imply only 29% non-woman/non-youth ownership).

# 11. SUMMARY OF SPECIALIST REPORTS

**Table 12: Summary of Specialist Reports** 

LIST OF STUDIES UNDERTAKEN	RECOMMENDATIONS OF SPECIALIST REPORTS	SPECIALIST RECOMMENDATIONS THAT HAVE BEEN INCLUDED IN THE EIA REPORT (Mark with an X Where applicable)	REFERENCE TO APPLICABLE SECTION OF REPORT WHERE SPECIALIST RECOMMENDATIONS HAVE BEEN INCLUDED.
Terrestrial Ecological Assessment and Aquatic (Wetland) Assessment for the Improvement of National Route R574 km 0 to km 38 by Flori Scientific Services, 2022	<ul> <li>The following are recommended:</li> <li>The only biodiversity areas of 'high' sensitivity encountered within the study site are the larger watercourse crossings and a section near Motetema where the road goes up a slight rise and onto higher lying ground / plateau. This is in the area where the 'cutting' for widening of the road will need to take place. The area of the Gemsbokspruit (stream) and Mahtrombi Nature Reserve are shown as having animal and plant sensitivities of 'Medium'. This was verified as such during site investigations (ground-truthing).</li> <li>There are no 'no-go zones' along the study site that might trigger a 'fatal flaw' in terms of the project brief and scope.</li> <li>There are no 'high' sensitive habitats present on site.</li> <li>No red data listed (RDL) fauna species were found to be present and / or</li> </ul>	X	EMPr

LIST OF STUDIES UNDERTAKEN	RECOMMENDATIONS OF SPECIALIST REPORTS	SPECIALIST RECOMMENDATIONS THAT HAVE BEEN INCLUDED IN THE EIA REPORT (Mark with an X Where applicable)	REFERENCE TO APPLICABLE SECTION OF REPORT WHERE SPECIALIST RECOMMENDATIONS HAVE BEEN INCLUDED.
	breeding with the study area boundaries., but it is likely that a few might occasional move through the area.  • Site investigations were conducted during the summer (wet) season of the region and the findings and availability of field data is sufficient to reached acceptable findings and outcomes from the assessment.  • There are no obvious fatal flaws in terms of the natural environment.  • Taking all findings and recommendations into account it is the reasonable opinion of the author / specialist that the activity may be authorised. The project and related activities may proceed to the next phase.		
	<ul> <li>Recommendations</li> <li>Recommended mitigating measures as proposed in this study and report should be implemented if the findings of this report are to remain pertinent.</li> <li>The only bufferzones required for the</li> </ul>		

LIST OF STUDIES UNDERTAKEN	RECOMMENDATIONS OF SPECIALIST REPORTS	SPECIALIST RECOMMENDATIONS THAT HAVE BEEN INCLUDED IN THE EIA REPORT (Mark with an X Where applicable)	REFERENCE TO APPLICABLE SECTION OF REPORT WHERE SPECIALIST RECOMMENDATIONS HAVE BEEN INCLUDED.
	project are along the watercourses. Obviously work on crossings has to take place and this acceptable. However, a 32m buffer zone, from the edge of the stream banks should be implemented along all watercourses (upstream and downstream). No buffer zones are necessary in areas of normal stormwater culverts and pipes that are simply installed to prevent impeding and impounding general surface flow of rainfall.  • A final walkdown is recommended in the area of the cutting to determine how many protected trees will be impacted. Thereafter a tree permit / plant permit application will be required to obtain permission.		
Phase 1 Cultural Heritage Impact Assessment: The Improvement of National Route R574 by Dr J van Schalkwyk, 2021	• If an artefact or grave on-site is uncovered, work in the immediate vicinity shall be stopped immediately and it should immediately be reported to a heritage practitioner so that an investigation and evaluation of the finds can be made. The Contractor shall take reasonable	X (all were included)	EMPr

LIST OF STUDIES UNDERTAKEN	RECOMMENDATIONS OF SPECIALIST REPORTS	SPECIALIST RECOMMENDATIONS THAT HAVE BEEN INCLUDED IN THE EIA REPORT (Mark with an X Where applicable)	REFERENCE TO APPLICABLE SECTION OF REPORT WHERE SPECIALIST RECOMMENDATIONS HAVE BEEN INCLUDED.
	precautions to prevent any person from removing or damaging any such article.  • The South African Heritage Resources Agency (SAHRA) shall be contacted such that an archaeological/heritage resources consultant can be appointed to record the site and excavate if necessary. Work may only resume once clearance is given in writing by the archaeologist/heritage resources consultant.		

#### 12. ENVIRONMENTAL IMPACT STATEMENT

# The following presents a summary of the key findings of the environmental impact assessment:

The study site is an existing transformed and highly degraded environment. Most of the study site (R574) also runs through built up villages and townships with high levels of transformed, altered and degraded natural environments. In reality there are no sensitive areas within the study site itself. The only sensitive areas along the study site route, which can be negatively impacted on during the construction phase are the watercourse crossings and the 'cutting' area.

Most of the watercourses are small and badly degraded but are all, by default, viewed and approached as 'sensitive'. There are no 'high' sensitive habitats present on site, with the exception of the watercourse crossings. The most important environmental impacts as a result of the upgrade of the road pertain to the possible impacts to the aquatic resources along the route. There are eight main watercourses (rivers or streams) that the study site (R574) crosses over. Starting from KM 0,0, near Groblersdal these are: Bloed, Rulokwane, Puleng, Puleng tributary, Ga-Makatle, Gemsbokspruit tributary, Gemsbokspruit and Malekani. There are no significant or independent wetlands in the study site. Mitigation measures are included in the EMPr to minimise the impact.

The vegetation of the study site is mostly transformed, altered and highly degraded. The vegetation present in the study site is within the road reserve and consists mainly of grasses and a few herbaceous plants. The road reserve is routinely cut and burnt thereby altering and degrading the natural vegetation. Most of the study site runs through villages and townships where the natural environment has been totally transformed and highly degraded. Only one protected tree, namely the Marula (*Sclerocarya birrea*), was found to be present within the study site. There are a few scattered trees along the road in the road reserve.

The essence of the Basic Assessment process is aimed at ensuring informed decision-making and environmental accountability, and to assist in achieving environmentally sound and sustainable development. The environmental impacts associated with the upgrade of the road are deemed to be low. No long-term environmental impact should arise.

# Option 1 is recommended due to the following:

- Duelling km0 km1 improve the Level of Service (LOS) from LOS E to LOS A,
- Prevent choking of traffic between R33 and the Bloed river Bridge km1,
- No additional tapers required at the R33/R574 intersection,
- The difference in width between the single and dual carriageway is marginal and there is a limited cost difference.
- Future cost saving by constructing the portion of dual carriageway and Bloed river bridge,
- Internal Rate of return of 21,6.
- This is the most cost effective option.
- The safety to the traveling public will be significantly improved as the traffic will be flowing optimally.

- The road could be upgraded to acceptable horizontal and vertical geometric requirements.
- This option drastically lowers the possibilities of head-on collisions.
- It is anticipated that the traffic accidents that occur on this road will be reduced with this option.
- It is anticipated that the road upgrade will cater for future traffic demand and will support economic growth. This will benefit the communities in the area including local residents, motorists, the road freight industry and its customers. The upgrade of the road will, therefore, ensure safer driving conditions for the traveling public by enabling vehicles to travel more efficiently and smoothly with less congestion.
- Improved traffic flow, particularly during peak periods.
- Reduced congestion is anticipated.
- The environmental impact of the upgrade of the road is deemed to be low.

#### 10.1 Final Site Map

Please see the final site maps included in Appendix C.

# 10.2 Summary of the positive and negative impacts and risks of the proposed activity and identified alternatives

The possible negative environmental impacts related to the project are associated with the construction phase i.e.

- a. Dust Pollution
- b. Soil Erosion
- c. Noise Impact
- d. Visual impact
- e. Impact on terrestrial ecology;
- f. Impact on uncovered heritage aspects
- g. Contamination of site due to hydrocarbon spillage
- h. Emissions from heavy vehicles
- i. Water pollution

These negative impacts have a low significance and can be mitigated during the construction period.

The positive impacts associated with the project are the following:

- The safety to the traveling public will be improved.
- Improved traffic flow, particularly during peak periods;
- · Reduced congestion is anticipated;
- It is anticipated that the project will cater for future traffic demand and will support
  economic growth. This will benefit the communities in the area including local
  residents, motorists, the road freight industry and its customers. The project will,
  therefore, ensure safer driving conditions for the traveling public by enabling vehicles
  to travel more efficiently and smoothly with less congestion.

# 13. PROPOSED IMPACT MANAGEMENT OBJECTIVES AND THE IMPACT MANAGEMENT OUTCOMES FOR INCLUSION IN THE EMPR

The following impact management measures will be implemented by SANRAL to prevent or remedy any possible pollution or degradation of the environment:

# a. Possible dust and air pollution

- Dust will be suppressed through a watering management programme, especially during windy conditions.
- Dust generated will be carefully monitored by the DEO and should be suppressed by means of water regularly.
- Any temporary access roads will be watered regularly, especially in the dry winter months and in periods of high wind.
- Vegetation will not be unnecessary stripped.
- · Domestic fires will be prohibited on site.
- Heavy vehicle will be serviced regularly to ensure emission control.

#### b. Soil Erosion

- Minimal amounts of topsoil shall be lost due to erosion, either by wind or water.
- Condition of soil in walk or drive areas should be checked daily for erosion.
- · Access road conditions will be checked daily.
- If erosion is noted at walk and drive areas, access road or topsoil berms, the erosion channel will be fixed by placing cut vegetation, sandbags or rocks within the erosion channel and the cause of the erosion will be mitigated through the creation of runoff channels.

#### c. Possible Noise Pollution

- The working hours shall be limited to between 07:00 hrs and 18:00 hrs on weekdays, and 07:00 hrs and 17:00 hrs on Saturdays, or as per contract documentation.
- Vehicles must be driven at a moderate speed (50 kph) on private roads.
- Noise generated from the heavy vehicles on the project shall only be carried out during normal working hours.
- Extended working hours will be in accordance with contract documentation.
- SANRAL shall be obligated to maintain vehicles used at the project in a good condition;
- SANRAL will be obliged to ensure that all personnel on site apply occupational health and safety requirements with respect to hearing protection.

# d. Possible Visual impact

- Where areas are going to be disturbed through the destruction of vegetation, use appropriate indigenous and endemic plants to replace screening vegetation lost.
- If practically possible, locate construction camps in areas that are already disturbed or where it isn't necessary to remove established vegetation.

- Keep the construction sites and camps neat, clean and organised (i.e. no littering) in order to portray a tidy appearance.
- In visually sensitive areas screen the construction camp and lay-down yards by enclosing the entire area with a dark green or black shade cloth of no less than 2 m height.
- Maintain natural vegetation where possible.
- Rehabilitate disturbed areas as soon as practically possible after construction. This should be done to restrict extended periods of exposed soil.
- Utilise existing screening features such as dense vegetation stands or topographical features to place the construction camps and lay-down yards out of the view of sensitive visual receptors.
- Where vegetation clearance must be done for safety reasons, this should be kept to a minimum.
- Hydro-seeding must be undertaken as soon as possible.
- The success of hydro-seeding must be monitored over a period of 1 year and be repeated in areas of low success.

#### e. Aquatic and Terrestrial Ecology

# **Construction phase**

- No watercourses (streams, drainage lines, rivers) may be impeded or impounded during the construction phase or at any stage of the project.
- Work at watercourse crossings and on stormwater culverts should preferably be carried out during the dry, winter season when water flow is at its lowest or non-existent.
- The main flow of watercourses at crossings must not be altered or rerouted during the construction phase.
- Preferably any major upgrades and construction of water crossings, and stormwater culverts should be done during the dry, winter period when water flow is at its' lowest.
- Erosion and potential siltation of watercourses must be monitored at all times during the construction phase of the project.
- Any temporary storage, lay-down areas or accommodation facilities to be setup in existing disturbed areas only.
- Ensure small footprint during construction phase.
- 32m Buffer zones, from the edge of the banks of all watercourses need to be implemented. These are 'No-Go' zones in terms movement of vehicles and contractors. The only areas of exception are the work areas and footprints at the road crossings of watercourses.
- No temporary site offices or lay-down areas are allowed within 50m of the edge of any watercourses.
- No temporary site offices or lay-down areas are allowed on top of any rocky hills or along any steep hill slopes. All laydown areas must be on flat, plains / surfaces and must be within disturbed areas as far as possible. No areas of trees may be specifically cleared for a laydown area or temporary office site.
- All hazardous materials must be stored appropriately to prevent these contaminants from entering the water environment;
- All excess materials brought onto site for construction must be removed after construction.

- No open trenches or mounds of soils to be left.
- A rehabilitation plan for disturbed areas to be compiled and implemented as part of the construction phase of the project. This includes access roads and temporary laydown / site office areas.
- There are a few marula trees within the road reserve. These are protected trees and a
  permit will be required if any need to be removed. However, it seems unlikely that any
  will need to be removed.
- A General Authorisation (GA) process will be required for work on the stream crossings.
- There are a few protected trees (Marulas) within the study area. All efforts must be made to avoid these trees, along with other any other large, well-established trees.
- The study site is within a transformed and degraded environment and therefore impact on natural vegetation will be low.
- Any priority species encountered must be identified and rescue prior to any excavation or construction activities. However, it is unlikely that any are present within the study site or the road and road reserve.
- A weed control programme should be implemented. This can form part of the routine maintenance programme for the road.
- Care must be taken not to interact directly with any wild life encountered.
- Any bird nests encountered in the grass, trees or on the ceilings of culverts must not be interfered with. If encountered must first be discussed with specialist as how best to proceed. This also applies to any active animal burrows encountered.
- Care must be taken with heavy machinery used on the project. All access roads used during construction must be monitored for erosion and maintained.
- Soils and stones excavated may be used on site as backfill, fixing of roads, filling of dongas, etc.
- Excavated soils and rocks may not be simply dumped in any open veld or even on site.
- All temporary access roads, laydown areas, temporary camps, site offices, etc. must be fully rehabilitated by the contractors prior to final signing off of the construction phase of the project.

### Maintenance phase (to be implemented in defect liability period for 1 year)

- Mechanical control of alien plants around disturbed areas to be implemented within three
  months of completion of construction. Thereafter every six months. Mechanical control to
  be of such a nature as to allow local, indigenous grasses and other pioneers to colonise
  the previously disturbed areas, thereby keeping out alien invasives.
- No chemical control (herbicides) of alien plants to be used within 100m of any watercourses.
- Areas around foundations, culverts, gabions, etc. need to be check before and after the summer rainy season for signs of soil erosion due to stormwater run-off. Such sites need to be modified and rehabilitated to prevent ongoing erosion. These sites need to be monitored more closely than other sites which show no or minimal signs of erosion.
- Inspection of road shoulders in areas of steep topography to be inspected after the summer rainy season for signs of erosion and rehabilitated and rectified as required.

### f. Possible Impact on Uncovered Cultural or Archaeological site

• If an artefact or grave on-site is uncovered, work in the immediate vicinity shall be stopped immediately and it should immediately be reported to a heritage practitioner so

that an investigation and evaluation of the finds can be made. The Contractor shall take reasonable precautions to prevent any person from removing or damaging any such article.

 The South African Heritage Resources Agency (SAHRA) shall be contacted such that an archaeological/heritage resources consultant can be appointed to record the site and excavate if necessary. Work may only resume once clearance is given in writing by the archaeologist/heritage resources consultant.

# g. Possible contamination of site due to hydrocarbons spillage

- All heavy vehicles, excavators and generators used during construction will be in good working condition.
- A drip tray will be available to place underneath haul vehicles while the vehicles are parked at night.
- Should a vehicle have a break down, it will be serviced immediately. If soil contamination
  with diesel and oils occurred, the spill will be cleared up promptly. If the spill is small, it
  will be cleaned with a spill kit. If the spill is large, a spill clean-up company will be used to
  clean-up the spill;
- Proper functioning of heavy vehicles will be ensured.

# h. Possible establishment and spread of alien vegetation

- Every 3 months casual labour will be employed on site to hand pull out known alien vegetation that may have established in the disturbed area.
- Casual labour will be provided with photographs of the alien vegetation that could establish.

#### i. Sanitation Facilities

• Chemical toilet facilities shall preferably be used on site. The toilets shall be serviced every second week by a reputable service provider.

#### j. Emissions from heavy vehicles

- All heavy vehicles, excavators and generators used on site will be in good working condition and will be serviced regularly.
- Should a vehicle have a break down, it will be serviced immediately.

#### k. Unsafe working conditions for employees

• Appropriate safety clothing will be worn at all times i.e. head gear, shoes, ear plugs.

#### 14. ASPECTS FOR INCLUSION AS CONDITIONS OF AUTHORISATION

- a. A Site Environmental Control Officer must be on site for implementation of the EMPr;
- b. All activities must take place in accordance with the approved EMPr;
- c. Should archaeological sites or graves be exposed during construction work, it must immediately be reported to a heritage practitioner so that an investigation and evaluation of the finds can be made. Should any archaeological artefact be exposed during construction activities, construction must be stopped. Under no circumstances shall any artefact be destroyed. The area must be fenced off and a heritage practitioner must be must be contacted as soon as possible.

# 15. DESCRIPTION OF ANY ASSUMPTION, UNCERTAINTIES AND GAPS IN KNOWLEDGE

- a. The following assumptions have been made for the purposes of this report:
  - All information received from sources contributing to this project is correct;
  - That SANRAL will consider the recommendations derived from this study, and
  - The National Department of Forestry, Fisheries and the Environment will be the decision making authority with regard to this application.
- b. Limitations

None.

c. Knowledge Gaps

None

# 16. REASONED OPINION AS TO WHETHER THE PROPOSED ACTIVITY SHOULD OR SHOULD NOT BE AUTHORISED

## i) Reasons why the activity should be authorized or not

The activity should be authorised by the Department of Forestry, Fisheries and the Environment as the significance of the environmental impacts identified is low while there are positive impacts that will benefit the community as a whole.

## ii) Conditions that must be included in the authorisation

- a. A Site Environmental Control Officer must be on site for implementation of the EMPr;
- c. All activities must take place in accordance with the approved EMPr;
- d. Should any archaeological artefact be exposed during construction activities, construction must be stopped. Under no circumstances shall any artefact be destroyed. The area must be fenced off and a heritage practitioner must be must be contacted as soon as possible.

# 17. PERIOD FOR WHICH THE ENVIRONMENTAL AUTHORISATION IS REQUIRED

The period for which the environmental authorisation is required is 5 years. The date on which the activity will be concluded is unclear at this stage.

## 18. UNDERTAKING

I, Josephine Bothma, declare that -

- I act as the independent environmental practitioner in this application.
- The information contained in the report is correct.
- All comments and inputs from stakeholders and I&APs are included in the report.
- The inputs and recommendations from specialist reports are included in the report.
- All information provided to I&APs are included in the report.
- Responses to I&APs to comments or inputs made by I&APs are included in the report.

Signature of the environmental assessment practitioner:
Chameleon Environmental
Name of company:
Date:
Commissioner of Oaths

# **LIST OF APPENDICES**

Appendix A – CV and qualification certificate of EAP

Appendix B - Locality Plan, Sensitivity Plan

Appendix C - Facility Illustrations/site map

Appendix D – Public Participation Process

Appendix E – Specialist studies

Appendix F – Licenses/Permits received

Appendix G – Photographs

Appendix H - EMPr