


GENERAL NOTES:

1. ALL MARINE WORKS ARE SCHEMATIC ONLY.
2. THE SUPPLIER TO USE THE MARINE PIPEWORK SCHEMATIC AS A GUIDE ONLY AND HE SHOULD CHOOSE POSITIONS OF INLET STRUCTURES AND OUTLET DISCHARGE POINTS BASED ON HIS OWN DESIGN TAKING COGNISANCE OF AMONGST OTHERS THE WATER QUALITY REQUIRED AT THE PLANT AS WELL AS DAMAGE DUE TO ENVIRONMENTAL CONDITIONS, SUCH AS WAVE AND SHORELINE VARIATION.
3. ALL PHASE 1 PIPEWORK TO BE DECOMMISSIONED AFTER COMPLETION OF PHASE 2.
4. ALL PUMP STATION POSITIONS TO BE VERIFIED.
5. SUPPLIERS DESIGN SHALL ENSURE PIPELINE STABILITY AND PROTECTION ALONG THE ENTIRE PIPELINE(S) LENGTH, INCLUDING THE BEACH CROSSING, TIDAL ZONE, SURF ZONE AND OFFSHORE PORTION.
6. ALL PIPELINE(S) LOCATED ON THE BEACH AND TIDAL ZONE AREA SHALL BE BURIED TO ALLOW MINIMUM 1 M COVER FOR AESTHETIC PURPOSES. ALL PIPELINE(S) LOCATED INSIDE THE TIDAL POOL AREA SHALL BE BURIED ALONG THE BEACH AREA AS WELL AS WITHIN THE TIDAL POOL, EXTENDING TO THE BOUNDARY FENCE FOR AESTHETIC PURPOSES.
7. ALL BUOYS AND OTHER AIDS TO NAVIGATION MARKERS SHALL MEET THE SAMSA STANDARDS IN TERMS OF MARINE NOTICE No. 8 OF 2016



LEGEND

| DESCRIPTION | SYMBOL |
|--|--------|
| OFFSHORE 1xØ315mm RAW WATER ABSTRACTION PIPELINE | |
| OFFSHORE TIDAL POOL SUPPLEMENTAL 1xØ250mm PIPELINE | |

| | |
|----------------------|-------------------------------------|
| FOR INFORMATION ONLY | |
| PRELIMINARY | |
| FOR APPROVAL | |
| FOR TENDER PURPOSES | <input checked="" type="checkbox"/> |
| FOR CONSTRUCTION | |
| AS BUILT | |

| REV | DATE | REVISION DESCRIPTION | DRAWN | DESIGNED | REV ENGINEER | CONSULTING ENGINEER |
|-----|----------|----------------------|-------|----------|--------------|---------------------|
| A | 25/08/17 | FOR TENDER | KL | MC | WS | WPRSA |
| B | 11/09/17 | ADDENDUM 1 CHANGES | KL | MLR | MC | WPRSA |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

OneWay
to zero harm

Copyright ©
WorleyParsons Services Pty Ltd
ABN 61 001 279 812

CLIENT

CITY OF CAPE TOWN
ISIXEKO SASEKAPA
STAD KAAPSTAD

PROJECT

WATER RESILIENCE PROJECT

WorleyParsons
resources & energy
P.O.Box 398
BELLVILLE 7535
TEL:+27 21912 3000
FAX:+27 21912 3222
e-mail: capetown.office@worleyparsons.com

DATE: AUGUST 2017

SCALE: (ORIGINAL A3)
1:1000

DRG No. C00686-ZB-MA-DAL-0001-001

REV. B

DRAWING DESCRIPTION

MONWABISI PHASE 1 DREDGE/EXCAVATION CONCEPTUAL LAYOUT OF TIDAL POOL

"This drawing is prepared solely for the use of the contractual customer of WorleyParsons and WorleyParsons assumes no liability to any other party for any representations contained in this drawing."