

- Cramer C. H, Petersen M. D, Cao T, Topozada T. R, and Reichle M., 2000. A Time Dependent Probabilistic Seismic Hazard Model for California. Bull. Seismol. Soc. Am., 90: 1–21
- Cornell, C. A., and Toro, G. 1970. Seismic Hazard Assessment. In Hunter R. L., Mann C. J. (ed.), International Association for Mathematical Geology Studies. Mathematical Geology, No. 4, Techniques for Determining Probabilities of Geologic Events and Processes. Oxford: Oxford University Press, pp. 147-166
- Dargahi-Noubary, G. R., 1983. A Procedure for Estimation of the Upper Bound for Earthquake Magnitudes. Phys. Earth Planet. Interiors, 33: 91-93
- Douglas, J., 2003. Earthquake ground motion estimation using strong-motion records: a review of equations for the estimation of peak round acceleration and response spectral ordinates. Earth Sci. Rev. 61(1–2): 43–104
- Douglas, J., 2004. Ground Motion Estimation Equations. Imperial College London, Department of Civil & Environmental Engineering Soil Mechanics. Research Report Number 04-001-SM
- EERI Committee on Seismic Risk, (H. C. Shah, Chairman), 1984. Glossary of Terms for Probabilistic Seismic Risk and Hazard Analysis, Earthquake Spectra, 1: 33-36
- Epstein, B., and Lomnitz, C., 1966. A Model for the Occurrence of Large Earthquakes. Nature, 211: 954-956
- Faenza, L., Hainzl, S., Scherbaum, F., and Beauval, C., 2007. Statistical Analysis of Time Dependent Earthquake Occurrence and its Impact on Hazard in the Low Seismicity Region Lower Rhine Embayment. Geophys. J. Int., 171: 797-806
- Field, D. H., 1995. Probabilistic Seismic Hazard Analysis. A Primer. (http://www.relm.org/tutorial_materials)
- Field, D. H., Jackson, D. D., and Dolan, J. F., 1999. A mutually consistent seismic-hazard source model for Southern California. Bull. Seism. Soc. Am., 89: 559-578
- Frankel, A. D., Mueller, C. S., Barnhard, T. P., Perkins, D. M., Leyendecker, E. V., Dickman, N. C., Hanson, S. L., and Hopper, M. G., 1996. National Seismic Hazard Maps. U.S. Geol. Surv. Open-file Report, 96: pp.1-532
- Frankel, A. D., Petersen, M. D., Mueller, C. S., Haller, K. M., Wheeler, R. L., Leyendecker, E. V., Wesson, R. L., Harmsen, S. C., Cramer, C. H., Perkins, D. M., and Rukstales, K. S., 2002. Documentation for the 2002 Update of the National Seismic Hazard Maps. U.S. Geol. Surv. Open-File Report, 02: pp.1- 42
- Frohlich, C., 1998. Does maximum earthquake size depend on focal depth? Bull. Seism. Soc. Am., 88: 329-336
- Giardini, D., 1999. The Global Seismic hazard Assessment Program (GSHAP) 1992-1999. Ann. Geofis., 42: 957-1230
- Gibowicz, S. J., and Kijko, A., 1994. An Introduction to Mining Seismology. San Diego: Academic Press.
- Gupta, I. D., and Trifunac, M. D., 1988. Attenuation of Intensity with Epicentral Distances in India. Soil Dyn. Earthq. Eng., 7: 162-169
- Gupta, I. D., and Deshpande, V. C., 1994. Application of Log-Pearson Type-3 Distribution for Evaluation of Design Earthquake Magnitude. Jour. Inst. Engineers (India), Civil Div., 75: 129-134
- Gupta, L. D., 2002. The state of the art in seismic hazard analysis. ISET Journal of Earthquake Technology, Paper No. 428, 39: 311-346
- Gutenberg, B., and Richter, C. F., 1944. Frequency of Earthquakes in California. Bull. Seism. Soc. Am., 34: 185–188
- Hanks, T. C. and Cornell, C. A. 1999. Probabilistic Seismic Hazard Analysis: a Beginners Guide (available from T.C. Hanks at thanks@usgs.gov)
- Jackson, D.D., and Kagan, Y.Y., 1999. Testable Earthquake Forecasts for 1999. Seism. Res. Lett., 70: 393-403
- Jin, A., and Aki, K., 1988. Spatial and Temporal Correlation Between Coda Q and Seismicity in China. Bull. Seism. Soc. Am., 78: 741-769
- Kagan, Y. Y., 1991. Seismic moment distribution. Geophys. J. Int., 106: 123-134


- Kagan, Y. Y., 1994. Observational Evidence of Earthquakes as a Nonlinear Dynamical Process. Physica D, 77: 160-192
- Kagan, Y. Y., 1997. Seismic Moment-Frequency Relation for Shallow Earthquakes: Regional Comparison. J. Geophys. Res., 102: 2835-2852
- Kijko, A., 2004. Estimation of the Maximum Earthquake Magnitude m_{max} . Pure Appl. Geophys., 161, 1-27
- Kijko, A., and Sellevoll, M. A., 1989. Estimation of Earthquake Hazard Parameters From Incomplete Data Files, Part I, Utilization of Extreme and Complete Catalogues with Different Threshold Magnitudes. Bull. Seism. Soc. Am., 79: 645-654
- Kijko, A., and Sellevoll, M. A., 1992. Estimation of Earthquake Hazard Parameters From Incomplete Data Files, Part II, Incorporation of Magnitude Heterogeneity. Bull. Seism. Soc. Am., 82: 120-134
- Kijko, A., and Graham, G., 1998. "Parametric-Historic" Procedure for Probabilistic Seismic Hazard Analysis. Part I: Assessment of Maximum Regional Magnitude m_{max} . Pure Appl. Geophys., 152: 413-442
- Kijko, A., and Graham, G., 1999. "Parametric-Historic" Procedure for Probabilistic Seismic Hazard Analysis. Part II: Assessment of Seismic Hazard at Specified Site. Pure Appl. Geophys., 154: 1-22
- Kijko, A., Lasocki, S., and Graham, G., 2001. Nonparametric Seismic Hazard Analysis in Dams. Pure Appl. Geophys., 158: 1655-1675
- Klügel, J.-U., 2007. Error Inflation in Probabilistic Seismic Hazard Analysis. Engineering Geology, 90: 186-192
- Kramer, S. L., 1996. Geotechnical Earthquake Engineering. Englewood Cliffs, N.J. Prentice-Hill
- Lomnitz-Adler, J., and Lomnitz, C., 1979. A Modified Form of the Gutenberg-Richter Magnitude-Frequency Relation. Bull. Seism. Soc. Am., 69: 1209-1214
- Main, I. G., 1996. Statistical Physics, Seismogenesis and Seismic Hazard. Rev. Geophys., 34: 433-462
- Main, I. G., Irving, D., Musson, R., and Reading, A., 1999. Constrains on the Frequency-Magnitude Relation and Maximum Magnitudes in the UK from Observed Seismicity and Glacio-Isostatic Recovery Rates. Geophys. J. Int., 137: 535-550
- Main, I. G., and Burton, P. W., 1984. Information Theory and the Earthquake Frequency-Magnitude Distribution. Bull. Seism. Soc. Am., 74: 1409-1426
- Matthews M. V., Ellsworth W. L., and Reasenber, P. A., 2002. A Brownian Model for Recurrent Earthquakes. Bull. Seismol. Soc. Am., 92: 2233-2250
- McCalpin, J.P., 1996. Paleoseimology, (ed.), New York: Academic Press.
- McGarr, A., 1984. Some Applications of Seismic Source Mechanism Studies to Assessing Underground Hazard, In Rockburst and Seismicity in Dams, (eds Gay, N. C., and Wainwright, E. H.) (Symp. Ser. No. 6, 199-208. S. Afric. Inst. Min. Metal., Johannesburg, 1984)
- McGuire, R. K., 1976. FORTRAN computer program for seismic risk analysis, U.S. Geol. Surv. Open-file Report 76: pp.1-67
- McGuire, R. K., 1993. Computation of Seismic Hazard. Ann. Di Geofisica, 36: 181-200
- McGuire, R. K., 1995. Probabilistic Seismic Hazard Analysis and Design Earthquakes: Closing the Loop. Bull. Seism. Soc. Am., 85: 1275-1284
- McGuire, R. K., 2004. Seismic Hazard and Risk Analysis. Oakland: Earthquake Engineering Research Institute, MNO-10.
- McGuire, R. K., 2008. Review. Probabilistic Seismic Hazard Analysis: Early History. Earthquake Enging Struct. Dyn., 37: 329-338
- Merz, H. A., and Cornell, C. A., 1973. Seismic Risk Based on Quadratic Magnitude Frequency Low. Bull. Seism. Soc. Am., 69: 1209-1214
- Molchan, G., and Dmitrieva, O., 1992. Aftershock Identification: Methods and New Approaches. Geophys. J. Int., 109: 501-516


- Molina S., Lindholm, C. D., and Bungum, H., 2001. Probabilistic Seismic Hazard Analysis: Zoning Free Versus Zoning Methodology. Bolletino di Geofisica Teoretica ed Applicata, 42: 19-39
- Muir-Wood, R., 1993. From Global Seismotectonics to Global Seismic Hazard. Ann. Di Geofisica, 36: 153-168
- Nishenko, S. P., and Buland, R., 1987. A Generic Recurrence Interval Distribution for Earthquake Forecasting. Bull. Seism. Soc. Am., 77: 1382-1399
- Nuttli, O. W., 1981. On the Problem of Maximum Magnitude of Earthquakes. U.S. Geol. Surv. Open-file Report 81: pp. 1-13
- Ogata, Y., 1999. Estimating the Hazard of Rupture Using Uncertain Occurrence Times of Paleoearthquakes. J. Geophys. Res., 104: 17,995-18014
- Page, R., 1968. Aftershocks and Microaftershocks. Bull. Seism. Soc. Am., 58: 1131-1168
- Panel of Seismic Hazard Analysis, 1988. Probabilistic Seismic Hazard Analysis. Washington DC: National Academy Press.
- Papastamatiou, D., 1980. Incorporation of Crustal Deformation to Seismic Hazard Analysis. Bull. Seism. Soc. Am., 70: 1321-1335
- Peruzza L., Pace B., and Cavallini F., 2008. Error Propagation in Time-Dependent Probability of Occurrence for Characteristic Earthquakes in Italy. J. Seismol., 14: 119-141
- Pisarenko, V. F., Lyubushin, A. A., Lysenko, V. B., and Golubieva, T. V., 1996. Statistical Estimation of Seismic Hazard Parameters: Maximum Possible Magnitude and Related Parameters. Bull. Seism. Soc. Am., 86: 691-700
- Reiter, L., 1990. Earthquake Hazard Analysis: Issues and Insights. New York: Columbia University Press.
- Rhoades, D. A., 1996. Estimation of the Gutenberg-Richter Relation Allowing for Individual Earthquake Magnitude Uncertainties. Tectonophysics, 258: 71-83
- Rhoades, D., Van Dissen, R. J., and Dowrick, D. J., 1994. On the Handling of Uncertainties in Estimating the Hazard Rupture on a Fault. J. Geophys. Res., 99: 13,701-13,712
- Robson, D. S., and Whitlock, J. H., 1964. Estimation of a Truncation Point. Biometrika, 51: 33-39
- Rydelek, P. A., and Sacks, I. S., 1989. Testing the Completeness of Earthquake Catalogues and the Hypothesis of Self-Similarity. Nature, 337: 249-251
- Scholz, C. H., 1990. The Mechanics of Earthquakes and Faulting. Cambridge: Cambridge University Press.
- Schorlemmer, D., and Woessner J., 2008. Probability of Detecting an Earthquake. Bull. Seism. Soc. Am., 98: 2103-2117
- Shepherd, J. B, Tanner, J. G. and Prockter, L., 1993. Revised Estimates of the Levels of Ground Acceleration and Velocity with 10% probability of exceedance in any 50-year period for the Trinidad and Tobago Region. Caribbean Conference on Earthquakes, Volcanoes, Windstorms and Floods, 11-15 October, Trinidad
- Shimazaki, K., and Nakata, T., 1980. Time-Predictable Recurrence Model for Large Earthquakes. Geophys. Res. Lett., 7: 279-282
- Sornette, D., and Sornette, A. 1999. General Theory of the Modified Gutenberg-Richter Law for Large Seismic Moments. Bull. Seism. Soc. Am., 89: 1121-1130
- SSHAC - Senior Seismic Hazard Committee, 1997. Recommendations for Probabilistic Seismic Hazard Analysis: Guidance on Uncertainty and Use of Experts. NUREG/CR-6372, UCR-ID-122160, Main Report 1. Prepared for Lawrence Livermore National Laboratory.
- Stein, R. S., and Hanks, T. C., 1998. M₆ Earthquakes in Southern California During the Twentieth Century: No Evidence for a Seismicity or Moment Deficit. Bull. Seism. Soc. Am., 88: 635-652
- Stepp, J. C., 1972. Analysis of Completeness of the Earthquake Sample in the Puget Sound Area and Its Effect on Statistical Estimates of Earthquake Hazard. In Proceedings of the International Conference on Microzonation, Seattle, U.S.A., 2, pp. 897-910
- Tate, R. F., 1959. Unbiased Estimation: Function of Location and Scale Parameters. Ann. Math. Statist., 30: 331-366


- Thenhaus, P. C., and Campbell, K. W., 2003. Seismic Hazard Analysis. In W. F. Chen and C. Scawthorn, eds. Earthquake Engineering Handbook. Boca Raton, FL: CRC Press, pp. 8-1 – 8-50.
- Toro, G. R., Abrahamson, N. A. and Schneider, J. F., 1997. Model of Strong Ground Motions from Earthquakes in Central and Eastern North America: Best Estimates and Uncertainties. Seism. Res. Lett., 68: 41–57
- Utsu, T., 1965. A Method for Determining the Value of b on the Formula $\log n = a-bM$ Showing the Magnitude-Frequency Relation for Earthquakes. Geophys. Bull. Hokkaido Univ., 13: 99-103, (In Japan.; Engl. abstr.)
- Utsu, T., 1984. Estimation of Parameters for Recurrence Models of Earthquakes. Bull. Earthq. Res. Inst., Univ. Tokyo., 59: 53-66
- Wang, Z., and Zhou, M., 2007. Comment on “Why do Modern Probabilistic Seismic-Hazard Analyses Often Lead to Increased Hazard Estimates?” by Julian J. Bommer and Norman A. Abrahamson. Bull. Seism. Soc. Am., 97: 2,212–2,214
- Wang, Z., 2009. Comment on “Sigma: Issues, Insights, and Challenges” by F. O. Strasser, N. A. Abrahamson, and J. J. Bommer, Seism. Res. Lett., 80: 491-493
- Ward, S. N., 1997. More on M_{\max} , Bull. Seism. Soc. Am., 87: 1199-1208
- Weichert, D. H., 1980. Estimation of the Earthquake Recurrence Parameters for Unequal Observation Periods for Different Magnitudes. Bull. Seism. Soc. Am., 70: 1337-1346
- Weichert, D. H., and Kijko, A., 1989. Estimation of Earthquake Recurrence Parameters from Incomplete and Variably Complete Catalogue. Seism. Res. Lett., 60: p. 28
- Weimer, S., and Wyss, M., 2000. Minimum Magnitude of Completeness in Earthquake Catalogs: Examples from Alaska, the Western United States, and Japan. Bull. Seism. Soc. Am., 90: 859–869
- Wesson, R. L., and Perkins D. M., 2001. Spatial Correlation of Probabilistic Earthquake Ground Motion and Loss, Bull. Seism. Soc. Am., 91: 498–1515
- WGCEP (Working Group on Central California Earthquake Probabilities), 1995. Seismic Hazard in Southern California: Probable Earthquakes, 1994 to 2024. Bull. Seism. Soc. Am., 85: 379-439
- WGCEP (Working Group on California Earthquake Probabilities), 2008. The Uniform California Earthquake Rupture Forecast, version 2 (UCERF 2), U.S. Geol. Surv. Open-File Rept. 2007-1437, California Geological Survey Special Report 203, 104 pp. (<http://pubs.usgs.gov/of/2007/1437/>)
- Wheeler, R. L., 2009. Methods of M_{\max} Estimation East of Rocky Mountains. USGS, Open-File Report 2009-1018
- Wells, D. L., and Coppersmith, K. J., 1994. New Empirical Relationships Among Magnitude, Rupture Length, Rupture Width, Rupture Area, and Surface Displacement. Bull. Seism. Soc. Am., 84: 974-1002
- Woo, G., 1996. Kernel Estimation Methods for Seismic Hazard Area Source Modeling. Bull. Seism. Soc. Am., 86: 353-362
- Veneziano, D., Cornell, C.A. and O'Hara, T., 1984. Historic Method for Seismic Hazard Analysis. Elect. Power Res. Inst., Report, NP-3438, Palo Alto.
- Youngs, R.R. and Coppersmith, K. J., 1985. Implications of Fault Slip Rates and Earthquake recurrence Models to Probabilistic Seismic Hazard Estimates. Bull. Seism. Soc. Am., 75: 939-964
- Yeats, R. S., Sieh, K., and Allen, C. R., 1997. The Geology of Earthquakes. New York: Oxford University Press.


APPENDIX D


Seepage & Slope Stability Output




	Project			Kareerand TSF Extension		
	Analysis Description			Normal Slope at 1:6		
	Drawn By	RG	Scale	1:5689	Company	Knight Piesold
	Date		File Name	Normal elv 1424 mamsl.sli		




	Project		
	Analysis Description		
	Drawn By	Scale 1:5689	Company
	Date	File Name Normal elv 1424 mamsl 1in5 - Copy.sli	



Method Name	Min FS
Bishop simplified	1.412
Janbu simplified	1.358
Janbu corrected	1.410

	Project			Kareerand TSF Extension		
	Analysis Description			Seismic Conditions		
	Drawn By	RG	Scale	1:5689	Company	Knight Piesold
	Date		File Name	Seismic 0.166 elv 1424 mamsl.sli		



	Project			Kareerand TSF Extension
	Analysis Description			Seismic 0.166g, slope 1:5
	Drawn By	RG	Scale	1:6321
	Company		Knight Piesold	
Date	File Name		Seismic elv 1424 mamsl 1in5 0.166g.sli	

APPENDIX E

Water Balance

Your reference:
Our reference: 301-00204/13
Contact: A du Plessis

2019/03/11

AnglogoldAshanti Limited
Mine Waste Solutions
Private Bag X5010
Vaal Reef
2621

Dear Sir

Re: WATER BALANCE CALCULATION FOR THE KAREERAND TSF EXPANSION PROJECT

The purpose of this letter is to explain the Water Balance Calculations done for the detail design of the Kareerand TSF Expansion Project. This letter cannot expand on the detail of the calculations inside the model, but it will attempt to summarise the results. The letter refers to the Model: "301-00204-13 KR Ext WB 20190311 SmallRWD pumps DWS AdP". This letter differs from the previous versions, in that the pump rates between the RWD's have been reduced to 500 m³/h and RWD 4 has been removed. The capacities of RWD1-3 have also been modified.

The Water Balance is based on the production schedule, stage capacity curves and layout of the TSF Expansion.

The balance model was done in Excel as provided. The layout used is presented in Figure 1.

The TSF's were divided in areas. The stage capacity curve was used to determine when which bench becomes available. The stage capacity curve shows the elevations of the two portions only meet in mid 2037 – see Figure 2.

1. Model Information

In reference to the Excel model, the following information can be found on the various sheets in the model.

Balance Sheet:

The Balance sheet has the daily calculation of all the in and out flows of all the areas. This sheet is used to:

- Cell C11 - Change the date of the storm
- Cell C13 – change the range of days where the monthly rain will be reduced before and after a storm

- Cell G15 – change the number of days of no power after a storm
- Cell G16 – H20 – Change the number of days and % throttling on decants after power has been restored
 - Area 1 refers to the Existing TSF (Eastern area in Figure 1)
 - Area 2 refers to the TSF Expansion (Western area in Figure 1).




Figure 1: Layout of TSF

Data Input Sheet:

This sheet presents the areas, and various input parameters to be completed by the user

Climatic Data

Provides rainfall and evaporation data

Picture

Schematic of model and system

Areas

Provides measured areas, lengths and volumes of the various components such as Benches, RWD's etc.

Production

This sheet provides

- Production schedule per month
- Elevations from capacity curve
- Side slope Zones
 - Areas un-rehabilitated
 - Areas re-habilitated
 - Bench lengths

Elevation vs Time




Figure 2: Elevation curves (Area 1 = Existing TSF, Area 2 = Extension)

Volumes of dams

Graph presenting the required number of dams

Decant on TSF's

Decant shortfall = volume stored on dam

Summaries

Summary of volumes required

Runoff Factor calculations

- Rational - Dry Beach
- Rational - Side wall no vegetation
- Rational - Side wall Rehab

2. Assumptions:

For this model, it was assumed that the Existing TSF (A1) Decant flows to the Bufferdam (BD), which will overflow into the East Stormwater dam (ESWD), while the ESWD will overflow into the RWD1 and the full Midway capacity will be pumped from RWD1. In practice this could be varied to pump from either RWD1 or the BD.

When RWD1 has reached its limit and can't pump away enough water, it overflow into RWD2, which overflow into RWD3 when it reaches its capacity etc.

When a month for example January 2018 is considered, the volumes appearing in RWD2 and 3 are from the rain falling on the dam, which can be ignored since the dams have not been constructed – see more detail in Process description below.

The worst month to receive a 1:100 24h storm event is in January. The storm events were applied to 15 January in the years considered.

The production figures show that TSF Expansion only starts in 2022.

Bufferdam starts @ 80% full – cell Data Input!\$E88, therefore BD overflow to ESWD in wet months

ESWD start @ 20% full – Cell Data Input!\$E89.

RWD1 start @ 10% full – Cell Data Input!\$E90.

3. Process:

Considering the rise in the TSF's over time, specific dates were chosen to calculate the required capacities of the RWD's.

The dates and volumes required are summarized below (from Summaries tab):

Year	Month	RWD1 Vol required	RWD2 Vol required	RWD3 Vol required
2019	Jan	260000	0	0
2021	Jan	284000	0	0
2022	Jan	431000	187000	219000
2029	Jan	431000	187000	219000
2029	March	431000	187000	219000
2030	Jan	431000	187000	219000
2038	Jan	431000	187000	219000
2040	Feb	431000	187000	219000

Some of the data in the model is discussed in more detail below to provide an explanation of the model.

2019/01/15

Considering for example a storm on 15 January 2019, note the following:

- BD receives extra runoff and spills more to ESWD (column IM)
- The power is off for 5 days and then the decant starts

Bufferdam																
	+		+		+		+		+		+		-		-	
	BD Start of day	Decant	Rain BD	ZoneA Side Runoff	ZoneE Side Runoff	Seepage to filtersA1	Scavenger holes A1	Total In BD	Max evaporati on BD	Dust Suppress	Sub-Total Out BD	Interim Vol BD	Pump to Midway BD	Overflow to ESW	BD End of day	
Date	(m ³)	A1 (m ³)	(m ³)	(m ³)	(m ³)2	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	
2019/01/14	169 830	61 188	83	431	95	3 167	7 742	72 706	323	2 500	2 823	239 712	0	69 882	169 830	
2019/01/15	169 830	0	8 711	76 944	19 165	3 167	0	107 987	323	0	323	277 493	0	107 663	169 830	
2019/01/16	169 830	0	83	431	95	3 167	0	3 775	323	0	323	173 282	0	3 452	169 830	
2019/01/17	169 830	0	83	431	95	3 167	0	3 775	323	0	323	173 282	0	3 452	169 830	
2019/01/18	169 830	0	83	431	95	3 167	0	3 775	323	0	323	173 282	0	3 452	169 830	
2019/01/19	169 830	0	83	431	95	3 167	0	3 775	323	0	323	173 282	0	3 452	169 830	
2019/01/20	169 830	0	83	431	95	3 167	0	3 775	323	0	323	173 282	0	3 452	169 830	
2019/01/21	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	
2019/01/22	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	
2019/01/23	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	
2019/01/24	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	
2019/01/25	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	
2019/01/26	169 830	72 000	83	431	95	3 167	7 742	83 517	323	2 500	2 823	250 524	0	80 694	169 830	

- ESWD overflows to RWD1

East Storm dam									
	+		+		-		-		
	ESW Start of day	Rain ESW	Overflow from BD	Total In ESW	Max evaporati on ESW	Sub-Total Vol ESW	Interim Vol ESW	Overflow to RWD1	ESW End of day
Date	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)
2019/01/14	162 846	90	69 882	69 972	352	352	232 466	69 620	162 846
2019/01/15	162 846	9 481	107 663	117 144	352	352	279 638	116 792	162 846
2019/01/16	162 846	90	3 452	3 542	352	352	166 036	3 190	162 846
2019/01/17	162 846	90	3 452	3 542	352	352	166 036	3 190	162 846
2019/01/18	162 846	90	3 452	3 542	352	352	166 036	3 190	162 846
2019/01/19	162 846	90	3 452	3 542	352	352	166 036	3 190	162 846
2019/01/20	162 846	90	3 452	3 542	352	352	166 036	3 190	162 846
2019/01/21	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846
2019/01/22	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846
2019/01/23	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846
2019/01/24	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846
2019/01/25	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846
2019/01/26	162 846	90	80 694	80 784	352	352	243 278	80 432	162 846

- RWD1 receives the water, but can't pump for 5 days – no power, therefore it needs to contain all the water = 260 000 m³
- Dust suppression also only start after 5 days

2022/01/15

The run-off areas have increased therefore the volumes to the dams increase.

- BD receives extra runoff and spills more to ESWD (column IM)
- The power is off for 5 days and then the decant starts

Bufferdam															
	+	+	+	+	+	+									
	BD Start of day	Decant	Rain BD	ZoneA Side Runoff	ZoneE Side Runoff	Seepage to filtersA1	Scavenger holes A1	Total In BD	Max evaporati on BD	Dust Suppress ion	Sub-Total Out BD	Interim Vol BD	Pump to Midway BD	Overflow to ESW	BD End of day
Date	(m ³)	A1 (m ³)	(m ³)	(m ³)	(m ³)2	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)
2022/01/14	169 830	10 049	83	399	150	3 167	7 742	21 589	323	2 500	2 823	188 596	0	18 766	169 830
2022/01/15	169 830	0	8 711	91 848	29 527	3 167	0	133 252	323	0	323	302 759	0	132 929	169 830
2022/01/16	169 830	0	83	399	150	3 167	0	3 798	323	0	323	173 305	0	3 475	169 830
2022/01/17	169 830	0	83	399	150	3 167	0	3 798	323	0	323	173 305	0	3 475	169 830
2022/01/18	169 830	0	83	399	150	3 167	0	3 798	323	0	323	173 305	0	3 475	169 830
2022/01/19	169 830	0	83	399	150	3 167	0	3 798	323	0	323	173 305	0	3 475	169 830
2022/01/20	169 830	0	83	399	150	3 167	0	3 798	323	0	323	173 305	0	3 475	169 830
2022/01/21	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830
2022/01/22	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830
2022/01/23	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830
2022/01/24	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830
2022/01/25	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830
2022/01/26	169 830	72 000	83	399	150	3 167	7 742	83 540	323	2 500	2 823	250 547	0	80 717	169 830

- ESWD overflows to RWD1

East Storm dam										
	+	+								
	ESW Start of day	Rain ESW	Overflow from BD	Total In ESW	Max evaporati on ESW	Sub-Total Vol ESW	Interim Vol ESW	Overflow to RWD1	ESW End of day	
Date	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	(m ³)	
2022/01/14	162 846	90	18 766	18 856	352	352	181 350	18 504	162 846	
2022/01/15	162 846	9 481	132 929	142 410	352	352	304 904	142 058	162 846	
2022/01/16	162 846	90	3 475	3 565	352	352	166 059	3 213	162 846	
2022/01/17	162 846	90	3 475	3 565	352	352	166 059	3 213	162 846	
2022/01/18	162 846	90	3 475	3 565	352	352	166 059	3 213	162 846	
2022/01/19	162 846	90	3 475	3 565	352	352	166 059	3 213	162 846	
2022/01/20	162 846	90	3 475	3 565	352	352	166 059	3 213	162 846	
2022/01/21	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	
2022/01/22	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	
2022/01/23	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	
2022/01/24	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	
2022/01/25	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	
2022/01/26	162 846	90	80 717	80 807	352	352	243 301	80 455	162 846	

- RWD1 receives the water, but can't pump for 5 days, therefore it needs to keep the water = 431 000 m³

2029/03/15

Although January is the worst month, an additional bench was added in March, which resulted in higher throttling requirement.

- BD – note that the decant rate was 0 (power outage). After the power outage the decant rate was 100% for a few days and then decreased to prevent spillage out of RWD 3

Bufferdam															
	+	+	+	+	+	+		-	-						
Date	BD Start of day (m³)	Decant A1 (m³)	Rain BD (m³)	ZoneA Side Runoff (m³)	ZoneE Side Runoff (m³)2	Seepage to filtersA1 (m³)	Scavenger holes A1 (m³)	Total In BD (m³)	Max evaporati on BD (m³)	Dust Suppress ion (m³)	Sub-Total Out BD (m³)	Interim Vol BD (m³)	Pump to Midway BD (m³)	Overflow to ESW (m³)	BD End of day (m³)
2029/03/14	169 830	8 235	71	514	182	3 167	7 742	19 910	229	2 500	2 729	187 011	0	17 181	169 830
2029/03/15	169 830	0	8 698	119 595	37 887	3 167	0	169 347	229	0	229	338 948	0	169 118	169 830
2029/03/16	169 830	0	71	514	182	3 167	0	3 934	229	0	229	173 535	0	3 705	169 830
2029/03/17	169 830	0	71	514	182	3 167	0	3 934	229	0	229	173 535	0	3 705	169 830
2029/03/18	169 830	0	71	514	182	3 167	0	3 934	229	0	229	173 535	0	3 705	169 830
2029/03/19	169 830	0	71	514	182	3 167	0	3 934	229	0	229	173 535	0	3 705	169 830
2029/03/20	169 830	0	71	514	182	3 167	0	3 934	229	0	229	173 535	0	3 705	169 830
2029/03/21	169 830	72 000	71	514	182	3 167	7 742	83 675	229	2 500	2 729	250 777	0	80 947	169 830
2029/03/22	169 830	72 000	71	514	182	3 167	7 742	83 675	229	2 500	2 729	250 777	0	80 947	169 830
2029/03/23	169 830	72 000	71	514	182	3 167	7 742	83 675	229	2 500	2 729	250 777	0	80 947	169 830
2029/03/24	169 830	72 000	71	514	182	3 167	7 742	83 675	229	2 500	2 729	250 777	0	80 947	169 830
2029/03/25	169 830	72 000	71	514	182	3 167	7 742	83 675	229	2 500	2 729	250 777	0	80 947	169 830
2029/03/26	169 830	43 200	71	514	182	3 167	7 742	54 875	229	2 500	2 729	221 977	0	52 147	169 830
2029/03/27	169 830	43 200	71	514	182	3 167	7 742	54 875	229	2 500	2 729	221 977	0	52 147	169 830

RWD2													RWD3												
Date	RWD2 Start of day (m³)	Rain RWD2 (m³)	Overflow from RWD1 (m³)	Total In RWD2 (m³)	Max evaporati on RWD2 (m³)	Sub Total RWD2 (m³)	Interim Vol RWD2 (m³)	Pump RWD2 to RWD1 (m³)	Overflow to RWD3 (m³)	RWD2 End of day (m³)	SP30	RWD3 Start of day (m³)	Rain RWD3 (m³)	Overflow from RWD2 (m³)	Total In RWD3 (m³)	Max evaporati on RWD3 (m³)	Sub Total RWD3 (m³)	Interim Vol RWD3 (m³)	Pump RWD3 to RWD1 (m³)	Overflow to Env (m³)	RWD3 End of day (m³)				
2029/03/14	0	78	0	78	254	254	0	0	0	0		0	113	0	113	364	364	0	0	0	0				
2029/03/15	0	9 637	0	9 637	254	254	9 383	0	0	9 383		0	13 829	0	13 829	364	364	13 465	0	0	13 465				
2029/03/16	9 383	78	0	78	254	254	9 208	0	0	9 208		13 465	113	0	113	364	364	13 214	0	0	13 214				
2029/03/17	9 208	78	0	78	254	254	9 033	0	0	9 033		13 214	113	0	113	364	364	12 962	0	0	12 962				
2029/03/18	9 033	78	0	78	254	254	8 858	0	0	8 858		12 962	113	0	113	364	364	12 711	0	0	12 711				
2029/03/19	8 858	78	0	78	254	254	8 683	0	0	8 683		12 711	113	0	113	364	364	12 460	0	0	12 460				
2029/03/20	8 683	78	0	78	254	254	8 508	0	0	8 508		12 460	113	0	113	364	364	12 208	0	0	12 208				
2029/03/21	8 508	78	64 948	65 026	254	254	73 280	0	0	73 280		12 208	113	0	113	364	364	11 957	0	0	11 957				
2029/03/22	73 280	78	67 571	67 650	254	254	140 676	0	0	140 676		11 957	113	0	113	364	364	11 706	0	0	11 706				
2029/03/23	140 676	78	67 571	67 650	254	254	208 072	0	21 072	187 000		11 706	113	21 072	21 184	364	364	32 526	0	0	32 526				
2029/03/24	187 000	78	67 571	67 650	254	254	254 396	0	67 396	187 000		32 526	113	67 396	67 508	364	364	99 671	0	0	99 671				
2029/03/25	187 000	78	67 571	67 650	254	254	254 396	0	67 396	187 000		99 671	113	67 396	67 508	364	364	166 815	0	0	166 815				
2029/03/26	187 000	78	9 971	10 050	254	254	196 796	0	9 796	187 000		166 815	113	9 796	9 908	364	364	176 360	0	0	176 360				
2029/03/27	187 000	78	9 971	10 050	254	254	196 796	0	9 796	187 000		176 360	113	9 796	9 908	364	364	185 905	0	0	185 905				
2029/03/28	187 000	78	9 971	10 050	254	254	196 796	0	9 796	187 000		185 905	113	9 796	9 908	364	364	195 449	0	0	195 449				
2029/03/29	187 000	78	9 971	10 050	254	254	196 796	0	9 796	187 000		195 449	113	9 796	9 908	364	364	204 994	0	0	204 994				

From 2030 to 2037:

- the top surface areas are combined and all rain is accounted for on Area2 (Production sheet)
- the side slope runoff change as follows:
 - the higher benches have smaller areas, so the increase in un-rehabilitated areas slow down
 - the lower benches are assumed to be re-habilitated therefore reducing the run-off

2038/01/01:

In mid 2037, the two TSF's reach the same elevation. Both Areas now have 8 benches.

- BD – once again gets water from Area1. The water from Area1 decant is due to production water, which builds up as it could not be decanted for 5 days

Bufferdam																									
Date	BD Start of day (m³)	Decant A1 (m³)	Rain BD (m³)	ZoneA Side Runoff (m³)	ZoneE Side Runoff (m³)2	Seepage to filtersA1 (m³)	Scavenger holes A1 (m³)	Total In BD (m³)	Max evaporati on BD (m³)	Dust Suppress ion (m³)	Sub-Total Out BD (m³)	Interim Vol BD (m³)	Pump to Midway BD (m³)	Overflow to ESW (m³)	BD End of day (m³)										
2038/01/14	169 830	24 447	83	559	161	3 167	7 742	36 158	323	2 500	2 823	203 165	0	33 335	169 830										
2038/01/15	169 830	0	8 711	142 032	38 912	3 167	0	192 821	323	0	323	362 328	0	192 498	169 830										
2038/01/16	169 830	0	83	559	161	3 167	0	3 970	323	0	323	173 477	0	3 647	169 830										
2038/01/17	169 830	0	83	559	161	3 167	0	3 970	323	0	323	173 477	0	3 647	169 830										
2038/01/18	169 830	0	83	559	161	3 167	0	3 970	323	0	323	173 477	0	3 647	169 830										
2038/01/19	169 830	0	83	559	161	3 167	0	3 970	323	0	323	173 477	0	3 647	169 830										
2038/01/20	169 830	0	83	559	161	3 167	0	3 970	323	0	323	173 477	0	3 647	169 830										
2038/01/21	169 830	72 000	83	559	161	3 167	7 742	83 712	323	2 500	2 823	250 718	0	80 888	169 830										
2038/01/22	169 830	72 000	83	559	161	3 167	7 742	83 712	323	2 500	2 823	250 718	0	80 888	169 830										
2038/01/23	169 830	72 000	83	559	161	3 167	7 742	83 712	323	2 500	2 823	250 718	0	80 888	169 830										
2038/01/24	169 830	28 466	83	559	161	3 167	7 742	40 178	323	2 500	2 823	207 185	0	37 355	169 830										
2038/01/25	169 830	24 447	83	559	161	3 167	7 742	36 158	323	2 500	2 823	203 165	0	33 335	169 830										
2038/01/26	169 830	24 447	83	559	161	3 167	7 742	36 158	323	2 500	2 823	203 165	0	33 335	169 830										
2038/01/27	169 830	24 447	83	559	161	3 167	7 742	36 158	323	2 500	2 823	203 165	0	33 335	169 830										

- ESWD – overflows to RWD1

East Storm dam									
	+		+		-		-		
Date	ESW Start of day (m ³)	Rain (m ³)	ESW from BD (m ³)	Total In ESW (m ³)	Max evaporati on ESW (m ³)	Sub-Total Vol ESW (m ³)	Interim Vol ESW (m ³)	Overflow to RWD1 (m ³)	ESW End of day (m ³)
2038/01/14	162 846	90	33 335	33 425	352	352	195 919	33 073	162 846
2038/01/15	162 846	9 481	192 498	201 979	352	352	364 473	201 627	162 846
2038/01/16	162 846	90	3 647	3 737	352	352	166 231	3 385	162 846
2038/01/17	162 846	90	3 647	3 737	352	352	166 231	3 385	162 846
2038/01/18	162 846	90	3 647	3 737	352	352	166 231	3 385	162 846
2038/01/19	162 846	90	3 647	3 737	352	352	166 231	3 385	162 846
2038/01/20	162 846	90	3 647	3 737	352	352	166 231	3 385	162 846
2038/01/21	162 846	90	80 888	80 979	352	352	243 473	80 627	162 846
2038/01/22	162 846	90	80 888	80 979	352	352	243 473	80 627	162 846
2038/01/23	162 846	90	80 888	80 979	352	352	243 473	80 627	162 846
2038/01/24	162 846	90	37 355	37 445	352	352	199 939	37 093	162 846
2038/01/25	162 846	90	33 335	33 425	352	352	195 919	33 073	162 846
2038/01/26	162 846	90	33 335	33 425	352	352	195 919	33 073	162 846
2038/01/27	162 846	90	33 335	33 425	352	352	195 919	33 073	162 846

• RWD1 – overflows to RWD2

RWD1																										
	+		+		+		+		+		+		+		+		+		=		-		-		=	
Date	RWD1 Start of day (m ³)	Rain RWD1 (m ³)	Overflow from Decant (m ³)	ZoneB Side Runoff (m ³)	ZoneC Side Runoff (m ³)	ZoneD Side Runoff (m ³)	ZoneE Side Runoff (m ³)	ZoneF Side Runoff (m ³)	ZoneG Side Runoff (m ³)	ZoneH Side Runoff (m ³)	ZoneI Side Runoff (m ³)	Seepage from FiltersA2 (m ³)	Pump from RWD2 (m ³)	Pump from RWD3 (m ³)	Total In RWD1 (m ³)	Max evaporati on RWD1 (m ³)	Dust Suppressi on A2 (m ³)	Sub Total RWD1 (m ³)	Interim Vol RWD1 (m ³)	Pump to Midway (m ³)	Overflow to RWD2 (m ³)	Overflow to RWD3 (m ³)	RWD1 End of day (m ³)			
2038/01/14	0	191	33 073	29 100	313	0	0	0	0	0	0	0	3 167	0	0	65 844	744	2 500	3 244	62 599	62 599	0	0	0		
2038/01/15	0	20 051	201 627	0	80 460	0	0	70 942	11 974	54 399	3 167	0	0	0	442 621	744	0	744	441 877	0	10 877	431 000	0	431 000		
2038/01/16	431 000	191	3 385	0	313	0	0	0	0	0	0	0	3 167	0	0	7 055	744	0	744	437 311	0	6 311	431 000	431 000		
2038/01/17	431 000	191	3 385	0	313	0	0	0	0	0	0	0	3 167	0	0	7 055	744	0	744	437 311	0	6 311	431 000	431 000		
2038/01/18	431 000	191	3 385	0	313	0	0	0	0	0	0	0	3 167	0	0	7 055	744	0	744	437 311	0	6 311	431 000	431 000		
2038/01/19	431 000	191	3 385	0	313	0	0	0	0	0	0	0	3 167	0	0	7 055	744	0	744	437 311	0	6 311	431 000	431 000		
2038/01/20	431 000	191	3 385	0	313	0	0	0	0	0	0	0	3 167	0	0	7 055	744	0	744	437 311	0	6 311	431 000	431 000		
2038/01/21	431 000	191	80 627	72 000	313	0	0	0	0	0	0	0	3 167	0	0	156 297	744	2 500	3 244	584 053	86 400	66 653	431 000	431 000		
2038/01/22	431 000	191	80 627	72 000	313	0	0	0	0	0	0	0	3 167	0	0	156 297	744	2 500	3 244	584 053	86 400	66 653	431 000	431 000		
2038/01/23	431 000	191	80 627	72 000	313	0	0	0	0	0	0	0	3 167	0	0	156 297	744	2 500	3 244	584 053	86 400	66 653	431 000	431 000		
2038/01/24	431 000	191	37 093	72 000	313	0	0	0	0	0	0	0	3 167	0	0	112 763	744	2 500	3 244	540 519	86 400	23 119	431 000	431 000		
2038/01/25	431 000	191	33 073	72 000	313	0	0	0	0	0	0	0	3 167	0	0	108 744	744	2 500	3 244	536 499	86 400	19 099	431 000	431 000		
2038/01/26	431 000	191	33 073	72 000	313	0	0	0	0	0	0	0	3 167	0	0	108 744	744	2 500	3 244	536 499	86 400	19 099	431 000	431 000		
2038/01/27	431 000	191	33 073	72 000	313	0	0	0	0	0	0	0	3 167	0	0	108 744	744	2 500	3 244	536 499	86 400	19 099	431 000	431 000		

• Overflow to RWD 2 and RWD 3

RWD2										RWD3											
	+		+		=		-		=			+		+		=		-		=	
Date	RWD2 Start of day (m ³)	Rain RWD2 (m ³)	Overflow from RWD1 (m ³)	Total In on RWD2 (m ³)	Max evaporati on RWD2 (m ³)	Sub Total RWD2 (m ³)	Interim Vol RWD2 (m ³)	Pump RWD2 to RWD1 (m ³)	Overflow to RWD3 (m ³)	RWD2 End of day (m ³)	RWD3 Start of day (m ³)	Rain RWD3 (m ³)	Overflow from RWD2 (m ³)	Total In on RWD3 (m ³)	Max evaporati on RWD3 (m ³)	Sub Total RWD3 (m ³)	Interim Vol RWD3 (m ³)	Pump RWD3 to RWD1 (m ³)	Overflow to Env (m ³)	RWD3 End of day (m ³)	
2038/01/15	0	9 650	10 877	20 527	358	358	20 169	0	0	20 169	0	13 848	0	13 848	514	514	13 334	0	0	13 334	
2038/01/16	20 169	92	6 311	6 403	358	358	26 213	0	0	26 213	13 334	132	0	132	514	514	12 952	0	0	12 952	
2038/01/17	26 213	92	6 311	6 403	358	358	32 258	0	0	32 258	12 952	132	0	132	514	514	12 569	0	0	12 569	
2038/01/18	32 258	92	6 311	6 403	358	358	38 302	0	0	38 302	12 569	132	0	132	514	514	12 187	0	0	12 187	
2038/01/19	38 302	92	6 311	6 403	358	358	44 346	0	0	44 346	12 187	132	0	132	514	514	11 805	0	0	11 805	
2038/01/20	44 346	92	6 311	6 403	358	358	50 391	0	0	50 391	11 805	132	0	132	514	514	11 422	0	0	11 422	
2038/01/21	50 391	92	66 653	66 745	358	358	116 777	0	0	116 777	11 422	132	0	132	514	514	11 040	0	0	11 040	
2038/01/22	116 777	92	66 653	66 745	358	358	183 163	0	0	183 163	11 040	132	0	132	514	514	10 657	0	0	10 657	
2038/01/23	183 163	92	66 653	66 745	358	358	249 549	0	62 549	187 000	10 657	132	62 549	62 681	514	514	72 824	0	0	72 824	
2038/01/24	187 000	92	23 119	23 211	358	358	209 852	0	22 852	187 000	72 824	132	22 852	22 984	514	514	95 295	0	0	95 295	
2038/01/25	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	95 295	132	18 833	18 965	514	514	113 745	0	0	113 745	
2038/01/26	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	113 745	132	18 833	18 965	514	514	132 196	0	0	132 196	
2038/01/27	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	132 196	132	18 833	18 965	514	514	150 646	0	0	150 646	
2038/01/28	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	150 646	132	18 833	18 965	514	514	169 097	0	0	169 097	
2038/01/29	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	169 097	132	18 833	18 965	514	514	187 547	0	0	187 547	
2038/01/30	187 000	92	19 099	19 191	358	358	205 833	0	18 833	187 000	187 547	132	18 833	18 965	514	514	205 998	0	0	205 998	

The results after 2038 are similar to the results of 2038.

4. Conclusion

The water balance considered the construction of the TSF's, the production schedule, bench geometry, paddocks containment, rehabilitation of benches, a storm rainfall event and various other factors and variables.

It was found that three RWD's are required based on these assumptions and calculations. Factors that could have significant effects on the water balance are:

- Rehabilitation is not done as expected – the run-off factors make a significant difference in the volumes on these large areas
- The model considers one 1:100 year storm event, but if several smaller events occur a few days after each other, additional capacity may be required. The model does apply the daily average rainfall over every day of the month.
- If another storm hits the facility within the storm month, additional storage will be required or throttling of the TSF will have to be extended for a longer period.

Yours sincerely



Albertus du Plessis
Principal Tailings Engineer
For Knight Piésold (Pty) Limited

Thabang Mokoma
Principal Tailings Engineer
For Knight Piésold (Pty) Limited


Duncan Grant-Stuart
Technical Consultant
For Knight Piésold (Pty) Limited

APPENDIX F

Feasibility Study Drawings



Project Name:		TSF EXPANSION									
Location:		MINE WASTE SOLUTIONS - KAREERAND TAILINGS STORAGE FACILITY									
Work package description:		Knight Piesold									
Work package service provider:		Approved for construction (AFC) drawings for all engineering design disciplines as listed									
Work package tangible deliverables:		Approved for construction (AFC) drawings for all engineering design disciplines as listed									
Engineering Discipline:	Service provider drawing number	AGA matching drawing number	Drawings Descriptions	Drawing revision number and date							
				Rev A	Rev B	Rev C	Rev D	Rev E	Rev F	Rev G	
General	301-00204/13-000	MET-MWS-39-C0000	Kareerand TSF Expansion Project List Of Drawings	2018/11/20	2018/11/27	2019/01/30					
General	301-00204/13-001	MET-MWS-39-C0001	Site Location Plan	2018/11/20	2019/01/25	2019/02/28	2019/03/29				
General	301-00204/13-002	MET-MWS-39-C0002	Existing Tailings Storage Facility -Layout	2018/11/20	2019/01/30	2019/03/29					
General	301-00204/13-003	MET-MWS-39-C0003	Tailings Storage Facility Extension-Layout	2018/11/20	2018/11/27	2019/01/30	2019/02/23	2019/03/29			
General	301-00204/13-004	MET-MWS-39-C0004	Tailings Storage Facility Combined-Layout	2018/11/20	2019/01/28						
General	301-00204/13-005	MET-MWS-39-C0005	Battery limits layout	2018/11/20	Cancelled						
General	301-00204/13-006	MET-MWS-39-C0006	Fencing Layout and Details	2018/11/20	2019/01/30	2019/03/29					
General	301-00204/13-007	MET-MWS-39-C0007	Tailings Storage Facility And By Property	2018/11/21	2019/01/30	2019/03/29					
General	301-00204/13-008	MET-MWS-39-C0008	Contractor's Yard Layout Plan	2019/01/16							
Geotech	301-00204/13-050	MET-MWS-39-C0007	Geotechnical Test Pit and Borehole Locations-Layout	2018/11/21	2019/01/25	2019/03/29					
Geotech	301-00204/13-051	MET-MWS-39-C0008	Borrow pits areas	2018/11/21	Cancelled						
Geotech	301-00204/13-052	MET-MWS-39-C0008	Geotechnical Zones-Layout	2018/11/21	2019/01/28						
TSF Earthworks	301-00204/13-100	MET-MWS-39-C0009	TSF Starter Walls-Layout	2018/11/21	2019/01/25	2019/03/29					
TSF Earthworks	301-00204/13-101	MET-MWS-39-C0010	TSF Starter Walls-Section	2018/11/20	2018/11/27	2019/01/30	2019/03/29				
TSF Earthworks	301-00204/13-102	MET-MWS-39-C0011	TSF Embankment-Sections	2018/11/21	2019/01/30	2019/03/29					
TSF Earthworks	301-00204/13-103	MET-MWS-39-C0072	TSF Starter Walls-Section	2019/01/30	2019/03/29						
TSF Earthworks	301-00204/13-104	MET-MWS-39-C0073	TSF Starter Walls-Section	2019/01/30	2019/03/29						
Decant	301-00204/13-150	MET-MWS-39-C0012	TSF-Gravity Decant-Layout	2019/01/30	2019/03/29						
Decant	301-00204/13-151	MET-MWS-39-C0013	TSF-Intermediate Decant-Sections and details	2018/11/20	2018/11/27	2019/01/30	2019/03/29				
Decant	301-00204/13-152	MET-MWS-39-C0022	TSF-Final Gravity Decant-Sections and Details	2018/11/21	2019/01/30						
Decant	301-00204/13-153	MET-MWS-39-C0023	TSF Energy Dissipater-Sections and Details	2018/11/21	2019/01/25	2019/03/29					
Decant	301-00204/13-154	MET-MWS-39-M0027	Temporary catwalk, layout, sections and details	2019/02/28	2019/03/29						
Decant	301-00204/13-155	MET-MWS-39-M0028	Floating walkway, layout, sections and details	2019/02/28	2019/03/29						
Decant	301-00204/13-156	MET-MWS-39-M0029	Relocated RW Pipeline and Discharge into solution trench	2019/02/28	2019/03/29						
Decant	301-00204/13-157		Relocated RW Pipeline Layout and pipe schedule	2019/02/28	2019/03/29						
Slurry Pipework	301-00204/13-200	MET-MWS-39-M0021	Slurry Delivery Piping-General Arrangement Sheet 1 of 4	2019/01/28	2019/01/30	2019/02/01	2019/03/29	2019/04/26			
Slurry Pipework	301-00204/13-200		Slurry Delivery Piping-General Arrangement Sheet 2 of 4 (Line E)	2019/03/29	2019/04/26						
Slurry Pipework	301-00204/13-200		Slurry Delivery Piping-General Arrangement Sheet 3 of 4 (Line F)	2019/03/29	2019/04/26						
Slurry Pipework	301-00204/13-200		Slurry Delivery Piping-General Arrangement Sheet 4 of 4 (Line G)	2019/03/29	2019/04/26						
Slurry Pipework	301-00204/13-201	MET-MWS-39-M0020	Slurry Distribution Pipelines - Station No. 1 Plan, Details and Material List	2019/01/28	2019/01/30	2019/02/01	2019/03/13	2019/03/29	2019/04/26		
Slurry Pipework	301-00204/13-202	MET-MWS-39-M0019	Slurry Distribution Pipelines - Station No. 2 to 6 Plan, Details and Material List	2019/01/28	2019/01/30	2019/02/01	2019/03/13	2019/03/29	2019/04/26		
Slurry Pipework	301-00204/13-203	MET-MWS-39-M0018	Slurry Delivery Piping System - Pipeline onto Existing TSF (Line G)	2019/01/28	2019/01/30	2019/02/01	2019/03/13	2019/03/29	2019/04/26		
Slurry Pipework	301-00204/13-204	MET-MWS-39-M0017	Slurry Delivery Piping System - Valve Station: General Layout sht 1 of 3	2019/01/28	2019/01/30	2019/02/01	2019/03/29	2019/04/26			
Slurry Pipework	301-00204/13-205	MET-MWS-39-M0016	Slurry Delivery Piping System - Valve Station: Pipe Schedule sht 2 of 3	2019/01/28	2019/01/30	2019/02/01	2019/03/29	2019/04/26			
Slurry Pipework	301-00204/13-206	MET-MWS-39-M0015	Slurry Delivery Piping System - Valve Station: Pipe Schedule sht 3 of 3	2019/01/28	2019/01/30	2019/02/01	2019/03/29	2019/04/26			
Dust Suppression	301-00204/13-207	MET-MWS-39-M0022	Dust Suppression Transfer Systems: General Layout sht 1 of 2	2019/02/01	2019/02/28	2019/03/29					
Dust Suppression	301-00204/13-207	MET-MWS-39-M0022	Dust Suppression Transfer Systems: General Layout sht 2 of 2	2019/02/28	2019/03/29						
Dust Suppression	301-00204/13-211	MET-MWS-39-M0030	Dust Suppression Transfer Systems-Plans, Sections and Material List - Detail 7	2019/02/28	2019/03/13	2019/03/29					
Dust Suppression	301-00204/13-212	MET-MWS-39-M0031	Dust Suppression Transfer Systems-Plans, Sections and Material List - Detail 4	2019/02/28	2019/03/13	2019/03/29					
Dust Suppression	301-00204/13-213	MET-MWS-39-M0032	Dust Suppression Transfer Systems-Plans, Sections and Material List - Detail 5	2019/02/28	2019/03/13	2019/03/29					
Dust Suppression	301-00204/13-214	MET-MWS-39-M0033	Dust Suppression Transfer Systems-Plans, Sections and Material List - Detail 6	2019/02/28	2019/03/13	2019/03/29					
Filters and Drains	301-00204/13-250	MET-MWS-39-C0019	Seepage Interception-Underdrainage-General Layout	2018/11/20	2018/11/27	2019/01/30					
Filters and Drains	301-00204/13-251	MET-MWS-39-C0074	Seepage Interception-Underdrainage-Layout (Main Drain)	2018/11/21	2019/01/30						
Filters and Drains	301-00204/13-252	MET-MWS-39-C0075	Seepage Interception-Underdrainage-North Layout	2018/11/21	2019/01/30						
Filters and Drains	301-00204/13-253	MET-MWS-39-C0076	Seepage Interception-Underdrainage-West Layout	2018/11/21	2019/01/30						
Filters and Drains	301-00204/13-254	MET-MWS-39-C0077	Seepage Interception-Filter Drain Outlet-Sections and Details	2018/11/21	2019/01/30						
Filters and Drains	301-00204/13-255	MET-MWS-39-C0077	Seepage Interception-Underdrainage-Sections	2018/11/21	2019/01/30						
Filters and Drains	301-00204/13-256	MET-MWS-39-C0074	Seepage Interception-Underdrainage-Layout and Sections (Existing Drain Outlet)	2018/11/21	2018/11/27	2019/01/30					
Filters and Drains	301-00204/13-257	MET-MWS-39-C0078	Collector pipe for Existing Seepage Outlet Drains - Layout	2019/01/21	2019/01/30	2019/03/29					
Filters and Drains	301-00204/13-258	MET-MWS-39-C0079	Collector pipe for Existing Seepage Outlet Drains - Section and Details	2019/01/21	2019/01/30						
Solution Trench	301-00204/13-300	MET-MWS-39-C0025	Solution Trench Layout, Section & Details	2019/01/30	2019/01/25	2019/03/29					
Solution Trench	301-00204/13-301	MET-MWS-39-C0026	Solution Trench Northern Long Section	2019/01/30	2019/01/25						
Solution Trench	301-00204/13-302	MET-MWS-39-C0080	Solution Trench Southern Long Section	2019/01/30	2019/01/25						
Solution Trench	301-00204/13-304	MET-MWS-39-C0027	North Pump Sump Concrete Details	2019/01/30	2019/01/25						
RWD's	301-00204/13-350	MET-MWS-39-C0029	Return Water and Storm Water Dams - Layout	2018/11/20	2019/01/30	2019/02/23					
RWD's	301-00204/13-351	MET-MWS-39-C0030	Return Water and Storm Water Dams-Sections and Earthwork Details	2018/11/20	2019/01/30	2019/03/29					
RWD's	301-00204/13-352	MET-MWS-39-C0031	Return Water and Storm Water Dams-Liners And Details	2018/11/20	2019/01/30						
RWD's	301-00204/13-353	MET-MWS-39-C0032	Return Water Dam Pump Sump Concrete Details	2018/11/20	2019/01/21						
RWD's	301-00204/13-354	MET-MWS-39-C0034	Silt Traps-Layout and Sections (Concrete Details)	2018/11/20	2019/01/30	2019/02/23					
RWD's	301-00204/13-356	MET-MWS-39-C0035	Return water and storm water dams liners and details	2018/11/20	2019/01/30	2019/02/23					
RWD's	301-00204/13-357	MET-MWS-39-C0035	Return water & stormwater dam details, Sections & Earthworks	2019/01/30	2019/01/25	Cancelled					
RWD's	301-00204/13-358	MET-MWS-39-C0089	Intercompartment pumps system: Concrete layout, section and details.	2019/03/29							
RWD's Pipework	301-00204/13-360		Return water pipeline layout and pipe schedule	2019/03/29							
RWD's Pipework	301-00204/13-361	MET-MWS-39-M0023	INTER-COMPARTMENT LAYOUT, SECTION AND MATERIAL LIST - DETAIL 1	2019/02/01		2019/03/29					
RWD's Pipework	301-00204/13-362	MET-MWS-39-M0024	INTER-COMPARTMENT LAYOUT, SECTION AND MATERIAL LIST - DETAIL 2	2019/02/01		2019/03/29					
RWD's Pipework	301-00204/13-363	MET-MWS-39-M0025	INTER-COMPARTMENT LAYOUT, SECTION AND MATERIAL LIST - DETAIL 3	2019/02/01		2019/03/29					
Stormwater Management	301-00204/13-400	MET-MWS-39-C0053	Stormwater Management-Berm Drainage Details	2018/11/20	2019/01/30						
Stormwater Management	301-00204/13-401	MET-MWS-39-C0054	Stormwater Management-Northern Diversion Channel-Layout	2018/11/20	2019/01/30						
Stormwater Management	301-00204/13-402	MET-MWS-39-C0050	Stormwater Management: River Entry layout, section and details	2019/02/28							
Access	301-00204/13-450	MET-MWS-39-C0059	Access Roads-Layout	2018/11/20	2019/01/30						
Spills Dam	301-00204/13-500	MET-MWS-39-C0082	New Emergency Spills Dam - Layout	2019/01/21	2019/03/29						
Spills Dam	301-00204/13-501	MET-MWS-39-C0083	New Emergency Spills Dam -Sections and Liner Details	2019/01/21							
	C00787-39-PR-DWG-0001-01	MET-MWS-39-P0011	Kareerand TSF Expansion Project- Legend Sheet 1 Piping & Instrumentation	2018/10/16	2018/10/20	2018/10/24					
	C00787-39-PR-DWG-0001-02	MET-MWS-39-P0012	Kareerand TSF Expansion Project- Legend Sheet 2 Piping & Instrumentation	2018/10/16	2018/10/20	2018/10/24					
	C00787-39-PR-DWG-0001-03	MET-MWS-39-P0013	Kareerand TSF Expansion Project Legend Sheet 3 Piping & Instrumentation Diagram	2018/10/16	2018/10/20	2018/10/24					
	C00787-39-PR-PFD-0001-01	MET-MWS-39-P0001	Kareerand TSF Capacity Expansion Project- Tailings Disposal Process Flow Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PFD-0002-01	MET-MWS-39-P0002	Kareerand Return Water Dam and Pumping	2018/10/23	2018/10/30	2018/11/05	2018/11/28				
	C00787-39-PR-PFD-0004-01	MET-MWS-39-P0031	Kareerand Gland Service Water								
	C00787-39-PR-PID-0001-01	MET-MWS-39-P0003	Kareerand TSF Capacity Expansion Project-Residue Tank Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PID-0001-02	MET-MWS-39-P0004	Kareerand TSF Capacity Expansion Project-Stage 1 Pump -Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PID-0001-03	MET-MWS-39-P0005	Kareerand TSF Capacity Expansion Project-Stage 2 Pump -Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PID-0001-04	MET-MWS-39-P0006	Kareerand TSF Capacity Expansion Project-Stage 3 Pump -Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PID-0001-05	MET-MWS-39-P0007	Kareerand TSF Capacity Expansion Project-Stage 4 Pump -Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05	2018/11/28				
	C00787-39-PR-PID-0001-06	MET-MWS-39-P0010	Kareerand TSF Capacity Expansion Project-Stage 5 Pump -Piping & Instrumentation Diagram	2018/09/26	2018/09/28	2018/10/05					



Legend:

Contractors Yard	Access Roads
Decant System	Return Water Dams
Starter Wall	RWD Diversion
Stormwater Dam	Paddocks
Diversion	Existing Infrastructure
Solution Trench	Fenceline
TSF @ 1432m	

Projection: WGS27


SITE LOCATION PLAN
SCALE: N.T.S



DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

SCALE: N.T.S


TITLE	DRG. No	DETAIL	MARK	DATE	INT	APP'D	PROJECT / MET ENGINEER	DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
ISSUED FOR APPROVAL				20.11.2018			DRAWN		FB/ME			20/11/2018
ISSUED FOR TENDER				25.01.2019			CHECKED		TM			20/11/2018
ISSUED FOR TENDER (RETURN WATER DAMS AND P STATION UPDATED)				27.02.2019			SENIOR DESIGNER MET PROJECTS					
ISSUED FOR TENDER (ACCESS GATES UPDATED)				26.03.2019			PR ENGINEER					
							PR TECH					
							PROJECT / MET ENGINEER		DGS			20/11/2018
							MET PROJECTS MANAGER					20/11/2018



301-00204/13-001
 REGION SOUTH AFRICA REGION - VR
 BUSINESS UNIT MINE WASTE SOLUTIONS
 PROJECT KAREERAND TSF EXPANSION PROJECT
 DRAWING TITLE SITE LOCATION PLAN

COPYRIGHT MET PROJECTS

CWR1806001 MET-MWS-39-C0001 REV D



SITE LEGEND	
EXISTING SITE LEGEND	
	EXISTING GRAVE SITES
	EXISTING POWER LINE
	EXISTING ACCESS ROADS
	EXISTING DELIVERY PIPELINES
	EXISTING PUMP STATION



EXISTING TAILINGS STORAGE FACILITY
SCALE 1:7 500


DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

SCALE: 1:7500

TITLE	DRG. No	DETAIL	MARK	DATE	INIT	APP'D	PROJECT / MET ENGINEER	DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE
ISSUED FOR APPROVAL			A	20.11.2018			DRAWN		FB			20.11.2018
ISSUED FOR TENDER			B	25.01.2019			CHECKED		TM			20.11.2018
ISSUED FOR TENDER			C	26.03.2019			SENIOR DESIGNER MET PROJECTS					
							PR ENGINEER					
							PR TECH					
							MET PROJECTS MANAGER		DGS			20.11.2018
												20.11.2018



301-00204/13-002	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	KAREERAND TSF EXPANSION PROJECT
	DRAWING TITLE	EXISTING TAILINGS STORAGE FACILITY - LAYOUT
MET PROJECTS	CWR1806001	MET-MWS-39-C0002



TEST PIT SETTING OUT DATA Lo-27-WGS84

POINT	EASTING	NORTHING	ELEVATION
PSO-1	12000.00	2974500.00	1322.00
PSO-2	12125.47	2975731.07	1311.14

STARTER WALL VOLUMES YEAR 1, 2 AND 3

YEAR	AREA	LENGHT	VOLUME
YEAR 1	29599.2m ²	1517m	74259.1m ³
YEAR 2	76677.5m ²	2180m	510036.2m ³
YEAR 3	23999.1m ²	1520m	37875.2m ³
YEAR 1,2,3	129857.7m ²		622170.5m ³

STORAGE FACILITY YEARLY EXPANSION AREAS

YEAR	AREA
YEAR 1	452665.8m ²
YEAR 2	1148949.3m ²
YEAR 3	452665.8m ²

SITE LEGEND

EXISTING AND NEW DRAIN PIPE LEGEND	
[Blue dashed line]	INTERMEDIATE DRAIN 1
[Blue solid line]	INTERMEDIATE DRAIN 2
[Blue dotted line]	INNER TOE DRAIN
[Green dashed line]	OUTER TOE DRAIN
[Red dashed line]	CENTRAL TOE DRAIN
[Purple dashed line]	EXISTING TOE DRAIN
[Red dashed line]	EXISTING SEEPAGE DRAINS
[Green dashed line]	EXISTING SEEPAGE DRAINS

YEARLY CONSTRUCTION LEGEND	
[Black dashed line]	TEMPORARY GRADER CUT
[Green fill]	YEAR 1 CONSTRUCTION
[Orange fill]	YEAR 2 CONSTRUCTION
[Purple fill]	YEAR 3 CONSTRUCTION
[Grey fill]	NEW CONTRACTORS YARD
[Hatched fill]	NEW TSF ACCESS ROAD
[Cross-hatched fill]	NEW TSF SECURITY FENCE LINE

EXISTING SITE LEGEND	
[Circle with cross]	EXISTING GRAVE SITES
[Dashed line]	EXISTING POWER LINE
[Dotted line]	EXISTING ACCESS ROADS
[Dashed line]	EXISTING DELIVERY PIPELINES
[Square with cross]	EXISTING PUMP STATION



TSF-STARTER WALLS-LAYOUT
 FENCING LAYOUT AND DETAILS
 SEEPAGE INTERCEPTION-UNDERDRAINAGE-SECTION
 SEEPAGE INTERCEPTION-UNDERDRAINAGE-GENERAL LAYOUT
 RETURN WATER AND STORM WATER DAMS-LAYOUT


DRG. No	DETAIL	MARK	DATE	INT	APP'D
301-00204/13-100	ISSUED FOR INFORMATION	A	21.11.2018		
301-00204/13-006	ISSUED FOR APPROVAL	B	27.11.2018		
301-00204/13-255	ISSUED FOR TENDER	C	25.01.2019		
301-00204/13-250	ISSUED FOR TENDER (RETURN WATER DAM AND AMENDED)	D	23.02.2019		
301-00204/13-350	ISSUED FOR TENDER	E	26.03.2019		

DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
DRAWN	FB			20.11.2018
CHECKED	TM			20.11.2018
SENIOR DESIGNER	MET PROJECTS			
PR ENGINEER				
PR TECH				
PROJECT / MET ENGINEER	DGS			20.11.2018
MET PROJECTS MANAGER				20.11.2018



301-00204/13-003
 REGION SOUTH AFRICA REGION - VR
 BUSINESS UNIT MINE WASTE SOLUTIONS
 PROJECT KAREERAND TSF EXPANSION PROJECT
 DRAWING TITLE TAILINGS STORAGE FACILITY EXTENSION-LAYOUT

DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				



SITE LEGEND	
YEARLY CONSTRUCTION LEGEND	
	TEMPORARY GRADER CUT
	NEW CONTRACTORS YARD
	NEW TSF ACCESS ROAD
	NEW TSF SECURITY FENCE LINE
EXISTING SITE LEGEND	
	EXISTING GRAVE SITES
	EXISTING POWER LINE
	EXISTING ACCESS ROADS
	EXISTING DELIVERY PIPELINES
	EXISTING PUMP STATION



TAILINGS STORAGE FACILITY LAYOUT
SCALE 1:12,500



TITLE	DRG. No	DETAIL
ACCESS ROAD-LAYOUT	301-00204/13-450	ISSUED FOR APPROVAL
SOLUTION TRENCH LAYOUT	301-00204/13-300	ISSUED FOR TENDER
TSF-GRAVITY DECANT LAYOUT	301-00204/13-150	RETURN WATER DAM LAYOUT CHANGED
STORMWATER MANAGEMENT NORTHERN DIVERSION CHANNEL-LAYOUT SECTIONS	301-00204/13-400	
	301-00204/13-400	

MARK	DATE	INIT	APP'D	REVISIONS
A	20.11.2018			
B	25.01.2019			
C	25.03.2019			

DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
DRAWN	FB/ME			20.11.2018
CHECKED	TM			20.11.2018
SENIOR DESIGNER	MET PROJECTS			
PR ENGINEER				
PR TECH				
PROJECT / MET ENGINEER	DGS			20.11.2018
MET PROJECTS MANAGER				20.11.2018



301-00204/13-004	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	MINE WASTE SOLUTION-KAREERAND EXTENSION PROJECT
	DRAWING TITLE	TAILINGS STORAGE FACILITY COMBINED LAYOUT AT CLOSURE
CWR1806001	MET-MWS-39-C0004	REV c



PADDOCKS
SOLUTION TRENCH
TSF ROAD
POWER LINES
TSF BOUNDARY FENCE

FUTURE TSF EXTENSION

SUMMIT

EXISTING SLURRY PIPE

EXISTING ROAD


EXISTING TSF

EXISTING ACCESS ROAD

EXISTING PIPELINE

EXISTING SITE OFFICE

POWER LINE




DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

SCALE: 1:12500

TITLE	DRG. No	DETAIL	MARK	DATE	INIT	APP'D	DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
							DRAWN	FB			31/10/2018
							CHECKED	DGS			31/10/2018
							SENIOR DESIGNER MET PROJECTS	DGS			31/10/2018
							PR ENGINEER	DGS			31/10/2018
							PR TECH				
							PROJECT / MET ENGINEER	DGS			31/10/2018
							MET PROJECTS MANAGER	NAME			31/10/2018




301-00204/13-005	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	MINE WASTE SOLUTION-KAREERAND EXTENSION PROJECT
	DRAWING TITLE	BATTERY LIMITS-LAYOUT
MET PROJECTS	CWR1806001	MET-MWS-39-C0005



FENCE SETTING OUT DATA Lo-27-WGS84

POINT	EASTING	NORTHING
BLY-P-15	11461.90	2973556.29
SOP-1	13500.00	2973153.29
SOP-2	13279.06	2973031.79
SOP-3	11142.16	2973618.33
SOP-4	12137.52	2973139.54
SOP-5	9201.07	2974498.10
SOP-6	9881.08	2977043.74
SOP-7	10893.93	2977654.08
SOP-8	12607.93	2977723.67
SOP-9	12288.07	2975891.23
SOP-10	11890.98	2973476.49
SOP-11	12554.74	2975938.98
SOP-12	10532.75	2973682.55
SOP-13	10821.40	2973682.46
SOP-14	13500.00	2975322.36
SOP-16	25109.47	5951877.96



DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				


SCALE: 1:10000

FENCING SETTING OUT PLAN
SCALE 1: 10 000

TITLE	DRG. No	DETAIL	MARK	DATE	INT	APP'D	DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE
ISSUED FOR APPROVAL			A	20.11.2018			DRAWN	FB			16.01.2018
ISSUED FOR TENDER			B	16.01.2019			CHECKED	TM			20.11.2018
RETURN WATER DAM LAYOUT CHANGED			C	25.03.2019			SENIOR DESIGNER MET PROJECTS	DGS			
							PR ENGINEER				
							PR TECH				
							PROJECT / MET ENGINEER	DGS			20.11.2018
							MET PROJECTS MANAGER				20.11.2018



301-00204/13-006	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	KAREERAND TSF EXPANSION PROJECT
	DRAWING TITLE	FENCING SETTING OUT PLAN
MET PROJECTS	CWR1806001	MET-MWS-39-C0049



TAILINGS STORAGE FACILITY AND BLY PROPERTY FENCE LAYOUT
SCALE N.T.S




DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

SCALE N.T.S

TITLE	DRG. No	DETAIL	MARK	DATE	INT	APP'D	PROJECT / MET ENGINEER	DGS NAME	REGISTRATION No:	SIGNATURE	DATE
SOLUTION TRENCH LAYOUT	301-00204/13-300	ISSUED FOR APPROVAL	A	20.11.2018			DRAWN	FB			31.10.2018
STORMWATER MANAGEMENT NORTHERN DIVERSION CHANNEL-LAYOUT SECTIONS	301-00204/13-401	ISSUED FOR TENDER	B	25.01.2019			CHECKED	TM			31.10.2018
ACCESS ROAD-LAYOUT	301-00204/13-450	ISSUED FOR TENDER	C	26.03.2019			SENIOR DESIGNER MET PROJECTS				
TSF-STARTER WALLS-LAYOUT	301-00204/13-100						PR ENGINEER				
							PR TECH				
							MET PROJECTS MANAGER				

COPYRIGHT
MET PROJECTS

301-00204/13-007	REGION SOUTH AFRICA REGION - VR	BUSINESS UNIT MINE WASTE SOLUTIONS	PROJECT KAREERAND TSF EXPANSION PROJECT	DRAWING TITLE TAILINGS STORAGE FACILITY AND BLY PROPERTY FENCE LAYOUT
CWR1806001	MET-MWS-39-C0070			REV C




CONTRACTOR YARD LEGEND

A: OFFICES	1500m ²
B: STORES	2000m ²
C: ABLUTIONS	900m ²
D: WORKSHOPS	2000m ²
E: PLANT YARD	5100m ²
F: DIESEL STORE	900m ²
G: LAY DOWN AREA	6100m ²
H: PARKING	1500m ²

CONTRACTOR YARD SETTING OUT DATA LO-27-WGS84

POINT	EASTING	NORTHING
SOP-1	12763.64	2975670.98
SOP-2	12563.64	2975670.98
SOP-3	12563.64	2975770.98
SOP-4	12763.64	2975770.98

CONTRACTOR YARD LAYOUT PLAN
SCALE 1: 1500



DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				


TITLE	DRG. No	DETAIL	REVISIONS	MARK	DATE	INT	APP'D	PROJECT / MET ENGINEER	DGS	DATE
ACCESS ROAD-LAYOUT	301-00204/13-450	ISSUED FOR TENDER		A	16.01.2019			DRAWN	FB	16.01.2019
								CHECKED	TM	20.11.2018
								SENIOR DESIGNER MET PROJECTS		
								PR ENGINEER	DGS	20.11.2018
								PR TECH		
								PROJECT / MET ENGINEER	DGS	20.11.2018
								MET PROJECTS MANAGER	NAME	20.11.2018

DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE



301-00204/13-008
 REGION SOUTH AFRICA REGION - VR
 BUSINESS UNIT MINE WASTE SOLUTIONS
 PROJECT KAREERAND TSF EXPANSION PROJECT
 DRAWING TITLE CONTRACTORS YARD LAYOUT PLAN
 CWR1806001





LEGEND

- BORROW AREA : FINE GRAINED (LOWER HORIZONS)
- BORROW PIT AREAS : COARSE GRAINED (UPPER HORIZONS)

CANCELLED

SITE LEGEND

EXISTING SITE LEGEND	
	EXISTING GRAVE SITES
	EXISTING POWER LINE
	EXISTING ACCESS ROADS
	EXISTING DELIVERY PIPELINES
	EXISTING PUMP STATION



BORROW PIT AREAS LAYOUT
SCALE: 1:10 000

SCALE: 1:10 000

ACCESS ROAD-LAYOUT	301-00204/13-450
TITLE	DRG. No
REFERENCE DRAWINGS	DETAIL


DRAWING CANCELLED
ISSUED FOR APPROVAL

MARK	DATE	INIT	APP'D
B	29.03.2019		
A	20.11.2018		

DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
DRAWN	FB			20.11.2018
CHECKED	DGS			20.11.2018
SENIOR DESIGNER MET PROJECTS				
PR ENGINEER				
PR TECH				
PROJECT / MET ENGINEER	DGS			20.11.2018
MET PROJECTS MANAGER	NAME			20.11.2018



301-00204/13-051	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	KAREERAND TSF EXPANSION PROJECT
	DRAWING TITLE	BORROW PIT AREAS LAYOUT
MET PROJECTS	CWR1806001	MET-MWS-39-C0006



NOTES

ZONE 1:
REMOVE TOPSOIL COLLUVIUM AND FERRICRETE TO BE USED IN STARTER WALL FILL. STARTER WALL FOUNDATION PREPARATION TO BE COMPACTED TO 95% PROCTER

ZONE 2:
STARTER WALL FILL TO BE PLACED DIRECTLY ON HARDPAN

DRAINAGE_ZONE:
REMOVE TOPSOIL, RIP AND COMPACT TO 95% PROCTER. THICK ALLUVIUM LAYER. SILTY CLAY.

FUTURE TSF EXTENSION:
REMOVE AND STOCKPILE TOPSOIL. COMPACT IN-SITU COLLUVIUM TO 95% PROCTER

LEGEND

- - - - - GEOTECHNICAL ZONE 1
- - - - - GEOTECHNICAL ZONE 2
- - - - - DRAINAGE ZONES

SITE LEGEND	
EXISTING SITE LEGEND	
	EXISTING GRAVE SITES
	EXISTING POWER LINE
	EXISTING ACCESS ROADS
	EXISTING DELIVERY PIPELINES
	EXISTING PUMP STATION




DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				


SCALE: 1:7500

GEOTECHNICAL ZONES-LAYOUT
SCALE: 1:7 500

ISSUED FOR APPROVAL		ISSUED FOR TENDER		DRAWN		CHECKED		SENIOR DESIGNER MET PROJECTS		PR ENGINEER		PR TECH		PROJECT / MET ENGINEER		MET PROJECTS MANAGER		
MARK	DATE	INIT	APP'D	DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE	DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE	DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE
A	20.11.2018			DRAWN	FB			20.11.2018										
B	25.01.2019			CHECKED	TM			20.11.2018										
				PR ENGINEER														
				PR TECH														
				PROJECT / MET ENGINEER	DGS			20.11.2018										
				MET PROJECTS MANAGER				20.11.2018										




301-00204/13-052
 REGION SOUTH AFRICA REGION - VR
 BUSINESS UNIT MINE WASTE SOLUTIONS
 PROJECT KAREERAND TSF EXPANSION PROJECT
 DRAWING TITLE GEOTECHNICAL ZONES-LAYOUT



**STARTER WALL
SETTING OUT TABLE L_o-27-WGS84**

NAME	DESCRIPTION	CHAINAGE (m)	EASTING (m)	NORTHING (m)	LENGTH (m) RADIUS (m)
L6		0.00	-11709.549	-2975949.622	45.711
C1	BCC	45.71	-11732.527	-2975910.106	374.323 2135.979
	PI	420.03	-11832.414	-2975751.260	
C2	BCC	420.03	-11958.465	-2975612.262	521.053 1027.570
	ECC	941.09	-12151.808	-2975429.202	
L1	BCC	941.09	-12409.721	-2975363.069	516.990
	PI	1458.08	-12907.574	-2975223.713	
C3	BCC	1458.08	-13099.280	-2975144.640	362.179 297.414
	ECC	1820.26	-13091.366	-2974937.418	
L2	BCC	1820.26	-13091.366	-2974937.418	553.948
	PI	2374.20	-13044.398	-2974385.464	
C5	BCC	2374.20	-13044.259	-2974383.833	3.274 200.000
	ECC	2377.48	-13044.147	-2974382.200	
L3	BCC	2377.48	-13044.147	-2974382.200	615.464
	PI	2992.94	-13002.010	-2973768.180	
C4	BCC	2992.94	-12952.269	-2973585.170	330.318 268.796
	ECC	3323.26	-12763.175	-2973570.671	
L4	BCC	3323.26	-12763.175	-2973570.671	560.921
	PI	3884.18	-12207.583	-2973647.810	
C6	BCC	3884.18	-12201.143	-2973648.704	12.999 200.000
	ECC	3897.18	-12194.774	-2973650.015	
L5		3897.18	-12194.774	-2973650.015	1280.720



SITE LEGEND

EXISTING SITE LEGEND	
	EXISTING GRAVE SITES
	EXISTING POWER LINE
	EXISTING ACCESS ROADS
	EXISTING DELIVERY PIPELINES
	EXISTING PUMP STATION



DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

TITLE	DRG. No	DETAIL
FENCE SETTING OUT PLAN	301-00204/13-006	ISSUED FOR APPROVAL
TSF STARTER WALL - SECTIONS SHEET 1/3	301-00204/13-101	ISSUED FOR TENDER
TSF STARTER WALL - SECTIONS SHEET 2/3	301-00204/13-103	DIVERSION CHANNEL UPDATED
TSF STARTER WALL - SECTIONS SHEET 3/3	301-00204/13-104	



MARK	DATE	INIT	APP'D
A	21.11.2018		
B	28.01.2019		
C	25.03.2019		

DESIGNATION	NAME	REGISTRATION No.	SIGNATURE	DATE
DRAWN	FB			20.11.2018
CHECKED	TM			20.11.2018
SENIOR DESIGNER	MET PROJECTS			
PR ENGINEER				
PR TECH				
PROJECT / MET ENGINEER	DGS			20.11.2018
MET PROJECTS MANAGER				20.11.2018



301-00204/13-100	REGION	SOUTH AFRICA REGION - VR
	BUSINESS UNIT	MINE WASTE SOLUTIONS
	PROJECT	KAREERAND TSF EXPANSION PROJECT
	DRAWING TITLE	TSF STARTER WALL - LAYOUT AND DETAILS

MET PROJECTS	CWR1806001	MET-MWS-39-C0009	REV c
--------------	------------	------------------	-------



A SECTION
100 SCALE: N.T.S.



DESCRIPTION	DOCUMENT NUMBER	NAME	SIGNATURE	DATE
DESIGN CALCULATIONS				
RISK ASSESSMENT				

TITLE	DRG. No	DETAIL	MARK	DATE	INIT	APP'D
TSF STARTER WALL - LAYOUT AND DETAILS	301-00204/13-100	ISSUED FOR INFORMATION	A	20.11.2018		
TSF-STARTER WALLS-SECTION-SHEET 1/3	301-00204/13-101	ISSUED FOR APPROVAL	B	28.11.2018		
TSF-STARTER WALLS-SECTION-SHEET 2/3	301-00204/13-103	ISSUED FOR TENDER	C	25.01.2019		
TSF-STARTER WALLS-SECTION-SHEET 3/3	301-00204/13-104	ISSUED FOR TENDER (DRAINS NAMING UPDATED)	D	26.03.2019		
SEEPAGE INTERCEPTION-FILTER DRAIN OUTLET-SECTIONS AND DETAILS	301-00204/13-254					

TITLE	DRG. No	DETAIL	MARK	DATE	INIT	APP'D
REFERENCE DRAWINGS						
REVISIONS						

P:\301-00204\13\A\DRWINGS\VP\F\For Tender\301-00204-13-100-104 RevB.C.dwg

DESIGNATION	NAME	REGISTRATION No:	SIGNATURE	DATE
DRAWN	FB			20.11.2018
CHECKED	TM			20.11.2018
SENIOR DESIGNER	MET PROJECTS			
PR ENGINEER				
PR TECH				
PROJECT / MET ENGINEER	TM			20.11.2018
MET PROJECTS MANAGER	NAME			20.11.2018

ANGOLD ASHANTI
COPYRIGHT

301-00204/13-101

REGION SOUTH AFRICA REGION - VR

BUSINESS UNIT MINE WASTE SOLUTIONS

PROJECT KAREERAND TSF EXPANSION PROJECT

DRAWING TITLE TSF STARTER WALL - SECTIONS

MET PROJECTS

CWR1806001

MET-MWS-39-C0010

REV D