



# **BEESHOEK**

# **WASTE ROCK DUMP REVIEW**

# **SUMMARY REPORT**

Document Version: Draft1

Customer Name: Beeshoek Mine
Date: 18 December 2020
Prepared by: A.F von Wielligh

Document No: BHAO \_181220\_1

#### Consent, Copyright and Liability

This review report has been compiled by Mr A.F von Wielligh for the exclusive use of ABGM Australia PTY LTD (ABGM), Beeshoek Mine and is not intended for use by any other party. Neither the whole, part, or abstract of this report, including any reference hereto, may be included in any other document without the prior written consent of ABGM. Copyright of any text or other matter in this document, including presentation, is the exclusive property of ABGM. NB: It is an offence to publish this document, or any part or abstract of the document, either under a different cover, or to reproduce or duplicate and/or use, without the written consent of ABGM, any procedure/technique contained herein. The intellectual property within the contents of this document resides with ABGM and shall not be used for any purpose without the involvement of ABGM, or without the written consent of ABGM. All rights are reserved and without prejudice. ABGM only completed a review on the waste rock dump designs and therefore rely completely on the validity and accuracy of the geotechnical review completed on these waste rock dump designs.

#### Disclaimer

This Report has been prepared for Beeshoek Mine by ABGM PTY LTD based on assumptions as identified throughout the text and upon information and data supplied by Beeshoek Mine and external references as required by Beeshoek Mine. The Report is to be read in the context of the methodology, procedures and techniques used, ABGM's assumptions, and the circumstances and constraints under which the Report was written. The Report is to be read as a whole, and sections or parts thereof should therefore not be read or relied upon out of context. ABGM has, in preparing the Report, followed methodology and procedures, and exercised due care consistent with the intended level of accuracy, using its professional judgment and reasonable care. However, no warranty should be implied as to the accuracy of estimates or other values and all estimates and other values are only valid as at the date of the Report and will vary thereafter. Baseline information and data has been supplied by Beeshoek Mine and other third-party contributors, as detailed in the document annexures. While the information and data has been generally reviewed by ABGM for inclusion/consideration, they have not been fully audited or sought to be verified by ABGM as this was not the agreed scope of work. ABGM is not able to, and does not, verify the accuracy or completeness of, or adopt as its own, the information and data supplied by others and disclaims all liability, damages or loss with respect to such information and data. In respect of all parts of the Report, no express or implied representation or warranty is made by ABGM or by any person acting for and/or on behalf of ABGM to any third party that the contents of the Report are verified, accurate, suitably qualified, reasonable or free from errors, omissions or other defects of any kind or nature. Third parties who rely upon the Report do so at their own risk and ABGM disclaims all liability, damages or loss with respect to such reliance. ABGM disclaims any liability, damage and loss to Beeshoek Mine and to third parties in respect of the publication, reference, quoting or distribution of the Report or any of its contents to and reliance thereon by any third party. This disclaimer must accompany every copy of this Report, which is an integral document and must be read in its entirety.

# **List of Report Abbreviations and Definitions**

### **Abbreviations:**

ABGM : ABGM PTY LTD (Consultant)

MSO : Mineable Shape Optimiser (Software)

LOM : Life-of-Mine

QA/QC : Quality Assurance/Quality Control

NPV : Net Present Value

Ogl : Original ground level

ROM : Run-of-Mine (Mined Ore)

SR : Stripping Ratio

Fe In-Situ : In-situ Resource metal grade (Fe)

Fe ROM : Mining grade/Mill Feed Grade

NPV Scheduler : Mine Scheduling and optimisation software

Whittle : Mine Optimisation Software

Datamine Studio : Geological and Mine planning Software

PEA : Preliminary Economic Assessment – study

PFS : Preliminary feasibility study

DFS : Definitive feasibility study

SAMREC : South African Mineral Reporting Codes

RoM : Run of Mine (modified ore mined and processed)

#### **Definitions:**

Ramp : Access road within an open pit

Bench : Height of mining ground between safety berms

Berm : Catchment area to be left intact for safety and stability

Flitch : Interim mining cut or sub-mining bench

Batter angle : Bench angle or mining face angle

High Level : Less detailed –desktop study level of accuracy

# **TABLE OF CONTENTS**

 Summary of Review
 5

 1.1 General
 5

 1.2 Data and parameters considered
 5

1.3 Key criteria for WRD	5
1.4 Waste Rock Dump Designs Reviewed	6
1.5 Geotechnical Review of the WRD designs	2
1.5.1 General	
1.5.2 Geotechnical Summary	3
2. Summary of Conclusions	4
3. Annexure A	6
TABLE OF FIGURES	
Figure 1-1: GF and HF Waste Rock Dump (WRD) Designs - Plan view	
Figure 1-2: GF Dump North-South Section view (Profile)	
Figure 1-3: GF Dump East-West Section Profile	
Figure 1-4: GF Waste Rock Dump Design Criteria	
Figure 1-5: HF WRD Dump North-South Section Profile	8
Figure 1-6: HF WRD East-West Section Profile	
Figure 1-7: HF WRD Design Criteria	8
Figure 1-8: Village WRD South Design	
Figure 1-9: Village WRD South Design Criteria	
Figure 1-10: Village WRD North Designs	10
Figure 1-11: Village WRD North Design Criteria	10
Figure 1-12: East Pit WRD design	
Figure 1-13: East Dump (Section Profiles)	
LIST OF TABLES	
Table 1-1: WRD Factors of Safety (FoS)	13

## 1. Summary of Review

#### 1.1 General

ABGM PTY LTD - Australia (ABGM) are involved in all the planning activities (medium- and long-range planning) for Beeshoek Mine's deposits. This report is a brief summary of a review completed for the Waste Rock Dump (WRD). designs of Beeshoek mine.

## 1.2 Data and parameters considered

Beeshoek mine supplied all the topography data, mined survey files and a series of WRD designs completed. The purpose of this report is to review all the supplied data and also obtain a geotechnical analysis of these rock dump designs to finally conclude on the appropriateness of the WRD designs. The following data was received:

- All the topography data as at end of June 2020;
- An updated geotechnical report "Assmang Beeshoek, Waste Rock Dump Design validation" compiled by Mr. Franz Bruwer of Middindi Consulting PTY LTD;
- All the existing topography data including WRD as they are at end of June 2020;
- 3D DXF solids files of each WRD design.

The data was generally assumed to be in good order. ABGM do however strongly recommend that where new dumps are being placed or where existing WRDs are extended or enlarged, that the Asset Optimization study be reviewed as some of the older open pit areas (thought to have been depleted) do come back into profitable mine plans with export iron ore price assumptions.

ABGM furthermore strongly recommend that where WRD are to be placed over un-mined ground, that these areas be explored to ensure there are no potential future resources that might be covered and therefore possibly rendered sub-economical with any new WRD or extensions of WRD designs.

#### 1.3 Key criteria for WRD

The key criteria when developing WRD designs are typically:

- Angle of rock repose (WRD bench face angle modelled). A good guide for WRD
  designs is 34 to 36 degrees but could vary depending on the type of waste rock
  material being dumped and the soil/WRD floor stability but also based on the
  potential risk factors associated with the location of the WRD;
- Large WRD lift heights generally 15m to 20m lift heights but where topography
  is undulating life heights might be as high as 20m to 30m. A good standard would
  be approximately 20m lift heights to minimise the potential failure consequence
  and volume of failure;
- Overall WRD slope is another important design consideration and should also consider the WRD rehabilitation which are mostly dozing, profiling soiling and seeding. If the overall slope is steep it will require a lot more effort and cost to rehabilitate the WRD.

### 1.4 Waste Rock Dump Designs Reviewed

The WRD's consists of a mixture of material as a result of the various lithology's that make up the waste material at Beeshoek. Based on historic drilling conducted at the mine, the rock mass is made up of the following geological units:

- Overburden;
- Calcrete;
- Paling Shale;
- Quartzites;
- Sishen Shales;
- Banded Iron Stone;
- Manganese;
- Chert Breccia;
- Dolomite.

The following WRD designs were reviewed:

- GF Dump;
- HF Dump;
- East Pit Dump;
- Village Pit Dump South;
- Village Pit Dump North.




Figure 1-1: GF and HF Waste Rock Dump (WRD) Designs - Plan view




Figure 1-2: GF Dump North-South Section view (Profile)




Figure 1-3: GF Dump East-West Section Profile




Figure 1-4: GF Waste Rock Dump Design Criteria

The GF WRD is a large rock dump and have a maximum height of approximately 81.5m. The design criteria are in-line with typical WRD designs and the angle of repose seems very reasonable. The average total slope of the WRD design angle is approximately 24.5 degrees, with bench angles (repose) of approximately 33.7 degrees.

Beeshoek Mine - Waste Rock Dump (WRD) Design Review

Page **7** of **16** 




Figure 1-5: HF WRD Dump North-South Section Profile




Figure 1-6: HF WRD East-West Section Profile

The HF WRD have a maximum height of approximately 40m with the average dump height of approximately 38.37m. The design criteria are in-line with typical WRD design criteria and the angle of repose seems very reasonable. The average total slope angle is approximately 26.8 degrees, with bench angles (repose) of approximately 34.5 degrees. There seems to be potential for more waste to be placed on another lift on this WRD and the berm width and top lift face angle could be optimised to add more rock onto this dump if needed.




Figure 1-7: HF WRD Design Criteria

Beeshoek Mine - Waste Rock Dump (WRD) Design Review

Page **8** of **16** 




Figure 1-8: Village WRD South Design




Figure 1-9: Village WRD South Design Criteria

Village WRD South design criteria are very reasonable and within the expected design criteria for rock dumps.




Figure 1-10: Village WRD North Designs



Figure 1-11: Village WRD North Design Criteria

The Village WRD North design are also deemed reasonable and within the expected WRD design criteria. The Village North and South WRD's have a maximum height of approximately 110.82m and 97.6m respectively. The design criteria are in-line with typical WRD designs and the angle of repose seems very reasonable. The average total slope on design angle is approximately 26.2 and 26.5 degrees for Village North and Village South WRD respectively. The average bench angles (repose) of approximately 34.8 and 35.4 degrees for Village North and South WRD, respectively.




Figure 1-12: East Pit WRD design




Figure 1-13: East Dump (Section Profiles)

East dump also abides by reasonable WRD design criteria. The East Pit WRD design is deemed reasonable and within the expected WRD design criteria. The East Pit WRD have a maximum height of approximately 93.52m. The design criteria are in-line with typical WRD design and the angle of repose seems very reasonable. The average total design slope angle is approximately 20.4 degrees, with bench angles (repose) of approximately 35.0 degrees.

Waste Rock Dump	Elevati on Min	Elevati on Max	Max Thickn ess / Height (m)	Ben ch Wid th	Approximate Average Bench / Repose On Design Angle	Approximate Total Rehabilitated Slope Angle	Approximate Average Total Slope On Design Angle
EP	-525.5	-432	93.5		35.0	-	20.4
EP-Rehab	-526.3	-432	94.4		-	17.9	-
GF	-469.3	-389	80.3		33.7	-	24.5
GF-Rehab	-469.3	-389	80.3		-	18.0	-
HF	-470.3	-432	40.0		34.5	-	26.8
HF-Rehab	-494.6	-432	62.6		-	18.0	-
VP North	-525.7	-414.9	110.8		34.8	-	26.2
VP North-Rehab	-525.1	-454.9	70.2		-	17.8	-
VP South	-524.6	-427	97.6		35.4	-	26.5
VP South-Rehab	-532.5	-427	105.5		-	17.9	-

All WRD's indicated and analysed above for Beehsoek Mine Pty Ltd, will consider the methods and measures necessary to be applied at the appropriate time when rehabilitation is started on each of the WRD's to ensure water runoff is optimally managed.

The WRD designs and WRD dump rehabilitation design plans for each of the WRD's is included in Annexure A. The designs include the below information for each:

- Footprints of the designs, pre-rehabilitation and post -rehabilitation;
- Overlay of WRD designs;
- Overlay of WRD rehabilitation designs;
- Sections of the designs, pre-rehabilitation and post –rehabilitation;
- Overlay of WRD designs including contours for water run-off management;
- Overlay of WRD rehabilitation designs including contours for water run-off management.

#### 1.5 Geotechnical Review of the WRD designs

Middindi Consulting PTY LTD completed a Waste Rock Dump Design review (geotechnical review) of the main five (5) WRD designs of Beeshoek mine. The following sub-sections and paragraphs are directly referring to the Middindi report ("Assmang — Beeshoek, Waste Rock Dump Design validation" compiled by Mr. Franz Bruwer of Middindi Consulting PTY LTD").

#### 1.5.1 General

The WRD's at Beeshoek was designed using industry guidelines, however, was never validated by a Mining Geotechnical Engineer. The purpose of this study is to individually assess the stability of the five dumps using numerical analysis, to subsequently determine

whether the designs will ensure long-term stability. The WRD's are located on both North and South Mine and consist of the following:

- East Pit Dump;
- GF Dump;
- HF Dump;
- Village Pit South Dump;
- Village Pit North Dump.

### 1.5.2 Geotechnical Summary

The analysis indicated that the five WRD's at Beeshoek are well within the required limits for long term stability. To reduce the need for assumptions and ensure a high level of confidence in the analysis, conservative material parameters were selected for the models. The minimum safety factor required for long-term stability is 1.3, as taken from the work conducted by Stacey (2009). The safety factors obtained for each of the sections taken along the dumps are summarised below. The following table

Waste Rock Dump	Safety Factor (Section along ramp)	Safety Factor (Section away from ramp)
East Pit Dump	1.769	1.702
GF Dump	1.385	1.517
HF Dump	2.971	1.500
Village Pit Dump 1	1.741	1.448
Village Pit Dump 2	2.026	1.530

Table 1-1: WRD Factors of Safety (FoS)

## 2. Summary of Conclusions

The pertinent review summaries are:

- The WRD designs all proved to be reasonable and within the typical design criteria that would be deemed industry standard;
- The WRD designs were also completed to a reasonable design standard (for WRD designs);
- It is important to review the WRD designs and the actual resultant WRD lifts as deviations in high lifts might pose risks;
- ABGM would strongly advocate the Beeshoek have continuous WRD rock movement monitoring and observations;
- Beeshoek is in the process of optimising all of the Mineral Assets and it is conceivable that there might be the requirement to either move small parts of the WRD or possible adjust the designs somewhat to cater for possible open pit design expansions.

This report has been compiled by Mr. Anton von Wielligh (PR. ENG ECSA, Fellow – AUSIMM and Member of the SAIMM).

Anton von Wielligh A. von Wielligh	
Signature Signature	_
23 January 2021	
Date	_

