


Door frame : repair and make good all imperfections to timber door frame to receive new hardwood door
 Door:
 - replace missing door with Swartland winsters entrance traditional panel back door, code - PD8,
 - ironmongery as per spec.

FLOOR FINISH	• Floors: ex. timber floors to be sanded & made good to receive new floor finish as per specifications - 29.74m ²
WALL FINISH	• Existing plaster & paint: - Walls to be scraped, treated, fill all imperfections. - Walls to receive new finish as per specifications
DOOR	• Timber door frames to be inspected for wood rot and water damage. door frames to be repaired with salvaged and made good to match ex. Doors: Refer to door detail

 P.O.BOX 37188 OVERPORT DURBAN 4067 TELE : 2097245/6 FAX : 2097247 E-MAIL : seedat@ion.co.za AHMED.SEEDAT-ARCHITECT REG no :3140(S.A.C.A.P)	ROOM NAME - PROJECT: NATAL COMMAND -DILAPIDATION REPORT	SCALE: 1/50	DRWG.No: 21126
	DRAWING TITLE: ROOM AND OFFICE DATA SHEETS	DATE: DEC 2022	PAGE.No: 1