

This Chapter provides an overview of the proposed Solaire Direct Graspan Photovoltaic (PV) Power Facility. Project activities and requirements for the construction, operation and decommissioning of the PV power facility are discussed in this section, as well as the motivation for the project and the alternatives considered.

4.1

MOTIVATION

Global dependence on fossil fuels, rising fossil fuel prices and concern regarding the impacts of climate change has resulted in increasing international pressure on countries around the world to increase their share of energy derived from renewable sources. Targets for the promotion of renewable energy now exist in more than 58 countries around the world and solar energy is emerging as an important component of the energy market in a number of countries.

The South African government has developed a policy framework (the White Paper on Renewable Energy) and set a target of sourcing 10,000 GWh from renewable energy projects by 2013. This amounts to approximately 4 percent of South Africa's total estimated energy demand by 2013. At the Copenhagen Conference in December 2009, South Africa's president also set a target for the reduction of CO₂ emissions, as laid out in the Integrated Resource Plan (IRP 2010), which sets a target reduction of CO₂ emissions by 34 percent by 2020. The utilisation of renewable energy will play a major role in achieving this goal. South Africa's commitment to achieving this goal was reiterated by Minister Edna Molewa at the December 2010 Climate Change Conference in Cancun, Mexico. At present, South Africa generates approximately 77 percent of the power consumed from coal and as a country, South Africa is among the largest emitters of CO₂ globally.

The potential for the Northern Cape to become a key area for the generation of electricity through solar energy is recognized by the Northern Cape Provincial Government. The Premier of the Northern Cape, Ms H. Jenkins, has stated to delegates of the Northern Cape Climate Change and Green Jobs Summit in Upington on 14 April 2011, '*The Northern Cape has been identified as one of the provinces best suited and strategically poised for a number of solar and wind renewable energy projects. These projects will be responsible for creating a number of green jobs in the province and will also be contributing to the clean energy that will be put on to the electricity grid. These projects will also contribute in reducing South Africa's green house gas emissions at a national level.*'

In addition, PV power facilities are more effective where there is a high level of solar radiation. South Africa and more specifically the Northern Cape Province experiences some of the highest levels of solar radiation in the world.

As such, the development of renewable energy projects such as this presents an opportunity for contributing to sustainable development and growth of the province and the country at large.


The intentions of Solaire Direct in establishing a PV power facility include reducing South Africa's dependence on non-renewable fossil fuel resources, contributing towards the targets and goals the South African government has set out, and contributing to climate change mitigation.

The Renewable Energy Independent Power Procurement Programme (IPP Procurement Programme) has been designed for the following reasons:

- To allow the private sector to contribute to the generation of renewable energy (and the target set by government);
- To contribute towards socio-economic and environmentally sustainable growth; and
- To enhance the renewable energy sector in South Africa.

Applicants are allowed to submit a proposal for the finance, construction, operation and maintenance of renewable energy facilities. *Figure 4.1* illustrates the total new additional energy capacity needed by 2030, and the different sources of this additional energy.

Figure 4.1 Cabinet Approved Energy Contribution for South Africa from 2010 to 2030



Source: Department of Energy, March 2011.

The cumulative impact of this 90 MW development as well as the numerous other proposed solar power facilities in the area may prove significant.

Beyond the positive climate impact, however, solar energy is very well placed to rapidly be implemented and contribute to alleviating the power gap in South Africa. Emergency load shedding in South Africa during 2007 and 2008 highlighted the challenges facing South Africa in terms of electricity generation, transmission and distribution. The National Energy Response Plan (NERP), drafted at the time, acknowledged the role that independent power producers (IPPs) (including those harnessing renewable energy resources) can play in ensuring sustainable electricity generation, and sets a goal that 30 percent of all new power generation will be derived from IPPs.

The development of solar energy in the Northern Cape offers the opportunity for a new industry in the province. Existing levels of employment are low within the province and wider site locality. Employment is considered to be the single biggest opportunity outside of the advantages expressed above, associated with the project. Training provided to employees will provide individuals with a skill set that will be highly desirable throughout the industry sector in South Africa as the renewable energy industry and

specifically the solar energy sector rapidly develops, increasing potential opportunities available to such individuals.

4.2

PROJECT LOCATION AND EXISTING LAND USE

The proposed PV power facility is located on the remaining extent of Farm Graspan (No. 172), situated in the Siyancuma Local Municipality in the Northern Cape (see *Figure 4.2*). The site is located approximately 40 km north-east of Hopetown and is accessible from the N12 (tarred road).

The site is designated for agricultural use, with current agricultural practices including sheep and cattle farming. Land use in the surrounding area includes further stock farming, cultivation approximately 15 km to the east and 30 km to the northeast of the site, and various salt works within a 15 km radius of the site.

There is an existing railway line traversing the site in a northeast-southwest direction. An existing gravel road network exists on the site, which crosses the railway line. The existing 132 kV Graspan Traction Substation is located within the northern section of the site, and an existing 132 kV power line traverses the site from the Graspan Traction Substation in a north-south direction, exiting the southern boundary of the site.

Legend

- Graspan Photovoltaic (PV) Power Facility
- Windpump
- Contours
- Rivers
- Cadastral Farms
- Power Line
- Main Roads
- Secondary Roads
- Other Roads
- Track and Hiking Trail
- Railway
- Water Bodies
- Non-Perennial Water

Figure 4.2: Location of Graspan PV Power Facility on the Topographical Map


CLIENT: **solairedirect**
Southern Africa
The solar MWh company

DATE: July 2012	CHECKED: DA	PROJECT: 0156408
DRAWN: AB	APPROVED: SHC	SCALE: 1:30 000
DRAWING:		REV: 0
Graspan EIR Topo Map.mxd		

ERM
Block A, Silverwood House
Silverwood Close
Steenberg Office Park, 7945
Cape Town, SOUTH AFRICA
Tel: +27 (0)21 705 9100
Fax: +27 (0)21 701 7900

Projection: Geographic: WGS84
2824 AD, 2805, E83, 25011 F
Inset Map: East Data & Maps

SIZE: A3



Solar energy systems produce energy by converting solar irradiation into electricity or heat. For the proposed PV power facility, Solaire Direct will utilise photovoltaic (PV) technology to generate electricity. PV technology consists of the following components:

- **PV cell**; a basic photovoltaic device, which generates electricity when exposed to solar radiation. The absorbed solar energy excites electrons inside the cells and produces electrical energy. The PV cells are commonly constructed from polycrystalline silicon. All photovoltaic cells produce direct current (DC).
- **PV module or panel**; the smallest complete assembly of interconnected photovoltaic cells. In the case of crystalline silicon cells, following testing and sorting to match the current and voltage, the cells are interconnected and encapsulated between a transparent front (usually glass) and a backing material. The module is then typically mounted in an aluminium frame.
- **PV array**; a mechanically integrated assembly of modules and panels together with support structures to form a direct current power producing unit. The proposed PV power facility will consist of antireflective modules arranged in numerous arrays. The feeding of electricity into the grid requires the transformation of DC from the PV array into alternating current (AC) by means of an inverter.

It is anticipated that the project will feed a total of 90 MW into the national grid. The key components of the proposed PV power plant are discussed in detail below:

- PV solar panels/modules (arranged in arrays);
- PV module mountings;
- DC-AC current inverters and transformers;
- New grid connection substation;
- Underground cabling/ overhead power lines;
- On-site buildings (including an operational control centre, office, ablutions and a guard house);
- Access roads and internal road network; and
- Ancillary infrastructure.

4.4.1

PV Arrays and Mountings

The proposed development will include PV panels that will occupy approximately 150 ha (1.5 km²) of the site area in total. The footprint of PV arrays will be approximately 127 ha. The PV panels will be 1975 mm in length, 990 mm in width and 50 mm in height with each producing an output of 300 W. Each PV panel will weigh approximately 26 kg. Within each PV panel there will be 60 polycrystalline cells (each 156 mm x 156 mm). These polycrystalline cells will be encapsulated in Ethylene Vinyl Acetate (EVA). The front substrate of the PV panel will be 3.2 mm of antireflection glass, while the back substrate will be Tedlar or APA composite sheeting. Each PV panel will be placed in a black or raw anodized aluminium frame 45 mm in width and equipped with drainage holes. PV panels will be connected in arrays to form units with a total power of 1 MW each (around 264000 PV panels will be installed on a 90 MW project). See *Annex F* for further technical specifications of the PV panels.

The PV panels will be mounted on aluminium fixed-frame structures approximately 3.33 m in height from the ground (see *Figure 4.3*). The aluminium structures will be mounted on steel screw piles or concrete foundations 1500 mm deep, depending on soil conditions. The distance or spacing between rows will be approximately 6.2 m. The PV arrays will face north in order to capture maximum sunlight. *Figure 4.4* shows a typical array of PV panels.

Figure 4.3 Typical Anodized Aluminium Frame



Source: Solaire Direct, 2012

Figure 4.4 Typical PV Array



4.4.2 Electrical Connections and Controls


The PV panel arrays will be connected via underground cables (800 mm depth) to array enclosures (see *Figure 4.5* and *Figure 4.6*). Array enclosures combine the power generated by multiple PV panels and transmit that power via two underground DC cables (the array enclosures will be mounted underneath the PV module mounting structures and each array enclosure will occupy an area of approximately 1 m²) to an inverter/transformer enclosure.

Figure 4.5 Typical Array Enclosure



Source: Solaire Direct, 2012

Figure 4.6 Array Enclosure Components



Source: Solaire Direct, 2012

The inverter/transformer enclosures convert the direct current (DC) produced by the PV panels to alternating current (AC) (see Figure 4.7). The inverter/transformer enclosures also contain transformers that transform low voltage AC (350 V) from the inverter to medium voltage AC (22 kV). The rated power of each central inverter is 630 kW at peak output. Two central

inverters, along with an Low Voltage AC to Medium Voltage AC step-up transformer is placed inside a pre-fabricated concrete container. The container size is approximately 7m x 3m x 3.5m (length x width x height). Between 57 and 60 inverter/transformer enclosures will be required. The inverter/transformer enclosures will connect via underground cabling (depth 800 mm) to a new grid connection substation of approximately 400 m². The new grid connection substation will be a brick building containing medium voltage (22 kV) circuit breakers that will combine the power generated by each inverter/transformer enclosure. This combined power will then be transformed from Medium Voltage (22 kV) up to High Voltage (132 kV) for connection to the existing Eskom Graspan Traction Substation by power transformers. The power transformer units will be two 40 MW power transformers or three 25 MW power transformers. The power transformers and associated protection equipment (circuit breakers, etc) will be installed in the new grid connection substation yard, constructed to Eskom specifications (see *Figure 4.8* and *Figure 4.9*).

Figure 4.7 *Typical Inverter/Transformer Enclosures*



Source: Solaire Direct, 2012

Figure 4.8 Power Transformer



Source: Solaire Direct, 2012

Figure 4.9 *Transformer in Grid Connection Substation Yard*



Source: Solaire Direct, 2012

4.4.3 *Grid Connection*

The 132 kV power from the new grid connection substation will be connected to the existing Eskom Graspan Traction Substation, located in the northern part of the site on the east side of the railway line, by two overhead power lines of approximately 800 m in length (see *Figure 4.10*). Both power lines will be installed on the same steel lattice structure, according to Eskom specifications.

Figure 4.10 Existing Graspan Traction Substation



4.4.4 Auxiliary Electrical Equipment

The following additional electrical equipment will be required for the project:

- A 200 kVA (10 MW) diesel generator will supply power to security and monitoring systems in the event of a grid failure;
- Security system, electrical fence and 24 hour on-site security access control;
- Fire detection system;
- Weather monitoring equipment (rainfall, wind speed/direction, solar irradiation, air moisture) will be located inside the guard house;
- PV power facility monitoring equipment and associated telecommunication links will be located inside the guard house; and
- Airconditioning equipment inside inverter/transformer enclosures which will regulate the operating temperature of the inverters.

4.4.5 Access Roads and Internal Paths

The site will be accessed from the N12 national road at the existing site entrance (29°20'42.59" S 24°24'51.66" E). An existing gravel road will be upgraded to approximately 6 m in width and used to cross the western portion of the site to the railway line. The railway line crossing will be

upgraded to decrease the slope to between 26-45 degrees and 5 m width on either side of the railway line. The existing gravel road on the east side of the railway line running north will be used and upgraded to approximately 6 m in width in order to reach the PV power facility's direct footprint. Internal paths will be created to enable access within the PV power facility.

Within the PV arrays, a minimum spacing of 6.2 m is required between each row to avoid shadowing of the panels by adjacent rows. These spaces will not be gravelled or paved. PV power facility maintenance will consist mainly of PV panel replacement, PV panel cleaning and other minor mechanical and electrical infrastructure repairs. Access will be needed primarily for light service vehicles entering the site for maintenance, inspection and PV panel cleaning purposes. During the operational phase, traffic impacts will be reduced, with vehicles only required to transport infrastructure during routine maintenance and upgrading phases.

4.4.6 Additional Infrastructure

Additional infrastructure that will be required for the project includes the following:

- site perimeter fencing (electrical palisade fencing of approximately 2.8 m in height) including access gates;
- lighting at the main entrance only;
- temporary construction camp of approximately 4,800 m² (to house 35 personnel);
 - an office for project supervision;
 - a meeting room;
 - an office for the caretaker of the site;
 - two cloakrooms;
 - two chemical toilets, as there is no water on the site; and
 - a lay-down area for the temporary storage of materials during the construction activities of approximately 4,800 m².

At this stage it is unknown and unlikely if a borrow pit for rock or soil material will be required for the construction of project infrastructure. A temporary soil stockpile of approximately 6,000 m² will be required.

4.5 TRANSPORT, EQUIPMENT AND MACHINERY REQUIREMENTS

During the construction phase, it is expected that potential traffic impacts will be higher than normal as trucks will be required to transport materials and equipment (PV panels, frames, etc) to the site. Infrastructure required for the proposed PV power facility, including support structures, PV modules, frames, as well as machinery will be transported to and from the site from various locations in the region.

It is anticipated that the following number of trips would be required:

- Delivery of panels: 200 loads consisting of 18.9 tons each on 12 m long trailers.
- Delivery of electrical equipment and components: 28 loads of 20 tons each.
- Delivery of frames: 21 loads of 20 tons each.
- Earthworks: potentially 1400 loads of 10 m³ each to the identified Local Authority Landfill Site.

During the operational phase, it is expected that potential traffic impacts will be reduced, with vehicles only required to transport infrastructure during routine maintenance and upgrading phases.

4.6

WATER REQUIREMENTS

During the construction phase the primary water use requirement will be for dust control. However, water may also be required to moisture condition the soils for proper compaction at roads and foundations. It is estimated that for dust control and compaction, approximately 4,800,000 litres of water will be required (an average of three truck loads per day for the first 60 days of construction and one truck load per day for the following 60 days of construction, with each truck carrying approximately 20,000 litres). Water will also be required for the concrete mixing for the foundations. It is estimated that 575,586 litres of water will be required for the concrete foundations (with a total of 209 litres/m³ x 2,754 m³). The estimated construction-related water requirement is 5.4 million litres with a daily usage of 60,000 kilolitres. Temporary ablution facilities will be required during construction. Water requirements for the construction phase of the PV power facility will be supplied by the Local Water Users' Association. Alternatively, additional water will be provided via a rainwater tank.

During the operational phase it is estimated that PV panel cleaning will require a total of approximately 100,000 litres/year (10,000 litres/MW/year). The PV panels will be cleaned manually with a window washer type device (covered with a specialized cloth material), soft brush, window squeegee or soft cloth. A composting toilet will be installed in the guard house requiring no water. During the operational phase drinking water and process water will also be supplied by existing boreholes and may require treatment for domestic use.

During the operational phase, it is the intention of Solaire Direct to source the required water from an existing reticulation system, either from the local municipality or the landowner. If this is not feasible, alternative options

would be to tanker in the required water and / or amend the existing landowner's water use license to include the activity of the required water use.

During decommissioning and site restoration, dust control will be required, and it is anticipated that similar volumes of water as the construction phase will be required. Similar temporary ablution facilities as in the construction phase will be required during the decommissioning phase.

4.7 *WASTE MANAGEMENT*

All project generated wastes will need to be managed and disposed of in a manner to prevent potential impacts on the environment and risks to human health. A Waste Management Plan (WMP) for the proposed project will be developed. This will follow the principles of waste minimisation at source, segregation for reuse, recycling, treatment or disposal.

All wastes produced from the project activities on site will be temporarily stored in designated waste storage areas. Waste streams will be generated from logistical activities associated with project activities and accommodating personnel.

4.7.1 *Waste Types and Quantities Generated*

All wastes generated from the project will be categorised as either *non-hazardous* or *hazardous* following an assessment of the hazard potentials of the material in line with South African requirements. The main sources of waste will result from the temporary construction camp and construction and decommissioning activities. One of the main sources of non-hazardous wastes will be the domestic type solid waste from the approximately 35 personnel at the temporary construction camp. These wastes will be produced daily and comprise of the following:

- Domestic type waste, such as mixed waste from kitchens/canteen or living quarters;
 - residual packaging and food wastes
 - metal cans (from food and drinks)
 - plastics drinks bottles
 - glass jars and bottles
- Wooden pallets and cartons;
- Scrap metal;
- Concrete waste;
- Paper and cardboard;
- Grey water - from ablutions; and
- Food wastes.

The following hazardous wastes will also be produced from construction activities.

- Batteries (including large lead acid type);
- Medical/clinical wastes - from camp clinic;
- Oily rags and absorbents;
- Used oil and oil filters - from generators or vehicle maintenance;
- Contaminated water - slops and oily water from drip trays; and
- Sewage from toilets.

All wastes produced from project activities on site will be transferred to designated temporary storage areas and where possible into secure containers. Solid wastes will be segregated to facilitate reuse and recycling of specific materials. All wastes that cannot be reused or recycled will be collected by approved waste contractors and transferred to an appropriately licensed waste management facility for treatment and disposal.

4.7.2 Hazardous Materials and Hazardous Wastes

The construction and decommissioning phases will require the use of hazardous materials such as fuels and greases to fuel equipment and vehicles and maintain equipment. These substances will be stored on-site in temporary aboveground storage tanks. Fuels on site will be stored in a locked container within a fenced and secure temporary staging area. Trucks and construction vehicles will be serviced off-site. The use, storage, transport and disposal of hazardous materials used for the project will be carried out in accordance with all applicable South African regulations. Material Safety Data Sheets for all applicable materials present on site will be readily available to on-site personnel. It is proposed that the construction contracting company supply the required temporary ablution facilities and be responsible for the removal and treatment thereof. Solaire Direct will be responsible to ensure that the contracting company is accredited and has the necessary permits to remove the sewage. The sewage will be treated in accordance with the municipal sewage works policies and guidelines.

Operations and maintenance of the PV power plant is not expected to require hazardous materials to be present and used on site or to generate hazardous waste. PV panels, array enclosures and inverter/transformer enclosures will not produce waste during operation.

The composting toilet to be used in the guardhouse makes use of an aerobic process to treat human waste material. The composting toilet requires no water and produces compost-like, odourless, dehydrated material that could be either disposed of via municipal waste services or be used in the production of compost.

4.7.3

Non-hazardous Wastes

Construction waste will most likely consist of concrete (if concrete foundations are utilised to support mounting structures) and scrap metal. All concrete mixing be undertaken on impermeable plastic lining to prevent contamination of the soils and surrounding areas. Construction solid waste will be managed by a Construction Environmental Management Plan (EMP) and will incorporate reduction, recycling and re-use principles.

All waste that cannot be reused or recycled will be appropriately disposed of. All construction debris will be placed in appropriate on-site storage containers and periodically disposed of by a licensed waste contractor in accordance with applicable South African regulations. The construction contractor will remove refuse collected from the designated waste storage areas at the site at least once a week. All rubble generated during the construction phase will be removed from the site regularly to a licensed landfill site. It is estimated that approximately 222 m³ of construction debris will be produced per month, while it is estimated that approximately 0.2 m³ of solid waste will be generated during the operational phase.

4.8

SOCIO-ECONOMIC ASPECTS

The total investment cost of the project is estimated to be approximately R1,350 million.

During the construction phase, the following employment opportunities will be created:

- Site management: 25 employees
- Civil works: 54 employees
- Frames & foundations: 27 employees
- PV modules: 125 employees
- Electrical system & components: 60 employees

Of the PV power facility's employees during construction, approximately 174 employees are estimated to be skilled.

During the operation phase, the PV power facility is expected to create the following opportunities:

- General administration & maintenance: 30 employees
- Compliance related activities: 3 employees
- Performance monitoring of the PV power facility: 2 employees
- Security: 24 employees

Of the PV power facility's employees during operation, 21 employees are estimated to be skilled.

Certain aspects of the project will provide better opportunities for local employment and economic development than others. The conditions of contract between Solaire Direct and the subcontractor will include requirements for local Enterprise Development addressing the following identified opportunities:

- Electrical system: there will be a requirement for the electrical contractor to make use of local electrical companies for certain elements of the installation of the electrical system. The requirement will be for a minimum of 5 percent of the subcontract value to be spent on local enterprises.
- Security: there will be a contractual requirement for the security service contractor to subcontract the provision of local security staff to a local company. If such a company does not exist, then the requirement will be for the security service contractor to establish such a subcontractor. The requirement will be for a minimum of 25 percent of the subcontract value to be spent on local enterprises.

The labour contract between Solaire Direct and contractors who are appointed to provide services during the construction phase of the development will specify local labour employment criteria, e.g. percentage of total workforce.

Expected value of the employment opportunities during the construction phase is estimated to be 5 % of the total investment cost of the project, ie R 67.5 million, of which local labour is expected to receive 75 percent (approximately R 50 million). This estimate excludes the value of manufacturing labour costs.

Numerous local employment opportunities will be created in the manufacturing process of the PV panels, steel frames, etc. During the operation phase, the PV power plant is expected to generate approximately 24 security and 35 operation and maintenance employment opportunities (totalling an estimated R 59 million during the first 10 years (excluding construction). On-going reporting to the PSC regarding these specifics is required.

All financial returns will accrue to beneficiaries, including equity partners, according to Solaire Direct's company structure. Solaire Direct intends to contribute a portion of the gross profit (before tax and depending on the project stage) to a local community trust that has been set up specifically for this project. The value of this contribution will be determined on finalisation of the tariff as part of the Power Purchase Agreement (PPA).

4.9

PROJECT STAGES AND ACTIVITIES

The project life-cycle can be divided into three key stages as follows:

- site preparation and construction;

- operation (including maintenance and repair); and
- decommissioning.

Each of these stages is outlined in the sections below.

4.9.1 *Site Preparation and Construction*

Prior to construction of the PV power plant, the site would be prepared. The 150 ha site is generally flat. Site preparation would include the following activities:

- vegetation clearance – removal or cutting of any tall vegetation if present (bush cutting);
- levelling and grading of areas where the array will be sited, to remove steep slopes and undulations normally occurring, but this is not deemed necessary given the flat nature of the terrain on the site ;
- levelling of hard-standing areas, e.g. for temporary laydown and storage areas;
- erection of site fencing;
- construction of a temporary construction camp; and
- upgrading of farm tracks/ construction of on-site access roads.

Once the site has been prepared, prior to the installation of the PV components, the following construction activities will take place:

- the installation of fixed aluminium structures to support the PV modules;
- the construction of the new grid connection substation;
- the construction of electrical and control room;
- the construction of site office and storage facilities, including security and ablution facilities and associated septic tanks;
- the construction of array enclosure and inverter/transformer foundations and housing; and
- the installation of cables.

The PV, electrical and structure equipment will be procured in South Africa where available, or from an international manufacturer when sourcing from within the country is not possible. It is expected that these components will be delivered to site via road in small trucks. Once the PV components have arrived on site, technicians will supervise the assembly of the panels and test

the facility. The PV panels will be installed on the fixed aluminium structures anchored to the ground through poles which will be screwed or piled into the ground.

Phased Approach to Construction

The development will be constructed in a phased approach. The exact size of each phase will be dependent on the various consents and authorisations to be obtained for the project, primarily the Power Purchase Agreement, as well as the interconnection technical constraints to be discussed and agreed with Eskom in the Interconnection Agreement. Installation of the full 90 MW could take up to 18 - 24 months or more to complete.

During the site preparation period, the workforce required for site security, manual labour, civil works, transportation of goods and other similar services will most likely be drawn from the local labour pool. During the first phase of construction, a highly-skilled team of solar energy technicians (the majority of which would likely be from outside South Africa as a workforce with the required skills is not currently available in the country) will train a number of the potential employees, preferably from the province, where available. Up to 291 personnel will be required to construct the full 90 MW PV power facility. However, any accurate employment number is dependent on how the phasing of the project is undertaken. For the purposes of the impact assessment, we have assumed that the development will take place in consecutive phases rather than all at once.

4.9.2

Operation

Once each phase of the facility is complete and operational, it is expected that it will have a lifespan of at least 20 years. Measuring the performance of the PV power plant will be done remotely, through the use of a monitoring system. Day to day facility operations will involve both regular on-site preventive and corrective maintenance tasks in order to keep the PV power plant in optimal working order throughout the operational period. Maintenance will consist mostly of panel replacement and other mechanical and electrical infrastructure repairs. Intermittent cleaning of the panels will be carried out as necessary, which is anticipated to be once or twice a year. Faulty components will be replaced as soon as problems are identified.

4.9.3

Decommissioning

The PV power facility will be decommissioned after 20 to 30 years. Alternatively, it will be upgraded or an application submitted to obtain a new license. Solaire Direct intend for the salvage value to cover the cost of decommissioning. Should the plant be decommissioned, the site will be rehabilitated to its original state.

Decommissioning activities will comprise:

- PV panels will be removed from the fixed aluminium frames.
- Fixed aluminium frame structures will be removed.
- PV panels will be transported to special recycling facilities (alternatively used at other operational sites).
- Electrical equipment (transformers) will either be re-used on other developments/projects or sold.
- Underground cable runs (where applicable) will be removed.
- Gravel/chipped stone on the access roads and on-site service roads, and guardhouse foundations, will be removed.
- Buildings such as the guardhouse can be taken over by the landowner for operational purposes. Alternately all the reusable material can be removed, the shells demolished and the rubble transported to a municipal waste site.
- Disturbed land areas will be rehabilitated, and replanted with indigenous vegetation if required.

4.10

CONSIDERATION OF ALTERNATIVES

In terms of the EIA Regulations, Section 28(1)(c) and NEMA, Section 24(4), feasible and reasonable alternatives are required to be considered in the EIA process. ' "Alternatives", in relation to a proposed activity, means different ways of meeting the general purposes and requirements of the activity, which may include alternatives to –

- (a) the property on which, or location where, it is proposed to undertake the activity;
- (b) the type of activity to be undertaken;
- (c) the design or layout of the activity;
- (d) the technology to be used in the activity;
- (e) the operational aspects of the activity; and
- (f) the option of not implementing the activity (No Go)'.

This section outlines the alternatives considered for the Graspan PV power facility.

4.10.1

Site Location Alternatives

As part of the site selection process, a number of potential sites were investigated in the Northern Cape through a desk-top analysis and intrusive

studies. The Graspan site was identified based on a number of criteria, including:

- **Solar resource:** Analysis of available data from existing weather stations suggests that the site has sufficient solar exposure to make a solar energy facility viable. The site is located in one of the most irradiated areas of the country.
- **Site extent:** An adequate portion of land was purchased to enable sufficient power supply and to allow for a minimum number of PV panels to make the project feasible.
- **Grid access:** Access to the grid and adequate transmission lines were key considerations for site location, i.e. proximity to Eskom's Graspan Traction Substation.
- **Land suitability:** Sites that facilitate easy construction conditions (relatively flat land with deep soft soil and few rock outcrops or waterbodies) were favoured during site selection.
- **Landowner consent:** The selection of sites where the land owners are supportive of the development of renewable energy is essential for ensuring the success of the project.
- **Environmental and socio-economic impacts:** Consideration was given to identifying a site with low agricultural potential, low level of biodiversity value and potentially low visual impacts during site selection.
- **Workforce:** The availability of a potential work force in surrounding area was taken into consideration.

4.10.2 *Site Layout Alternatives*

The PV power facility layout and project component design was subjected to a number of iterations, based on technical aspects of the project. These included aspects such as detailed site-specific solar data, construction conditions, as well as specialist input and sensitivity ratings for the site that were explored during the EIA process.

From a technical perspective, the final PV plant layout depends on a number of factors, including:

- Site-specific topographical conditions;
- Geotechnical features of the site;
- Drainage analysis;

- Final available interconnection capabilities to the Graspan Traction Substation;
- Final dimensions and sizing of structures to be done by specialized engineers to insure that all built equipment will be suitable for the local weather conditions; and
- Any additional inputs, obstacles, or constraints identified during the EIA and site survey process, as discussed below.

An original layout (Layout Alternative 1 shown in *Figure 4.11*) provided by Solaire Direct and based on limited data was used as the basis for the initial specialist assessment. After field surveys and workshops by the EIA team, particular areas posing additional environmental and social constraints or specific unsuitable locations were identified and fed back to the Solaire Direct technical team. Areas considered unsuitable by the environmental specialists were excluded where possible, based on potential impacts to vegetation, ecology, heritage and visual considerations. *Figure 4.12* indicates Layout Alternative 1 on the Constraints map. The technical team then generated a revised 'buildable areas map' based on these environmental and social constraints, as well as additional technical constraints, and from there developed a revised layout design, namely Layout Alternative 2 (*Figure 4.13*), taking these constraints into consideration.

Technical criteria and buffer zones considered in deriving the final site layout (Layout Alternative 2) included:

- Where possible, avoiding areas which are very rocky or uneven, in order to minimise earthworks and thus real and potential environmental impact;
- Buffer around dry pans of 50 m;+
- National road buffer of 1 km;
- Local district road buffer of 100 m;
- Railway buffer of 100 m;
- External farm boundary buffer of 50 m; and
- Buffer along existing Eskom grid infrastructure of 500 m.

The aim of considering layout alternatives was to balance the technical and financial objectives of maximising the output of the proposed facility with the other critical environmental and social constraints, including visual, botanical, faunal, heritage, archaeology, and palaeontology.

It is reiterated that Layout Alternative 2 is the preferred and **final PV power facility layout** design applied for in this EIR.

Legend

- Windpump
- Contours
- Rivers
- Cadastral Farms
- National Roads
- Secondary Roads
- Other Roads
- Track and Hiking Trail
- Railway
- Existing Overhead Transmission Line ESKOM
- Transmission Line
- Water Bodies
- Non-Perennial Water
- Proposed Substation
- Graspan Eskom Traction Substation
- Site Layout Alternative 1 (90MW)
- Graspan Photovoltaic (PV) Power Facility

Study Area

SCALE

0 500 1000 1500 Metres

TITLE:

Figure 4.11: Site Layout Alternative 1 showing Project Infrastructure (Topographical Map)

CLIENT:


solairedirect
SOUTH AFRICA
The solar MWh company

DATE: Oct 2012	CHECKED: DA	PROJECT: 0156408
DRAWN: AB	APPROVED: SHC	SCALE: 1: 30 000
DRAWING:	Graspan EIR Site Layout Alt1 proj infra-Topo.mxd	REV:
		0


ERM
Block A, Silverwood House
Silverwood Close
Steenberg Office Park, 7945
Cape Town, SOUTH AFRICA
Tel: +27 (0)21 705 9100
Fax: +27 (0)21 701 7900


Projection: Geographic: WGS84
28240_2805_E03_GEOITF
Inert Wap: East Data 8 Waps

SIZE: A3





Legend <ul style="list-style-type: none"> ● Town — Contours — Non-Perennial River — Water Bodies — National Route — Secondary Road — Other Access — Railway Line — Existing Overhead Transmission Line ESKOM — Transmission Line — Access Road ■ Proposed Substation ■ Graspan Eskom Traction Substation ■ 50m Existing Transmission Line Buffer ■ 100m Railway Buffer ■ 50m Dry Pan Buffer --- 50m Visual Setback Line □ Site Layout Alternative 1 (90MW) □ Graspan Photovoltaic (PV) Power Facility 	Ecological Sensitivity <ul style="list-style-type: none"> ■ Very High ■ High ■ Medium 	 TITLE: Figure 4.12: Site Layout Alternative 1 on Constraints Map	CLIENT: solairedirect SOUTHERN AFRICA The solar MWh company	DATE: Oct 2012	CHECKED: DA	PROJECT: 0156408
				DRAWN: AB	APPROVED: SHC	SCALE: 1 : 25 000
DRAWING: Graspan EIR Alt1 on Constraints Map.mxd			REV: 0		 Block A, Silverwood House Silverwood Close Steenberg Office Park, 7945 Cape Town, SOUTH AFRICA Tel: +27 (0)21 702 9100 Fax: +27 (0)21 701 7900 Projection: Transverse Mercator, CM 23, WGS84 Source: Chief Directorate National Geo-Spatial Information - Base Data Simon Tools - Ecological Sensitivity Insert Map, Esri Data & Maps	





Legend

- Windpump
- Contours
- Rivers
- Cadastral Farms
- National Roads
- Secondary Roads
- Other Roads
- Track and Hiking Trail
- Railway
- Existing Overhead Transmission Line ESKOM
- Transmission Line
- Water Bodies
- Non-Perennial Water
- Proposed Substation
- Graspan Eskom Traction Substation
- Site Layout Alternative 2 (10MW)
- Site Layout Alternative 2 (60MW)
- Graspan Photovoltaic (PV) Power Facility



TITLE:
 Figure 4.13: Site Layout Alternative 2
 showing Project Infrastructure
 (Topographical Map)

CLIENT: **solairedirect**
 Southern Africa
 The solar MWh company

DATE: Oct 2012	CHECKED: DA	PROJECT: 0156408
DRAWN: AB	APPROVED: SHC	SCALE: 1 : 30 000
DRAWING:		REV:
Graspan EIR Site Layout A1P2 prof infra-Topo.mxd		0

ERM
 Block A, Silverwood House
 Silverwood Close
 Steenberg Office Park, 7945
 Cape Town, SOUTH AFRICA
 Tel: +27 (0)21 705 9100
 Fax: +27 (0)21 701 7900

Projection: Geographic: WGS84
 28240_2805_E03_GEO11F
 (not App: East Data 8 Maps)

SIZE: A3

24°27'0"E 24°25'30"E 24°24'0"E

29°19'30"S 29°22'30"S 29°21'0"S

PIXLEY KA SEME DISTRICT MUNICIPALITY

SIYANCUMA LOCAL MUNICIPALITY


Graspan West Fergus West

Klein Karélaagte

GRASPAN 172

1247 1247.6 1241 1241.6 1239 1239.9 1237 1237.9 1235 1235.9 1233 1233.9 1231 1231.9 1229 1229.9 1227 1227.9 1225 1225.9 1223 1223.9 1221 1221.9 1219 1219.9 1217 1217.9 1215 1215.9 1213 1213.9 1211 1211.9 1209 1209.9 1207 1207.9 1205 1205.9 1203 1203.9 1201 1201.9 1199 1199.9 1197 1197.9 1195 1195.9 1193 1193.9 1191 1191.9 1189 1189.9 1187 1187.9 1185 1185.9 1183 1183.9 1181 1181.9 1179 1179.9 1177 1177.9 1175 1175.9 1173 1173.9 1171 1171.9 1169 1169.9 1167 1167.9 1165 1165.9 1163 1163.9 1161 1161.9 1159 1159.9 1157 1157.9 1155 1155.9 1153 1153.9 1151 1151.9 1149 1149.9 1147 1147.9 1145 1145.9 1143 1143.9 1141 1141.9 1139 1139.9 1137 1137.9 1135 1135.9 1133 1133.9 1131 1131.9 1129 1129.9 1127 1127.9 1125 1125.9 1123 1123.9 1121 1121.9 1119 1119.9 1117 1117.9 1115 1115.9 1113 1113.9 1111 1111.9 1109 1109.9 1107 1107.9 1105 1105.9 1103 1103.9 1101 1101.9 1099 1099.9 1097 1097.9 1095 1095.9 1093 1093.9 1091 1091.9 1089 1089.9 1087 1087.9 1085 1085.9 1083 1083.9 1081 1081.9 1079 1079.9 1077 1077.9 1075 1075.9 1073 1073.9 1071 1071.9 1069 1069.9 1067 1067.9 1065 1065.9 1063 1063.9 1061 1061.9 1059 1059.9 1057 1057.9 1055 1055.9 1053 1053.9 1051 1051.9 1049 1049.9 1047 1047.9 1045 1045.9 1043 1043.9 1041 1041.9 1039 1039.9 1037 1037.9 1035 1035.9 1033 1033.9 1031 1031.9 1029 1029.9 1027 1027.9 1025 1025.9 1023 1023.9 1021 1021.9 1019 1019.9 1017 1017.9 1015 1015.9 1013 1013.9 1011 1011.9 1009 1009.9 1007 1007.9 1005 1005.9 1003 1003.9 1001 1001.9 999 999.9 997 997.9 995 995.9 993 993.9 991 991.9 989 989.9 987 987.9 985 985.9 983 983.9 981 981.9 979 979.9 977 977.9 975 975.9 973 973.9 971 971.9 969 969.9 967 967.9 965 965.9 963 963.9 961 961.9 959 959.9 957 957.9 955 955.9 953 953.9 951 951.9 949 949.9 947 947.9 945 945.9 943 943.9 941 941.9 939 939.9 937 937.9 935 935.9 933 933.9 931 931.9 929 929.9 927 927.9 925 925.9 923 923.9 921 921.9 919 919.9 917 917.9 915 915.9 913 913.9 911 911.9 909 909.9 907 907.9 905 905.9 903 903.9 901 901.9 899 899.9 897 897.9 895 895.9 893 893.9 891 891.9 889 889.9 887 887.9 885 885.9 883 883.9 881 881.9 879 879.9 877 877.9 875 875.9 873 873.9 871 871.9 869 869.9 867 867.9 865 865.9 863 863.9 861 861.9 859 859.9 857 857.9 855 855.9 853 853.9 851 851.9 849 849.9 847 847.9 845 845.9 843 843.9 841 841.9 839 839.9 837 837.9 835 835.9 833 833.9 831 831.9 829 829.9 827 827.9 825 825.9 823 823.9 821 821.9 819 819.9 817 817.9 815 815.9 813 813.9 811 811.9 809 809.9 807 807.9 805 805.9 803 803.9 801 801.9 799 799.9 797 797.9 795 795.9 793 793.9 791 791.9 789 789.9 787 787.9 785 785.9 783 783.9 781 781.9 779 779.9 777 777.9 775 775.9 773 773.9 771 771.9 769 769.9 767 767.9 765 765.9 763 763.9 761 761.9 759 759.9 757 757.9 755 755.9 753 753.9 751 751.9 749 749.9 747 747.9 745 745.9 743 743.9 741 741.9 739 739.9 737 737.9 735 735.9 733 733.9 731 731.9 729 729.9 727 727.9 725 725.9 723 723.9 721 721.9 719 719.9 717 717.9 715 715.9 713 713.9 711 711.9 709 709.9 707 707.9 705 705.9 703 703.9 701 701.9 699 699.9 697 697.9 695 695.9 693 693.9 691 691.9 689 689.9 687 687.9 685 685.9 683 683.9 681 681.9 679 679.9 677 677.9 675 675.9 673 673.9 671 671.9 669 669.9 667 667.9 665 665.9 663 663.9 661 661.9 659 659.9 657 657.9 655 655.9 653 653.9 651 651.9 649 649.9 647 647.9 645 645.9 643 643.9 641 641.9 639 639.9 637 637.9 635 635.9 633 633.9 631 631.9 629 629.9 627 627.9 625 625.9 623 623.9 621 621.9 619 619.9 617 617.9 615 615.9 613 613.9 611 611.9 609 609.9 607 607.9 605 605.9 603 603.9 601 601.9 599 599.9 597 597.9 595 595.9 593 593.9 591 591.9 589 589.9 587 587.9 585 585.9 583 583.9 581 581.9 579 579.9 577 577.9 575 575.9 573 573.9 571 571.9 569 569.9 567 567.9 565 565.9 563 563.9 561 561.9 559 559.9 557 557.9 555 555.9 553 553.9 551 551.9 549 549.9 547 547.9 545 545.9 543 543.9 541 541.9 539 539.9 537 537.9 535 535.9 533 533.9 531 531.9 529 529.9 527 527.9 525 525.9 523 523.9 521 521.9 519 519.9 517 517.9 515 515.9 513 513.9 511 511.9 509 509.9 507 507.9 505 505.9 503 503.9 501 501.9 499 499.9 497 497.9 495 495.9 493 493.9 491 491.9 489 489.9 487 487.9 485 485.9 483 483.9 481 481.9 479 479.9 477 477.9 475 475.9 473 473.9 471 471.9 469 469.9 467 467.9 465 465.9 463 463.9 461 461.9 459 459.9 457 457.9 455 455.9 453 453.9 451 451.9 449 449.9 447 447.9 445 445.9 443 443.9 441 441.9 439 439.9 437 437.9 435 435.9 433 433.9 431 431.9 429 429.9 427 427.9 425 425.9 423 423.9 421 421.9 419 419.9 417 417.9 415 415.9 413 413.9 411 411.9 409 409.9 407 407.9 405 405.9 403 403.9 401 401.9 399 399.9 397 397.9 395 395.9 393 393.9 391 391.9 389 389.9 387 387.9 385 385.9 383 383.9 381 381.9 379 379.9 377 377.9 375 375.9 373 373.9 371 371.9 369 369.9 367 367.9 365 365.9 363 363.9 361 361.9 359 359.9 357 357.9 355 355.9 353 353.9 351 351.9 349 349.9 347 347.9 345 345.9 343 343.9 341 341.9 339 339.9 337 337.9 335 335.9 333 333.9 331 331.9 329 329.9 327 327.9 325 325.9 323 323.9 321 321.9 319 319.9 317 317.9 315 315.9 313 313.9 311 311.9 309 309.9 307 307.9 305 305.9 303 303.9 301 301.9 299 299.9 297 297.9 295 295.9 293 293.9 291 291.9 289 289.9 287 287.9 285 285.9 283 283.9 281 281.9 279 279.9 277 277.9 275 275.9 273 273.9 271 271.9 269 269.9 267 267.9 265 265.9 263 263.9 261 261.9 259 259.9 257 257.9 255 255.9 253 253.9 251 251.9 249 249.9 247 247.9 245 245.9 243 243.9 241 241.9 239 239.9 237 237.9 235 235.9 233 233.9 231 231.9 229 229.9 227 227.9 225 225.9 223 223.9 221 221.9 219 219.9 217 217.9 215 215.9 213 213.9 211 211.9 209 209.9 207 207.9 205 205.9 203 203.9 201 201.9 199 199.9 197 197.9 195 195.9 193 193.9 191 191.9 189 189.9 187 187.9 185 185.9 183 183.9 181 181.9 179 179.9 177 177.9 175 175.9 173 173.9 171 171.9 169 169.9 167 167.9 165 165.9 163 163.9 161 161.9 159 159.9 157 157.9 155 155.9 153 153.9 151 151.9 149 149.9 147 147.9 145 145.9 143 143.9 141 141.9 139 139.9 137 137.9 135 135.9 133 133.9 131 131.9 129 129.9 127 127.9 125 125.9 123 123.9 121 121.9 119 119.9 117 117.9 115 115.9 113 113.9 111 111.9 109 109.9 107 107.9 105 105.9 103 103.9 101 101.9 99 99.9 97 97.9 95 95.9 93 93.9 91 91.9 89 89.9 87 87.9 85 85.9 83 83.9 81 81.9 79 79.9 77 77.9 75 75.9 73 73.9 71 71.9 69 69.9 67 67.9 65 65.9 63 63.9 61 61.9 59 59.9 57 57.9 55 55.9 53 53.9 51 51.9 49 49.9 47 47.9 45 45.9 43 43.9 41 41.9 39 39.9 37 37.9 35 35.9 33 33.9 31 31.9 29 29.9 27 27.9 25 25.9 23 23.9 21 21.9 19 19.9 17 17.9 15 15.9 13 13.9 11 11.9 9 9.9 7 7.9 5 5.9 3 3.9 1 1.9 0 0.9

This is unclassified for any firm or individual to reproduce copyright maps, graphics or drawings, in whole or in part, without permission of the copyright owner. ERM Southern Africa (Pty) Ltd ©




Legend

- Town
- Contours
- Non-Perennial River
- Water Bodies
- National Route
- Secondary Road
- Other Access
- Railway Line
- Existing Overhead Transmission Line ESKOM
- Transmission Line
- Access Road
- Proposed Substation
- Graspán Eskom Traction Substation
- 50m Existing Transmission Line Buffer
- 100m Railway Buffer
- 50m Dry Pan Buffer
- 50m Visual Setback Line
- Site Layout Alternative 1 (10MW)
- Site Layout Alternative 2 (80MW)
- Graspán Photovoltaic (PV) Power Facility

Ecological Sensitivity

- Very High
- High
- Medium



TITLE:

Figure 4.14: Site Layout Alternative 2 on Constraints Map

CLIENT:



DATE: Oct 2012	CHECKED: DA	PROJECT: 0156408
DRAWN: AB	APPROVED: SHC	SCALE: 1 : 25 000
DRAWING: Graspán EIR A12 on Constraints Map.mxd	REV: 0	

ERM
Block A, Silverwood House
Silverwood Close
Steenberg Office Park, 7945
Cape Town, SOUTH AFRICA
Tel: +27 (0)21 702 9100
Fax: +27 (0)21 701 7900

Projection: Transverse Mercator, CM 23, WGS84
Source: Chief Directorate National Geo-Spatial Information - Base Data Simon Tool - Ecological Sensitivity
Inset Map: Esri Data & Maps

SIZE: A3

T:\GIS\Projects\0156408_Solaire_Direct\Maping\MXD\Graspán\EIR_A12 on Constraints Map.mxd

Solar energy is considered to be the most suitable renewable energy technology for this site, based on the site location, ambient conditions and energy resource availability. There are a number of different solar energy technologies that include:

- Fixed PV plants;
- Tracking PV plants (with solar panels that rotate to follow the sun's movement);
- Concentrated Solar Power (CSP) plants; and
- Concentrated PV Plants.

Financial, technical and environmental factors were taken into account when choosing the type of solar power technology for the site, including the local solar resource and its likely generation output, the economics of the proposed facility and availability of government feed-in tariffs and energy production licenses, and the requirement for other development inputs such as water resource requirements. PV is the most environmentally sensitive technology for the preferred site, as large volumes of water are not needed for power generation purposes compared to the CSP option. CSP requires large volumes of water for cooling purposes. PV is also preferred when compared to CSP technology because of the lower visual profile.

The remaining types of technologies were evaluated and the preferred configuration was selected based primarily on the operating environment. The suitability of different types of PV solar panels was assessed, including thin film and polycrystalline panels. Based on known performance in high temperature environments similar to those typical of the Northern Cape, thin film panels were selected as the preferred option. The Graspan PV power facility will install fixed structures rather than tracking systems as they require less repair work and maintenance during the operational life of the project. This decision is based on the benefits demonstrated by fixed structures with a longer track record in other markets, showing their high reliance over long periods of time. High capacity inverters (typically 1 MW) are considered more robust than smaller inverters and thus were selected as part of the preferred configuration.

Fixed Mounted PV System (Preferred Alternative)

In a fixed mounted PV system, PV panels are installed at a pre-determined angle from which they will not move during the lifetime of the plant's operation. The limitations imposed on this system due to its static placement are offset by the fact that the PV panels are able to absorb incident radiation reflected from surrounding objects. In addition, the misalignment of the angle of PV panels has been shown to only marginally affect the efficiency of energy

collection. There are further advantages which are gained from fixed mounted systems, including;

- The maintenance and installation costs of a fixed mounted PV system are lower than that of a tracking system, which is mechanically more complex given that these PV mountings include moving parts.
- Fixed mounted PV systems are an established technology with a proven track record in terms of reliable functioning. In addition, replacement parts are able to be sourced more economically and with greater ease than with alternative systems.
- Fixed mounted systems are robustly designed and able to withstand greater exposure to winds than tracking systems.

Dual Axis Tracking System

In a dual axis tracking system, PV panels are fixed to mountings which track the sun's movement. There are various tracking systems. A 'single axis tracker' will track the sun from east to west, while a dual axis tracker will in addition be equipped to account for the seasonal waning of the sun. These systems utilise moving parts and complex technology, including solar irradiation sensors to optimise the exposure of PV panels to sunlight.

Tracking systems are a new technology and as such are less suitable to operations in South Africa. This is because:

- A high degree of maintenance is required due to the nature of the machinery used in the system, which consists of numerous components and moving parts. A qualified technician is required to carry out regular servicing of these parts, which places a question on the feasibility of this system given the remote location of the proposed project site.
- The costs of the system are necessarily higher than a fixed mounted system due to the maintenance required for its upkeep and its complex design.
- A larger project site is required for this system given that the separate mountings need to be placed a distance apart to allow for their tracking movement.
- A power source is needed to mechanically drive the tracking system and this would offset a certain portion of the net energy produced by the plant.

4.10.4

Grid Connection Alternatives

The options of connecting the PV power facility to Eskom's national grid are subject to on-going discussions between Solaire Direct and Eskom. The most efficient and practical option which is considered viable for the site is

connection into the existing Eskom Graspan Traction Substation located in the northern section of the site. As the existing Graspan Traction Substation is located on the site, connection to this substation with an overhead powerline is considered the most efficient option as the length of the powerline will be relatively short (approximately 800 m). Two new grid connection substations will be built (one of 400 m² extent and the second of 2,500 m² extent) containing Medium Voltage (22 kV) circuit breakers that will combine the power generated by each inverter/transformer enclosure. This combined power will then be transformed from Medium Voltage (22 kV) up to High Voltage (132 kV) for connection to the existing Eskom Graspan Traction Substation by means of power transformers.

4.10.5 ***No-go Alternative***

The no-go alternative is the option of not implementing the activity or executing the proposed development. Assuming that the solar power plant would not be developed at the proposed site, the site would remain in its current state. There would be no negative environmental and social impacts associated with the development of a solar power facility. The agricultural potential (although limited for this site) would not be lost due to the establishment of the facility on agricultural land. Similarly, there would be no positive impacts if the power plant is not executed; there will be no increase in electricity generation, no CO₂ offsets associated with the proposed development, no economic benefit to the landowners associated with the potential income generated through the operation of the facility and there would be no contribution to meeting South Africa's targets for renewable energy generation.

The direct benefits associated with both the construction and operational phases of the solar power plant such as increased employment opportunities and associated economic benefits would also not occur should the development not go ahead. It should be noted that requests for employment opportunities have been found to be the overwhelming theme from respondents to consultation opportunities provided to date.