Detail Plan of
Durban University of Technology-
Intersection of Steve Biko &
Botanic Gardens Road-

Situate in the Ethekwini Metropolitan
Registration Division - FU
Province of KwaZulu Natal

Scale : 1/200
System : WG.31
Datum : Mean Sea Level
File Ref : DBN - 68
Drawn : S Shange

CONTROL POINTS

Name	Y	X	Z	Remark
457N1	-313.090	3303756.440	30.006	TSM
458N1	-531.630	3303805.600	22.825	TSM
SB10	-322.439	3303747.112	29.833	Cutnail in kerb
SB11	-370.457	3303776.091	27.308	Cutnail in kerb
SB12	-447.241	3303795.312	25.043	Cutnail in tar pave
SB13	-280.478	3303846.777	31.434	Cutnail in tar
SB14	-299.938	3303853.550	31.139	Cutnail in kerb
SB15	-357.054	3303869.928	28.495	Cutnail in tar pave
SB16	-399.074	3303793.844	26.318	10mm iron peg
SB17	-359.262	3303814.481	27.827	Cutnail in tar/conc

Survey by me

V D Mngomezulu (GPr LS 1418)
June 2021

Notes:

1. For full extent of the drawing - see DWG drawing.
2. Majority of sealed manhole are on tar roads.
3. Only main cable routes ascertained.
4. Tree canopies not necessarily to scale.
5. Walls with columns are drawn at column line for simplicity.
6. Legend :

CBMH denotes cable manhole
CL denotes cover level
ELP denotes electricity light pole
FH denotes fire hydrant
FL denotes floor level
IL denotes invert level
LP denotes light pole
MH denotes manhole
RE denotes rodding eye
RMH denotes round manhole
SMH denotes sewer manhole.
SP denotes signpost
SWMH denotes stormwater manhole
WM denotes water meter
stormwater pipe
sewer pipe
Telkom/communication cables
Electrical cables
Buildings
49.96 Green levels denotes roof levels

VM GEOMATICS
Registration No.: 2017/175976/07
- Professional Land Surveyors
- Engineering Surveyors
- Sectional Title Practitioners
- Town Planners
- GIS Practitioners

Professional Land Surveyor [GPr LS 1418 - D] Candidate Planner: C 8572/2019

34 Thuthuka Drive,Kloof 3610
South Africa
Cellphone number: 0711047707
Email Adress: velemseni14@gmail.com

SHEET 1 of 2