APPLICATION FOR ENVIRONMENTAL AUTHORISATION FOR PROPOSED CONSTRUCTION OF 6.9 KM GRAVEL ROAD IN MABASO VILLAGE, MSINGA LOCAL MUNICIPALITY – REF. NUMBER: DC24/0007/2016\_KZN/EIA/0000 316/2016







#### BASIC ASSESSMENT REPORT

SUBMITTED TO: PROVINCE OF KWAZULU NATAL DEPARTMENT OF ECONOMIC DEVELOPMENT, TOURISM AND ENVIRONMENTAL AFFAIRS



Economic Development, Tourism and Environmental Affairs

PROVINCE OF KWAZULU-NATAL Private Bag X1048 Richardsbay 3900

#### **SUBMITTED BY:**

Magalela and Associates Tel: 031 535 7094 Fax: 086 556 5646 E-Mail: info@magalelas.co.za Mobile: 071 307 2675 Contact Person: Simphiwe Mtshali



### 30 AUGUST 2016

Project Title:	CONSTRUCTION OF 6.9 KM GRAVEL ROAD IN MABASO VILLAGE, MSINGA LOCAL MUNICIPALITY				
Report Title	APPLICATION FOR ENVIRONMENTAL AUTHORISATION FOR PROPOSED CONSTRUCTION OF 6.9 KM GRAVEL ROAD IN MABASO VILLAGE, MSINGA LOCAL MUNICIPALITY				
DETEA REFERENCE NUMBER	DC24/0007/2016_KZN/EIA/0000316/2016				
EAP Author	K Motsepe, Pr. Nat.Sci				

Revision	Date	Report Status
Draft 1	26/07/2016	First draft for comments by stakeholders
Final	01/09/2016	Final Report

#### Consultants: Magalela & Associates

Approved for Consultants by:

.....

Mr. S Mtshali, Pr. Nat. Sci.

Technical Study Specialist

#### Client: Msinga Local Municipality

Approved for MSINGA LOCAL MUNICIPALITY:

.....

Mr. S Sokhela

#### BASIC ASSESSMENT REPORT

Submitted in requirements of the Environmental Impact Assessment Regulations, December 2014 promulgated in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998)

#### TABLE OF CONTENTS

<u>A.</u>	DETAILS AND EXPERTISE OF ENVIRONMENTAL ASSESSMENT PRACTITIONER (EAP)	9
<u>B.</u>	THE LOCATION DESCRIPTION AND LOCALITY MAP OF 6.9 KM GRAVEL ROAD IN MABASO LAGE, MSINGA LOCAL MUNICIPALITY	10
VIL	LAGE, MISINGA LOCAL MUNICIPALITY	10
<u>C.</u>	LAYOUT PLAN OF THE CONSTRUCTION OF GRAVEL ROAD	11
<u>D.</u>	DESCRIPTION OF THE SCOPE OF THE PROPOSED CONSTRUCTION OF 6.9 KM GRAVEL ROA	
<u>IN I</u>	MABASO VILLAGE	12
<u>E.</u> <u>GR</u>	DESCRIPTION OF THE POLICY AND LEGISLATIVE CONTEXT WITHIN WHICH CONSTRUCTION AVEL ROAD FALLS	1 OF 15
	MOTIVATION FOR THE NEED AND DESIRABILITY FOR THE PROPOSED CONSTRUCTION OF NSTRUCTION OF 6.9 KM GRAVEL ROAD IN MABASO VILLAGE INCLUDING THE NEED AND SIRABILITY OF THE ACTIVITY IN THE CONTEXT OF THE PREFERRED LOCATION	<u>18</u>
<u>G.</u>	MOTIVATION FOR THE PREFERRED SITE, ACTIVITY AND TECHNOLOGY ALTERNATIVE	<u>19</u>
<u>н.</u>	A FULL DESCRIPTION OF THE PROCESS FOLLOWED TO REACH THE PROPOSED PREFERRED	
AL	TERNATIVE WITHIN THE SITE	20
	DETAILS OF ALL THE ALTERNATIVE CONSIDERED	20
	DETAILS OF THE PUBLIC PARTICIPATION PROCESS (PPP) UNDERTAKEN INTERMS OF REGULATION 41 INCLUI	
	PIES OF THE SUPPORTING DOCUMENTS AND INPUTS	21
	2.1 Identification of stakeholders 2.2 Announcement of the project	21 21
	2.2 ANNOUNCEMENT OF THE PROJECT 2.3 MEETINGS	21 21
	2.4 Site Notice	21
	2.5 Newspaper Advertisement	22
	SUMMARY OF ISSSUES RAISED BY INTERESTED AND AFFECTED PARTIES (I&AP'S)	23
-	ENVIRONMENTAL ATTRIBUTES ASSOCIATED WITH ALTERNATIVES FOCUSING ON THE GEOGRAPHICAL,	_0
-	/SISCAL, BIOLOGICAL, SOCIAL, ECONOMIC, HERITAGE AND CULTURAL ASPECTS	24
	THE METHODOLOGY USED IN DETERMINING AND RANKING THE NATURE/SEVERITY, SIGNIFICANCE,	
-	SEQUENCE, EXTENT, DURATION AND PROBABILITY OF POTENTIAL ENVIRONMENTAL IMPACTS AND RISK	
ASS	OCIATED WITH ALTERNATIVES	25
H.5	5.1 Severity	25
H.5	5.2 Extent	26
H.5	5.3 DURATION	26
Β.	LIKELIHOOD	26
	5.4 Probability	27
	5.5 FREQUENCY	27
	5.6 Environmental Significance	27
	IMPACTS AND RISK IDENTIFIED FOR EACH ALTERNATIVE, INCLUDING THE NATURE, SIGNIFICANCE,	
	ISEQUENCE, EXTENT, DURATION AND PROBABILITY OF THE IMPACTS, INCLUDING THE DEGREE TO WHICH THE	
	ECTS CAN BE REVERSED, MAY CAUSE IRREPLACEABLE LOSS OF RESOURCES AND CAN BE AVOIDED, MANAGED	
MIT	IGATED	29

-	Positive and negative impacts that the proposed activity and alternatives will have on the	
ENVI	RONMENT AND ON THE COMMUNITY THAT MAY BE AFFECTED FOCUSING ON THE GEOGRAPHICAL, PHYSICAL,	
BIOL	OGICAL, SOCIAL, ECONOMIC, HERITAGE AND CULTURAL ASPECTS	40
H.8	THE POSSIBLE MITIGATION MEASURES THAT COULD BE APPLIED AND LEVEL OF RESIDUAL RISK	45
H.9	THE OUTCOME OF THE SITE SELECTION MATRIX	<b>48</b>
H.10	) IF NO ALTERNATIVES, INCLUDING ALTERNATIVE LOCATIONS FOR THE ACTIVITY WERE INVESTIGATED, THE	
мот	IVATION FOR NOT CONSIDERING SUCH.	49
H.11	A CONCLUDING STATEMENT INDICATING THE PREFERRED ALTERNATIVES, INCLUDING PREFERRED LOCATION	OF
THE	ΑCTIVITY	50
<u>l.</u>	FULL DESCRIPTION OF THE PROCESS UNDERTAKEN TO IDENTIFY, ASSESS AND RANK THE	
IMP	ACTS THE ACTIVITY WILL IMPOSE ON THE PREFERRED LOCATION THROUGH THE LIFE OF	
АСТ	Ίνιτγ.	51
_	A SUMMARY OF THE FINDINGS AND IMPACT MANAGEMENT MEASURES IDENTIFIED IN AN	Y
	SPECIALIST REPORT COMPLYING WITH APPENDIX 6 TO THESE REGULATIONS AND A	
	ICATION AS TO HOW THESE FINDING AND RECOMMENDATIONS HAVE BEEN INCLUDED IN 1	
FIN/	AL REPORT	<u>66</u>
<u>K.</u>	AN ENVIRONMENTAL IMPACT STATEMENT	67
<u>L.</u>	ENVIRONMENTAL MANAGEMENT PROGRAMME INCLUDING WHERE APPLICABLE IMPACT	
MA	NAGEMENT MEASURES FROM SPECIALIST REPORT, THE RECORDING OF THE PROPOSED	
IMP	ACT MANAGEMENT OBJECTIVES, AND THE IMPACT MANAGEMENT OUTCOMES FOR THE	
DEV	/ELOPMENT	<u>69</u>
<u>M.</u>	ANY ASPECTS WHICH WERE CONDITIONAL TO THE FINDING OF THE ASSESSMENT EITHER	
THE	EAP OR SPECIALIST WHICH ARE TO BE INCLUDED AS CONDITIONS OF AUTHORIZATION	<u>70</u>
N.	A DESCRIPTION OF ANY ASSUMPTIONS, UNCERTAINITIES, GAPS IN KNOWLEDGE WHICH	
	ATE TO THE ASSESSMENT AND MITIGATION MEASURES PROPOSED	71
		<u>,                                     </u>
0.	A REASONED OPINION AS TO WHETHER THE PROPOSED ACTIVITY SHOULD OR SHOULD N	от
BE A	AUTHORIZED, AND IF THE OPINION IS THAT IT SHOULD BE AUTHORIZED, ANY CONDITIONS	
THA	T SHOULD BE MADE IN RESPECT OF THAT AUTHORIZATION	72
<u>P.</u>	WHERE THE PROPOSED ACTIVITY DOES NOT INCLUDE OPERATIONAL ASPECTS, THE PERIO	D
	WHICH THE ENVIRONMENTAL AUTHORIZATION IS REQUIRED, THE DATE ON WHICH THE	
	IVITY WILL BE CONCLUDED, AND THE POST CONSTRUCTION MONITORING REQUIREMNTS	74
ACI	WITT WILL BE CONCLUDED, AND THE TOST CONSTRUCTION MONITONING REQUIREMNTS	11
<u>Q.</u>	AN UNDERTAKING UNDER OATH OR AFFIRMATION BY THE EAP IN RELATION TO:	75
<u>R.</u>	WHERE APPLICABLE, DETAILS OF ANY FINANCIAL PROVISIONS FOR REHABILITATION,	
	SURE, AND ONGOING POST DECOMMISSIONING MANAGEMENT OF NEGATIVE	
	/IRONMENTAL IMPACTS	77
		//
<u>s.</u>	ANY SPECIFIC INFORMATION THAT MAY BE REQUIRED BY THE COMPETENT AUTHORITY	<u>78</u>
<u>T.</u>	ANY OTHER MATTERS REQUIRED IN TERMS OF SECTION 24(4)(A) AND (B) OF THE ACT	<u>79</u>

#### LIST OF TABLES

Table 1: Farm Names of Proposed Development 1	0
Table 2: Surveyor-General 21 digit of Farm Portions 1	0
Table 3: Coordinates of Gravel Road Construction 1	0
Table 4: Proposed Activity Listing interms 2014 EIA Regulations1	2
Table 5: List of Legislation relevant to application 1	5
Table 6: List of State Department Stakeholders1	.6
Table 7: Environmental Attributes associated with construction of gravel road 2	24
Table 8: Determination of Consequence 2	
Table 9: Severity Estimation 2	26
Table 10: Extent of Activity Estimation 2	26
Table 11: Duration of the Impact 2	
Table 12: Determination of Likelihood 2	27
Table 13: Probability of Impact 2	27
Table 14: Frequency of the Impact 2	
Table 15: Environmental Significance of Impact 2	
Table 16: Environmental Significance of Impacts during Design and Planning Phase 3	30
Table 17: Environmental Significance of Impacts during the Construction Phase	32
Table 18: Environmental Significance of Impacts during Decommisioning Phase	
Table 19: Environmental Significance of Impacts during Operational Phase	38
Table 20: Positive and Negative Impacts on the Environmental Attributes 4	1
Table 21: Mitigation Measures to negate Negative Impacts on the Environmental	
Attributes4	6
Table 22: Environmental Significance of Impacts of Prefered Alternative during Design	
and Planning Phase5	52
Table 23: Environmental Significance of Impact of the Prefered Alternative during	
Construction Phase5	54
Table 24: Environmental SIgnificance of Impact on the Prefered Alternative during	
Decommisioning Phase	
Table 25: Environmnetal Significance of Impact of Prefered Alternative during Operation	
Phase6	50
Table 26: Cumulative Impacts of Prefered Alternative during Construction Phase	52
Table 27: Cumalative Impact of Prefered Alternative during Decommisioning Phase 6	
Table 28: Cumulative Impact of Prefered Alternative during the Operation Phase	54

#### LIST OF APPENDICES

- APPENDIX 1: LOCALITY MAP OF PROJECT SITE
- APPENDIX 2: THE MAP SHOWING FARM PORTIONS.
- APPENDIX 3: THE LAYOUT PLAN OF PROPOSED GRAVEL ROAD
- APPENDIX 4: PROOF OF SUBMISSION OF BASIC ASSESSMENT REPORT TO
- **STAKEHOLDERS**
- APPENDIX 5: PROOF OF WRITTEN COMMENTS FROM I&AP
- APPENDIX 6: PROOF OF SUBMISSION OF BACKGROUND INFORMATION

#### **DOCUMENT TO STAKEHOLDERS**

- APPENDIX 7: COPY OF BACKGROUND INFORMATION DOCUMENT
- APPENDIX 8: DISCUSSIONS RECORDS WITH STAKEHOLDERS
- APPENDIX 9: COPY OF COMMENTS SHEET
- APPENDIX 10: COPY OF SITE NOTICE AND NEWSPAPER ADVERT
- APPENDIX 11: PROOF OF SITE NOTICE DISPLAYED IN PUBLIC SPACE
- APPENIDIX 12: PROOF ADVERT IN THE ISOLWEZE NEWSPAPER

- APPENDIX 13: ISSUES AND RESPONSE REPORT
- APPENDIX 14: MSINGA LOCAL MUNICIPALITY IN RELATION TO UMZINYATHI
- **DISTRCT MUNICIPALITY**
- APPENDIX 15: THE ENVIRONMENTAL SIGNIFICANCE RATING TABLE OF
- **ASPECTS**
- APPENDIX 16: PROPOSED ACTIVITY AND ITS ASSOCIATED INFRASTRUCTURE

IN RELATION TO ENVIRONMENTAL SENSITIVITY OF THE SITE.

- APPENDIX 17: ENVIRONMENTAL MANAGEMENT PROGRAMME
- APPENDIX 18: SPECIALIST REPORT/S
- APPENDIX 19: SITE PHOTOS
- APPENDIX 20: COPY OF APPLICATION FORMS

Appendix 21: PROPOSED ENGINEERING DESIGN OF THE 6.9 KM GRAVEL ROAD IN MABASO VILLAGE, MSINGA LOCAL MUNICIPALITY.

#### A. Details and Expertise of Environmental Assessment Practitioner (EAP)

#### PERSONAL PARTICULARS (EAP)

#### Name and Surname: Mr. Kgomotso Motsepe

Years of experience: 17 of working experience environmental sector and 9 years as independent water and environmental resources consultant

#### **EDUCATION**

- Management Development Programme, University of South Africa, 2006,
- Certificate in Business Management, University of South Africa, 2004,
- B Tech Chemistry, Pretoria Technikon 2003,
- N Diploma: Analytical Chemistry, Pretoria Technikon 1998

#### **MEMBERSHIP OF PROFESSIONAL INSTITUTIONS**

- South African Council for Scientific Professions Pr.Sci.Nat.
- International Association of Impact Assessments MIAIA.
- Water Institute of South Africa MWISA
- Institute of Waste Management in South Africa MIWMSA

#### **KEY RELEVANT EXPERIENCE**

- 2014, Environmental Impact Assessment for continuation of mining through wetlands for Optimum Colliery in Hendrina
- 2014, Environmental Impact Assessment for Construction of Bridges in Edenvale for Ekurhuleni Metropolitan Municipality
- 2014, Environmental Impact Assessment for construction of bulkwater pipeline in Garankua and Mabopane Township for Tshwane Metropolitan Municpality
- 2014, Application for Water Use Licence Application for Wescoal Elandspruit Colliery Project
- 2013, Application for Water Use License Application for Optimum Kwagga North and Tweefontein

#### CERTIFICATION

I, the undersigned, certify that to the best of my knowledge and belief, this data correctly describes me, my qualifications, and my experience. I hereby confirm my involvement in the proposed project.

Kgomotso Motsepe

Date:\_\_\_\_\_

# B. The Location Description and Locality Map of 6.9 km gravel road in Mabaso Village, Msinga Local Municipality

The site is located in the Mabaso Village area and falls under the jurisdiction of the Msinga Local Municipality and Umzinyathi District Municipality. The map showing the Mabaso Village within Msinga Local Municipality and Umzinyathi District Municipality is attached herewith in **Appendix 1**.

The development of the gravel road occurs on the following property as tabulated in **Table 1**:

#### Table 1: Farm Names of Proposed Development

Farm Name	ERF	Portion
KLIP RIVER NATIVE LOCATION	4665	-

Table 2 contains the Surveyor-General 21 digit site reference numbers for thefarms shown in Table 1.

#### Table 2: Surveyor-General 21 digit of Farm Portions

Ν	0	G	Т	0	0	0	0	0	0	0	4	6	5	5	0	0	0	0	0	0

The farm is shown on map in Appendix 2.

The start and end of each of the phases of the pipeline is shown in Table 3.

#### **Table 3: Coordinates of Gravel Road Construction**

1	28.667191°S	30.442938°E	28°40'1.888''S	30°26'34.577''E
2	28.665531°S	30.448771°E	28°39'55.912''S	30°26'55.576''E
3	28.66548°S	30.449019°E	28°39'55.728''S	30°26'56.468''E
4	28.664439°S	30.453823°E	28°39'51.98''S	30°27'13.763''E

#### C. Layout Plan of the Construction of Gravel Road

The layout plan for the proposed construction of 6.9 km gravel road in Mabaso Village is shown in **Appendix 3**.

# D. Description of the scope of the proposed construction of 6.9 km gravel road in Mabaso Village

The project involves the construction of 6.9 km Gravel Road in Mabaso Village. The Mabaso Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality.

The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

The scope of work is also shown in the map attached herewith in **Appendix 3**. The above activities triggered environmental authorization in terms of the Environmental Impact Assessment Regulations, December 2014 promulgated in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998), hence the compilation of this Basic Assessment Report. The listed activity and its description is described in **Table 4**.

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
12	The development of – i. Canals exceeding 100 square meters in size ii. Channels exceeding 100 square meters in size	The project involves the construction of 6.9 km Gravel Road in Mabaso Village. The Mabaso Village area falls within the Msinga Local Municipality in Umzinyathi
	square meters in size iii. Bridges exceeding 100 square meters in size iv. Dams, where the dam, including infrastructure and water surface area, exceeds 100 square meters in size v. Weirs, where the eir, including infrastructure and water surface area,	District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

Table 4: Proposed Activity Listing interms 2014 EIA Regulations

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
	exceeds 100 square meters	
	in size	
	vi. Bulk stormwater outlet structures exceeding 100 square meters in size	
	vii. Marines exceeding 100 square meters in size	
	viii. Jetties exceeding 100 square meters in size	
	ix. Spillways exceeding 100 square meters in size	
	x. Buildings exceeding 100 square meters in size	
	xi. Boardwalkings exceeding 100 square meters in size	
	xii. Infrastructure or structures with a physical footprint of 100 square meters or more;	
	Where such development occurs	
	<ul> <li>a) Within a watercourse</li> <li>b) In front of a development setback; or</li> <li>c) If no development setback exist, within 32 metres of a watercourse, measured from the edge of a watercourse</li> </ul>	
	Excluding (aa) The development of infrastructure or structure witin existing ports or harbours that will not increase the development footprint of the port or harbor (bb) Where such development activities are related to the development of a port or harbor, in which case activity 26 in Listing	

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
	Notice 2 of 2014 (cc) Activities listed in activity 14 in Listing Notice 2 of 2014 or activity 14 in Listing Notice 3 of 2014, in which activity applies;	
	(dd) Where such development occurs within an urban area; or	
	(ee) Where such development occurs within existing roads or road reserve.	
19	The infilling or depositing of any material of more than 5 cubic metres into, or the dredging, excavation, removal or moving of soil, sand, shells, shell grit, pebbles or rock of more than 5 cubic metres from- (i) a watercourse; (ii) the seashore; or (iii) the littoral active zone, an estuary or a distance of 100 metres inland of the high-water mark of the sea or an estuary, whichever distance is the greater but excluding where such infilling, depositing, dredging, excavation, removal or moving- (a) will occur behind a development setback; (b) is for maintenance purposes undertaken in accordance with a maintenance management plan; or (c) falls within the ambit of activity 21 in this Notice, in which case	The project involves the construction of 6.9 km Gravel Road in Mabaso Village. The Mabaso Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.
		The project involves the

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
24	The development of – i. A road for which an environmental authorization was obtained for the route determination in terms of activity 5 in Government Notice 545 of 2010; or ii. A raod with a reserve wider than 13,5 meters, or where no reserve exists where the road the is wider than 5 meters; But excluding – a) Roads which are identified and included in activity 27 in Listing Notice 2 of 2014; or b) Roads where the entire	construction of 6.9 km Gravel Road in Mabaso Village. The Mabaso Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.
	road falls within an urban area	

# E. Description of the policy and legislative context within which construction of gravel road falls

The list all legislation, policies and/or guidelines of any sphere of government that are relevant to the application as contemplated in the EIA regulations, where applicable are contained in the following **Table 5**:

Title of legislation, policy or guideline	Administering authority	Date of Promulgation
The Constitution of the	The 3 spheres of National	1996
Republic of South Africa	Government	August
The National Water Act	Department of Water and	1998
	Sanitation	

Table 5: List of Legislation	relevant to application
------------------------------	-------------------------

Water Services Act	The municipalities	1997
The National	National and Provincial	1998
Environmental	Environmental Affairs Department	
Management Act		
Environmental Impact	National and Provincial	2014
Assessment Regulations	Environmental Affairs Department	
The National Health Act	Department of Health	2004
National Heritage	Amafa and Dept. of Arts and	1999
Resources Act	Culture	
Conservation of	Department of Agriculture	1983
Agricultural Resources Act		
KwaZulu Land Affairs Act	Department of Local Government	1992
	and Traditional Affairs	
Department of Transport	National Road Traffic Act	1996

In the context of the above legislations having direct or indirect impact on the development, the following state departments in **Table 6** are listed as interest and affected parties. This basic assessment report has been circulated to the respective department to solicit comments and inputs in terms of the report. The records of submission is contained in **Appendix 4**. The comments or response received from the interest and affected state department is included in the issues and response report under **Section H** of this report. The proof written comments or report is attached in **Appendix 5**.

Name of Department	Contact person	Address	Document Submitted for	Comments (Yes/No)
Depaninen	person		Comments (Yes/No)	(103/110)
Ezemvelo KZN Wildlife	Musa Mntambo	1 Peter Brown Drive Pietermaritzburg, 3201	Yes	No
Amafa	Weziwe Tshabalala	P.O. Box 2685, Pietermaritzburg, 3200 Tel: 0333 946543 Fax: 0333 426097	Yes	No
Department of Water and Sanitation	Lindiwe Dladla	P O Box 1018 Durban, 4000	Yes	No

#### Table 6: List of State Department Stakeholders

Prepared by Magalela and Associates on behalf of Msinga Local Municipality

		Tel: 031 336 2700		
Department of Agriculture, Forestry and Fisheries	Khwazi Hlongwane	P O Box 345 Pietermarisburg, 3200 Tel: 033 345 3515	Yes	No
Department of Cooperative	Induna Dumakude	P O Box 20 Pomeroy, 3020 Tel: 076 099 2704	Yes	Yes
Governance and Traditional Affairs	Cllr. M Sokhela	P O Box 141 Tugela Ferry Tel: 071 332 2441	Yes	Yes
uMzinyathi District Municipality	David Mvelase	P.O. Box 1965, 3000, South Africa 034-219 1500	Yes	No

# F. Motivation for the need and desirability for the proposed construction of Construction of 6.9 km gravel road in Mabaso Village including the need and desirability of the activity in the context of the preferred location

As per Msinga Local Municipality IDP 2015/2016, and uMzinyathi Backlog Study (2007) determined road backlogs based on hut count data in the Traditional Authority areas indicates that 58% of households have inadequate access to roads.

The Road Infrastructure Strategic Framework for South Africa (RIFSA) classifications indicates a major dependency on lower order access roads for most of the residents within Msinga Local Municipality. With the high dependency on the lower order nodes, it is necessary to ensure proper transport infrastructure exist, especially with the view of creating economic growth in the municipality, which positively affects everybody. Should the residents not have proper access to opportunities; the initiatives will not be successful.

# G. Motivation for the preferred site, activity and technology alternative

### PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

# H. A full description of the process followed to reach the proposed preferred alternative within the site

#### H.1 Details of all the alternative considered

### PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

# H.2 Details of the Public Participation Process (PPP) undertaken interms of regulation 41 including copies of the supporting documents and inputs

The public participation process for the construction of construction of 6.9 km gravel road in Mabaso Village entailed the following:

#### H.2.1 Identification of stakeholders

Identification of stakeholders took place by way of contacting with local municipalities, the Tribal Authority and Induna of the communities Obisini Village, Ward Councillor and State Department that development of the gravel road will trigger their participation. The stakeholder identified are listed in **Table 6**, above.

#### H.2.2 Announcement of the project

A Background Information Document (BID) was prepared as a basis for discussion with stakeholders about the project. The proof of distribution of the BID during the meeting with stakeholders is attached in **Appendix 6**. The BID in the main contained the following among others:

- Background to the project (who, why, where) and the motivation thereof;
- Description of the project;
- Process that will be followed (who can participate in the process, how and when);
- Information about the independent consultants (experience of technical and public participation processes and local experience in the study area).

The copy of the BID is attached herewith in Annexure 7.

#### H.2.3 Meetings

In anticipation of the desirability of the project within the community of the Mabaso Village, a decision was taken to advance the cause of the project with the Triabla Authority, Induna of the Area and Ward Councillor. Therefore meetings were held on 28 July 2016 at proposed project site for the gravel road

with the respective community leaders, Induna M Dumakude and Councillor M Sokhela and community members. The notes or discussion points covered in meeting are contained in **Annexure 8**. The comments sheet issued was discussed with the attendees in order to record issues or comments they could have with regards to the project development. The copy of the comments sheet is attached in **Annexure 9**.

#### H.2.4 Site Notice

A site notice was displyed on the notice board of the municipality as well as public library. The public was given 30-days to comment on the Draft Basic Assessment Report, in which they were invited to express interest if they need the copy of the report. The report was also made available for reading at the Public Libray near Msingal Local Municipality Head Office. The copy of the site notice and advertisement is attached in **Annexure 10**. The proof of site notice displayed on site is contained in **Annexure 11**.

#### H.2.5 Newspaper Advertisement

The project was advertised in Greytown Gazette Newspaper. The public was given 30-days to comment on the Draft Basic Assessment Report, in which they were invited to express interest if they need the copy of the report. The report was also made available for comments at the Public Library in Msinga Public Library in Tugela Ferry. The copy of the advertisement in the Greytown Gazette Newspaper is attached in **Annexure 12**.

#### H.3 Summary of Isssues raised by Interested and Affected Parties (I&AP's)

The summary of isssues raised during the public participation process are as follows:-

The Issues and Response Report is contained in Annexure 13.

# H.4 Environmental Attributes associated with Alternatives focusing on the Geographical, Physiscal, Biological, Social, Economic, Heritage and Cultural Aspects

Mabaso Village is one of the settlements of the Msinga Local Municiaplity sitiuated in the rural area of the northern part of province of KwaZulu Natal. The town in the area as part of the municipality is Tugela Ferry, which host the seating of Municipal Offices and Pomeroy. The District Municipality is Umzinyathi District Municipality. The map showing the town of Keates Drift within Msinga Local Municipality in relation to Umzinyathi District Municipality is shown in **Appendix 14**.

The environtal attribute associated with the constrution of the gravel road is demonstrated and summarised in the **Table 7** below:-

Environmental Attribute	Description
Gradient of the site	1.5 -1.2 m
Location in Landscape	Undulating plain/low hills
Groundwater	Water table below 1.5m deep
Soil	Often Dry hard soil in the area
Geological Stability	The geology is rocky but stable
Groundcover	Natural veld with heavy alien
	infestation
Land use character of surrounding	The area is charecterised by vacant
area	land, followed by rural community
	settlement. The pipeline crosses
	streams along distribution network
Cultural and Historical Features	There are cultural/historical features
	affected by the pipeline
Social and Economic aspect	The project will create employment
	opportunities during construction
	phase

Table 7: Environmental Attributes associated with construction of gravel road

# H.5 The methodology used in determining and ranking the nature/severity, significance, consequence, extent, duration and probability of potential environmental impacts and risk associated with alternatives

The risk assessment methodology was used for the ranking of the impacts. The severity/intensity of the potential environmental impacts were evaluated according to their severity (how bad the impact is), duration (how long the environment will take to recover from the impact), extent (the area that is effected by the impact), probability (the probability of the impact actually happening), frequency of occurrence (how often the aspect happens) and finally the environmental significance of the impact. All the above was rated on a scale of 5 with 1 being the least impacted.

This system derives environmental significance on the basis of the consequence of the impact on the environment and the likelihood of the impact occurring. Consequence is calculated as the average of the sum of the ratings of severity, duration and extent of the environmental impact. Likelihood considers the frequency of the activity together with the probability of an environmental impact occurring. The following tables **(Table 8 to Table 15)** describe the process in detail:

#### A. CONSEQUENCE

Consequence **(Table 8)** is calculated as the average of the sum of the ratings of severity **(Table 9)**, duration **(Table 10)** and extent **(Table 11)** of the environmental impact.

### Table 8: Determination of ConsequenceDetermination of Consequence (C)(Severity + Duration + Extent) / 3

#### H.5.1 Severity

This is an appraisal of the type of effect the activity would have on the affected environment. This description including what is being affected and how is shown in **Table 9**.

#### **Table 9: Severity Estimation**

Rating	Description
1	Negliable / non-harmful / minimal deterioration (0 – 20%)
2	Minor / potentially harmful / measurable deterioration (20 – 40%)
3	Moderate / harmful / moderate deterioration (40 – 60%)
4	Significant / very harmful / substantial deterioration (60 – 80%)
5	Irreversible / permanent / death (80 – 100%)

#### H.5.2 Extent

This indicates the spatial area that may be affected by the impact and further describes the possibility that adjoining areas may be impacted upon. This includes four classes that are listed as follows in **Table 10**:

#### Table 10: Extent of Activity Estimation

Rating	Description
1	Within immediate area of activity
2	Surrounding area within project boundary
3	Beyond project boundary
4	Regional / provincial
5	National / international

#### H.5.3 Duration

This refers to the period of time that the impact may be operative for (i.e. the lifetime of the impact). This includes the following classes that are listed as follows **Table 11**:

#### Table 11: Duration of the Impact

Rating	Description
1	Less than 1 month / quickly reversible
2	Less than 1 year / quickly reversible
3	More than 1 year / reversible over time
4	More than 10 years / reversible over time / life of project or facility
5	Beyond life of project of facility / permanent

#### B. LIKELiHOOD

Likelihood **(Table 12)** considers the frequency of the activity together with the probability of the environmental impact associated with that activity occurring.

#### Table 12: Determination of Likelihood

Determination of Likelihood (L) = (Frequency + Probability) / 2

#### H.5.4 Probability

This refers to the probability of the impact actually occurring. The following classes in **Table 13** are used to describe the probability of the impact:

Rating	Description
1	Almost impossible
2	Unlikely
3	Probable
4	Highly likely
5	Definite

#### Table 13: Probability of Impact

#### H.5.5 Frequency

This refers to the frequency of the impact actually occurring. The following classes of rating in **Table 14** are used to describe the frequency of the impact occurring:

#### Table 14: Frequency of the Impact

Rating	Description
1	Less than once a year
2	Once in a year
3	Quarterly
4	Weekly
5	Daily

#### H.5.6 Environmental Significance

The significance of the impact (i.e. whether it will lead to a marked change in the environment or not) is determined through a synthesis of the aspects produced in terms of their severity, exent, duration, probability and frequency. Therefore, Environmental significance is the product of the consequence and likelihood values. Four classes of environmental significance are tabulated in **Table 15** as follows:

- None (the impact will not have an influence on the decision and requires no mitigation)
- Low (the impact will have a limited influence on the decision and requires mitigation to manage the environment)
- Medium (it is likely that to have an influence on the decision and requires mitigation)
- High (mitigation is required and this may not be sufficient to ensure that the environment is not detrimentally affected by the proposed development

Environmental Significance (Impact) = C × L	Description
N (1 – 4.9)	None environmental significance
L (5 – 9.9)	Low environmental significance
M (10 – 14.99)	Medium environmental significance
H (15 – 25)	High environmental significance. Likely to be a fatal flaw.

**Table 15: Environmental Significance of Impact** 

H.6 Impacts and Risk identified for each alternative, including the nature, significance, consequence, extent, duration and probability of the impacts, including the degree to which these aspects can be reversed, may cause irreplaceable loss of resources and can be avoided, managed or mitigated

Table 16 to Table 19 shows the environmental significance of impacts and riskidentified for the identified alternative (preferred option) both pre-mitigationmeasures and post-mtigation measures. The environmental significance ratingof each aspects pre and post mitigation measures is contained in Appendix15.

#### Table 16: Environmental Significance of Impacts during Design and Planning Phase

DESIGN AND PLANNING PHASE			
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
Loss of vegetation	None	<ul> <li>Minimize vegetation destruction to minimum area</li> </ul>	None
Soil Erosion	None	<ul> <li>The gravel road must be constructed along the topography and channeled properly in the drainage lines using storm water channel and erosion gullies.</li> </ul>	None
Water pollution	None	<ul> <li>The Stormwater Channels must be installed in the area where the gravel road will intercept the drainage channel</li> </ul>	None
Dust generation	None	<ul> <li>TLB's to only be driven in area that is identified for road construction</li> </ul>	None
Hazardous Substance contamination	None	<ul> <li>The TLB's must be provided with drip trays when not in use</li> </ul>	None
Noise generation	None	<ul> <li>Avoid excessive revving and ignition of equipment.</li> </ul>	None
Waste pollution	None	<ul> <li>Dispose waste at registered waste disposal facility</li> </ul>	None
Fire ignition	None	<ul> <li>TLB's to always have fire extinguishers and have employees trained on their use</li> </ul>	None
Damage to existing	None	<ul> <li>Infrastructure mapping and confirmation.</li> </ul>	

Potential impacts:		Proposed mitigation:	Significance rating of impacts after mitigation:
infrastructure e.g. sewage lines			
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> </ul>	None
Traffic congestion	None	<ul> <li>Avoid traffic jamming e.g. move machinery and plant outside of rush hour</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	None
Traffic incidents	None	<ul> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None
Pedestrian injuries and route closures	None	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None
Stormwater Management	None	<ul> <li>The contractor will be advised to implement proper storm management plan</li> </ul>	None
Cultural Heritage Resources	None	<ul> <li>If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to AMAFA and SAPS.</li> </ul>	None

#### **DESIGN AND PLANNING PHASE**

CONSTRUCTION PHASE				
Loss of vegetation	None	<ul> <li>Minimize vegetation destruction to minimum area where construction operations are.</li> </ul>	None	
Soil Erosion	Medium	<ul> <li>Minimize vegetation destruction to minimum area where construction operations are.</li> <li>Divert stormwater away from the disturbed areas and loose soils</li> <li>Compact well after clearing the road</li> </ul>	None	
Water pollution	Medium	<ul> <li>Avoid soil erosion (see above)</li> <li>Avoid loss of vegetation (see above)</li> </ul>	None	
Dust generation	None	<ul> <li>Limit loss of vegetation (see above)</li> <li>Avoid over movement of plant on site</li> <li>Limit speed to 20km/hr. or less in the construction site</li> <li>Apply dust suppression regularly and as required</li> <li>Cover soil heaps</li> </ul>	None	
Hazardous Substance contamination	Medium	<ul> <li>Avoid refueling onsite</li> <li>Refueling to occur at designated areas and with drip trays installed</li> <li>Training of substance handlers for correct handling</li> </ul>	None	

### Table 17: Environmental Significance of Impacts during the Construction Phase CONSTRUCTION PHASE

Prepared by Magalela and Associates on behalf of Msinga Local Municipality

#### **CONSTRUCTION PHASE**

Noise generation	None	<ul> <li>Proper plant, machinery and motor maintenance</li> <li>Use noise reduction apparatus where applicable</li> <li>Avoid excessive revving and ignition of equipment.</li> <li>Operational hours between 07h00 and 17h00</li> </ul>	None
Waste pollution	Medium	<ul> <li>Use dedicated waste bins</li> <li>Practice waste separation (General and Hazardous)</li> <li>Dispose waste at registered waste disposal facility</li> </ul>	None
Fire ignition	Low	<ul> <li>Avoid lighting fires on site</li> <li>Ban smoking near flammable substances</li> <li>Ensure correct handling of flammable substances</li> <li>Have fire extinguishers and have employees trained on their use</li> </ul>	None
Loss of fauna and Flora	Low	<ul> <li>Avoid vegetation loss (see above)</li> <li>Avoid fires (see above)</li> <li>Avoid hazardous substance contamination of soil and water (see above)</li> <li>Prevent collection/capture of fauna by employees</li> </ul>	None
Damage to existing infrastructure e.g. sewage lines	None	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> <li>Barricade all works with barricade fence</li> <li>NO ENTRY and DANGER signs erected and maintained</li> <li>Smallest lead times between trenching and pipe burying.</li> </ul>	None

#### **CONSTRUCTION PHASE**

		<ul> <li>Close dig-up areas as soon as pipes have been laid.</li> </ul>	
Traffic congestion	Medium	<ul> <li>Avoid traffic jamming e.g. move machinery and plant outside of rush hour</li> <li>Move plant and machinery away from high traffic areas</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	None
Traffic incidents	Medium	<ul> <li>Avoid traffic congestion (see above)</li> <li>Implement traffic safety measures</li> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None
Stormwater Management	Low	• The contractor will be advised to implement proper storm management plan	None
Cultural Heritage Resources	None	<ul> <li>If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to SAPS.</li> </ul>	None

DECOMMISIONING	ГПАЗЕ		
Loss of vegetation	None	<ul> <li>Topsoil removed must be used to level the area, in order to allow the seeds to regerminate</li> <li>Indigenous vegetation (if any) will need to be relocated and planted again</li> </ul>	None
Soil Erosion	None	<ul> <li>Rows of straw, hay or bundles of cut vegetation may also be used. In this instance, the hay, straw or vegetation is dug into the soil in contours, in order to help slow surface wash and capture eroded soil.</li> <li>The spacing between rows would be dependent on slope and the specific area.</li> </ul>	None
Water pollution	Low	<ul> <li>Waste Materials collected on site after decommisiong the site must not be diverted into nearby water courses</li> </ul>	None
Dust generation	Low	<ul> <li>Avoid over movement of plant on site</li> <li>Limit speed to 20km/hr. or less in the construction site</li> </ul>	None
Hazardous Substance contamination	Low	<ul> <li>Refueling to occur at designated areas and with drip trays installed</li> <li>All waste material generated on site must be disposed off at registererd hazardous landfill site.</li> <li>Proof of disposal must be made available to Site Engineer</li> </ul>	None
Noise generation	None	<ul> <li>Avoid excessive revving and ignition of equipment.</li> <li>Operational hours between 07h00 and 17h00</li> </ul>	None
Waste pollution	None	<ul> <li>Use dedicated waste bins</li> </ul>	None

### Table 18: Environmental Significance of Impacts during Decommisioning Phase DECOMMISIONING PHASE

		<ul> <li>Practice waste separation (General and Hazardous)</li> </ul>	
		<ul> <li>Dispose waste at registered waste disposal facility</li> </ul>	
Fire ignition	None	<ul> <li>Avoid lighting fires on site</li> <li>Ban smoking near flammable substances</li> <li>Ensure correct handling of flammable substances</li> <li>Have fire extinguishers and have employees trained on their use</li> </ul>	None
Loss of fauna and Flora	None	<ul> <li>Rehabilitate the area workings within the water course to allow natural flows</li> <li>Remove structures that can impede natural flow in the water</li> <li>Use Gabion baskets and Rhino mattress to stabilize river banks</li> </ul>	None
Damage to existing infrastructure e.g. sewage lines	None	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> <li>Barricade all works with barricade fence</li> <li>NO ENTRY and DANGER signs erected and maintained</li> <li>Smallest lead times between trenching and pipe burying.</li> <li>Close dig-up areas as soon as pipes have been laid.</li> </ul>	None
Traffic congestion	Low	<ul> <li>Avoid traffic jamming e.g. move machinery and plant</li> </ul>	None

		<ul> <li>outside of rush hour</li> <li>Move plant and machinery away from high traffic areas</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	
Traffic incidents	Low	<ul> <li>Avoid traffic congestion (see above)</li> <li>Implement traffic safety measures</li> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None
Pedestrian injuries and route closures	Low	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None
Stormwater Management	None	<ul> <li>The design of drainage and stormwater pipes should be to reduce flow velocity and avoid soil erosion. This can be achieved through the construction of water velocity dissipators below the pipe head wall.</li> <li>Rocks, boulders or concrete blocks may be utilised for these purposes, and they are set into the concrete pron below the headwall. Stone pitching may also be utilised.</li> </ul>	None

#### Table 19: Environmental Significance of Impacts during Operational Phase

<b>OPERATION PHASE</b>			
Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
Soil Erosion	Low	<ul> <li>Implement the appropriate topsoil and stormwater runoff control management measures to prevent the loss of topsoil.</li> <li>The site should be graded well to permit drainage and to prevent ponding</li> </ul>	None
Water pollution	Low	<ul> <li>Dust suppression must be conducted to minimal level to avoiding flooding of gravel road</li> </ul>	None
Loss of fauna and Flora	Low	<ul> <li>Trees and shrubs conserved shall be clearly introduced to the site under the supervision of the Project Enginner.</li> </ul>	None
Damage to existing infrastructure e.g. sewage lines	Low	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None
Traffic incidents	Medium	<ul> <li>Dust suppression must be conducted to minimal level to avoiding flooding of gravel road Install illuminating warning lights, traffic calming structures, etc. should flooding be the resultant impact</li> <li>Use flagman to slow and direct traffic</li> </ul>	None
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from pipe burst areas</li> <li>Use barricades and signage</li> </ul>	None

Prepared by Magalela and Associates on behalf of Msinga Local Municipality

<b>OPERATION PHASE</b>			
Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
		<ul> <li>Prevent unauthorized access to working areas</li> </ul>	
Stormwater Management	Low	<ul> <li>Ensure effective storm water management will be exercised to limit negative impacts on the environment and enhance the positive impacts</li> <li>All contaminated standing water should be immediately removed and treated or disposed of appropriately.</li> <li>Surfaces and conduits should be constructed to drain the run off more efficiently</li> </ul>	None

#### H.7 Positive and negative impacts that the proposed activity and alternatives will have on the environment and on the community that may be affected focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects

**Table 20** shows the positive and negative impacts the proposed activity will have on the environment and on the community that may be affected focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects.

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
Gradient of the site	1.5 -1.2 m	Positive , no change	Positive, as the gravel	<b><u>Positive</u></b> , as the gravel
		to the gradient of	road will follow the slope	road will follow the
		the site	of the area.	slope of the area.
Location in	Undulating	Positive, there will	Positive, as the gravel	Positive, as the gravel
Landscape	plain/low hills	be no change in	road will be following the	will be following the
		Landscape	land scape	land scape
Groundwater	Water table below	Positive, No drilling	Positive, No drilling will	<u><b>Positive</b></u> , No drilling will
	1.5m deep	will conducted for	conducted for road	conducted for road
		road survey of	survey of gravel roads.	survey of gravel roads.
		gravel roads.		
Soil	Often Dry hard soil	Positive, No soil will	Positive, minimal soil will	Negative, the
	in the area	be removed during	be removed, as top soil	excavated portion of
		the road survey.	will also be used to	the gravel road will be
			compact the gravel	permanent as it will be
			road.	compacted to avoid
				regermiantion of
				vegatation on the road.

 Table 20: Positive and Negative Impacts on the Environmental Attributes

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
Geological Stability	The geology is	Positive, No drilling	<b><u>Positive</u></b> , the ground will	Negative, the
	rocky but stable	will conducted for	only be excavated	excavated portion of
		road survey of	limited along the	the gravel road will be
		gravel roads.	surveyed gravel road	soft and dry during
			route	backfilling process and
				will take longer to
				harden to pre-soil
				condition structural
				properties
Groundcover	Natural veld with	Positive, No	Negative, as the natural	Negative, as the natural
	heavy alien	excavations will be	veld cover will be lost	veldcover will not
	infestation	conducted during	during the excavations	regerminate on the
		the survey		compacted surface
Land use character	The area is	Positive, No	Positive, the gravel road	Positive, the gravel road
of surrounding area	charecterised by	excavations will be	will be following the	will be following the
	vacant land,	conducted during	existing gravel roads that	existing gravel roads
	followed by rural	the survey	are in bad condition and	that are in bad

Environmental Description Design and Planning During Construction – Post Construction **Attributes** (Positive (Positive / Negative (Positive / Negative Negative / Impact Impact) Impact) condition and will now community will now be accessible for settlement. of basic be accessible for use The use interms services. interms of aravel road basic services. crosses nonperenial streams reach other to of sites the settlements Cultural Positive, there Positive, as there are no and There are as **Positive**, as there are no no Historical Features cultural/historical are no cultural and cultural and historical cultural and historical features affected historical features features affected by the features affected by by the aravel road affected by aravel road. the aravel road. the gravel road. Social proiect **Positive**, as the project **Positive**, as the project The will Positive. and the as Economic aspect create project will will be creating jobs and will be creating jobs be employment creating improving the lives of the and improving the lives iobs and opportunities improving the lives community as there will of the community as

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
	during	of the community as	now be acess to basic	there will now be acess
	construction	there will now be	serives.	to basic serives.
	phase	acess to basic		
		serives.		

H.8 The possible mitigation measures that could be applied and level of residual risk

Table 21 demonstrate mitigation measures to negate negative impacts on theenvironmental attributes.

Environmental	Impact	<b>Construction Stage</b>	Mitigation Measures
Attribute			
Soil	Negative, the excavated portion	Post Construction	The road compaction process
	of the gravel road will be		must be supervised by the
	permanent as it will be		profeesional engineer, to avoid
	compacted to avoid		soil erosion that can lead to
	regermiantion of vegatation on		dongas creasing the road.
	the road.		
Geological Stability	Negative, the excavated portion	Post Construction	The road compaction process
	of the gravel road will be soft and		must be supervised by the
	dry during backfilling process and		profeesional engineer, to avoid
	will take longer to harden to pre-		soil erosion that can lead to
	soil condition structural properties		dongas creasing the road.
Groundcover	Negative, as the natural veld	During Construction	Top soil stock piling must be well
	cover will be lost during the		protected and cordoned off
	excavations		from other soil material
			generated on site, so as to allow
			natural seeds to regerminate
			successfully during the

#### Table 21: Mitigation Measures to negate Negative Impacts on the Environmental Attributes

Environmental	Impact	<b>Construction Stage</b>	Mitigation Measures
Attribute			
			rehabilitation of construction
			works
Groundcover	<b><u>Negative</u></b> , as the natural	Post Construction	The road compaction process
	veldcover will not regerminate on		must be supervised by the
	the compacted surface		profeesional engineer, to avoid
			soil erosion that can lead to
			dongas creasing the road.

#### H.9 The outcome of the site selection matrix

# PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

H.10 If no alternatives, including alternative locations for the activity were investigated, the motivation for not considering such.

## PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

H.11 A concluding statement indicating the preferred alternatives, including preferred location of the activity

## PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

As a result the community will now be able to benefit from the gravel road construction as the basic services, such as ambulance, police vehicles and municipal services.

## I. Full description of the process undertaken to identify, assess and rank the impacts the activity will impose on the preferred location through the life of activity.

Table 22 to Table 25 shows the environmental significance of impacts and riskidentified for the identified alternative (preferred option) both pre-mitigationmeasures and post-mtigation measures. The environmental significance ratingof each aspects pre and post mitigation measures is contained in Appendix15.

The cummaltive impacts associated with the project life cycle is demonstrated in **Table 26 to Table 28**.

DESIGN AND PLANN	DESIGN AND PLANNING PHASE				
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:		
Loss of vegetation	None	<ul> <li>Minimize vegetation destruction to minimum area</li> </ul>	None		
Soil Erosion	None	<ul> <li>The gravel road must be constructed along the topography and channeled properly in the drainage lines using storm water channel and erosion gullies.</li> </ul>	None		
Water pollution	None	<ul> <li>The Stormwater Channels must be installed in the area where the grave road will intercept the drainage channel</li> </ul>	None		
Dust generation	None	<ul> <li>TLB's to only be driven in area that is identified for road construction</li> </ul>	None		
Hazardous Substance contamination	None	<ul> <li>The TLB's must be provided with drip trays when not in use</li> </ul>	None		
Noise generation	None	<ul> <li>Avoid excessive revving and ignition of equipment.</li> </ul>	None		
Waste pollution	None	<ul> <li>Dispose waste at registered waste disposal facility</li> </ul>	None		
Fire ignition	None	<ul> <li>TLB's to always have fire extinguishers and have employees trained on their use</li> </ul>	None		
Damage to existing	None	<ul> <li>Infrastructure mapping and confirmation.</li> </ul>			

Potential impacts:		Proposed mitigation:	Significance rating of impacts after mitigation:
infrastructure e.g. sewage lines			
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> </ul>	None
Traffic congestion	None	<ul> <li>Avoid traffic jamming e.g. move machinery and plant outside of rush hour</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	None
Traffic incidents	None	<ul> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None
Pedestrian injuries and route closures	None	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None
Stormwater Management	None	<ul> <li>The contractor will be advised to implement proper storm management plan</li> </ul>	None
Cultural Heritage Resources	None	<ul> <li>If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to AMAFA and SAPS.</li> </ul>	None

#### **DESIGN AND PLANNING PHASE**

#### Table 23: Environmental Significance of Impact of the Prefered Alternative during Construction Phase

CONSTRUCTION PHA	CONSTRUCTION PHASE				
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:		
Loss of vegetation	None	<ul> <li>Minimize vegetation destruction to minimum area where construction operations are.</li> </ul>	None		
Soil Erosion	Medium	<ul> <li>Minimize vegetation destruction to minimum area where construction operations are.</li> <li>Divert stormwater away from the disturbed areas and loose soils</li> <li>Compact well after clearing the road</li> </ul>	None		
Water pollution	Medium	<ul> <li>Avoid soil erosion (see above)</li> <li>Avoid loss of vegetation (see above)</li> </ul>	None		
Dust generation	None	<ul> <li>Limit loss of vegetation (see above)</li> <li>Avoid over movement of plant on site</li> <li>Limit speed to 20km/hr. or less in the construction site</li> <li>Apply dust suppression regularly and as required</li> <li>Cover soil heaps</li> </ul>	None		
Hazardous Substance contamination	Medium	<ul> <li>Avoid refueling onsite</li> <li>Refueling to occur at designated areas and with drip trays installed</li> </ul>	None		

Potential impacts: Significance rating of impacts:		Proposed mitigation:	Significance rating of impacts after mitigation:	
		<ul> <li>Training of substance handlers for correct handling</li> </ul>		
Noise generation	None	<ul> <li>Proper plant, machinery and motor maintenance</li> <li>Use noise reduction apparatus where applicable</li> <li>Avoid excessive revving and ignition of equipment.</li> <li>Operational hours between 07h00 and 17h00</li> </ul>	None	
Waste pollution	Medium	<ul> <li>Use dedicated waste bins</li> <li>Practice waste separation (General and Hazardous)</li> <li>Dispose waste at registered waste disposal facility</li> </ul>	None	
Fire ignition	Low	<ul> <li>Avoid lighting fires on site</li> <li>Ban smoking near flammable substances</li> <li>Ensure correct handling of flammable substances</li> <li>Have fire extinguishers and have employees trained on their use</li> </ul>	None	
Loss of fauna and Flora	Low	<ul> <li>Avoid vegetation loss (see above)</li> <li>Avoid fires (see above)</li> <li>Avoid hazardous substance contamination of soil and water (see above)</li> <li>Prevent collection/capture of fauna by employees</li> </ul>	None	
Damage to existing infrastructure e.g. sewage lines	None	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None	
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> <li>Barricade all works with barricade fence</li> <li>NO ENTRY and DANGER signs erected and maintained</li> <li>Smallest lead times between trenching and pipe</li> </ul>	None	

CONSTRUCTION PHA	SE			
Potential impacts:	Potential impacts: Significance Proposed mitigation: rating of impacts:		Significance rating of impacts after mitigation:	
		<ul><li>burying.</li><li>Close dig-up areas as soon as pipes have been laid.</li></ul>		
Traffic congestion	Medium	<ul> <li>Avoid traffic jamming e.g. move machinery and plant outside of rush hour</li> <li>Move plant and machinery away from high traffic areas</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	None	
Traffic incidents	Medium	<ul> <li>Avoid traffic congestion (see above)</li> <li>Implement traffic safety measures</li> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None	
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>		
Stormwater Management	Low	<ul> <li>The contractor will be advised to implement proper None storm management plan</li> </ul>		
Cultural Heritage Resources	None	<ul> <li>If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to SAPS.</li> </ul>		

Table 24: Environmental Significance of Impact on the Prefered Alternative during Decommisioning Phase	
DECOMMISIONING PHASE	

Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures
Loss of vegetation	None	<ul> <li>Topsoil removed must be used to level the area, in order to allow the seeds to regerminate</li> <li>Indigenous vegetation (if any) will need to be relocated and planted again</li> </ul>	None
Soil Erosion	None	<ul> <li>Rows of straw, hay or bundles of cut vegetation may also be used. In this instance, the hay, straw or vegetation is dug into the soil in contours, in order to help slow surface wash and capture eroded soil.</li> <li>The spacing between rows would be dependent on slope and the specific area.</li> </ul>	
Water pollution	Low	<ul> <li>Waste Materials collected on site after decommisiong the site must not be diverted into nearby water courses</li> </ul>	None
Dust generation	Low	<ul> <li>Avoid over movement of plant on site</li> <li>Limit speed to 20km/hr. or less in the construction site</li> </ul>	
Hazardous Substance contamination	Low	<ul> <li>Refueling to occur at designated areas and with drip trays installed</li> <li>All waste material generated on site must be disposed off at registererd hazardous landfill site.</li> <li>Proof of disposal must be made available to Site Engineer</li> </ul>	None
Noise generation	None	<ul> <li>Avoid excessive revving and ignition of equipment.</li> <li>Operational hours between 07h00 and 17h00</li> </ul>	
Waste pollution	None	Use dedicated waste bins	None

DECOMMISIONING PHASE					
Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures		
		<ul> <li>Practice waste separation (General and Hazardous)</li> <li>Dispose waste at registered waste disposal facility</li> </ul>			
Fire ignition	None	<ul> <li>Avoid lighting fires on site</li> <li>Ban smoking near flammable substances</li> <li>Ensure correct handling of flammable substances</li> <li>Have fire extinguishers and have employees trained on their use</li> </ul>	None		
Loss of fauna and Flora	None	<ul> <li>Rehabilitate the area workings within the water course to allow natural flows</li> <li>Remove structures that can impede natural flow in the water</li> <li>Use Gabion baskets and Rhino mattress to stabilize river banks</li> </ul>	None		
Damage to existing infrastructure e.g. sewage lines	None	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None		
Injury to public and animals due to falling into workings	None	<ul> <li>Prevent unauthorized entry to the working area</li> <li>Barricade all works with barricade fence</li> <li>NO ENTRY and DANGER signs erected and maintained</li> <li>Smallest lead times between trenching and pipe burying.</li> <li>Close dig-up areas as soon as pipes have been laid.</li> </ul>	None		
Traffic congestion	Low	<ul> <li>Avoid traffic jamming e.g. move machinery and plant</li> </ul>	None		

DECOMMISIONING I			
Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures
		outside of rush hour	
		<ul> <li>Move plant and machinery away from high traffic</li> </ul>	
		<ul><li>areas</li><li>Plan work area to minimize traffic obstruction</li></ul>	
Traffic incidents	Low	<ul> <li>Avoid traffic congestion (see above)</li> </ul>	None
		<ul> <li>Implement traffic safety measures</li> </ul>	
		<ul> <li>Install illuminating warning lights, traffic calming</li> </ul>	
		<ul> <li>structures, etc.</li> <li>Use flaaman to slow and direct traffic</li> </ul>	
Pedestrian injuries	Low	<ul> <li>Use flagman to slow and direct traffic</li> <li>Redirect pedestrians away from working areas</li> </ul>	None
and route closures		<ul> <li>Use barricades and signage</li> </ul>	
		<ul> <li>Prevent unauthorized access to working areas</li> </ul>	
Stormwater	None	<ul> <li>The design of drainage and stormwater pipes should</li> </ul>	None
Management		be to reduce flow velocity and avoid soil erosion. This can be achieved through the construction of water	
		velocity dissipators below the pipe head wall.	
		<ul> <li>Rocks, boulders or concrete blocks may be utilised for</li> </ul>	
		these purposes, and they are set into the concrete	
		pron below the headwall. Stone pitching may also be utilised.	

<b>OPERATION PHASE</b>	-		
Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
Soil Erosion	Low	<ul> <li>Implement the appropriate topsoil and stormwater runoff control management measures to prevent the loss of topsoil.</li> <li>The site should be graded well to permit drainage and to prevent ponding</li> </ul>	None
Water pollution	Low	<ul> <li>A comprehensive water pressure management must be adhered to prevent pressure build ups resulting in pipe burst</li> <li>A use pressure reducing valves must be implemented</li> </ul>	None
Loss of fauna and Flora	Low	<ul> <li>Trees and shrubs conserved shall be clearly introduced to the site under the supervision of the Project Enginner.</li> <li>This trees cannot be planted directly on the pipeline, but appropriate planting site must be negotiated well with all interest and affected parties</li> <li>Pipeline crossing over the stream must always be freed of debris building up</li> </ul>	None
Damage to existing infrastructure e.g. sewage lines	Low	<ul> <li>Infrastructure mapping and confirmation.</li> <li>Servitude applications</li> <li>Contingency and emergency measures</li> </ul>	None
Traffic incidents	Medium	<ul> <li>A comprehensive water pressure management must</li> </ul>	None

Table 25: Environmnetal Significance of Impact of Prefered Alternative during Operation Phase

Prepared by Magalela and Associates on behalf of Msinga Local Municipality

<b>OPERATION PHASE</b>			
Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
		<ul> <li>be adhered to prevent pressure build ups resulting in pipe burst</li> <li>A use pressure reducing valves must be implemented</li> <li>Implement traffic safety measures in case of pipe burst</li> <li>Install illuminating warning lights, traffic calming structures, etc. should flooding be the resultant impact</li> <li>Use flagman to slow and direct traffic</li> </ul>	
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from pipe burst areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None
Stormwater Management	Low	<ul> <li>Ensure effective storm water management will be exercised to limit negative impacts on the environment and enhance the positive impacts</li> <li>All contaminated standing water should be immediately removed and treated or disposed of appropriately.</li> <li>Surfaces and conduits should be constructed to drain the run off more efficiently</li> </ul>	None

CONSTRUCTION PH	CONSTRUCTION PHASE					
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:	Cumulative Impact		
Soil Erosion	Medium	<ul> <li>Minimize vegetation destruction to minimum area where construction operations are.</li> <li>Divert stormwater away from the disturbed areas and loose soils</li> <li>Compact well after clearing the road</li> </ul>	None	Creation of dongas along the road, which could lead to sinkholes in the area.		
Water pollution	Medium	<ul><li>Avoid soil erosion (see above)</li><li>Avoid loss of vegetation</li></ul>	None	Loss of water quality of the streams in the area.		
Hazardous Substance contamination	Medium	<ul> <li>Avoid refueling onsite</li> <li>Refueling to occur at designated areas and with drip trays installed</li> <li>Training of substance handlers for correct handling</li> </ul>	None	Loss of land capability and groundwater pollution due to Oil and Grease contamination		
Waste pollution	Medium	<ul> <li>Use dedicated waste bins</li> <li>Practice waste separation (General and Hazardous)</li> <li>Dispose waste at registered waste disposal facility</li> </ul>	None	Creation of illegal dumping site and could cause significant health hazard to the surrounding community and living animals		

Table 26: Cumulative Impacts of Prefered Alternative during Construction Phase

	CONSTRUCTION PHASE				
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:	Cumulative Impact	
Traffic congestion	Medium	<ul> <li>Avoid traffic jamming e.g. move machinery and plant outside of rush hour</li> <li>Move plant and machinery away from high traffic areas</li> <li>Plan work area to minimize traffic obstruction</li> </ul>	None	Traffic Congestions may lead to illegal driving and creation of alternative routes around the works leading to damage of the surrounding environments, and infrastructure.	
Traffic incidents	Medium	<ul> <li>Avoid traffic congestion (see above)</li> <li>Implement traffic safety measures</li> <li>Install illuminating warning lights, traffic calming structures, etc.</li> <li>Use flagman to slow and direct traffic</li> </ul>	None	Road closures my lead to road rages by motorist to fellow motorists or pedestrians	
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from working areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None	Public injuries may lead to negativity by the communities against the project	

 Table 27: Cumalative Impact of Prefered Alternative during Decommisioning Phase

Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation	Cumulative Impact
N/A	N/A	N/A	measures N/A	N/A

#### **DECOMMISIONING PHASE**

Table 28: Cumulative Impact of Prefered Alternative during the Operation Phase

OPERATION PHASE							
Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures	Cumulative Impact			
Traffic incidents	Medium	<ul> <li>A comprehensive water pressure management must be adhered to prevent pressure build ups resulting in pipe burst</li> <li>A use pressure reducing valves must be implemented</li> <li>Implement traffic safety measures in case of pipe burst</li> <li>Install illuminating warning</li> </ul>		<ul> <li>Background leaking of pipelines, that leads unaccounted for water in the system</li> </ul>			

Prepared by Magalela and Associates on behalf of Msinga Local Municipality

Potential impacts:		Proposed mitigation measures	Significance rating of impacts after rehabilitation	Cumulative Impact
			measures	
		<ul> <li>lights, traffic calming structures, etc. should flooding be the resultant impact</li> <li>Use flagman to slow and direct traffic</li> </ul>		
Pedestrian injuries and route closures	Medium	<ul> <li>Redirect pedestrians away from pipe burst areas</li> <li>Use barricades and signage</li> <li>Prevent unauthorized access to working areas</li> </ul>	None	<ul> <li>Background leaking of pipelines, that leads unaccounted for water in the system</li> </ul>

J. A summary of the findings and impact management measures identified in any of specialist report complying with Appendix 6 to these regulations and a indication as to how these finding and recommendations have been included in the final report

### K. An environmental impact statement

The impact associated with the construction of the gravel road in this village have been adequately assessed in this report at different phase of the life of activity of the project i.e planning and design phase, construction phase, decommissioning phase and operational phase.

A map is attached herewith in **Appendix 16** showing the proposed activity and its associated infrastructure in relation to environmental sensitivity of the site. The objective here is delineate where feasible the areas that are sensitive and proper care and due diligence must be activated during the construction, rehabilitation and operation of the project. **Appendix 21** details the proposed Engineering Design of the Gravel Road.

There will be less environmental significance during the planning and design phase, as much of the work is designed around ground trothing and review of the information in the general public domain.

During the construction phase, there are aspects of construction that needs to managed accordingly to reduce the environmental significance of the impacts. The Environmental Management Programme (EMPr) to manage and monitor mitigation of this impacts by the contractor.

Although an aspect might have a rating of none or low environmental significance, that aspect might have cumulative impact if not properly managed. In this case some of issues such as management of soil generated on site as well as loss of vegetation, noise of construction machinery and traffic management if not properly mitigated can have high environmental significance and makes the whole project undesirable to the environment.

Aspect such as, refueling at dedicated fuel storage, improper waste management practices and insufficient traffic management practice have a medium environmental significance. If the aspects are not monitored as per the recommended mitigation measures, they will also trigger high environmental significance, and thus the desirable objective of the will not be realized. This will have negative consequences as the community will continue without access to basic service guaranteed by the Constitution of the Republic of South Africa.

It is therefore desirable that the Project Manager appoint the Environmental Control Officer whom's primary responsibility is to ensure compliance by the Contractor with all the mitigation measures contained in the EMPr.

The negative environmtal impact of the project on the environmental attributes are far outweighed by the sole delivery of the basic services of acess road provision to the people. Therefore, although there will be such negative effect on the environment, the mititigation measures recommended must be adhered to as will be outlined in the EMPr.

It is therefore imperative that EMPr is well versed with the contractor during the construction and rehabilitation phase.

L. Environmental Management Programme including where applicable impact management measures from specialist report, the recording of the proposed impact management objectives, and the impact management outcomes for the development

The Environmental Management Programme is attached herewith in **Appendix 17** of this report.

M. Any aspects which were conditional to the finding of the assessment either by the EAP or specialist which are to be included as conditions of authorization

N. A description of any assumptions, uncertainities, gaps in knowledge which relate to the assessment and mitigation measures proposed

## O. A reasoned opinion as to whether the proposed activity should or should not be authorized, and if the opinion is that it should be authorized, any conditions that should be made in respect of that authorization

The government's Integrated Sustainable Rural Development Strategy (ISRDS) as incepted in October 2001 gave birth to a programme that focussed to achieve integrated sustainable development in the rural areas. This programme selected nodes based on identified local development problems and opportunities. Its aim is to respond to indicators of poverty and economic opportunities.

The current access road provides a thoroughfare for the local villagers and farm workers. There is virtually no public transport facility available. The proposed access is currently a clayey loamy gravel track road approximately 3,5m wide traversing over rolling mountainous terrain with steep inclines and side cuts. There are rock (Shale) outcrops in several isolated areas making road condition harsh and difficult and sometimes inaccessible especially during the frequent rainy periods.

As per Msinga Local Municipality IDP 2015/2016, and uMzinyathi Backlog Study (2007) determined road backlogs based on hut count data in the Traditional Authority areas indicates that 58% of households have inadequate access to roads.

The Road Infrastructure Strategic Framework for South Africa (RIFSA) classifications indicates a major dependency on lower order access roads for most of the residents within Msinga Local Municipality. With the high dependency on the lower order nodes, it is necessary to ensure proper transport infrastructure exist, especially with the view of creating economic growth in the municipality, which positively affects everybody. Should the

residents not have proper access to opportunities; the initiatives will not be successful.

The environmental impact assessment concluded that, yes, during implementation of magnitude of this project there will be temporal loss of certain environmental attributes along the route of target delivery community. Thus, we have appreciated that and acknowledge the loss. However the profound nature of this acess road negates the temporal environmental losses we are going to lose. We still have to protect same by the way. But the mitigation measures we recommend to be put in place to manage this less environmental significance impacts, should allow us to restore the environment to its close pristine conditions albeit not equivalent.

It is against this background that, I have assessed and processed all the possible environmental impacts within my knowledge that could be associated with the construction of 6.9 km gravel road in Mabaso Village and its desirable objectives, thus:-

I can, soundly recommend to the KwaZulu Natal Department of Economic Development, Tourism and Environmental Affairs <u>to authorize</u> Construction of 6.9km gravel road in Mabaso Village as proposed by Msinga Local Municipality.

This recommendation has the following bearing on to Municipality implementing in its entirety the mitigation measures and conditions suggested elsewhere in this report, contained in the **Environmental Management Programme (EMPr) dated August 2015** and further management measures and conditions recommended by the responding Authority.

P. Where the proposed activity does not include operational aspects, the period for which the environmental authorization is required, the date on which the activity will be concluded, and the post construction monitoring requiremnts

# Q. An undertaking under oath or affirmation by the EAP in relation to:

#### I, **KGOMOTSO MOTSEPE** declare that I

- am the independent environmental practitioner in this application;
- will comply with the requirements for an EAP as stipulated in Regulation 13 of the EIA Regulations, 2014;
- do not have and will not have any vested interest (either business, financial, personal or other) in the undertaking of the proposed activity, other than remuneration for work performed in terms of the Environmental Impact Assessment Regulations, 2014;
- will perform the work relating to the application in an objective manner, even if this results in views and findings that are not favourable to the applicant;
- declare that there are no circumstances that may compromise my objectivity in performing such work;
- have expertise in conducting environmental impact assessments, including knowledge of the National Environmental Management Act, 1998 (Act107 of 1998), regulations and any guidelines that have relevance to the proposed activity;
- will comply with the National Environmental Management Act, 1998 (Act107 of 1998), regulations and all other applicable legislation;
- undertake to disclose to the applicant and the KZN Department of Economic Development, Tourism & Environmental Affairs all material information in my possession that reasonably has or may have the potential of influencing its decision with respect to this application;
- will ensure that information containing all reports in respect of this application is distributed or made available to interested and affected parties and that their participation is facilitated in such a manner that they will be provided with a reasonable opportunity to participate and provide comments on the reports;
- will provide the competent authority with access to all information at my disposal regarding this application, whether such information is favourable to the applicant or not;
- declare that all the particulars furnished by me in this form are true and correct;
- I am aware that a person is guilty of an offence in terms of Regulation 48 (1) of the EIA Regulations, 2014, if that person provides incorrect or misleading information. A person who is convicted of an offence in terms of sub-regulation 48(1) (a)-(e) is liable to the penalties as contemplated in section 49B(1) of the National Environmental Management Act, 1998 (Act 107 of 1998); and

• I will comply with all the requirements as indicated in the National Environmental Management Act, 1998 (Act 107 of 1998) and Environmental Impact Assessment Regulations, 2014.

Name of the Environmental Assessment Practitioner

Signature of the Environmental Assessment Practitioner

Name of company

Date

Name of Commissioner of Oaths

Signature of Commissioner of Oaths

Date

Designation

Official stamp (below)

R. Where applicable, details of any financial provisions for rehabilitation, closure, and ongoing post decommissioning management of negative environmental impacts

# S. Any specific information that may be required by the competent authority

T. Any other matters required in terms of section 24(4)(a) and (b) of the Act