APPLICATION FOR ENVIRONMENTAL AUTHORISATION FOR PROPOSED CONSTRUCTION OF 7.6 KM GRAVEL ROAD IN OBISINI VILLAGE, MSINGA LOCAL MUNICIPALITY – REF. NUMBER:

DC24/0006/2016_KZN/EIA/0000 315/2016





MSINGA LOCAL MUNICIPALITY



BASIC ASSESSMENT REPORT

SUBMITTED TO:
PROVINCE OF KWAZULU NATAL
DEPARTMENT OF ECONOMIC
DEVELOPMENT, TOURISM AND
ENVIRONMENTAL AFFAIRS



Private Bag X1048 Richardsbay 3900

SUBMITTED BY:

Magalela and Associates Tel: 031 535 7094 Fax: 086 556 5646

E-Mail: info@magalelas.co.za

Mobile: 071 307 2675 Contact Person: Simphiwe Mtshali



30 AUGUST 2016

Project Title: CONSTRUCTION OF 7.6 KM GRAVEL ROAD IN OBISINI VILLAGE, MSINGA LOCAL MUNICIPALITY Report Title APPLICATION FOR ENVIRONMENTAL AUTHORISATION FOR PROPOSED CONSTRUCTION OF 7.6 KM GRAVEL ROAD OBISINI VILLAGE, IN MSINGA LOCAL MUNICIPALITY DETEA REFERENCE DC24/0006/2016_KZN/EIA/0000315/2016 NUMBER EAP Author K Motsepe, Pr. Nat.Sci **Revision** Date **Report Status** Draft 1 26/07/2016 First draft for comments by stakeholders Final 01/09/2016 Final Consultants: Magalela & Associates Approved for Consultants by: Mr. S Mtshali, Pr. Nat. Sci. Technical Study Specialist Client: Msinga Local Municipality Approved for MSINGA LOCAL MUNICIPALITY:

Mr. S Sokhela

BASIC ASSESSMENT REPORT

Submitted in requirements of the Environmental Impact Assessment Regulations, December 2014 promulgated in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998)

TABLE OF CONTENTS

<u>A.</u>	DETAILS AND EXPERTISE OF ENVIRONMENTAL ASSESSMENT PRACTITIONER (EAP)	9
<u>B.</u> VIL	THE LOCATION DESCRIPTION AND LOCALITY MAP OF 7.6 KM GRAVEL ROAD IN OBISINI LAGE, MSINGA LOCAL MUNICIPALITY	10
<u>c.</u>	LAYOUT PLAN OF THE CONSTRUCTION OF GRAVEL ROAD	12
<u>C.</u>	LATOUT PLAN OF THE CONSTRUCTION OF GRAVLE ROAD	12
<u>D.</u>	DESCRIPTION OF THE SCOPE OF THE PROPOSED CONSTRUCTION OF 7.6 KM GRAVEL RO	
<u>OB</u>	ISINI VILLAGE	13
<u>E.</u>	DESCRIPTION OF THE POLICY AND LEGISLATIVE CONTEXT WITHIN WHICH CONSTRUCTION	ON OF
<u>GR</u>	AVEL ROAD FALLS	16
	MOTIVATION FOR THE NEED AND DESIRABILITY FOR THE PROPOSED CONSTRUCTION ON NSTRUCTION OF 7.6 KM GRAVEL ROAD IN OBISINI VILLAGE INCLUDING THE NEED AND SIRABILITY OF THE ACTIVITY IN THE CONTEXT OF THE PREFERRED LOCATION	<u>19</u>
<u>G.</u>	MOTIVATION FOR THE PREFERRED SITE, ACTIVITY AND TECHNOLOGY ALTERNATIVE	20
<u>H.</u>	A FULL DESCRIPTION OF THE PROCESS FOLLOWED TO REACH THE PROPOSED PREFERR	ED.
AL ⁷	TERNATIVE WITHIN THE SITE	21
	DETAILS OF ALL THE ALTERNATIVE CONSIDERED	21
	DETAILS OF THE PUBLIC PARTICIPATION PROCESS (PPP) UNDERTAKEN INTERMS OF REGULATION 41 INCL	
	PIES OF THE SUPPORTING DOCUMENTS AND INPUTS	22
	2.1 IDENTIFICATION OF STAKEHOLDERS	22
	2.2 ANNOUNCEMENT OF THE PROJECT	22
	2.3 MEETINGS	22 23
	2.4 Site Notice 2.5 Newspaper Advertisement	23
	SUMMARY OF ISSSUES RAISED BY INTERESTED AND AFFECTED PARTIES (I&AP'S)	23 24
_	ENVIRONMENTAL ATTRIBUTES ASSOCIATED WITH ALTERNATIVES FOCUSING ON THE GEOGRAPHICAL,	41
_	YSISCAL, BIOLOGICAL, SOCIAL, ECONOMIC, HERITAGE AND CULTURAL ASPECTS	25
	THE METHODOLOGY USED IN DETERMINING AND RANKING THE NATURE/SEVERITY, SIGNIFICANCE,	
_	NSEQUENCE, EXTENT, DURATION AND PROBABILITY OF POTENTIAL ENVIRONMENTAL IMPACTS AND RISK	
	OCIATED WITH ALTERNATIVES	26
H.5	5.1 Severity	26
H.5	5.2 EXTENT	27
H.5	5.3 Duration	27
	LIKELIHOOD	27
	5.4 Probability	28
	5.5 FREQUENCY	28
	5.6 Environmental Significance	28
	MPACTS AND RISK IDENTIFIED FOR EACH ALTERNATIVE, INCLUDING THE NATURE, SIGNIFICANCE,	
	NSEQUENCE, EXTENT, DURATION AND PROBABILITY OF THE IMPACTS, INCLUDING THE DEGREE TO WHICH TH	
	PECTS CAN BE REVERSED, MAY CAUSE IRREPLACEABLE LOSS OF RESOURCES AND CAN BE AVOIDED, MANAGE	
MIL	TIGATED TO THE PROPERTY OF THE	30

H.7 Positive and negative impacts that the proposed activity and alter		
ENVIRONMENT AND ON THE COMMUNITY THAT MAY BE AFFECTED FOCUSING ON	,	
BIOLOGICAL, SOCIAL, ECONOMIC, HERITAGE AND CULTURAL ASPECTS		1
H.8 The possible mitigation measures that could be applied and level o		ŀ6
H.9 THE OUTCOME OF THE SITE SELECTION MATRIX		١9
H.10 IF NO ALTERNATIVES, INCLUDING ALTERNATIVE LOCATIONS FOR THE ACTIVIT		
MOTIVATION FOR NOT CONSIDERING SUCH.		60
H. 11 A CONCLUDING STATEMENT INDICATING THE PREFERRED ALTERNATIVES, INC		
THE ACTIVITY	5	51
I. FULL DESCRIPTION OF THE PROCESS UNDERTAKEN TO IDENTIFY	ASSESS AND RANK THE	
IMPACTS THE ACTIVITY WILL IMPOSE ON THE PREFERRED LOCATION	,	
ACTIVITY.		52
J. A SUMMARY OF THE FINDINGS AND IMPACT MANAGEMENT ME	ASURES IDENTIFIED IN ANY	
<u>OF SPECIALIST REPORT COMPLYING WITH APPENDIX 6 TO THESE RE</u>	GULATIONS AND A	
INDICATION AS TO HOW THESE FINDING AND RECOMMENDATIONS	HAVE BEEN INCLUDED IN TH	łΕ
FINAL REPORT	6	57
K. AN ENVIRONMENTAL IMPACT STATEMENT	6	<u>8</u>
L. ENVIRONMENTAL MANAGEMENT PROGRAMME INCLUDING WI		
MANAGEMENT MEASURES FROM SPECIALIST REPORT, THE RECORD	ING OF THE PROPOSED	
IMPACT MANAGEMENT OBJECTIVES, AND THE IMPACT MANAGEME	NT OUTCOMES FOR THE	
DEVELOPMENT	7	70
M. ANY ASPECTS WHICH WERE CONDITIONAL TO THE FINDING OF		
THE EAP OR SPECIALIST WHICH ARE TO BE INCLUDED AS CONDITION	NS OF AUTHORIZATION 7	1
A DESCRIPTION OF ANY ASSUMPTIONS UNISEDTAINITIES CARS		
N. A DESCRIPTION OF ANY ASSUMPTIONS, UNCERTAINITIES, GAPS		
RELATE TO THE ASSESSMENT AND MITIGATION MEASURES PROPOS	5ED 7	72
O. A REASONED OPINION AS TO WHETHER THE PROPOSED ACTIV	TY SHOULD OR SHOULD NO	т
BE AUTHORIZED, AND IF THE OPINION IS THAT IT SHOULD BE AUTH		÷
THAT SHOULD BE MADE IN RESPECT OF THAT AUTHORIZATION	•	73
THAT SHOOLD DE MINDE IN NEST ECT OF THAT AG THOMEMION		
P. WHERE THE PROPOSED ACTIVITY DOES NOT INCLUDE OPERATION	ONAL ASPECTS, THE PERIOD)
FOR WHICH THE ENVIRONMENTAL AUTHORIZATION IS REQUIRED, 1	•	-
ACTIVITY WILL BE CONCLUDED, AND THE POST CONSTRUCTION MO		′ 5
,		
Q. AN UNDERTAKING UNDER OATH OR AFFIRMATION BY THE EAP	IN RELATION TO: 7	76
R. WHERE APPLICABLE, DETAILS OF ANY FINANCIAL PROVISIONS	FOR REHABILITATION,	
CLOSURE, AND ONGOING POST DECOMMISSIONING MANAGEMENT	OF NEGATIVE	
ENVIRONMENTAL IMPACTS	7	78
S. ANY SPECIFIC INFORMATION THAT MAY BE REQUIRED BY THE C	OMPETENT AUTHORITY 7	79
T. ANY OTHER MATTERS REQUIRED IN TERMS OF SECTION 24(4)(A	A) AND (B) OF THE ACT 8	30

LIST OF TABLES

Table 1: Farm Names of Proposed Development	10
Table 2: Surveyor-General 21 digit of Farm Portions	10
Table 3: Coordinates of Gravel Road Construction	10
Table 4: Proposed Activity Listing interms 2014 EIA Regulations	13
Table 5: List of Legislation relevant to application	16
Table 6: List of State Department Stakeholders	17
Table 7: Environmental Attributes associated with construction of gravel road	25
Table 8: Determination of Consequence	26
Table 9: Severity Estimation	27
Table 10: Extent of Activity Estimation	27
Table 11: Duration of the Impact	27
Table 12: Determination of Likelihood	28
Table 13: Probability of Impact	28
Table 14: Frequency of the Impact	28
Table 15: Environmental Significance of Impact	29
Table 16: Environmental Significance of Impacts during Design and Planning Phase	31
Table 17: Environmental Significance of Impacts during the Construction Phase	33
Table 18: Environmental Significance of Impacts during Decommisioning Phase	36
Table 19: Environmental Significance of Impacts during Operational Phase	39
Table 20: Positive and Negative Impacts on the Environmental Attributes	42
Table 21: Mitigation Measures to negate Negative Impacts on the Environmental	
Attributes	47
Table 22: Environmental Significance of Impacts of Prefered Alternative during Design	l
and Planning Phase	53
Table 23: Environmental Significance of Impact of the Prefered Alternative during	
Construction Phase	55
Table 24: Environmental SIgnificance of Impact on the Prefered Alternative during	
Decommisioning Phase	58
Table 25: Environmnetal Significance of Impact of Prefered Alternative during Operati	on
Phase	_
Table 26: Cumulative Impacts of Prefered Alternative during Construction Phase	
Table 27: Cumalative Impact of Prefered Alternative during Decommisioning Phase	65
Table 28: Cumulative Impact of Prefered Alternative during the Operation Phase	65

LIST OF APPENDICES

APPENDIX 1: LOCALITY MAP OF PROJECT SITE

APPENDIX 2: THE MAP SHOWING FARM PORTIONS.

APPENDIX 3: THE LAYOUT PLAN OF PROPOSED GRAVEL ROAD

APPENDIX 4: PROOF OF SUBMISSION OF BASIC ASSESSMENT REPORT TO

STAKEHOLDERS

APPENDIX 5: PROOF OF WRITTEN COMMENTS FROM I&AP

APPENDIX 6: PROOF OF SUBMISSION OF BACKGROUND INFORMATION

DOCUMENT TO STAKEHOLDERS

APPENDIX 7: COPY OF BACKGROUND INFORMATION DOCUMENT

APPENDIX 8: DISCUSSIONS RECORDS WITH STAKEHOLDERS

APPENDIX 9: COPY OF COMMENTS SHEET

APPENDIX 10: COPY OF SITE NOTICE AND NEWSPAPER ADVERT

APPENDIX 11: PROOF OF SITE NOTICE DISPLAYED IN PUBLIC SPACE

APPENIDIX 12: PROOF ADVERT IN THE ISOLWEZE NEWSPAPER

APPENDIX 13: ISSUES AND RESPONSE REPORT

APPENDIX 14: MSINGA LOCAL MUNICIPALITY IN RELATION TO UMZINYATHI

DISTRCT MUNICIPALITY

APPENDIX 15: THE ENVIRONMENTAL SIGNIFICANCE RATING TABLE OF

ASPECTS

APPENDIX 16: PROPOSED ACTIVITY AND ITS ASSOCIATED INFRASTRUCTURE

IN RELATION TO ENVIRONMENTAL SENSITIVITY OF THE SITE.

APPENDIX 17: ENVIRONMENTAL MANAGEMENT PROGRAMME

APPENDIX 18: SPECIALIST REPORT/S

APPENDIX 19: SITE PHOTOS

APPENDIX 20: COPY OF APPLICATION FORMS

Appendix 21: PROPOSED ENGINEERING DESIGN OF THE 7.6 KM GRAVEL ROAD IN OBISINI VILLAGE, MSINGA LOCAL MUNICIPALITY.

A. Details and Expertise of Environmental Assessment Practitioner (EAP)

PERSONAL PARTICULARS (EAP)

Name and Surname: Mr. Kgomotso Motsepe

Years of experience: 17 of working experience environmental sector and 9 years as independent water and environmental resources consultant

EDUCATION

- Management Development Programme, University of South Africa, 2006,
- Certificate in Business Management, University of South Africa, 2004,
- B Tech Chemistry, Pretoria Technikon 2003,
- N Diploma: Analytical Chemistry, Pretoria Technikon 1998

MEMBERSHIP OF PROFESSIONAL INSTITUTIONS

- South African Council for Scientific Professions Pr.Sci.Nat.
- International Association of Impact Assessments MIAIA.
- Water Institute of South Africa MWISA
- Institute of Waste Management in South Africa MIWMSA

KEY RELEVANT EXPERIENCE

- 2014, Environmental Impact Assessment for continuation of mining through wetlands for Optimum Colliery in Hendrina
- 2014, Environmental Impact Assessment for Construction of Bridges in Edenvale for Ekurhuleni Metropolitan Municipality
- 2014, Environmental Impact Assessment for construction of bulkwater pipeline in Garankua and Mabopane Township for Tshwane Metropolitan Municipality
- 2014, Application for Water Use Licence Application for Wescoal Elandspruit Colliery Project
- 2013, Application for Water Use License Application for Optimum Kwagga North and Tweefontein

CERTIFICATION

I, the	unders	igned,	certif	y that	to	the	best	of	my	knowle	edge	and	belie ⁻	f, this	dato
corre	ctly des	cribes	me, r	my qu	alific	catio	ns, a	nd	my	experi	ence.	I hei	eby (confirr	n my
involv	ement i	n the p	oropos	sed pro	ojec	t.									

	Date:
Kgomotso Motsepe	

B. The Location Description and Locality Map of 7.6 km gravel road in Obisini Village, Msinga Local Municipality

The site is located in the Obisini Village area and falls under the jurisdiction of the Msinga Local Municipality and Umzinyathi District Municipality. The map showing the Obisini village within Msinga Local Municipality and Umzinyathi District Municipality is attached herewith in **Appendix 1**.

The development of the gravel road occurs on the following property as tabulated in **Table 1**:

Table 1: Farm Names of Proposed Development

Farm Name	ERF	Portion
QAMU	17486	-

Table 2 contains the Surveyor-General 21 digit site reference numbers for the farms shown in **Table 1**.

Table 2: Surveyor-General 21 digit of Farm Portions

N	0	G	Τ	0	0	0	0	0	0	0	0	1	7	4	8	6	0	0	0	0

The farm is shown on map in **Appendix 2**.

The start and end of each of the phases of the pipeline is shown in **Table 3**.

Table 3: Coordinates of Gravel Road Construction

1	-28,6016	30,2738
2	-28,6007	30,2786
3	-28,6001	30,2800
4	-28,5990	30,2825
5	-28,5950	30,2878
6	-28,5919	30,2898
7	-28,5908	30,2911
8	-28,5887	30,2937
9	-28,5847	30,2960
10	-28,5782	30,3116
11	-28,5809	30,3191

12	-28,5809	30,3227
13	-28,5808	30,3230
14	-28,5776	30,3246

C. Layout Plan of the Construction of Gravel Road

The layout plan for the proposed construction of 7.6 km gravel road in Obisini Village is shown in **Appendix 3**.

D. Description of the scope of the proposed construction of 7.6 km gravel road in Obisini Village

The project involves the construction of 7.6 km Gravel Road in Osibini Village. The Osibisini Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality.

The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

The scope of work is also shown in the map attached herewith in **Appendix 3**. The above activities triggered environmental authorization in terms of the Environmental Impact Assessment Regulations, December 2014 promulgated in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998), hence the compilation of this Basic Assessment Report. The listed activity and its description is described in **Table 4**.

Table 4: Proposed Activity Listing interms 2014 EIA Regulations

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
12	i. Canals exceeding 100 square meters in size ii. Channels exceeding 100 square meters in size iii. Bridges exceeding 100 square meters in size iv. Dams, where the dam, including infrastructure and water surface area, exceeds 100 square meters in size v. Weirs, where the eir, including infrastructure and water surface area,	The project involves the construction of 7.6 km Gravel Road in Osibini Village. The Osibisini Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

Government Notice R983 Activity No:	and EIA Activity(ies) in writing as	Describe the portion of the development as per the project description that relates to the applicable listed activity
	exceeds 100 square meters	
	in size	
	vi. Bulk stormwater outlet structures exceeding 100	
	structures exceeding 100 square meters in size	
	vii. Marines exceeding 100	
	square meters in size	
	viii. Jetties exceeding 100	
	square meters in size	
	ix. Spillways exceeding 100	
	square meters in size	
	x. Buildings exceeding 100 square meters in size	
	xi. Boardwalkings exceeding	
	100 square meters in size	
	xii. Infrastructure or structures	
	with a physical footprint of	
	100 square meters or more;	
	Where such development occurs	
	_	
	a) Within a watercourse	
	b) In front of a development	
	setback; or	
	c) If no development setback	
	exist, within 32 metres of a	
	watercourse, measured from the edge of a	
	watercourse	

	Excluding	
	(aa) The development of	
	infrastructure or structure witin	
	existing ports or harbours that will	
	not increase the development	
	footprint of the port or harbor	
	(bb) Where such development activities are related to the	
	development of a port or harbor,	
	in which case activity 26 in Listing	

Government Notice R983 Activity No:	Describe the relevant Scoping and EIA Activity(ies) in writing as per Listing Notice 1 (GN No. R983)	Describe the portion of the development as per the project description that relates to the applicable listed activity
	Notice 2 of 2014 (cc) Activities listed in activity 14 in Listing Notice 2 of 2014 or activity 14 in Listing Notice 3 of 2014, in which activity applies; (dd) Where such development occurs within an urban area; or (ee) Where such development occurs within existing roads or road reserve.	
19	The infilling or depositing of any material of more than 5 cubic metres into, or the dredging, excavation, removal or moving of soil, sand, shells, shell grit, pebbles or rock of more than 5 cubic metres from- (i) a watercourse; (ii) the seashore; or (iii) the littoral active zone, an estuary or a distance of 100 metres inland of the high-water mark of the sea or an estuary, whichever distance is the greater but excluding where such infilling, depositing, dredging, excavation, removal or moving- (a) will occur behind a development setback; (b) is for maintenance purposes undertaken in accordance with a maintenance management plan; or (c) falls within the ambit of activity 21 in this Notice, in which case that activity applies.	The project involves the construction of 7.6 km Gravel Road in Osibini Village. The Osibisini Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

Activity No: and E per Lis	ting Notice 1 (GN No. R983)	development as per the project description that relates to the applicable listed activity
i. ii. But ex	evelopment of – A road for which an environmental authorization was obtained for the route determination in terms of activity 5 in Government Notice 545 of 2010; or A raod with a reserve wider than 13,5 meters, or where no reserve exists where the road the is wider than 5 meters; cluding – Roads which are identified and included in activity 27 in Listing Notice 2 of 2014; or Roads where the entire road falls within an urban area	The project involves the construction of 7.6 km Gravel Road in Osibini Village. The Osibisini Village area falls within the Msinga Local Municipality in Umzinyathi District Municipality. The gravel road will be constructed as Standard Type 7A District Road in accordance with the Departament of Transport specifications. The final road carriageway width will be twelve (12m) meters.

E. Description of the policy and legislative context within which construction of gravel road falls

The list all legislation, policies and/or guidelines of any sphere of government that are relevant to the application as contemplated in the EIA regulations, where applicable are contained in the following **Table 5**:

Table 5: List of Legislation relevant to application

Title of legislation, policy or guideline	Administering authority	Date of Promulgation
The Constitution of the	The 3 spheres of National	1996
Republic of South Africa	Government	August
The National Water Act	Department of Water and	1998
	Sanitation	

Water Services Act	The municipalities	1997
The National	National and Provincial	1998
Environmental	Environmental Affairs Department	
Management Act		
Environmental Impact	National and Provincial	2014
Assessment Regulations	Environmental Affairs Department	
The National Health Act	Department of Health	2004
National Heritage	Amafa and Dept. of Arts and	1999
Resources Act	Culture	
Conservation of	Department of Agriculture	1983
Agricultural Resources Act		
KwaZulu Land Affairs Act	Department of Local Government	1992
	and Traditional Affairs	
Department of Transport	National Road Traffic Act	1996

In the context of the above legislations having direct or indirect impact on the development, the following state departments in **Table 6** are listed as interest and affected parties. This basic assessment report has been circulated to the respective department to solicit comments and inputs in terms of the report. The records of submission is contained in **Appendix 4**. The comments or response received from the interest and affected state department is included in the issues and response report under **Section H** of this report. The proof written comments or report is attached in **Appendix 5**.

Table 6: List of State Department Stakeholders

Name of Department	Contact person	Address	Document Submitted for Comments (Yes/No)	Comments (Yes/No)
Ezemvelo KZN Wildlife	Musa Mntambo	1 Peter Brown Drive Pietermaritzburg, 3201	Yes	No
Amafa	Weziwe Tshabalala	P.O. Box 2685, Pietermaritzburg, 3200 Tel: 0333 946543 Fax: 0333 426097	Yes	No
Department of Water and Sanitation	Lindiwe Dladla	P O Box 1018 Durban, 4000	Yes	No

		Tel: 031 336 2700		
Department of Agriculture, Forestry and Fisheries	Khwazi Hlongwane	P O Box 345 Pietermarisburg, 3200 Tel: 033 345 3515	Yes	No
Department of Cooperative	Induna MS Zondi	P O Box 22 Tugela Ferry Tel: 082 506 5218	Yes	Yes
Governance and Traditional Affairs	Cllr. K Sithole	P O Box 2555 Tugela Ferry Tel: 071 329 6904	Yes	Yes
uMzinyathi District Municipality	David Mvelase	P.O. Box 1965, 3000, South Africa 034-219 1500	Yes	No

F. Motivation for the need and desirability for the proposed construction of Construction of 7.6 km gravel road in Obisini Village including the need and desirability of the activity in the context of the preferred location

As per Msinga Local Municipality IDP 2015/2016, and uMzinyathi Backlog Study (2007) determined road backlogs based on hut count data in the Traditional Authority areas indicates that 58% of households have inadequate access to roads.

The Road Infrastructure Strategic Framework for South Africa (RIFSA) classifications indicates a major dependency on lower order access roads for most of the residents within Msinga Local Municipality. With the high dependency on the lower order nodes, it is necessary to ensure proper transport infrastructure exist, especially with the view of creating economic growth in the municipality, which positively affects everybody. Should the residents not have proper access to opportunities; the initiatives will not be successful.

G. Motivation for the preferred site, activity and technology alternative

PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

H. A full description of the process followed to reach the proposed preferred alternative within the site

H.1 Details of all the alternative considered

PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

H.2 Details of the Public Participation Process (PPP) undertaken interms of regulation 41 including copies of the supporting documents and inputs

The public participation process for the construction of construction of 7.6 km gravel road in Obisini Village entailed the following:

H.2.1 Identification of stakeholders

Identification of stakeholders took place by way of contacting with local municipalities, the Tribal Authority and Induna of the communities Obisini Village, Ward Councillor and State Department that development of the gravel road will trigger their participation. The stakeholder identified are listed in **Table 6**, above.

H.2.2 Announcement of the project

A Background Information Document (BID) was prepared as a basis for discussion with stakeholders about the project. The proof of distribution of the BID during the meeting with stakeholders is attached in **Appendix 6**. The BID in the main contained the following among others:

- Background to the project (who, why, where) and the motivation thereof;
- Description of the project;
- Process that will be followed (who can participate in the process, how and when);
- Information about the independent consultants (experience of technical and public participation processes and local experience in the study area).

The copy of the BID is attached herewith in **Annexure 7**.

H.2.3 Meetings

In anticipation of the desirability of the project within the community of the Obisini Village, a decision was taken to advance the cause of the project with the Tribal Authority, Induna of the Area and Ward Councillor. Therefore meetings were held on 28 July 2016 at Obisini Village – induna's house with the

respective community leaders, Induna Zondi and Councillor K Sithole. The notes or discussion points covered in the separate meetings are contained in **Annexure 8**. The comments sheet issued was discussed with the attendees in order to record issues or comments they could have with regards to the project development. The copy of the comments sheet is attached in **Annexure 9**.

H.2.4 Site Notice

A site notice was displyed on the notice board of the municipality as well as public library. The public was given 30-days to comment on the Draft Basic Assessment Report, in which they were invited to express interest if they need the copy of the report. The report was also made available for reading at the Public Library near Msingal Local Municipality Head Office. The copy of the site notice and advertisement is attached in **Annexure 10.** The proof of site notice displayed on site is contained in **Annexure 11.**

H.2.5 Newspaper Advertisement

The project was advertised in Greytown Gazette Newspaper. The public was given 30-days to comment on the Draft Basic Assessment Report, in which they were invited to express interest if they need the copy of the report. The report was also made available for comments at the Public Library in Msinga Public Library in Tugela Ferry. The copy of the advertisement in the Greytown Gazette Newspaper is attached in **Annexure 12**.

H.3 Summary of Isssues raised by Interested and Affected Parties (I&AP's)

The summary of isssues raised during the public participation process are as follows:-

The Issues and Response Report is contained in Annexure 13.

H.4 Environmental Attributes associated with Alternatives focusing on the Geographical, Physiscal, Biological, Social, Economic, Heritage and Cultural Aspects

Obisini Village is one of the settlements of the Msinga Local Municiaplity sitiuated in the rural area of the northern part of province of KwaZulu Natal. The town in the area as part of the municipality is Tugela Ferry, which host the seating of Municipal Offices and Pomeroy. The District Municipality is Umzinyathi District Municipality. The map showing the town of Keates Drift within Msinga Local Municipality in relation to Umzinyathi District Municipality is shown in **Appendix 14**.

The environtal attribute associated with the constrution of the gravel road is demonstrated and summarised in the **Table 7** below:-

Table 7: Environmental Attributes associated with construction of gravel road

Environmental Attribute	Description
Gradient of the site	1.5 -1.2 m
Location in Landscape	Undulating plain/low hills
Groundwater	Water table below 1.5m deep
Soil	Often Dry hard soil in the area
Geological Stability	The geology is rocky but stable
Groundcover	Natural veld with heavy alien
	infestation
Land use character of surrounding	The area is charecterised by vacant
area	land, followed by rural community
	settlement. The pipeline crosses
	streams along distribution network
Cultural and Historical Features	There are cultural/historical features
	affected by the pipeline
Social and Economic aspect	The project will create employment
	opportunities during construction
	phase

H.5 The methodology used in determining and ranking the nature/severity, significance, consequence, extent, duration and probability of potential environmental impacts and risk associated with alternatives

The risk assessment methodology was used for the ranking of the impacts. The severity/intensity of the potential environmental impacts were evaluated according to their severity (how bad the impact is), duration (how long the environment will take to recover from the impact), extent (the area that is effected by the impact), probability (the probability of the impact actually happening), frequency of occurrence (how often the aspect happens) and finally the environmental significance of the impact. All the above was rated on a scale of 5 with 1 being the least impacted.

This system derives environmental significance on the basis of the consequence of the impact on the environment and the likelihood of the impact occurring. Consequence is calculated as the average of the sum of the ratings of severity, duration and extent of the environmental impact. Likelihood considers the frequency of the activity together with the probability of an environmental impact occurring. The following tables (Table 8 to Table 15) describe the process in detail:

A. CONSEQUENCE

Consequence (Table 8) is calculated as the average of the sum of the ratings of severity (Table 9), duration (Table 10) and extent (Table 11) of the environmental impact.

Table 8: Determination of Consequence

Determination of Consequence (C) (Severity + Duration + Extent) / 3

H.5.1 Severity

This is an appraisal of the type of effect the activity would have on the affected environment. This description including what is being affected and how is shown in **Table 9**.

Table 9: Severity Estimation

Rating	Description
1	Negliable / non-harmful / minimal deterioration (0 – 20%)
2	Minor / potentially harmful / measurable deterioration (20 – 40%)
3	Moderate / harmful / moderate deterioration (40 – 60%)
4	Significant / very harmful / substantial deterioration (60 – 80%)
5	Irreversible / permanent / death (80 – 100%)

H.5.2 Extent

This indicates the spatial area that may be affected by the impact and further describes the possibility that adjoining areas may be impacted upon. This includes four classes that are listed as follows in **Table 10**:

Table 10: Extent of Activity Estimation

Rating	Description
1	Within immediate area of activity
2	Surrounding area within project boundary
3	Beyond project boundary
4	Regional / provincial
5	National / international

H.5.3 Duration

This refers to the period of time that the impact may be operative for (i.e. the lifetime of the impact). This includes the following classes that are listed as follows **Table 11**:

Table 11: Duration of the Impact

Rating	Description
1	Less than 1 month / quickly reversible
2	Less than 1 year / quickly reversible
3	More than 1 year / reversible over time
4	More than 10 years / reversible over time / life of project or facility
5	Beyond life of project of facility / permanent

B. LIKELIHOOD

Likelihood (**Table 12**) considers the frequency of the activity together with the probability of the environmental impact associated with that activity occurring.

Table 12: Determination of Likelihood

Determination of Likelihood (L) = (Frequency + Probability) / 2

H.5.4 Probability

This refers to the probability of the impact actually occurring. The following classes in **Table 13** are used to describe the probability of the impact:

Table 13: Probability of Impact

Rating	Description
1	Almost impossible
2	Unlikely
3	Probable
4	Highly likely
5	Definite

H.5.5 Frequency

This refers to the frequency of the impact actually occurring. The following classes of rating in **Table 14** are used to describe the frequency of the impact occurring:

Table 14: Frequency of the Impact

Rating	Description
1	Less than once a year
2	Once in a year
3	Quarterly
4	Weekly
5	Daily

H.5.6 Environmental Significance

The significance of the impact (i.e. whether it will lead to a marked change in the environment or not) is determined through a synthesis of the aspects produced in terms of their severity, exent, duration, probability and frequency. Therefore, Environmental significance is the product of the consequence and likelihood values. Four classes of environmental significance are tabulated in **Table 15** as follows:

- None (the impact will not have an influence on the decision and requires no mitigation)
- Low (the impact will have a limited influence on the decision and requires mitigation to manage the environment)
- Medium (it is likely that to have an influence on the decision and requires mitigation)
- High (mitigation is required and this may not be sufficient to ensure that the environment is not detrimentally affected by the proposed development

Table 15: Environmental Significance of Impact

Environmental Significance (Impact) = C × L	Description
N (1 – 4.9)	None environmental significance
L (5 – 9.9)	Low environmental significance
M (10 – 14.99)	Medium environmental significance
H (15 – 25)	High environmental significance. Likely to be a fatal flaw.

H.6 Impacts and Risk identified for each alternative, including the nature, significance, consequence, extent, duration and probability of the impacts, including the degree to which these aspects can be reversed, may cause irreplaceable loss of resources and can be avoided, managed or mitigated

Table 16 to **Table 19** shows the environmental significance of impacts and risk identified for the identified alternative (preferred option) both pre-mitigation measures and post-mtigation measures. The environmental significance rating of each aspects pre and post mitigation measures is contained in **Appendix 15**.

Table 16: Environmental Significance of Impacts during Design and Planning Phase DESIGN AND PLANNING PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
Loss of vegetation	None	Minimize vegetation destruction to minimum area	None
Soil Erosion	None	The gravel road must be constructed along the topography and channeled properly in the drainage lines using storm water channel and erosion gullies.	None
Water pollution	None	 The Stormwater Channels must be installed in the area where the gravel road will intercept the drainage channel 	None
Dust generation	None	 TLB's to only be driven in area that is identified for road construction 	None
Hazardous Substance contamination	None	 The TLB's must be provided with drip trays when not in use 	None
Noise generation	None	 Avoid excessive revving and ignition of equipment. 	None
Waste pollution	None	 Dispose waste at registered waste disposal facility 	None
Fire ignition	None	 TLB's to always have fire extinguishers and have employees trained on their use 	None
Damage to existing	None	 Infrastructure mapping and confirmation. 	

DESIGN AND PLANNING PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
infrastructure e.g. sewage lines			
Injury to public and animals due to falling into workings	None	Prevent unauthorized entry to the working area	None
Traffic congestion	None	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour Plan work area to minimize traffic obstruction 	None
Traffic incidents	None	 Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	None	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	None	 The contractor will be advised to implement proper storm management plan 	None
Cultural Heritage Resources	None	• If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to AMAFA and SAPS.	None

Table 17: Environmental Significance of Impacts during the Construction Phase CONSTRUCTION PHASE

Loss of vegetation	None	 Minimize vegetation destruction to minimum area where construction operations are. 	None
Soil Erosion	Medium	 Minimize vegetation destruction to minimum area where construction operations are. Divert stormwater away from the disturbed areas and loose soils Compact well after clearing the road 	None
Water pollution	Medium	Avoid soil erosion (see above)Avoid loss of vegetation (see above)	None
Dust generation	None	 Limit loss of vegetation (see above) Avoid over movement of plant on site Limit speed to 20km/hr. or less in the construction site Apply dust suppression regularly and as required Cover soil heaps 	None
Hazardous Substance contamination	Medium	 Avoid refueling onsite Refueling to occur at designated areas and with drip trays installed Training of substance handlers for correct handling 	None
Noise generation	None	Proper plant, machinery and motor maintenance	None

CONSTRUCTION PHASE

CONSTRUCTION THA		 Use noise reduction apparatus where applicable Avoid excessive revving and ignition of equipment. 	
Waste pollution	Medium	 Operational hours between 07h00 and 17h00 Use dedicated waste bins 	None
		Practice waste separation (General and Hazardous)Dispose waste at registered waste disposal facility	
Fire ignition	Low	 Avoid lighting fires on site Ban smoking near flammable substances Ensure correct handling of flammable substances Have fire extinguishers and have employees trained on their use 	None
Loss of fauna and Flora	Low	 Avoid vegetation loss (see above) Avoid fires (see above) Avoid hazardous substance contamination of soil and water (see above) Prevent collection/capture of fauna by employees 	None
Damage to existing infrastructure e.g. sewage lines	None	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None
Injury to public and animals due to falling into workings	None	 Prevent unauthorized entry to the working area Barricade all works with barricade fence NO ENTRY and DANGER signs erected and maintained Smallest lead times between trenching and pipe burying. 	None

CONSTRUCTION PHASE

		 Close dig-up areas as soon as pipes have been laid. 	
Traffic congestion	Medium	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour Move plant and machinery away from high traffic areas Plan work area to minimize traffic obstruction 	None
Traffic incidents	Medium	 Avoid traffic congestion (see above) Implement traffic safety measures Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	Low	 The contractor will be advised to implement proper storm management plan 	None
Cultural Heritage Resources	None	If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to SAPS.	None

Table 18: Environmental Significance of Impacts during Decommisioning Phase DECOMMISIONING PHASE

Loss of vegetation	None	 Topsoil removed must be used to level the area, in 	None
Loss of Vogoralion		order to allow the seeds to regerminate Indigenous vegetation (if any) will need to be relocated and planted again	
Soil Erosion	None	 Rows of straw, hay or bundles of cut vegetation may also be used. In this instance, the hay, straw or vegetation is dug into the soil in contours, in order to help slow surface wash and capture eroded soil. The spacing between rows would be dependent on slope and the specific area. 	None
Water pollution	Low	 Waste Materials collected on site after decommisiong the site must not be diverted into nearby water courses 	None
Dust generation	Low	Avoid over movement of plant on siteLimit speed to 20km/hr. or less in the construction site	None
Hazardous Substance contamination	Low	 Refueling to occur at designated areas and with drip trays installed All waste material generated on site must be disposed off at registererd hazardous landfill site. Proof of disposal must be made available to Site Engineer 	None
Noise generation	None	 Avoid excessive revving and ignition of equipment. Operational hours between 07h00 and 17h00 	None
Waste pollution	None	Use dedicated waste bins	None

DECOMMISIONING PHASE

DECOMMISIONING R		 Practice waste separation (General and Hazardous) Dispose waste at registered waste disposal facility 	
Fire ignition	None	 Avoid lighting fires on site Ban smoking near flammable substances Ensure correct handling of flammable substances Have fire extinguishers and have employees trained on their use 	None
Loss of fauna and Flora	None	 Rehabilitate the area workings within the water course to allow natural flows Remove structures that can impede natural flow in the water Use Gabion baskets and Rhino mattress to stabilize river banks 	None
Damage to existing infrastructure e.g. sewage lines	None	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None
Injury to public and animals due to falling into workings	None	 Prevent unauthorized entry to the working area Barricade all works with barricade fence NO ENTRY and DANGER signs erected and maintained Smallest lead times between trenching and pipe burying. Close dig-up areas as soon as pipes have been laid. 	None
Traffic congestion	Low	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour 	None

DECOMMISIONING PHASE

		 Move plant and machinery away from high traffic areas Plan work area to minimize traffic obstruction 	
Traffic incidents	Low	 Avoid traffic congestion (see above) Implement traffic safety measures Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	Low	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	None	 The design of drainage and stormwater pipes should be to reduce flow velocity and avoid soil erosion. This can be achieved through the construction of water velocity dissipators below the pipe head wall. Rocks, boulders or concrete blocks may be utilised for these purposes, and they are set into the concrete pron below the headwall. Stone pitching may also be utilised. 	None

Table 19: Environmental Significance of Impacts during Operational Phase OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
Soil Erosion	Low	 Implement the appropriate topsoil and stormwater runoff control management measures to prevent the loss of topsoil. The site should be graded well to permit drainage and to prevent ponding 	None
Water pollution	Low	 Dust suppression must be conducted to minimal level to avoiding flooding of gravel road 	None
Loss of fauna and Flora	Low	 Trees and shrubs conserved shall be clearly introduced to the site under the supervision of the Project Enginner. 	None
Damage to existing infrastructure e.g. sewage lines	Low	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None
Traffic incidents	Medium	 Dust suppression must be conducted to minimal level to avoiding flooding of gravel road Install illuminating warning lights, traffic calming structures, etc. should flooding be the resultant impact Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from pipe burst areas Use barricades and signage Prevent unauthorized access to working areas 	None

OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
Stormwater Management	Low	 Ensure effective storm water management will be exercised to limit negative impacts on the environment and enhance the positive impacts All contaminated standing water should be immediately removed and treated or disposed of appropriately. Surfaces and conduits should be constructed to drain the run off more efficiently 	None

H.7 Positive and negative impacts that the proposed activity and alternatives will have on the environment and on the community that may be affected focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects

Table 20 shows the positive and negative impacts the proposed activity will have on the environment and on the community that may be affected focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects.

Table 20: Positive and Negative Impacts on the Environmental Attributes

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
Gradient of the site	1.5 -1.2 m	<u>Positive</u> , no change	<u>Positive</u> , as the gravel	<u>Positive</u> , as the gravel
		to the gradient of	road will follow the slope	road will follow the
		the site	of the area.	slope of the area.
Location in	Undulating	<u>Positive</u> , there will	<u>Positive</u> , as the gravel	<u>Positive</u> , as the gravel
Landscape	plain/low hills	be no change in	road will be following the	will be following the
		Landscape	land scape	land scape
Groundwater	Water table below	<u>Positive</u> , No drilling	Positive, No drilling will	Positive, No drilling will
	1.5m deep	will conducted for	conducted for road	conducted for road
		road survey of	survey of gravel roads.	survey of gravel roads.
		gravel roads.		
Soil	Often Dry hard soil	<u>Positive</u> , No soil will	<u>Positive</u> , minimal soil will	Negative, the
	in the area	be removed during	be removed, as top soil	excavated portion of
		the road survey.	will also be used to	the gravel road will be
			compact the gravel	permanent as it will be
			road.	compacted to avoid
				regermiantion of

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
				vegatation on the road.
Geological Stability	The geology is	<u>Positive</u> , No drilling	Positive , the ground will	Negative, the
	rocky but stable	will conducted for	only be excavated	excavated portion of
		road survey of	limited along the	the gravel road will be
		gravel roads.	surveyed gravel road	soft and dry during
			route	backfilling process and
				will take longer to
				harden to pre-soil
				condition structural
				properties
Groundcover	Natural veld with	Positive, No	Negative, as the natural	<u>Negative</u> , as the natural
	heavy alien	excavations will be	veld cover will be lost	veldcover will not
	infestation	conducted during	during the excavations	regerminate on the
		the survey		compacted surface
Land use character	The area is	Positive, No	<u>Positive</u> , the gravel road	<u>Positive</u> , the gravel road
of surrounding area	charecterised by	excavations will be	will be following the	will be following the
	vacant land,	conducted during	existing gravel roads that	existing gravel roads

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
	followed by rural	the survey	are in bad condition and	that are in bad
	community		will now be accessible for	condition and will now
	settlement. The		use interms of basic	be accessible for use
	gravel road		services.	interms of basic
	crosses non-			services.
	perenial streams			
	to reach other			
	sites of the			
	settlements			
Cultural and	There are no	<u>Positive,</u> as there	Positive , as there are no	Positive, as there are no
Historical Features	cultural/historical	are no cultural and	cultural and historical	cultural and historical
	features affected	historical features	features affected by the	features affected by
	by the gravel road	affected by the	gravel road.	the gravel road.
		gravel road.		
Social and	The project will	<u>Positive</u> , as the	<u>Positive</u> , as the project	<u>Positive</u> , as the project
Economic aspect	create	project will be	will be creating jobs and	will be creating jobs
	employment	creating jobs and	improving the lives of the	and improving the lives

Environmental	Description	Design and Planning	During Construction –	Post Construction
Attributes		(Positive / Negative	(Positive / Negative	(Positive / Negative
		Impact	Impact)	Impact)
	opportunities	improving the lives	community as there will	of the community as
	during	of the community as	now be acess to basic	there will now be acess
	construction	there will now be	serives.	to basic serives.
	phase	acess to basic		
		serives.		

H.8 The possible mitigation measures that could be applied and level of residual risk

Table 21 demonstrate mitigation measures to negate negative impacts on the environmental attributes.

Table 21: Mitigation Measures to negate Negative Impacts on the Environmental Attributes

Environmental	Impact	Construction Stage	Mitigation Measures
Attribute			
Soil	Negative, the excavated portion	Post Construction	The road compaction process
	of the gravel road will be		must be supervised by the
	permanent as it will be		profeesional engineer, to avoid
	compacted to avoid		soil erosion that can lead to
	regermiantion of vegatation on		dongas creasing the road.
	the road.		
Geological Stability	Negative, the excavated portion	Post Construction	The road compaction process
	of the gravel road will be soft and		must be supervised by the
	dry during backfilling process and		profeesional engineer, to avoid
	will take longer to harden to pre-		soil erosion that can lead to
	soil condition structural properties		dongas creasing the road.
Groundcover	<u>Negative</u> , as the natural veld	During Construction	Top soil stock piling must be well
	cover will be lost during the		protected and cordoned off
	excavations		from other soil material
			generated on site, so as to allow
			natural seeds to regerminate
			successfully during the

Environmental	Impact	Construction Stage	Mitigation Measures
Attribute			
			rehabilitation of construction
			works
Groundcover	<u>Negative</u> , as the natural	Post Construction	The road compaction process
	veldcover will not regerminate on		must be supervised by the
	the compacted surface		profeesional engineer, to avoid
			soil erosion that can lead to
			dongas creasing the road.

H.9 The outcome of the site selection matrix

PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

H.10 If no alternatives, including alternative locations for the activity were investigated, the motivation for not considering such.

PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

H.11 A concluding statement indicating the preferred alternatives, including preferred location of the activity

PLEASE NOTE THAT THERE ARE NO SITE ALTERNATIVES FOR THE PROPOSED DEVELOPMENT

There are no site alternatives as the purpose of this development is to provide road acess to the local community, therefore the region under consideration is the target delivery for the gravel road acess and an alternate site is counterproductive. In addition there are no significant route alternatives as the linear development will be aligned adjacent to existing topography for the majority of the route. It is also deemed most appropriate / reasonable to locate the gravel road along the flat topography to minimize the cost of construction as well as maintenance.

The "no-go" alternative is for the proposed development not go ahead, the site will continue with its current activities and the provision of acess road to the local community will not be undertaken. This will also haper service delivery interms police, health and socio-economic services.

The village currently does not have proper acess road for basic services to reach the targeted community. The gravel road will be aligned to existing landscape of the area in order to minimize the environmental impacts in the area. Therefore in deciding the least cost option of the gravel road, the environmental consideration matrix of the following was utilized:

- existing landscape of the area
- existing infrastructure, like telecoms and powerlines
- existing dead roads in the area.

As a result the community will now be able to benefit from the gravel road construction as the basic services, such as ambulance, police vehicles and municipal services.

I. Full description of the process undertaken to identify, assess and rank the impacts the activity will impose on the preferred location through the life of activity.

Table 22 to Table 25 shows the environmental significance of impacts and risk identified for the identified alternative (preferred option) both pre-mitigation measures and post-mtigation measures. The environmental significance rating of each aspects pre and post mitigation measures is contained in **Appendix 15**.

The cummaltive impacts associated with the project life cycle is demonstrated in **Table 26 to Table 28**.

Table 22: Environmental Significance of Impacts of Prefered Alternative during Design and Planning Phase DESIGN AND PLANNING PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
Loss of vegetation	None	Minimize vegetation destruction to minimum area	None
Soil Erosion	None	The gravel road must be constructed along the topography and channeled properly in the drainage lines using storm water channel and erosion gullies.	None
Water pollution	None	 The Stormwater Channels must be installed in the area where the grave road will intercept the drainage channel 	None
Dust generation	None	 TLB's to only be driven in area that is identified for road construction 	None
Hazardous Substance contamination	None The TLB's must be provided with drip trays when not in use		None
Noise generation	None	 Avoid excessive revving and ignition of equipment. 	None
Waste pollution	None	Dispose waste at registered waste disposal facility	None
Fire ignition	None	 TLB's to always have fire extinguishers and have employees trained on their use 	None
Damage to existing infrastructure e.g.	None	 Infrastructure mapping and confirmation. 	

DESIGN AND PLANNING PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
sewage lines			
Injury to public and animals due to falling into workings	None	Prevent unauthorized entry to the working area	None
Traffic congestion	None	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour Plan work area to minimize traffic obstruction 	None
Traffic incidents	None	 Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	None	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	None	 The contractor will be advised to implement proper storm management plan 	None
Cultural Heritage Resources	None	If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to AMAFA and SAPS.	None

Table 23: Environmental Significance of Impact of the Prefered Alternative during Construction Phase CONSTRUCTION PHASE

Potential impacts:		Proposed mitigation:	Significance rating of impacts after mitigation:
Loss of vegetation	None	Minimize vegetation destruction to minimum area where construction operations are.	None
Soil Erosion	Medium	 Minimize vegetation destruction to minimum area where construction operations are. Divert stormwater away from the disturbed areas and loose soils Compact well after clearing the road 	None
Water pollution	Medium	Avoid soil erosion (see above)Avoid loss of vegetation (see above)	None
Dust generation	None	 Limit loss of vegetation (see above) Avoid over movement of plant on site Limit speed to 20km/hr. or less in the construction site Apply dust suppression regularly and as required Cover soil heaps 	None
Hazardous Substance contamination	Medium	 Avoid refueling onsite Refueling to occur at designated areas and with drip trays installed Training of substance handlers for correct handling 	None

CONSTRUCTION PHASE

Potential impacts:		Proposed mitigation:	Significance rating
	rating of impacts:		of impacts after mitigation:
Noise generation	None	 Proper plant, machinery and motor maintenance Use noise reduction apparatus where applicable Avoid excessive revving and ignition of equipment. Operational hours between 07h00 and 17h00 	None
Waste pollution	Medium	 Use dedicated waste bins Practice waste separation (General and Hazardous) Dispose waste at registered waste disposal facility 	None
Fire ignition	Low	 Avoid lighting fires on site Ban smoking near flammable substances Ensure correct handling of flammable substances Have fire extinguishers and have employees trained on their use 	None
Loss of fauna and Flora	Low	 Avoid vegetation loss (see above) Avoid fires (see above) Avoid hazardous substance contamination of soil and water (see above) Prevent collection/capture of fauna by employees 	None
Damage to existing infrastructure e.g. sewage lines	None	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None
Injury to public and animals due to falling into workings	None	 Prevent unauthorized entry to the working area Barricade all works with barricade fence NO ENTRY and DANGER signs erected and maintained Smallest lead times between trenching and pipe 	None

CONSTRUCTION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:
		burying. Close dig-up areas as soon as pipes have been laid.	
Traffic congestion	Medium	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour Move plant and machinery away from high traffic areas Plan work area to minimize traffic obstruction 	None
Traffic incidents	Medium	 Avoid traffic congestion (see above) Implement traffic safety measures Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	Low	 The contractor will be advised to implement proper storm management plan 	None
Cultural Heritage Resources	None	If any cultural and heritage resources can be discovered on the proposed site the construction will have to be halted and the case be reported to SAPS.	None

Table 24: Environmental Significance of Impact on the Prefered Alternative during Decommisioning Phase DECOMMISIONING PHASE

Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures
Loss of vegetation	None	 Topsoil removed must be used to level the area, in order to allow the seeds to regerminate Indigenous vegetation (if any) will need to be relocated and planted again 	None
Soil Erosion	None	 Rows of straw, hay or bundles of cut vegetation may also be used. In this instance, the hay, straw or vegetation is dug into the soil in contours, in order to help slow surface wash and capture eroded soil. The spacing between rows would be dependent on slope and the specific area. 	None
Water pollution	Low	 Waste Materials collected on site after decommisiong the site must not be diverted into nearby water courses 	None
Dust generation	Low	Avoid over movement of plant on siteLimit speed to 20km/hr. or less in the construction site	None
Hazardous Substance contamination	Low	 Refueling to occur at designated areas and with drip trays installed All waste material generated on site must be disposed off at registererd hazardous landfill site. Proof of disposal must be made available to Site Engineer 	None
Noise generation	None	 Avoid excessive revving and ignition of equipment. Operational hours between 07h00 and 17h00 	
Waste pollution	None	Use dedicated waste bins	None

DECOMMISIONING PHASE

Potential impacts:		Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures	
		 Practice waste separation (General and Hazardous) Dispose waste at registered waste disposal facility 		
Fire ignition	None	 Avoid lighting fires on site Ban smoking near flammable substances Ensure correct handling of flammable substances Have fire extinguishers and have employees trained on their use 	None	
Loss of fauna and Flora	None	 Rehabilitate the area workings within the water course to allow natural flows Remove structures that can impede natural flow in the water Use Gabion baskets and Rhino mattress to stabilize river banks 	None	
Damage to existing infrastructure e.g. sewage lines	None	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None	
Injury to public and animals due to falling into workings	None	 Prevent unauthorized entry to the working area Barricade all works with barricade fence NO ENTRY and DANGER signs erected and maintained Smallest lead times between trenching and pipe burying. Close dig-up areas as soon as pipes have been laid. 	None	
Traffic congestion	Low	 Avoid traffic jamming e.g. move machinery and plant outside of rush hour 	None	

DECOMMISIONING PHASE

Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures
		 Move plant and machinery away from high traffic areas Plan work area to minimize traffic obstruction 	
Traffic incidents	Low	 Avoid traffic congestion (see above) Implement traffic safety measures Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None
Pedestrian injuries and route closures	Low	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	None	 The design of drainage and stormwater pipes should be to reduce flow velocity and avoid soil erosion. This can be achieved through the construction of water velocity dissipators below the pipe head wall. Rocks, boulders or concrete blocks may be utilised for these purposes, and they are set into the concrete pron below the headwall. Stone pitching may also be utilised. 	None

Table 25: Environmnetal Significance of Impact of Prefered Alternative during Operation Phase OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
Soil Erosion	Low	 Implement the appropriate topsoil and stormwater runoff control management measures to prevent the loss of topsoil. The site should be graded well to permit drainage and to prevent ponding 	None
Water pollution	Low	 A comprehensive water pressure management must be adhered to prevent pressure build ups resulting in pipe burst A use pressure reducing valves must be implemented 	None
Loss of fauna and Flora	Low	 Trees and shrubs conserved shall be clearly introduced to the site under the supervision of the Project Enginner. This trees cannot be planted directly on the pipeline, but appropriate planting site must be negotiated well with all interest and affected parties Pipeline crossing over the stream must always be freed of debris building up 	None
Damage to existing infrastructure e.g. sewage lines	Low	 Infrastructure mapping and confirmation. Servitude applications Contingency and emergency measures 	None
Traffic incidents	Medium	 A comprehensive water pressure management must 	None

OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures
		 be adhered to prevent pressure build ups resulting in pipe burst A use pressure reducing valves must be implemented Implement traffic safety measures in case of pipe burst Install illuminating warning lights, traffic calming structures, etc. should flooding be the resultant impact Use flagman to slow and direct traffic 	
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from pipe burst areas Use barricades and signage Prevent unauthorized access to working areas 	None
Stormwater Management	Low	 Ensure effective storm water management will be exercised to limit negative impacts on the environment and enhance the positive impacts All contaminated standing water should be immediately removed and treated or disposed of appropriately. Surfaces and conduits should be constructed to drain the run off more efficiently 	None

Table 26: Cumulative Impacts of Prefered Alternative during Construction Phase CONSTRUCTION PHASE

CONSTRUCTION PH	_			
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:	Cumulative Impact
Soil Erosion	Medium	 Minimize vegetation destruction to minimum area where construction operations are. Divert stormwater away from the disturbed areas and loose soils Compact well after clearing the road 	None	Creation of dongas along the road, which could lead to sinkholes in the area.
Water pollution	Medium	Avoid soil erosion (see above)Avoid loss of vegetation	None	Loss of water quality of the streams in the area.
Hazardous Substance contamination	Medium	 Avoid refueling onsite Refueling to occur at designated areas and with drip trays installed Training of substance handlers for correct handling 	None	Loss of land capability and groundwater pollution due to Oil and Grease contamination
Waste pollution	Medium	 Use dedicated waste bins Practice waste separation (General and Hazardous) Dispose waste at registered waste disposal facility 	None	Creation of illegal dumping site and could cause significant health hazard to the surrounding community and living animals
Traffic congestion	Medium	 Avoid traffic jamming e.g. 	None	Traffic Congestions may lead

CONSTRUCTION PHASE

CONSTRUCTION III	_			
Potential impacts:	Significance rating of impacts:	Proposed mitigation:	Significance rating of impacts after mitigation:	Cumulative Impact
		 move machinery and plant outside of rush hour Move plant and machinery away from high traffic areas Plan work area to minimize traffic obstruction 		to illegal driving and creation of alternative routes around the works leading to damage of the surrounding environments, and infrastructure.
Traffic incidents	Medium	 Avoid traffic congestion (see above) Implement traffic safety measures Install illuminating warning lights, traffic calming structures, etc. Use flagman to slow and direct traffic 	None	Road closures my lead to road rages by motorist to fellow motorists or pedestrians
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from working areas Use barricades and signage Prevent unauthorized access to working areas 	None	Public injuries may lead to negativity by the communities against the project

Table 27: Cumalative Impact of Prefered Alternative during Decommisioning Phase DECOMMISIONING PHASE

Potential impacts:	Significance rating of impacts:	Proposed rehabilitation measures	Significance rating of impacts after rehabilitation measures	Cumulative Impact
N/A	N/A	N/A	N/A	N/A

Table 28: Cumulative Impact of Prefered Alternative during the Operation Phase OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures	Cumulative Impact
Traffic incidents	Medium	 A comprehensive water pressure management must be adhered to prevent pressure build ups resulting in pipe burst A use pressure reducing valves must be implemented Implement traffic safety measures in case of pipe burst Install illuminating warning 		Background leaking of pipelines, that leads unaccounted for water in the system

OPERATION PHASE

Potential impacts:	Significance rating of impacts:	Proposed mitigation measures	Significance rating of impacts after rehabilitation measures	Cumulative Impact
		lights, traffic calming structures, etc. should flooding be the resultant impact Use flagman to slow and direct traffic		
Pedestrian injuries and route closures	Medium	 Redirect pedestrians away from pipe burst areas Use barricades and signage Prevent unauthorized access to working areas 	None	 Background leaking of pipelines, that leads unaccounted for water in the system

J. A summary of the findings and impact management measures identified in any of specialist report complying with Appendix 6 to these regulations and a indication as to how these finding and recommendations have been included in the final report

K. An environmental impact statement

The impact associated with the construction of the gravel road in this village have been adequately assessed in this report at different phase of the life of activity of the project i.e planning and design phase, construction phase, decommissioning phase and operational phase.

A map is attached herewith in **Appendix 16** showing the proposed activity and its associated infrastructure in relation to environmental sensitivity of the site. The objective here is delineate where feasible the areas that are sensitive and proper care and due diligence must be activated during the construction, rehabilitation and operation of the project. **Appendix 21** details the proposed Engineering Design of the Gravel Road.

There will be less environmental significance during the planning and design phase, as much of the work is designed around ground trothing and review of the information in the general public domain.

During the construction phase, there are aspects of construction that needs to managed accordingly to reduce the environmental significance of the impacts. The Environmental Management Programme (EMPr) to manage and monitor mitigation of this impacts by the contractor.

Although an aspect might have a rating of none or low environmental significance, that aspect might have cumulative impact if not properly managed. In this case some of issues such as management of soil generated on site as well as loss of vegetation, noise of construction machinery and traffic management if not properly mitigated can have high environmental significance and makes the whole project undesirable to the environment.

Aspect such as, refueling at dedicated fuel storage, improper waste management practices and insufficient traffic management practice have a medium environmental significance. If the aspects are not monitored as per the recommended mitigation measures, they will also trigger high environmental significance, and thus the desirable objective of the will not be realized. This will have negative consequences as the community will continue without access to basic service guaranteed by the Constitution of the Republic of South Africa.

It is therefore desirable that the Project Manager appoint the Environmental Control Officer whom's primary responsibility is to ensure compliance by the Contractor with all the mitigation measures contained in the EMPr.

The negative environmtal impact of the project on the environmental attributes are far outweighed by the sole delivery of the basic services of acess road provision to the people. Therefore, although there will be such negative effect on the environment, the mititigation measures recommended must be adhered to as will be outlined in the EMPr.

It is therefore imperative that EMPr is well versed with the contractor during the construction and rehabilitation phase.

L. Environmental Management Programme including where applicable impact management measures from specialist report, the recording of the proposed impact management objectives, and the impact management outcomes for the development

The Environmental Management Programme is attached herewith in **Appendix**17 of this report.

M. Any aspects which were conditional to the finding of the assessment either by the EAP or specialist which are to be included as conditions of authorization

N. A description of any assumptions, uncertainities, gaps in knowledge which relate to the assessment and mitigation measures proposed

O. A reasoned opinion as to whether the proposed activity should or should not be authorized, and if the opinion is that it should be authorized, any conditions that should be made in respect of that authorization

The government's Integrated Sustainable Rural Development Strategy (ISRDS) as incepted in October 2001 gave birth to a programme that focussed to achieve integrated sustainable development in the rural areas. This programme selected nodes based on identified local development problems and opportunities. Its aim is to respond to indicators of poverty and economic opportunities.

The current access road provides a thoroughfare for the local villagers and farm workers. There is virtually no public transport facility available. The proposed access is currently a clayey loamy gravel track road approximately 3,5m wide traversing over rolling mountainous terrain with steep inclines and side cuts. There are rock (Shale) outcrops in several isolated areas making road condition harsh and difficult and sometimes inaccessible especially during the frequent rainy periods.

As per Msinga Local Municipality IDP 2015/2016, and uMzinyathi Backlog Study (2007) determined road backlogs based on hut count data in the Traditional Authority areas indicates that 58% of households have inadequate access to roads.

The Road Infrastructure Strategic Framework for South Africa (RIFSA) classifications indicates a major dependency on lower order access roads for most of the residents within Msinga Local Municipality. With the high dependency on the lower order nodes, it is necessary to ensure proper transport infrastructure exist, especially with the view of creating economic growth in the municipality, which positively affects everybody. Should the

residents not have proper access to opportunities; the initiatives will not be successful.

The environmental impact assessment concluded that, yes, during implementation of magnitude of this project there will be temporal loss of certain environmental attributes along the route of target delivery community. Thus, we have appreciated that and acknowledge the loss. However the profound nature of this acess road negates the temporal environmental losses we are going to lose. We still have to protect same by the way. But the mitigation measures we recommend to be put in place to manage this less environmental significance impacts, should allow us to restore the environment to its close pristine conditions albeit not equivalent.

It is against this background that, I have assessed and processed all the possible environmental impacts within my knowledge that could be associated with the construction of 7.6km gravel road in Obisini Village and its desirable objectives, thus:-

I can, soundly recommend to the KwaZulu Natal Department of Economic Development, Tourism and Environmental Affairs to authorize Construction of 7.6km gravel road in Obisini Village as proposed by Msinga Local Municipality.

This recommendation has the following bearing on to Municipality implementing in its entirety the mitigation measures and conditions suggested elsewhere in this report, contained in the **Environmental Management Programme (EMPr) dated August 2015** and further management measures and conditions recommended by the responding Authority.

P. Where the proposed activity does not include operational aspects, the period for which the environmental authorization is required, the date on which the activity will be concluded, and the post construction monitoring requiremnts

Q. An undertaking under oath or affirmation by the EAP in relation to:

I, **KGOMOTSO MOTSEPE** declare that I

- am the independent environmental practitioner in this application;
- will comply with the requirements for an EAP as stipulated in Regulation 13 of the EIA Regulations, 2014;
- do not have and will not have any vested interest (either business, financial, personal or other) in the undertaking of the proposed activity, other than remuneration for work performed in terms of the Environmental Impact Assessment Regulations, 2014;
- will perform the work relating to the application in an objective manner, even if this results in views and findings that are not favourable to the applicant;
- declare that there are no circumstances that may compromise my objectivity in performing such work;
- have expertise in conducting environmental impact assessments, including knowledge of the National Environmental Management Act, 1998 (Act107 of 1998), regulations and any guidelines that have relevance to the proposed activity;
- will comply with the National Environmental Management Act, 1998 (Act107 of 1998), regulations and all other applicable legislation;
- undertake to disclose to the applicant and the KZN Department of Economic Development, Tourism & Environmental Affairs all material information in my possession that reasonably has or may have the potential of influencing its decision with respect to this application;
- will ensure that information containing all reports in respect of this application is distributed or made available to interested and affected parties and that their participation is facilitated in such a manner that they will be provided with a reasonable opportunity to participate and provide comments on the reports;
- will provide the competent authority with access to all information at my disposal regarding this application, whether such information is favourable to the applicant or not;
- declare that all the particulars furnished by me in this form are true and correct;
- I am aware that a person is guilty of an offence in terms of Regulation 48 (1) of the EIA Regulations, 2014, if that person provides incorrect or misleading information. A person who is convicted of an offence in terms of subregulation 48(1) (a)-(e) is liable to the penalties as contemplated in section 49B(1) of the National Environmental Management Act, 1998 (Act 107 of 1998); and

• I will comply with all the requirements as indicated in the National Environmental Management Act, 1998 (Act 107 of 1998) and Environmental

Impact Assessment Regulations, 2014.

Name of the Environmental Assessment Practitioner Signature of the Environmental Assessment Practitioner Name of company Date Name of Commissioner of Oaths Signature of Commissioner of Oaths Date **Designation** Official stamp (below)

R. Where applicable, details of any financial provisions for rehabilitation, closure, and ongoing post decommissioning management of negative environmental impacts

S. Any specific information that may be required by the competent authority

T. Any other matters required in terms of section 24(4)(a) and (b) of the Act