

mineral resources

Department: Mineral Resources REPUBLIC OF SOUTH AFRICA

ENVIRONMENTAL IMPACT ASSESSMENT REPORT AND

ENVIRONMENTAL MANAGEMENT PROGRAMME REPORT

MINING RIGHT APPLICATION FOR THE MINING DIAMONDS GENERAL, DIAMONDS ALLUVIAL AND KIMBERLITE NEAR PRIESKA ON REMAINDER OF PORTION 1 OF THE FARM UITDRAAI 33, REGISTRATION DIVISION PRIESKA RD, NORTHERN CAPE PROVINCE.

SUBMITTED FOR ENVIRONMENTAL AUTHORIZATIONS IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT, 1998 AND THE NATIONAL ENVIRONMENTAL MANAGEMENT WASTE ACT, 2008 IN RESPECT OF LISTED ACTIVITIES THAT HAVE BEEN TRIGGERED BY APPLICATIONS IN TERMS OF THE MINERAL AND PETROLEUM RESOURCES DEVELOPMENT ACT, 2002 (MPRDA) (AS AMENDED).

NAME OF APPLICANT	Prieska Diamond Mining (Pty) Ltd
TEL NO	(018) 011 1925
FAX NO	087 231 7021
POSTAL ADDRESS:	P.O. Box 1086, Schweizer-Reneke, 2780
PHYSICAL ADDRESS:	4 Botha Street, Schweizer-Reneke, 2780
FILE REFERENCE NUMBER SAMRAD:	NC30/5/1/2/2/10099MR

IMPORTANT NOTICE

In terms of the Mineral and Petroleum Resources Development Act (Act 28 of 2002 as amended), the Minister must grant a prospecting or mining right if among others the mining "will not result in unacceptable pollution, ecological degradation or damage to the environment".

Unless an Environmental Authorisation can be granted following the evaluation of an Environmental Impact Assessment and an Environmental Management Programme report in terms of the National Environmental Management Act (Act 107 of 1998) (NEMA), it cannot be concluded that the said activities will not result in unacceptable pollution, ecological degradation or damage to the environment.

In terms of section 16(3)(b) of the EIA Regulations, 2014, any report submitted as part of an application must be prepared in a format that may be determined by the Competent Authority and in terms of section 17 (1) (c) the competent Authority must check whether the application has taken into account any minimum requirements applicable or instructions or guidance provided by the competent authority to the submission of applications.

It is therefore an instruction that the prescribed reports required in respect of applications for an environmental authorisation for listed activities triggered by an application for a right or permit are submitted in the exact format of, and provide all the information required in terms of, this template. Furthermore please be advised that failure to submit the information required in the format provided in this template will be regarded as a failure to meet the requirements of the Regulation and will lead to the Environmental Authorisation being refused.

It is furthermore an instruction that the Environmental Assessment Practitioner must process and interpret his/her research and analysis and use the findings thereof to compile the information required herein. (Unprocessed supporting information may be attached as appendices). The EAP must ensure that the information required is placed correctly in the relevant sections of the Report, in the order, and under the provided headings as set out below, and ensure that the report is not cluttered with un-interpreted information and that it unambiguously represents the interpretation of the applicant.

ENVIRONMENTAL IMPACT ASSESSMENT PROCESS

(1) The environmental impact assessment process must be undertaken in line with the approved plan of study for environmental impact assessment.

(2) The environmental impacts, mitigation and closure outcomes as well as the residual risks of the proposed activity must be set out in the environmental impact assessment report.

OBJECTIVE OF THE ENVIRONMENTAL IMPACT ASSESSMENT PROCESS

2. The objective of the environmental impact assessment process is to, through a consultative process-

(a) determine the policy and legislative context within which the activity is located and document how the proposed activity complies with and responds to the policy and legislative context;

(b) describe the need and desirability of the proposed activity, including the need and desirability of the activity in the context of the preferred location;

(c) identify the location of the development footprint within the preferred site based on an impact and risk assessment process inclusive of cumulative impacts and a ranking process of all the identified development footprint alternatives focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects of the environment;

(d) determine the ---

(i) nature, significance, consequence, extent, duration and probability of the impacts occurring to inform identified preferred alternatives; and

(ii) degree to which these impacts-

(aa) can be reversed;

(bb) may cause irreplaceable loss of resources, and

(cc) can be avoided, managed or mitigated;

(e) identify the most ideal location for the activity within the preferred site based on the lowest level of environmental sensitivity identified during the assessment;

(f) identify, assess, and rank the impacts the activity will impose on the preferred location through the life of the activity;

- (g) identify suitable measures to avoid, manage or mitigate identified impacts; and
- (h) identify residual risks that need to be managed and monitored.

OBJECTIVE OF THE ENVIRONMENTAL IMPACT ASSESSMENT

- 1) Contact Person and correspondence address
 - a) Details of:

i) The EAP who prepared the report

Name of The Practitioner: Danie Labuschagne Tel No.: (018) 011 1925 Fax No. : (053) 963 2009 e-mail address: <u>danie@milnex-sa.co.za</u>

Name of Practitioner: Percy Sehaole Tel No.: (018) 011 1925 Fax No. : (053) 963 2009 e-mail address: percy@milnex-sa.co.za

ii) Expertise of the EAP.

(1) **The qualifications of the EAP** (With evidence attached as **Appendix 1**).

Danie Labuschagne holds a Master's Degree in Environmental Management and Geography (refer to **Appendix 1**)

Percy Sehaole holds a Master's Degree in Environmental Science (refer to **Appendix 1**)

(2) Summary of the EAP's past experience.

(Attach the EAP's curriculum vitae as Appendix 2)

Milnex 189 CC was contracted by Prieska Diamond Mining (Pty) Ltd as the independent environmental consultant to undertake the Scoping and EIA process for a Mining Right for the removal of Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province. Milnex 189 CC does not have any interest in secondary developments that may arise out of the authorisation of the proposed project.

Milnex 189 CC is a specialist environmental consultancy with extensive experience in the mining industry which provides a holostic encironmental management service, including environmental assessment and planning to ensure compliance with relevant environmental legislation. Milnex 189 CC benefits from the pooled resources, diverse

skills and experience in the environmental and mining field held by its team that has been actively involved in undertaking environmental studies for a wide variety of mining related projects throughout South Africa. The Milnex 189 CC team has considerable expierence in environmental impact assessment and environmental management, esprcially in the mining industry.

Danie Labuschagne and Percy Sehaole has experience consulting in the environmental field. His key focus is on environmental assessment, advice and management and ensuring compliance to legislation and guidelines. He is currently involved in undertaking EIAs for several projects across the country (refer to **Appendix 2** for CV)

b) **Description of the property.**

Farm Name:	1. Remainder of Portion 1 of the farm Uitdraai No. 33
Application area (Ha)	3695.0244 Ha
Magisterial district:	Prieska
Distance and direction from	The property is situated on the Orange River approximately 30km
nearest town	from Prieska in a Northern Easterly direction.
21 digit Surveyor General Code	1. C060000000003300001
for each farm portion	

c) Locality map

(show nearest town, scale not smaller than 1:250000 attached as Appendix 3).

Farm	Latitude	Longitude
Remainder of Portion 1 of the farm Uitdraai No. 33	29°38'48.86"S	22°55'50.83"E
	29°35'55.52"S	22°57'44.17"E
	29°36'22.11"S	22°55'24.41"E
	29°35'7.83"S	22°54'9.86"E
	29°33'32.28"S	22°52'20.82"E
	29°32'26.11"S	22°51'8.52"E
	29°33'9.24"S	22°50'59.65"E
	29°32'47.43"S	22°50'36.64"E
	29°34'51.60"S	22°52'21.60"E
	29°36'10.77"S	22°52'33.92"E
	29°37'23.74"S	22°52'5.01"E
	29°37'40.69"S	22°53'5.09"E
	29°38'1.99"S	22°53'3.92"E

A Locality map is attached in **Appendix 3 and** figure 1 below.



Figure 1: Locality map

d) Description of the scope of the proposed overall activity.

i) Listed and specified activities

Provide a plan drawn to a scale acceptable to the competent authority but not less than 1: 10 000 that shows the location, and area (hectares) of all the aforesaid main and listed activities, and infrastructure to be placed on site and attach as **Appendix 4**

Refer to Site Plan included within Appendix 4 and figure 2 below.



Figure 2: Site Plan Map

NAME OF ACTIVITY (All activities including activities not listed) (E.g. Excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetcetc.)	Aerial extent of the Activity Ha or m ²	LISTED ACTIVITY Mark with an X where applicable or affected.	APPLICABLE LISTING NOTICE (GNR 544, GNR 545 or GNR 546)/NOT LISTED
Clearance of indigenous vegetation	3695.0244ha - Only the areas where mining takes place, will be cleared. Concurrent backfilling will take place in order to rehabilitate.	Х	GNR. 984
Office and Workshop	100m ²	-	-
Roads	+- 20 km	-	-
Stockpiling op topsoil	3695.0244ha – The active mining site will		

	be restricted to only 5ha at any given time in order for rehabilitation to take place.	-	-
Mining of Diamond Alluvial - Excavations	3695.0244ha – The active mining site will be restricted to only 5ha at any given time in order for rehabilitation to take place.	X	GNR. 984
Processing Plant	4 X 16 feet washing pan– 137,280 tons/month to be washed	Х	-

5.	Listing Notice GNR 984, Activity 21: "Any activity including the operation
	of that activity associated with the primary processing of a mineral resource
	including winning, reduction, extraction, classifying, concentrating, crushing,
	screening and washing but excluding the smelting, beneficiation, refining,
	calcining or gasification of the mineral resource in which case activity 6 in
	this Notice applies."

ii) <u>De</u>scription of the activities to be undertaken

(Describe Methodology or technology to be employed, and for a linear activity, a description of the route of the activity

Timeframes and scheduling of Implementation Phases

• Explanation of time taken to develop the mine and commence production.

It will take approximately three to six months to erect the mining sight, to build the infrastructure and to commence with production.

• Explanation of the production build-up period once production commences.

From date of mining activities commences the production will be build up so that the mine can be in full production a month after date of commencement.

• Explanation of production decline period (as grades deteriorate).

In the event that the diamond price is lower than estimate \$600 a carat and the grade drops below 0.15 carats per 100 ton, the holder will then consider to put the mine on care and maintenance.

• Production forecast for each year over the full period applied for based on the above explanations. (Not Life of Mine calculation).

Year	Production Period	Tons	Carats
Year 1-11	5 months	5x137,280 = 686,400 100 x 0.3	2059
Year 2-11	11 months	11x137,280= 1,510,080 100 x 0.3	4530

Year 1:R24 102 000Year 2:R53 024 400Year 3:R55 675 620Year 4:R58 459 401Year 5:R61382 371Year 6:R64 451 489Year 7:R67 674 064

Year 8: R71 057 767 Year 9: R74 610 655 Year 10: R78 341 188

Technically justified estimate of the period required

(Description of the rate of production, estimated payable reserve ratio, efficiency factors and extraction rates, relative to available resources to justify the period applied for).

The applicant will conduct his activities with at least 4x 16ft washing machines. These machines will wash 260 tonnes of gravel an hour. Activities will be conducted for 24 hours a day.

4 x (washing plants) x 65 (tonnes an hour) x 24 (working hours per day x 22 (working days during the month) = 137,280 tonnes a month.

137.280 (tonnes) 100 x 0.3 = 411,8 carats a month.

Mine design map

Due to the nature of alluvial mining it is extremely difficult to have a predetermined mine plan. Mining and mine planning is reviewed as per results achieved. See **Appendix 4** for the basic site plan.

Description of the mining method's impact on operating cost.

• Basic overview of the mining method

The gravel will be removed from the property by an excavator/s. It will be loaded by the excavator onto a dumper truck which will transport the gravel to the gravel stockpile. From here the gravel will be moved by a front-end loader to the screen and scrubber into the washing plants and to the flowsort plant. The gravel will be processed in the plant for later sorting of the concentrate derived from the plant in the flowsort. All waste will either be accumulated in a dump dam or used for rehabilitation, by washing the waste back into the excavations. Tailings will be pumped into the tailings dam.

• Equipment to be used

Excavators Front end loaders Dumper trucks

High level description of the processing plant

• Basic plant design

Except for processing it is not foreseen that there will be any technological processes for the extraction and preparation for the minerals. The minerals are diamonds, which will be sold in a form the way they are found. The Tender House

where the diamonds will be sold deep boil the diamonds. The cost of the deep boiling is subtract from the 1.5% commission payed over to the Tender House.

• Efficiency of the process

The mineral recovery rate will be 0.3 carats per 100 tons of gravel processed. Approximately 1.2t - 1.6t of the residue will be formed for everyone ton of gravel processed. The reason here for is for the water used during the processing activities. The residue will either be washed back into the excavations or washed into a tailings dam.

The diamond pan is one of the oldest methods that is used for concentrating and the recovery of diamonds in the North West Region. The pan is used to separate light material in the feed to the pan from the heavy minerals – the diamond being relatively heavy at an Rd of 3.53

The method is relatively cost effective but produces a large amount of concentrate and recovery efficiencies is very sensitive to size distribution of the feed and the quality of the medium – called puddle.

Pan efficiencies are normally calculated at approximately 80 % recovery of diamonds provided that all operational parameters are being adhered to and medium contamination is kept to the minimum. Losses will mainly occur in the very small diamond fractions.

The estimated mineral recovery rate will be dependent on the prevailing condition as well as the type of material to be processed varying from dry material with high sand content to high clay presence but on average a grade of 0.60 carats per 100 ton material processed can be achieved with operations being retarded during periods of high rain occurrence.

This may also be influenced by the uneven distribution of diamonds in the area.

Oversize material (25 % of ROM feed), pan tailings (40 %) of ROM Feed) are being backfilled into open and depleted mining trenches simultaneously with the Plant feed process.

Slimes/waste from the pan operations (water/fines/solids) are being re-directed to depleted mining trenches with the objective of replenishing underground water and the stabilization of the water table. This is estimated at about 25 % of ROM feed.

This is of critical importance in view of the relative scarcity of water in the area. The Pan Plant process water requirements is estimated at approximately 25 cubic meters per hour.

Rehabilitation and Closure

- Remove all mining related infrastructure
- Return tailings and overburden to the excavation in order to fill up the excavation.
- Place topsoil on top of the backfilled excavation.
- Rehabilitate disturbed areas appropriately

e) Policy and Legislative Context

APPLICABLE LEGISLATION AND GUIDELINES USED TO COMPILE THE	REFERENCE
REPORT (a description of the policy and legislative context within which the	WHERE
development is proposed including an identification of all legislation, policies, plans,	APPLIED
that are applicable to this activity and are to be considered in the assessment process):	
The Constitution of South Africa	
(Act No. 108 of 1996)	-
The National Environmental Management Act	S24(1) of NEMA
(Act No. 107 of 1998)	S28(1) of NEMA
The National Water Act (Act No. 36 of 1998)	S21 (a)(b) of NWA
Management: Air Quality Act	S21
(Act No. 39 of 2004)	
The National Heritage Resources Act	-
(Act No. 25 of 1999)	
Conservation of Agricultural Resources Act (Act No. 85 of 1983)	-
Mineral and Petroleum Resources Development Act (Act No. 28 of 2002)	-
National Infrastructure Plan	-
Northern Cape Province Growth and Development Strategy	-
Pixley Ka Seme District Municipality Integrated Development Plan (IDP)	
	-
Siyathemba Local Municipality Integrated Development Plan (IDP) Review	-

f) Need and desirability of the proposed activities.

(Motivate the need and desirability of the proposed development including the need and desirability of the activity in the context of the preferred location).

Prospecting rights, mining rights and mining permits have been applied for all around the proposed site, and the outcome of that prospecting activities under the prospecting right indicated that alluvial diamonds are found on site also more people from the surrounding community will be employed.

g) Period for which the environmental authorisation is required.

The environmental authorisation is required for a minimum period of 10 years.

h) Description of the process followed to reach the proposed preferred site.

NB!! – This section is not about the impact assessment itself; It is about the determination of the specific site layout having taken into consideration (1) the comparison of the originally proposed site plan, the comparison of that plan with the plan of environmental features and current land uses, the issues raised by interested and affected parties, and the consideration of alternatives to the initially proposed site layout as a result.

Due to the nature of alluvial mining it is extremely difficult to have a predetermined mine plan. Mining and mine planning is reviewed as per results achieved. For the purposes of this report, the overall mining area is presented in **Appendix 3**.

The stakeholder consultation phase has not been completed at this time, and therefore the comments raised by I&APs have not been incorporated in this section. This will be updated as part of the final report.

i) Details of all alternatives considered.

With reference to the site plan provided as Appendix 4 and the location of the individual activities on site, provide details of the alternatives considered with respect to:

- (a) the property on which or location where it is proposed to undertake the activity;
- (b) the type of activity to be undertaken;
- (c) the design or layout of the activity;
- (d) the technology to be used in the activity;
- (e) the operational aspects of the activity; and
- (f) the option of not implementing the activity.

(a) The property on which or location where it is proposed to undertake the activity

As discussed in the previous section, based on outcomes of prospecting activities under the prospecting right and previous studies in the vicinity of the proposed site, indicated that alluvial diamonds are found on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

Also it should just be mentioned that Prieska Diamond Mining (Pty) Ltd is not the land owner. According to the Mining work programme, DMR has been advised that the surface owner prevents the applicant from conducting prospecting activities on the property. The applicant was also advised that the surface owner will not allow him to mine on the property. This may have an effect on the development on the mine as it may be necessary for the applicant to approach the court for an interdict preventing the surface owner to prevent the applicant to conduct the mining activities on the property.

In terms of the technologies proposed, these have been chosen based on long term success in terms of their mining history. As the mining area has been determined by prospecting. The applicant will thus proceed with mining activities and the excavation of trenches. Trenches will be excavated by excavators. The topsoil will be removed and stored separately. The gravel will be removed and transported next to the processing plant. Here it will be stored and transported by a front-end loader into the processing plant. The gravel will be washed by using 4 x 16ft Pan processing plant. The waste will be washed back into the excavations. The possible diamond bearing gravel will be mortised into bins, where after the gravel will sorted by a sortex to separate the gravel to find the diamonds.

(c) The design or layout of the activity

Due to the nature of alluvial mining it is extremely difficult to have a predetermined mine plan. Mining and mine planning is reviewed as per results achieved. Where applicable a Water Use License Application will be launched for conducting mining operations in or near any water resource. A desktop study indicated that there are cultivated lands, water attributes, Perennial River, sand erosion and Non-perennial River. All infrastructure will be temporary and/or mobile.

(d) The technology to be used in the activity

In terms of the technologies proposed, these have been chosen based on the long term success of their mining history.

Although there are a number of different diamond recovery technologies being utilized worldwide, the two principal types are Rotary Pan Plants and Dense Media Separation (DMS). Both methods are in actual fact used for bulk material reduction and require a further process for the final diamond recovery. These systems are based on the property of diamonds having a much higher specific gravity (density) of ~3.52 g/cm3 compared to most of the other minerals that make up material in which diamonds are found.

The first stage of kimberlite processing is to crush and screen the mined ore as required in order to reduce its' size. For alluvial type deposits crushing is rarely required and the material goes straight to screening. Depending on the processing method being employed, material under a certain chosen size fraction may go through a scrubbing system to clean the ore prior to it being fed into the processing plant.

Rotary Pan Plants

In a Rotary Pan plant, crushed ore, when mining kimberlite, or alluvial gravel and soil is mixed with water to create a liquid slurry called "puddle" which has a density in the 1.3 to 1.5 g/cm3 range. The mix is stirred in the pan by angled rotating "teeth". The heavier minerals, or "concentrate", settle to the bottom and are pushed toward an extraction point, while lighter waste remains suspended and overflows out of the center of the pan as a separate stream of material. The concentrate, representing just a small percentage of the original kimberlite ore or alluvial gravels, is drawn off for final recovery of the diamonds.

Dense Media Separation (DMS) Plants

In a Dense Media Separation (DMS) plant, powdered ferrosilicon (an alloy of iron and silicone) is suspended in water to form a fluid near the density of diamond (3.52 g/cm3), to which the diamond bearing material is added to begin the separation process of the heavier minerals from the lighter material. Additional separation of the denser material occurs by centrifuge in "cyclones" that swirl the mixture at low and high speeds, forcing the diamonds and other dense minerals to the walls and then out the bottom of the cyclone. Waste water rises at the center of the cyclones and is sucked out and screened to remove waste particles. The DMS process results in a concentrate that generally weighs less than one percent of the original material fed into the plant at the beginning of the process.

Both recovery methods have their advantages and disadvantages, but in this case a pan will be used since it is much more advantageous. Its advantages are as follow:

- The diamond pan is one of the oldest methods that is used for concentrating and the recovery of diamonds in the North West Region.
- The capital required for an equivalent (high) throughput DMS plant is in the order of ten times higher than the capital required for a Rotary Pan plant.
- Water usage and operating costs for an equivalent DMS plant are also typically much higher than that of a Rotary Pan plant.
- Oversize material (25 % of ROM feed), pan tailings (40 %) of ROM Feed) can be backfilled into open and depleted mining trenches simultaneously with the Plant feed process.
- Slimes/waste from the pan operations (water/fines/solids) can be re-directed to depleted mining trenches with the objective of replenishing underground water and the stabilization of the water table.

(e) The operational aspects of the activity

Due to the nature of the mining activities, services in terms of water supply, electricity, or sewerage services are required for 10 years.

The activities will commence according to the results of the prospecting activities and the further prospecting activities, which will be taking place under the mining right. This will ensure that the applicant can clearly delineate areas which are suitable for further investigation and no unnecessary surface disturbance will be undertaken.

Trenches and pits will then be dugg according the above mentioned results.

Material from mining trenches delivered by ADT is stockpiled at the pan plant site in the vicinity of the pan feed bin. The material will then be fed to the pan feed bin with a front-end-loader at a rate of approximately 45 tons per hour depending on the type of material (lower feed rates for material with high sand or clay content).

The material will then be screened to minus 32 mm by using a barrel screen. The screened material will the be fed into the pan with a pan feed conveyor. The remaining oversize material (+ 32 mm) will then be directed to a tailings dump via a tailings conveyor.

The pan material will be separated with a medium of puddle applying the sink/float principle.at an operating density of Rd 1.35 - Rd 1.40. The floating particles (gravel/puddle/fines) is then directed to a chute onto a dewatering screen and screened at 1.00 mm. The plus 1.00 mm material or pan tailings are directed to a tailings dump with a tailings conveyor.

The minus 1.00 mm material (slimes) will be collected in the screen under the pan and pumped to an open and depleted mine trench inorder to replenish the underground water and to restore the underground water level. This operation is done during the same cycle of plant ROM feed.

As an alternative to the above mentioned; the pan may be situated on the side of an open and depleted mining trench in order to deposit oversize, pan tailings and slimes directly into the open and worked mining trench.

The concentrated material will tapped into a concentrate bin and transported to a Final Recovery Plant for final diamond concentration and recovery.

All data will be consolidated and processed to determine the diamond bearing resources on the property. This will be a continuous process throughout the mining work programme.

No feasible alternatives to the pitting and trenching method currently exists. Impacts associated with the mining operations will be managed through the implementation of a management plan, developed as part of the application for authorisation.

When it comes to dust suppression two main methods were considered, namely molasses stillage and the wetting (water) of roads. The table below provides a short summary of the advantages and disadvantages of each.

Water	Molasses stillage
More cost effective	Much more expensive
Could lead to the depleting of water	Requires less water
resources	
No damage (only if used excessively)	The product may be toxic to aquatic
	organisms. (As this product could have
	physical effects on aquatic organisms for
	e.g. floating, osmotic damage)
No harm to humans or animals(Only a high	Not Hazardous or toxic.
quantity will have harm to humans or	Could cause irritation to eyes, skin or when
animals)	ingested and inhaled.
Non-flammable	Non-flammable
Eye-wash fountains not needed	Eye-wash fountains in the work place are
	strongly recommended
	Working procedures should be designed to
	minimize worker exposure to this product.
Basic storing methods	Storing methods are a bit more complicated.
	Should be stored in a plastic, plastic lined or
	stainless steel, tight closed containers
	between 5 and 40 degrees Centigrade.

Considering the above mentioned information, water will be used for dust suppression purposes.

(f) The option of not implementing the activity

This alternative considers the option of 'do nothing' and maintaining the status quo. The description provided in section H of this report could be considered the baseline conditions (status quo) to persist should the no-go alternative be preferred. The site is currently zoned for agricultural land uses. Should the proposed activity not proceed, the site will remain unchanged and will continue to be used for low density cattle grazing.

(f) The option of not implementing the activity

This alternative considers the option of 'do nothing' and maintaining the status quo. The description provided in section H of this report could be considered the baseline conditions (status quo) to persist should the no-go alternative be preferred. The site is currently zoned for agricultural land uses. Should the proposed activity not proceed, the site will remain unchanged and will continue to be used for low density cattle grazing.

ii) Details of the Public Participation Process Followed

Describe the process undertaken to consult interested and affected parties including public meetings and one on one consultation. NB the affected parties must be specifically consulted regardless of whether or not they attended public meetings. (Information to be provided to affected parties must include sufficient detail of the intended operation to enable them to assess what impact the activities will have on them or on the use of their land.

1. Advertisement and Notices

Newspaper advertisement

Since the proposed development is unlikely to result in any impacts that extent beyond the municipal area where it is located, it was deemed sufficient to advertise in a local newspaper. An advertisement was placed in English in the local newspaper (Gemsbok) on the 19 February 2016 (see **Appendix 6**) notifying the public of the EIA process and requesting Interested and Affected Parties (I&APs) to register with, and submit their comments to Milnex 189 CC. I&APs were given the opportunity to raise comments within 30 days of the advertisement.

Site notices

Site notices was placed on site on the 16th February 2016, in English, to inform surrounding communities and immediately adjacent landowners of the proposed development. I&APs are given the opportunity to raise comments within 30 days. Photographic evidence of the site notices will be included in **Appendix 6**.

Direct notification and circulation of Scoping Report to identified I&APs

Identified I&APs, including key stakeholders representing various sectors, were directly informed of the proposed development and the availability of the Scoping Report via registered post on 17 February 2016 and were requested to submit comments by 18 March 2016. A copy of the report will also be available at the Milnex offices, Schweizer-Reneke, from 7:00 – 17:00, Monday to Friday. For a complete list of stakeholder details and for proof of registered post see **Appendix 6**. The consultees included:

- Northern Cape Department of Environmental Affairs and Nature Conservation (DEANC)
- The Department of Water and Sanitation (DWS)
- NC Department of Agriculture, Forestry and Fisheries (NC DAFF)
- The Department of Agriculture (Dep. Agric)
- Provincial Heritage Resources Agency (NC PHRA)
- Department of Roads and Public Works (NC DRPW)
- NC Department of Mineral Resources (NC DMR)
- Pixley Ka Seme District Municipality
- The Wildlife and Environment Society of South Africa (WESSA)
- Siyathemba Local Municipality

- Land Owner: Wonderdraai trust
- Leopont 474 Prop (Pty) Ltd (Charl Johan de Villiers)
- Rondom Water Boerdery (Pty) Ltd
- Uitdraai Boerdery CC
- Green Valley Nuts (Pty) Ltd
- Anna Jacoba De Villiers
- Connie Coetzee Familie Trust (Coenraad Nolte Coetzee)
- Hentiq 2338 Pty Ltd
- Schalk Theron Familie Trust (Schalk Willem Petrus Theron)
- Williams Romeo Daniel David Stanley
- Tedo Beleggings 86 (Pty) Ltd (Charl Johan de Villiers)
- Oldewage Trust
- Mahoebe Eiendomme Pty Ltd
- Cypher Boerdery Trust

It is expected from I&APs to provide their inputs and comments within 30 days after receipt of the notification or Scoping Report. Comments are attached on table below

Direct notification of surrounding land owners and occupiers

Written notices and the availability of the Scoping Report were also provided to all surrounding land owners and occupiers on 19 February 2016. The surrounding land owners were given the opportunity to raise comments by 18 March 2016. For a list of surrounding land owners see **Appendix 6**.

2. <u>Consultation</u>

All I&AP's were invited to attend the public meeting held at Siyathemba Local Municipality Hall, 09th of March 2016. The public meeting was an opportunity to share information regarding the proposed development and provide I&APs with an opportunity to raise any issues and provide comments.

Siyathemba Local Municipality Hall			
Address:	Time:	Coordinates:	
1 Victoria Street, Prieska, 8940,	13:00PM – 14:00PM	-29° 39'59.84"S 22°44'59.93"E	

The following key stakeholders and surrounding land owners were also directly informed of the public meeting via registered post 19 February 2016:

- Northern Cape Department of Environmental Affairs and Nature Conservation (DEANC)
- The Department of Water and Sanitation (DWS)
- NC Department of Agriculture, Forestry and Fisheries (NC DAFF)
- The Department of Agriculture (Dep. Agric)
- Provincial Heritage Resources Agency (NC PHRA)
- Department of Roads and Public Works (NC DRPW)
- NC Department of Mineral Resources (NC DMR)

- Pixley Ka Seme District Municipality
- The Wildlife and Environment Society of South Africa (WESSA)
- Siyathemba Local Municipality
- Land Owner: Wonderdraai trust
- Leopont 474 Prop (Pty) Ltd (Charl Johan de Villiers)
- Rondom Water Boerdery (Pty) Ltd
- Uitdraai Boerdery CC
- Green Valley Nuts (Pty) Ltd
- Anna Jacoba De Villiers
- Connie Coetzee Familie Trust (Coenraad Nolte Coetzee)
- Hentiq 2338 Pty Ltd
- Schalk Theron Familie Trust (Schalk Willem Petrus Theron)
- Williams Romeo Daniel David Stanley
- Tedo Beleggings 86 (Pty) Ltd (Charl Johan de Villiers)
- Oldewage Trust
- Mahoebe Eiendomme Pty Ltd
- Cypher Boerdery Trust

The meeting were attended by:

Milnex representative:

- Anica Nieuwoudt
- Mr Danie Labuschagne

<u> 1&AP</u>

• H. Morobisi (Municipality of Siyathemba)

No objections were raised

Circulation of EIR

The following registered I&APs and State Department were informed via a written notice, on the 30 May 2016 and informed about the availability of the EIR (refer to Appendix 6)

3. <u>Issues Raised by Interested and Affected Parties</u>

All comments received during the review period of the draft Scoping report, as well as response provided will be captured and recorded within the comment and response report and attached in the final Scoping Report (**Appendix 6**).

iii) Summary of issues raised by I&APs (Complete the table summarising comments and issues raised, and reaction to those responses)

Interested and A List the names of perso column, and Mark with an X where consulted were in	ffected Parties ons consulted in this those who must be fact consulted.	Date Comments Received	Issues raised	EAPs response to issues as mandated by the applicant	Section and paragraph reference in this report where the issue and or response where incorporated
Organisation	Contact person				
Land Owner Farm: Uitdraai 1/RE/33	Wonderdraai trust		No comments raised		
Landowners or lawful o Uitdraai 5/33	Ccupiers on adjacent Leopont 474 Prop (Pty) Ltd Charl Johan de Villiers	properties 14/03/2016 17/03/2016	The EAP received a call from Mr Charl Johan de Villiers requesting that the draft Scoping report should be emailed to him Insake: Kommentaar van omliggende grondeienaar 1	Pursuant the telephonic conversation the Draft Scoping report was emailed as per request (on the 14/03/2016) The EAP called Mr Johan on the 15 March 2016 to verify if he received the Draft scoping report and he confirmed that he did. Beste Johan,	
			 en 5 van Restant van Gedeelte 1 van die plaas Uitdraai 33 Met verwysing na u brief, gedateer 17 Februarie 2016, rig ons die volgende skrywe aan u: 1 Mynreg houers het 'n geskiedenis van onvermoë om rehabilitasie in die gebied te doen soos te Zilverstroom. Wie gaan toesien dat rehabilitasie gedoen word. Die Departement van Minerale en Engergie (DME) is disfunksioneel in die opsig om regulering toe te pas, ten spyte van versoeke van 	Hiermee bevestig ek net dat ek wel dié e-pos ontvang het.	

 die grondeienaar om dit aan te spreek. Sanddrif is ook'n voorbeeld van laagenoemde. 2 Geen slikdamme mag gemaak word nie. Slik van bestaande slikdamme moet ook everedig verspreid teruggepomp word in opgevulde gate voordat die bogrond teruggeplaas word - mynreg houers kon dit nie voorheen nakom nie, alhoewel dit aarvenklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestot word vir genef soos by Zilverstroom. Remhoogte, Sanddrif, Makoenskoof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemme deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het ges6 ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie - bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitaer is wat offet, Sanddrif, Nuwejaarskraal, Braktontein, Sonop, Wouterspan, Saxendrift en Makoenskoof, moet aangespreek word. In die lig van hierdie natatspreek word. In die lig van hierdie natatspreek word. 			
 is ook 'n voorbeeld van laasgenoemde. 2 Geen slikdamme mag gemaak word nie. Slik van bestaande slikdamme moet ook eweredig verspreid teruggepomp word in opgevulde gate voordat die bogrond teruggeplaas word – mynreg houers kon dit nie voorbeen nakom nie, alhoewel dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoensklod en Vouterspan nie. By Zilverstroom is die natuurlike loopplek van die mid dit taal vandt. Nakoensklod en Vouterspan nie. By Zilverstroom is die natuurlike loopplek van die mid dit taal avalt. Beinder die gruis auf geriefshalwe net oor die afgrond gestoot is on die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DIE aangemid wat dit toe gestop het, maar hulle het gesto on moet kyk as dit klaar genehabiliteer is, wat nooit gebeur het nie - bewys dat DIME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoé van DIME om rehabilitasite monitor en beheer in die mid extra dir Me geston het, makange, zuit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Braktontein, Sonop, Wouterspan, Saxendrift en Makensklod, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoé en disfunksionerie van dierdie nalatigheid, onvermoé en disfunksionerie van dierdie set on die angespreek word. In die lig van hierdie nalatigheid, onvermoé en disfunksionerie van dierdie set on die angespreek word. In die lig van hierdie nalatigheid, onvermoé en disfunksionerie van dierdie set onder ondervinding van en geskiedenis van dierdie nalatigheid, onvermoé en disfunksionerie van dierdie set ondervinding van en geskiedenis van dierdie nalatigheid, onvermoé en disfunksionerie van dierdie set ondervinding van en die undervinding van en disfunksionerie van dierdie set ondervinding van en disfunksionerie van dierdie set ondervindie van dierdie va		die grondeienaar om dit aan te spreek. Sanddrif	
 2 Geen slikdamme mag gemaak word ne. Slik van bestaande slikdamme moet ook everedig verspreid teruggepomp word in opgevulde gate voordat die bogrond teruggeplaas word – mynreg houers kon dit nie voorbeen nakom nie, alhoewel dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zliverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zliverstroom. Remhoogle, Sanddrif, Makoenskloof en Wouterspan nie. By Zliverstroom is die natuurlike loopplek van die wiid totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gerief soot is. Zliverstroom lis, wat nooit gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunktioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Renhoogte, Zliverstroom, Sanddrif, Nuwejaarskraal, Braktontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME angemenk van die na geskiedenis van Satelfrie hat were bevord. 		is ook 'n voorbeeld van laasgenoemde.	
 bestaande slikkdamme moet ook eweredig verspreid teruggepomp word in opgevulde gate voordat die bogrond teruggeplaas word – mynreg houers kon dit nie voorheen nakom mie, alhoewel dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis werd buite span nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis werd buite geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is on die kranse heen na die rivier gereinabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoe van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van dief, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Savendriff en Makoenskloof met aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionerig van die gruis provensoe en diskustien sonop, Wouterspan, Savendriff en Makoenskloof met aangespreek word. 	2	Geen slikdamme mag gemaak word nie. Slik van	
 verspreid teruggepomp word in opgevulde gate voordat die bogrond teruggeplaas word – mynreg houers kon dit nie voorheen nakom nie, alhoewel dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net or die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME angemeld wat dit toe gestop het, maar hulle het gesé ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunktioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoors onverntwordelik wees 		bestaande slikdamme moet ook eweredig	
 voordat die bogrond teruggeplaas word – mynreg houers kon dit nie voorheen nakom nie, alhoewel dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesé ons moet kyk as dit klaar gerenhabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoe van DME om rehabilitae is van neem kyk as dit klaar gerenhabiliteer is, van neem kyk as dit klaar gerenhabiliteer is, van meem kyk as dit klaar gerenhabiliteer is, van nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoe van DME om rehabilitae is van Remihoogte, Zilverstoom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendriff en Makoenskloof, moet aangegreek word. In die lig van hierdie nalatigheid, onvermoë en diskunksjonering van die DME sou dit hoorse noverantworende is was 		verspreid teruggepomp word in opgevulde gate	
 houers kon dit nie voorheen hakom nie, alhoewei dit aanvanklik ooreengekom was met die grondienaar by toestermning tot myn aktiwiteite op die plaas Zilverstroom. Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die nivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesé ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Braktontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksioneelig van die DME sou dit hoogs onverantwordelik wees 		voordat die bogrond teruggeplaas word - mynreg	
 dit aanvanklik ooreengekom was met die grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom. Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermeé van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionreel is disfunksionreel and the make part of the makeenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionreel 		houers kon dit nie voorheen nakom nie, alhoewel	
 grondeienaar by toestemming tot myn aktiwiteite op die plaas Zilverstroom. Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoenskloof en Vouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die breeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesé ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Braktontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionenig van 		dit aanvanklik ooreengekom was met die	
 op die plaas Zilverstroom. 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makeenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesé ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoé van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME Seut dit hoors onverentwoordelik wees 		grondeienaar by toestemming tot myn aktiwiteite	
 3 Geen gruis mag buite die mynarea gestort word vir gerief soos by Zilverstroom, Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesè ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aaangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoors onverentwoorrfelik wees 		on die plaas Zilverstroom	
 vicing sind mag data mag data mag betar transform. Remhoogte, Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hooss onverantwoordelik wees 	3	Geen gruis mag buite die mynarea gestort word	
 Sanddrif, Makoenskloof en Wouterspan nie. By Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendriff en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionerig van die DME sou dit hoors onverantwoordelik wees 	Ŭ	vir gerief soos by Zilverstroom Remboorte	
 Zilverstroom is die natuurlike loopplek van die wild totaal belemmer deur gruis wat geriefshalwe net oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabilteer is, wat nooit gebeur het nie - bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME disfunksionering van die DME sou dit hooss onverantwoordelik wees 		Sanddrif Makoanskloof an Wouterspan nie By	
 Liverstoom is used naturation loopplek van die wie het oor die afgrond gestoot is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit booss onverentwoordelik wees 		Zilverstreem is die natuurlike leennlek van die	
 wild totad de afgrond gestod is. Dieselfde het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die ongewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit boogs onverantwoordelik wees 		Zilverstroom is die natuunike loopplek van die	
 Net oor die argrond gestoot is. Diesende het by Sanddrif gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit boors onverantwoordelik wees 		wild total belefilitier deur gruis wat genershalwe	
 Sahadrit gebeur waar die gruis oor die kranse heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoors onverantwoorrelik wees 		net oor die afgrond gestoot is. Dieselfde net by	
 heen na die rivier gestoot is en die broeiplekke van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		Sanddrif gebeur waar die gruis oor die kranse	
 van diere permanent verlore gegaan het. Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		heen na die rivier gestoot is en die broeiplekke	
Laasgenoemde is skriftelik by DME aangemeld wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		van diere permanent verlore gegaan het.	
 wat dit toe gestop het, maar hulle het gesê ons moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		Laasgenoemde is skriftelik by DME aangemeld	
 moet kyk as dit klaar gerehabiliteer is, wat nooit gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		wat dit toe gestop het, maar hulle het gesê ons	
 gebeur het nie – bewys dat DME disfunksioneel is soos in punt 1 na verwys is. 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		moet kyk as dit klaar gerehabiliteer is, wat nooit	
 is soos in punt 1 na verwys is. Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		gebeur het nie – bewys dat DME disfunksioneel	
 4 Onvermoë van DME om rehabilitasie te monitor en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees 		is soos in punt 1 na verwys is.	
en beheer in die omgewing, soos bleik uit die ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit boogs onverantwoordelik wees	4	Onvermoë van DME om rehabilitasie te monitor	
ondervinding van en geskiedenis van Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		en beheer in die omgewing, soos bleik uit die	
Remhoogte, Zilverstroom, Sanddrif, Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		ondervinding van en geskiedenis van	
Nuwejaarskraal, Brakfontein, Sonop, Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		Remhoogte, Zilverstroom, Sanddrif,	
Wouterspan, Saxendrift en Makoenskloof, moet aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		Nuwejaarskraal, Brakfontein, Sonop.	
aangespreek word. In die lig van hierdie nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		Wouterspan, Saxendrift en Makoenskloof, moet	
nalatigheid, onvermoë en disfunksionering van die DME sou dit hoogs onverantwoordelik wees		aangespreek word. In die lig van hierdie	
die DME sou dit hoogs onverantwoordelik wees		nalatigheid, onvermoë en disfunksionering van	
		die DME sou dit hoogs onverantwoordelik wees	

om verdere mynregte uit te reik omdat die	
probleem net gaan vergroot en die eienaar gelaat	
gaan word met die probleme van myne wat nie by	
hul omgewingsimpakstudies hou. Die	
departement het met die toestaan van die mynreg	
op Remboogte geensins hieraan aandag gegee	
tot on datum nie ten snyte van skrywes aan die	
departement voor die toekenning van die mynreg	
on Domboosto in biordio vorband on latoro	
up remaine and the stan	
5 vvaarom sal die myn winsgewend bedryf kan	
word as Zilverstroom, Wouterspan,	
Nuwejaarskraal, Sonop en Makoenskloof nie	
winsgewend bedryf kon word nie en nou bloot	
gelos is om net so te lê sonder dat rehabilitasie	
gedoen is? Vorige delwers (en Rockwell tans op	
Remhoogte) was ook nie suksesvol op	
Zilverstroom en Remhoogte nie en kon nie	
ekonomies 'n bestaan uit die diamante hier maak	
nie. Telkens word die reg aan 'n nuwe	
maatskappy verkoon tesame met die rehabilitasie	
verantwoordelikheid maar die rehabilitasie wat	
nie gedoen word nie, eskaleer net met tyd	
6 Die genoekers het nie bewers det die men van	
diamanta ekonomiaa ragvardighaar on	
ulamante ekonomies regveruigbaar en	
iewensvalbaar is nie. Geen prospektering is	
gedoen om die graad van die diamantgruis te	
bepaal nie.	
/ Vorige uitstaande skuld aan die grondeienaar is	
nooit betaal deur die vorige twee mynreghourers	
op Zilverstroom nie en op die oomblik kom	
Rockwell nie hulle kontrak na op Remhoogte nie.	

Die oppervlaksgebruiksooreenkoms is nie
nagekom nie.
8 Wie gaan verantwoordelik wees vir ongedierte
beheer op die beplande mynarea om te keer dat
dit nie 'n teelarea vir die diere word nie? Dit moet
deurlopend gedoen word, ons doen dit tans
deurlopend op ons aangrensende grond.
9 Wie gaan verantwoordelik wees vir indringer
plantspesies (Prosonis, olieboom en boetebos
hyvoorbeeld) beheer in die benlande mynarea?
10 Hoe gaan mikro habitatte versteuring en
vernietiging binne die greter biediversiteite
amaguing benerik of verbood word? Mure on
aansoekers nou nie by die
omgewingsbestuursplan se voorstelle nie en die
DME kontroleer en beheer dit nie.
11 Die biodiversiteits opname moet volledig wees in
terme van grond, diere, plante en insekte en
gedoen word deur 'n geakkrediteerde
omgewingskundige wat vertroud is met die
plaaslike fauna en flora. Die huidige verslag is
afgewater en stel impakte as minimaal voor,
terwyl dit duidelik uit ander myne in die omgewing
bleik dat dit presies die teenoorgestelde is. Ook
wat geskiedkundige belange betref – wat van
bestaande boesmantekeninge waarvan geen
melding gemaak word nie? Dit gaan geensins
hewaar word as dit nie vooraf afgebaken word nie
en kan nie vanuit die benlande groot masijenerie
wat daar gaan work, raakgooion word nie on is
wat uaar yaari werk, raakyesien woru nie en is die nunt van em dit te heuveer eene dit gevind
die punt van om dit te bewaar soos dit gevind
word, irrelevant.

	12	Stofbesoedeling – wat gaan hieromtrent gedoen	
		word? Ons het ondervinding dat niks by huidige	
		en vorige myne hieromtrent gedoen word nie.	
		Wat gaan van ons aangrensende wildkamp word	
		as die diere nie daar kan vreet nie, weens stof.	
		Ons het foto's wat toon dat plante totaal met stof	
		bedek is. Die probleem hier is dat myne net	
		beloftes maak, maar niks daaromtrent doen nie.	
	13	Stofbesoedeling op gewasse wat oesverlies tot	
		gevolg het, hoe gaan dit aangespreek word?	
		Foto's van dit beskikbaar.	
	14	Geraasbesoedeling – hoe gaan dit beperk word.	
		veral in die nag. Vragmotors se trurat sirenes	
		moet gedemp word.	
	15	Effek op grondwater – besoedeling van	
		grondwater weens olie lekke en plofstof.	
	16	Die aangrensende grond word as wildkamp en	
		vir graanproduksie gebruik en gaan nadelig	
		beïnvloed.	
	17	Myn werknemers mag nie op die perseel hout	
		maak nie.	
	18	Ongemagtigde skietery deur sekuriteit soos in die	
		verlede op Zilverstroom voorgekom het, mag nie	
		gebeur nie.	
	19	Geen paaie mag gemaak word wat nie	
		noodsaaklik is vir die mynproses nie. Geen grid	
		paaie mag gemaak word soos op Zilverstroom en	
		Sonop wat nooit eers gebruik word nie en nou net	
		kaal stroke in die veld is.	
	20	Rehabilitasie van paaie na die tyd en deurlopend	
		sodat dit nie meer sigbaar sal wees na die tyd nie.	
	21	Pad - wie gaan die infrastruktuur in stand hou	
		waarvoor die boere 'n deel betaal het, nl.	

	Muishoek pad. Verkeer word as minimaal	
	genoem – die teendeel is waar en myne het geen	
	beheer oor onverskillige ry van hul werknemers	
	nie en spreek dit nie aan nie.	
22	2 Die finale Omgewingsbestuursplan en	
	Omgewingsimpakstudie moet aan ons	
	beskikbaar gestel word voor die aansoek en	
	gevolglike toekenning van die mynreg om dit na	
	te gaan vir volledigheid en verdere insette. Dit is	
	omdat die Departement Mineraal en Energie	
	disfunksioneel en afwesig is in hierdie verband en	
	dus nie die vermoë het om dit uit te reik of te	
	polisieer nie – wat op sig self beteken dat die	
	mynreg nie toegeken mag word nie – veral nie	
	alvorens die departement bewys dat die foute van	
	bogenoemde myne reggestel is nie	
2:	3 Geen behuising mag aan mynwerkers on die	
	plaas dedee word nie en mad werkers sleds op	
	die plaas kom vir hulle skofte. Die rede hiervoor	
	is om te verhoed dat mynwerkers buite bulle	
	skofte rondloon in die gebied om hout te maak	
	strikke te stel vir diere en veiligheid in die	
	strikke të stër vir diere en veligheid in die	
	algemeen. 1 Indion daar vordoro samosprokings mot ons	
2	nodig is in verband met die mynrog aansoek op	
	doorno tudons dio mun poriodo moot dit	
	plaasvind op die plaas Pomboogte Drieska	
	p_{100}	
	0340. E Hiermen word versoek det teekometige beswere	
23	onlennee word versoek dat loekonstige besware	
	oux in administring geneem sar word, omdat all	
	onmoonlink is om vooruit te sien watter probleme	
	nog mag opduik rondom die myn en ook omdat	
	verdere probleme met verloop van tyd mag	

onduik, soos bewys uit die geskiedenis van die	
aansoekers en ander myne in die omgewing, wat	
voorheen nie by reëls kon hou nie.	
26 Ons stel dit weer duidelik dat DME nie met die	
Remhoogte mynreg toekenning enigsins op	
soortgelyke kommentaar reageer het nie of hul	
verantwoordelikheid nagekom het nie en dat ons	
daarom geen toekomstige mynreg toekennings	
deur die departement kan erken nie, alvorens die	
toute by bogenoemde myne nie aangespreek en	
dat die DME die voortgesette verpietiging van	
andbougrond toelaat nie wat gevolglik	
voedselproduksie permanent op daardie grond in	
die toekoms verhoed.	
Ons vertrou dat u aandag sal gee aan hierdie	
kommentaar en ook dat u dit onder die aandag	
van die DiviE sai bring wat geensins op	
soorigeryke kommeniaar rakende die Remnoogle mynreg aansoek gereageer het nie	
Uitdraai 8/33 Wonderdraai Trust No comments raised	
	noil correspondence on the
Uitoraai 9/33 J.J. Botma Letter received on the U4/U4/2016 states that Van De Proof of letter and em Wall Incorporates' client Mr. J.J. Botma objects against 16/05/2016	iall correspondence on the
(Van der Wall & the application and he have questions that he wants The letter dated 16/05	5/2016 answers all Mr. J.J.
Vennote) answered. Botma's questions an	nd kindly request access to
the property to enable	e the appointed specialist to
Please find the questions in the attached documents. do an Ecological Habi	itat Survey; biodiversity
and wetland assessme baseline report: berits	ient; air quality monitoring

	1			
			the tailings storage facility will be on the property and a 1:100year flood line assessment on the Orange river.	
			Email with attached letter sent on 26/05/2016 to request access to the property to enable the appointed specialist to do an: Ecological Habitat Survey; biodiversity and wetland assessment; air quality monitoring' baseline report; heritage impact assessment; a generic engineers design to determine where the tailings storage facility will be on the property and a 1:100year flood line assessment on the Orange river. Email with attached letter sent 10/06/2016	
			states: In both our letters send, 16 and 26 May 2016, we requested that you provide us with a suitable date for the proposed round table meeting with both you and your client. We also requested access to the property to enable the appointed specialist to do the studies. We confirm that we still await your response on both of the above mentioned requests.	
Uitdraai 15/33	Uitdraai Boerdery CC	No comments raised		
Muishoek 17/34 & 22/34	Green Valley Nuts (Pty) Ltd	No comments raised		
Remhoogte RE/152	Anna Jacoba De Villiers	Comments addressed by Mr Johan de Villiers above.		

EIA019 – Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

Spitzkop 6/26 Hentiq 2338 Pty Ltd No comments raised Spitzkop 10/26 Schalk Theron Familie Trust No comments raised Schalk Willem Petrus Theron No comments raised Blaauwbanks Fontein RE/25 Williams Romeo Daniel David Stanley No comments raised Hospital RE/365 Tedo Beleggings 86 (Pty) Ltd No comments raised Hospital 4/365 Oldewage Trust No comments raised Hospital 7/365 & 9/365 Mahoebe Eiendomme Pty Ltd No comments raised Uitdraai 3/33 Cypher Boerdery Trust No comments raised	Spitzkop 4/26	Connie Coetzee Familie Trust Coenraad Nolte Coetzee	No comments raised	
Spitzkop 10/26 Schalk Theron Familie Trust No comments raised Schalk Willem Petrus Theron No comments raised Blaauwbanks Fontein RE/25 Williams Romeo Daniel David Stanley No comments raised Hospital RE/365 Tedo Beleggings 86 (Pty) Ltd No comments raised Hospital 4/365 Oldewage Trust No comments raised Hospital 7/365 & 9/365 Mahoebe Eiendomme Pty Ltd No comments raised Uitdraai 3/33 Cypher Boerdery Trust No comments raised	Spitzkop 6/26	Hentiq 2338 Pty Ltd	No comments raised	
Blaauwbanks Fontein RE/25 Williams Romeo Daniel David Stanley No comments raised Hospital RE/365 Tedo Beleggings 86 (Pty) Ltd No comments raised Charl Johan de Villiers No comments raised Image: Charl Johan de Villiers Hospital 4/365 Oldewage Trust No comments raised Hospital 7/365 & 9/365 Mahoebe Eiendomme Pty Ltd No comments raised Uitdraai 3/33 Cypher Boerdery Trust No comments raised	Spitzkop 10/26	Schalk Theron Familie Trust Schalk Willem Petrus Theron	No comments raised	
Hospital RE/365Tedo Beleggings 86 (Pty) LtdNo comments raisedCharl Johan de VilliersCharl Johan de VilliersNo comments raisedHospital 4/365Oldewage TrustNo comments raisedHospital 7/365 & 9/365Mahoebe Eiendomme Pty LtdNo comments raisedUitdraai 3/33Cypher Boerdery TrustNo comments raised	Blaauwbanks Fontein RE/25	Williams Romeo Daniel David Stanley	No comments raised	
Hospital 4/365Oldewage TrustNo comments raisedHospital 7/365 & 9/365Mahoebe Eiendomme Pty LtdNo comments raisedUitdraai 3/33Cypher Boerdery TrustNo comments raised	Hospital RE/365	Tedo Beleggings 86 (Pty) Ltd Charl Johan de Villiers	No comments raised	
Hospital 7/365 & 9/365 Mahoebe Eiendomme Pty Ltd No comments raised Uitdraai 3/33 Cypher Boerdery Trust No comments raised	Hospital 4/365	Oldewage Trust	No comments raised	
Uitdraai 3/33 Cypher Boerdery Trust No comments raised	Hospital 7/365 & 9/365	Mahoebe Eiendomme Pty Ltd	No comments raised	
	Uitdraai 3/33	Cypher Boerdery Trust	No comments raised	
Hospital 11/365 & 12/365Does not exist according to Search worksNo comments raised	Hospital 11/365 & 12/365	Does not exist according to Search works	No comments raised	
Spitzkop 5/26 en 9/26 Does not exist No comments raised	Spitzkop 5/26 en 9/26	Does not exist	No comments raised	

Siyathemba Local Municipality	Municipal Manager: J.R.M. Alexander	No comments raised		
Municipal councilor of Siyathemba Local Municipality	the ward in which the site is Ward 4 Councilor	s located No comments raised		
Organs of state having	jurisdiction			
Northern Cape Department of Environmental Affairs and Nature Conservation (DEANC)	Mrs. Doreen Werth	No comments raised		
The Department of Water and Sanitation (DWS)	Ms. M. Mei	Letter stamped 05/04/2016 acknowledges the intent to apply for a water use authorization.	e receipt of Letter dated 18 March 2016, the EAP submitted a notice of intention to apply for a Water Use License for the proposed mining activities of Prieska Diamond Mining (Pty) Ltd on the Remaining Extent of Portion 1 (Wonderdraai) of the Farm Uirdraai 33, Registration Division Prieska RD, near Prieska in the Northern Cape Province.	
NC Department of Agriculture, Forestry and Fisheries (NC DAFF)	Mr. Viljoen Mothibi	No comments raised		
The Department of Agriculture (Dep. Agric)	Ms. Anneliza Collett/ Ms. Mashudu Marubini	No comments raised		
Provincial Heritage Resources Agency (NC PHRA)	K. Sofoleng	No comments raised		
Department of Roads and Public Works (NC DRPW)	HOD: Ms. Ruth Palm	No comments raised		

		40/00/0040			
NC Department of	Mogomotsi Mogale	16/03/2016	Letter dated 16 March 2016 stated that the Application is		
Mineral Resources			accepted.		
(NC DMR)			Thus scoping needs to be submitted within 44		
			days,		
			 EMPr within 106 days 		
			 Land owner & I&AP be notified 		
			 Lodge notice of intent for WUL application 		
	Sunday Mabaso			Letter dated 01/03/2016 is proof of land claims	
	,			consultation.	
	K Shapo & Sunday			Email with attached letter sent on 23/05/2016	
	Mabaso			proof of land owner consultation	
	Kgaudi Shapo		Letter signed 15/04/2016 states that:		
	riguudi onapo				
			1) the SR has been reviewed		
			2) Milney 189 CC are there for requested to unload		
			online conv and submit 5 manual conies		
			2) EIAD and EMDr must include comments from		
			5) LIAN and LIMPT must include comments from		
			DENC and DWS)		
			4) The public participation process must meet		
			minimum standards		
			5) Submit detailed itemization of financial provision		
			quantum		
			6) The EIAr and EMPr must contain all information		
			set out in Appendix 3 of NEMA and EIAr must		
			also contain all information set out in Regulation		
			23 (1)(a)&(b);(2);(3);(4) and (5) if applicable of		
			EIA regulations. 2014 of NEMA. EMPr must		
			comply with section 24N of the Act.		
			7) The supporting specialist studies must be		
			compiled in manner which adhere to (NEMA) as		
			amended and the EIA Regulations, 2014.		
			8) The office reserves the right to revise and/or		
			withdraw this comment and to request further		
			information form the application.		

		Kindly specified how many equipment of machinery types that are going to be used on the proposed mining.		
NC Department of Rural Development & Land Reform: Land Restitution Support	Mr Ryan Oliver	The letters dated 22/02/2016 stated that "This communique serves to advise Milnex 189 CC that according to the Northern Cape database there are no restitution claims lodged against the above mentioned property description."	The office of the regional land claims commissioner in the Northern Cape was consulted on an email dated 15/02/2016 to inquire whether there are any land claims on the proposed farms. The letter was submitted to DMR in the Northern Cape on the 01/03/2016 as proof of consultation	
Other-				
Pixley Ka Seme District	Municipal Manager:	No comments raised		
Municipality	Mr R. E. Pieterse			
WESSA	Mr. Lemson Petha	No comments raised		

iv) The Environmental attributes associated with the sites

(1) Baseline Environment

The baseline environment is described with specific reference to geotechnical conditions, ecological habitat and landscape features, Soil, land capability and agricultural potential, climate and the visual landscape. A desktop study indicated that there are cultivated lands, water attributes, Perennial River, sand erosion and Non-perennial River. All infrastructure will be temporary and/or mobile. Where applicable a Water Use License Application will be launched for conducting mining operations in or near any water resource.

(a) Type of environment affected by the proposed activity.

(its current geographical, physical, biological, socio- economic, and cultural character).

The Council for Geo Science describes the gravel found in the area under application as follows:

Geological formation

<u>Stratigraphy</u>

The bedrock consists of Andesitic Ventersdorp lavas overlain by Dwyka Tillites and mudstones of the Ecca group - Karoo Supergroup. To the north the Asbesberge is made up of dolomites and banded iron formations of the Griqaland West Sequence.

Prior to the Karoo period the Orange River cut a netwerk of channels closely approximately the present floodplain. These channels were then utilized by the subsequent glaciers and filled with the Dwyka tillites and shales (250 milion years ago). The post-Karoo Orange River subsequently incised into these formations and deposited gravels of the Rietputs Formation on mainly 3 terraces.

The bedrock consisting of horizontally bedded greenish-grey tillites results in wide, braided channels in comparison to narrow, well-defined channels with potholes as found in the Ventersdorp lava bedrock.

Gravel deposit

The older gravels known as "Rooikoppie" is a reworked residual of the calcreted basel older gravels and does not occur on the Wonderdraai deposit. Only a rudaceous red plalaesol developed on the surface of the current gravel deposit that is calcreted.

The terrace being explored on Wonderdraai is classified as the Rietputs A gravels and is located 60 meters above the current Orange River.

In general these gravels can be decribed as follows: It comprises a crudely stratified granule-boulder conglomerate with a pale brown sandy matrix overlain by a 3m calcreted layer. The gravels have a maximum thickness of 15 m on Wonderdraai on top of the bedrock consisting of greenish Dwyka tillites (Fig 7.) The gravels are composed largely of rounded fragments of Ventersdorp andesite and iron formation, with smaller amounts of resistant material such as chalcedony, quartz and quartzite. The gravels are

almost invariably calcified and sometimes contain partings or lenses of sand and finegrained gravel. In some places the gravels have a thin covering of Hutton sand.

Ecological habitat and landscape features

In terms of vegetation type the site falls within the The proposed area falls within vegetation unit NKu 3 and AZa 4, which is known as the Northern Upper Karoo and Upper Gariep Alluvial Vegetation: the Northern Upper Karoo vegetation covers the Northern Cape and Free State Provinces which include the Northern regions of the Upper Karoo plateau from Prieska, Vosburg and Carnarvon in the west to Philipstown, Petrusville and Petrusburg in the east. Bordered in the north by Niekerkshoop, Douglas and Petrusburg and in the south by Carnarvon, Pampoenpoort and De Aar. A few Patches occur in Griqualand West. It is situated on an altitude of 1000m – 1500m. The conservation of the Northern Upper Karoo, is Least Threatened with a target of 21%. About 4% has been cleared for cultivation (the highest proportion of any type in the Nama-Karoo) or irreversibly transformed by building of dams (Houwater, Kalkfontein and Smart Syndicate Dams). Areas of human settlements are increasing in the north-eastern part of this vegetation types.

The Gariep Alluvial Vegetation covers the Free State and Northern Cape Province: Broad alluvia of the Orange River, lower Caledon as well as lower stretches of the Vaal, Riet and Modder rivers as far as Groblershoop. These river stretches are surrounded by vegetation units of broad transitional regions between the dry facies of the Savanna and Grassland and northern regions of the Nama-Karoo Biome. Altitude ranging from 1 000 – 1 500 m. The area has flat alluvial terraces supporting complex of riparian thickets (gallery forests) dominated by native Acacia karroo and Diospyros lycioides, flooded grasslands, reed beds and ephemeral herblands populating mainly sand banks within the river and on its banks. Gariep Alluvial Vegetation has a conservation which is vulnerable with a target of 31%. Only about 3% statutorily conserved in Tussen Die Riviere, Gariep Dam and Oviston Nature Reserve. More than 20% transformation for cultivation (vegetable grapes) and building of dams. Exotic woody species such as Salix babylonica, Eucalyptus camaldulensis, E. sideroxylon, Prosopis and Populus species have become common dominants in patches of heavily disturbed alluvial vegetation (Mucina and Rutherford, 2006:639-640).

See figure 3 below & Appendix 7 for the attached Ecological Desktop Study.



Figure 3: Vegetation Map

Land capability and agricultural potential

• Climate and water availability

Prieska normally receives about 132mm of rain per year, with most rainfall occuring mainly during autumn. The chart below (lower left) shows the average rainfall values for Prieska per month. It receives the lowest rainfall (0mm) in June and the highest (38mm) in March. The monthly distribution of average daily maximum temperatures (centre chart below) shows that the average midday temperatures for Prieska range from 17.9°C in June to 32.7°C in January. The region is the coldest during July when the mercury drops to 1.3°C on average during the night. Consult the chart below (lower right) for an indication of the monthly variation of average minimum daily temperatures.



<u>Agricultural / land capability</u>

Land capability is the combination of soil suitability and climate factors. The site and surrounds has a land capability classification, on the 8 category scale, of Class 7 – non-arable and not suited for crop production (refer to Land capability map attached as **Appendix 5** and figure 4 below.



Figure 4: Land capability map

Description of the socio-economic environment

<u>Socio-economic conditions</u>

According to the Siyathemba Local Municipality's IDP, the Municipality had a local population of just more than 21,000 people during 2010. In regional context, this meant that the Siyathemba Municipality contributed 11.9% to the District population (i.e. the second largest Local Municipality in the District by population) and 1.9% to the population of the Northern Cape.

The most dominant population group is Coloured4. This group represents 80% of the total population in the municipal area. The other groups are black (12%) and white (8%). Afrikaans is the most widely spoken language (78%). There are an insignificant number of people which speaks other languages. A total of 824 people indicated that IsiNdebele is their first language and 91 people speak Setswana.

There were slightly more females (51.4%) than males (48.6%) among the local population during 2010. It was, however, noted that the population became slightly less female dominant since 2000, when 52.4% of the population were female. The working age group (15 to 64) contributed 64.4% to the local population in 2010. This age group has increased proportionately (from 58.6% to 64.4%) in relation to the other age groups. Since 2000, this group increased by approximately 1,210 people. The working age population is slightly male dominant. Since 2000, male working age population increased by around 928 men in absolute terms whiles the number of women increased by about 282.

In the Draft LED Strategy for Siyathemba Municipality, reference is made to the HIV/AIDS prevalence in the area. It is indicated that data from the Actuarial Society of South Africa was used. During 2010, the HIV/AIDS prevalence rate of the Siyathemba population was 6.0% compared to the District rate of 6.5%. These rates compared well to the Northern Cape (7.6%) and South African (12.6%) averages in the same year.

Significant progress has been made regarding the provision of water but backlogs still exist. 95% of the households in the district are provided with free basic water (FBW) which is above the provincial average of 87, 7%. Only 3% of households had NO access to piped water 46% had piped water inside dwelling by 2011.Piped Water inside Dwelling is about 47.00%.

Pixley Ka Seme has Flush Toilet Connected to Sewerage at 65.70%households, Emthanjeni being the highest with 85.06% and Thembelihle being the east with 64.41%. However it must be mentioned that a project is currently in progress through funds from the Pixley Ka Seme District Municipality to replace buckets with the UDS system. The final 68 toilets have been finalised during this current financial year in Campbell. Full water borne sanitation is currently being constructed in Schmidtsdrift and the sanitation system will be completed with the completion of the house structures.

The proportion of households using electricity for lighting has increased from 57% in 1996 to 84% in 2011. South Africa aims to ensure that by 2030 at least 90% of people have access to grid electricity. Increase in both demand and tariffs may slow down this last effort. Households using electricity as a source of energy for cooking increased from 47,5% in 1993 to 73,9% in Census 2011.

All local municipalities are composed of various residential components varying from formal housing units to informal dwelling units as indicated in the table above. Within the District, 82, 8% of households live in formal housing, 10,8% in informal housing and only 2% in traditional houses. Households in the whole PKSD is about 49 193 in respect to the Census 2011, where the average Household Size is about 3.70%, female headed households is about 36.90%, formal dwellings at 86.30% and the housing owned is at 52.00%

There has been an 8,3% increase in the number of learners that have accessed education between 1996 and 2001. There has been a 27,1% increase in the number of learners that have matriculated.
Heritage aspects

Special attention will be given to the identification of possible cultural or heritage resources on site.

(b) Description of the current land uses.

The site survey revealed that land uses on and in the immediate vicinity of the proposed development are essentially comprised of some crop cultivation and trees plantations. The landscape is uneven with diamonds deposits and streams.

(c) Description of specific environmental features and infrastructure on the site.

The infrastructure on site consist of farm roads and basic farm infrastructure together with previous prospecting infrastructure. The baseline environment is described with specific reference to geotechnical conditions, ecological habitat and landscape features, Soil, land capability and agricultural potential, climate and the visual landscape. The proposed prospecting area consists of cultivated lands, water attributes, Perennial River, sand erosion and Non-perennial River. All infrastructure will be temporary and/or mobile. Where applicable a Water Use License Application will be launched for conducting mining operations in or near any water resource.

A Locality map is attached in **Appendix 3**.

 Impacts and risks identified including the nature, significance, consequence, extent, duration and probability of the impacts, including the degree to which these impacts

(Provide a list of the potential impacts identified of the activities described in the initial site layout that will be undertaken, as informed by both the typical known impacts of such activities, and as informed by the consultations with affected parties together with the significance, probability, and duration of the impacts. Please indicate the extent to which they can be reversed, the extent to which they may cause irreplaceable loss of resources, and can be avoided, managed or mitigated).

Significance of potential impacts

The following sections present the outcome of the significance rating exercise. The results suggest that almost none of the key issues identified as part of the basic assessment process had a negative high environmental significance. Instead the overall score indicate a low environmental significance score.

INITIAL CLEARANCE AND SITE PREPARATION PHASE

Direct impacts: During this phase minor negative impacts are foreseen over the short term. The latter refers to a period of weeks. The site preparation may result in the loss or fragmentation of indigenous natural fauna and flora, loss or fragmentation of habitats, soil erosion, hydrology, and temporary noise disturbance, generation of waste, visual

intrusions, increase in heavy vehicle traffic, and risk to safety, livestock and farm infrastructure, and increased risk of veld fires. The abovementioned impacts are discussed in more detail below:

- Loss or fragmentation of indigenous natural fauna and flora In terms of vegetation type the site falls within the The proposed area falls within vegetation unit NKu 3 and AZa 4, which is known as the Northern Upper Karoo and Upper Gariep Alluvial Vegetation: the Northern Upper Karoo vegetation covers the Northern Cape and Free State Provinces which include the Northern regions of the Upper Karoo plateau from Prieska, Vosburg and Carnarvon in the west to Philipstown, Petrusville and Petrusburg in the east. Bordered in the north by Niekerkshoop, Douglas and Petrusburg and in the south by Carnarvon, Pampoenpoort and De Aar. A few Patches occur in Griqualand West. It is situated on an altitude of 1000m 1500m. The conservation of the Northern Upper Karoo, is Least Threatened with a target of 21%. About 4% has been cleared for cultivation (the highest proportion of any type in the Nama-Karoo) or irreversibly transformed by building of dams (Houwater, Kalkfontein and Smart Syndicate Dams). Areas of human settlements are increasing in the north-eastern part of this vegetation types.
- The Gariep Alluvial Vegetation covers the Free State and Northern Cape Province: Broad alluvia of the Orange River, lower Caledon as well as lower stretches of the Vaal, Riet and Modder rivers as far as Groblershoop. These river stretches are surrounded by vegetation units of broad transitional regions between the dry facies of the Savanna and Grassland and northern regions of the Nama-Karoo Biome. Altitude ranging from 1 000 1 500 m. The area has flat alluvial terraces supporting complex of riparian thickets (gallery forests) dominated by native Acacia karroo and Diospyros lycioides, flooded grasslands, reed beds and ephemeral herblands populating mainly sand banks within the river and on its banks. Gariep Alluvial Vegetation has a conservation which is vulnerable with a target of 31%. Only about 3% statutorily conserved in Tussen Die Riviere, Gariep Dam and Oviston Nature Reserve. More than 20% transformation for cultivation (vegetable grapes) and building of dams. Exotic woody species such as Salix babylonica, Eucalyptus camaldulensis, E. sideroxylon, Prosopis and Populus species have become common dominants in patches of heavily disturbed alluvial vegetation (Mucina and Rutherford, 2006:639-640).

Loss or fragmentation of indigenous natural fauna and flora	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	Medium term (2)	Medium term (2)
Magnitude	Medium (2)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Significant loss of	Marginal loss of resource (2)
	resource (3)	
Cumulative impact	Negligible cumulative im	pacts (2),
Significance	Negative low (28)	Negative low (14)
Can impacts be mitigated?	If the development is	approved, contractors must
	ensure that no mamma	alian species are disturbed,

-
trapped, hunted or killed. If the development is approved, every effort should be made to confine the footprint to the blocks allocated for the development and have the least possible edge effects on the surrounding area. The EMPr also provides numerous mitigation measures – refer to section (f) of the EMPr.
 The potential impacts associated with damage to and loss of farmland should be effectively mitigated. The aspects that should be covered include: The site should be fenced off prior to commencement of construction activities; The footprint associated with the construction related activities (access roads, construction platforms, workshop etc.) should be confined to the fenced off area and minimised where possible; An Environmental Control Officer (ECO) should be appointed to monitor the establishment phase of the construction phase; All areas disturbed by construction related activities, such as access roads on the site, construction platforms, workshop area etc., should be rehabilitated at the end of the construction phase; The implementation of a rehabilitation programme should be included in the terms of reference for the contractor/s appointed. Specifications for the rehabilitation are provided throughout the EMPr – section (f) of the EMPr. The implementation of the Rehabilitation

Loss or fragmentation of habitats – Given the low probability of resident threatened species
occurring at the footprint site, the low probability of any significant conservation corridor or
buffer zone at the footprint site. If it deems necessary a Water Use License Application will be
lodged. The site proposed for development could be viewed as less sensitive in the region.

Loss or fragmentation of habitats	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	Medium term (2)	Medium term (2)
Magnitude	Low (1)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal loss of resource	Marginal loss of resource
	(2)	(2)
Cumulative impact	Negligible cumulative impac	ts (1).
Significance	Negative low (12)	Negative low (12)

Can impacts be mitigated?	Exotic and invasive plant species should not be allowed to establish, if the development is approved. Where exotic and invasive plant species are found at the site continuous eradication should take place. If the development is approved, every effort should be made to confine the footprint to the blocks allocated for development – section (f) of the EMPr also provides numerous mitigation measures related to fauna and flora.

 <u>Loss of topsoil</u> – Topsoil may be lost due to poor topsoil management (burial, erosion, etc.) during construction related soil profile disturbance (levelling, excavations, disposal of spoils from excavations etc.) The effect will be the loss of soil fertility on disturbed areas after rehabilitation.

Loss of topsoil	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Geographical extent	Site (1)	Site (1)
Probability	Possible (2)	Unlikely (1)
Duration	Medium term (2)	Medium term (2)
Magnitude	Medium (2)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal (2)	Marginal (2)
Cumulative impact	Negligible cumulative impac	et (1).
Significance	Negative low (20)	Negative low (18)
Can impacts be mitigated?	 The following mitigation or provided: If an activity will mecha in any way, then any av stripped from the entire re-spreading during reh Topsoil stockpiles must through erosion by esta them. Dispose of all subsurfa where they will not impa During rehabilitation, th evenly spread over the Erosion must be contro soiled areas. Establish an effective reco area where soil is disturbed These records should be performance reports, and s below. Record the GPS coordination of the set of the se	management measures are nically disturb below surface ailable topsoil should first be e surface and stockpiled for abilitation. be conserved against losses iblishing vegetation cover on ace spoils from excavations act on undisturbed land. e stockpiled topsoil must be entire disturbed surface. lled where necessary on top rd keeping system for each for constructional purposes. included in environmental hould include all the records
	 Record the GPS coordi Record the date of tops 	nates of each area. oil stripping.

 Record the GPS coordinates of where the topsoil is stockpiled.
 Record the date of cessation of constructional (or operational) activities at the particular site.
• Photograph the area on cessation of constructional activities.
 Record date and depth of re-spreading of topsoil.
 Photograph the area on completion of rehabilitation and on an annual basis thereafter to show vegetation establishment and evaluate progress of restoration over time.
Section (f) of the EMPr also provide mitigation measures related to topsoil management.

 <u>Soil erosion</u> – Soil erosion due to alteration of the land surface run-off characteristics. Alteration of run-off characteristics may be caused by construction related land surface disturbance, vegetation removal and the establishment of roads. Erosion will cause loss and deterioration of soil resources. The erosion risk is low due to the low slope gradients and low to moderate erodibility of the soils.

Soil erosion	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Geographical extent	Site (1)	Site (1)
Probability	Possible (2)	Unlikely (1)
Duration	Medium term (2)	Medium term (2)
Magnitude	Medium (2)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal (2)	Marginal (2)
Cumulative impact	Negligible cumulative impac	xt (1).
Significance	Negative low (20)	Negative low (18)
Can impacts be mitigated?	The following mitigation or provided: Implement an e control, where it is require disseminates run-off water and prevents potential dowr Include periodical site in performance reporting that the run off control system	management measures are effective system of run-off ed, that collects and safely from all hardened surfaces a slope erosion. spection in environmental inspects the effectiveness of and specifically records the
	occurrence any erosion on s section (f) of the EMPr.	site or downstream – refer to

 <u>Temporary noise disturbance</u> - Preparation activities will result in the generation of noise over a period of months. Sources of noise are likely to include vehicles, the use of machinery such as back actors and people working on the site. The noise impact is unlikely to be significant; but activities should be limited to normal working days and hours (6:00 - 18:00).

Temporary noise disturbance	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Definite (4)	Probable (3)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (2)	Low (1)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	The impact would result in	negligible to no cumulative
	effects (1).	
Significance	Negative low (20)	Negative low (9)
Can impacts be mitigated?	Yes, management actions	s related to noise pollution
	are included in section (f)	of the EMPr.

<u>Generation of waste - general waste, construction waste, sewage and grey water</u> - The workers on site are likely to generate general waste such as food wastes, packaging, bottles, etc. Construction waste is likely to consist of packaging, scrap metals, waste cement, etc If any). The applicant will need to ensure that general and construction waste is appropriately disposed of i.e. taken to the nearest licensed landfill. Sufficient ablution facilities will have to be provided, in the form of portable/VIP toilets. No pit latrines, French drain systems or soak away systems shall be allowed.

Generation of waste	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local/district (2)	Local/district (2)
Probability	Definite (4)	Definite (4)
Duration	Short term (1)	Short term (1)
Magnitude	Low (1)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Medium cumulative impact for landfill space could res impacts if services becom which in turn would nega community.	(3) - An additional demand ult in significant cumulative le unstable or unavailable, tively impact on the local
Significance	Negative medium (13)	Negative low (13)
Can impacts be mitigated?	Yes, it is therefore import actions and mitigation mean of the EMPr are implemented	rtant that all management sures included in section (f) ed.

 <u>Impacts on heritage objects</u> – Special attention will be given to the identification of possible cultural or heritage resources on site.

Impacts on heritage objects	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Possible (2)	Possible (2)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (2)	Low (1)
Reversibility	Irreversible (4)	Irreversible (4)
Irreplaceable loss of resources	Marginal loss of resource	Marginal loss of resource
	(2)	(2)
Cumulative impact	Low cumulative impact (2).	Should these impacts occur,
	there may be a cumulative in	mpact on the preservation of
	heritage objects in the area.	
Significance	Negative low (24)	Negative low (12)
Can impacts be mitigated?	If archaeological sites or g	graves are exposed during
	construction work, it should	immediately be reported to a
	heritage practitioner so	that an investigation and
	evaluation of the finds can b	e made. Also refer to section
	(f) of the EMPr.	

Indirect impacts: The nuisance aspects generally associated with the installation of infrastructure or ground preparation will also be applicable to this development, which relates primarily to the increase in vehicle traffic associated with mining practices, the influx of job seekers to the area, risk to safety, livestock and farm infrastructure, and increased risk of veld fires.

 Increase in vehicle traffic – The movement of heavy vehicles during the clearance of vegetation and topsoil has the potential to damage local farm roads and create dust and safety impacts for other road users in the area. Access will be obtained from gravel road off the R357/R386 to Prieska. While the volume of traffic along this road is low, the movement of heavy vehicles along this road is likely to damage the road surface and impact on other road users. The contractor should be required to ensure that damage to the road is repaired periodically.

Increase in vehicle traffic	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Probable (3)	Probable (3)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (1)	Medium (3)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Medium cumulative impact (3). If damage to roads is not
	repaired then this will affect the farming activities in the	
	area and result in higher mair	ntenance costs for vehicles

	of local farmers and other road users. The costs will be
	damage.
Significance	Negative low (22) Negative low (11)
Can impacts be mitigated?	The potential impacts associated with heavy vehicles can be effectively mitigated. The mitigation measures include:
	 The contractor must ensure that damage caused by construction R357/R386 is repaired. The costs associated with the repair must be borne by the contractor; Dust suppression measures must be implemented for heavy vehicles such as wetting of gravel roads on a regular basis and ensuring that vehicles used to transport sand and building materials are fitted with tarpaulins or covers; All vehicles must be road-worthy and drivers must be qualified and made aware of the potential road safety issues and need for strict speed limits. Speed limits of vehicles inside the application area must be strictly controlled to avoid excessive dust or the excessive deterioration of the roads to be used.
	Also refer section (f) of the EMPr. For mitigation measures related to traffic.

 <u>Risk to safety, livestock and farm infrastructure</u> - The presence on and movement of workers on and off the site poses a potential safety threat to local famer's and farm workers in the vicinity of the site threat. In addition, farm infrastructure, such as fences and gates, may be damaged and stock losses may also result from gates being left open and/or fences being damaged or stock theft linked either directly or indirectly to the presence of farm workers on the site.

Risk to safety, livestock and	Pre-mitigation impact	Post mitigation impact
farm infrastructure	rating	rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Probable (3)	Probable (3)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (2)	Low (1)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)

Cumulative impact	Negligible cumulative effects (1), provided losses are compensated for.	
Significance	Negative low (22) Negative low (11)	
Can impacts be mitigated?	 Regative row (22) [Regative row (11)] Key mitigation measures include: Prieska Diamond Mining (Pty) Ltd should enter into an agreement with the local farmers in the area whereby damages to farm property etc. during the construction phase will be compensated for. The agreement should be signed before the construction phase commences; The construction area should be fenced off prior to the commencement of the construction phase. The movement of construction workers on the site should be confined to the fenced off area; Contractors appointed by Prieska Diamond Mining (Pty) Ltd should provide daily transport for low and semi-skilled workers to and from the site. This would reduce the potential risk of trespassing on the remainder of the farm and adjacent properties; Prieska Diamond Mining (Pty) Ltd should hold contractors liable for compensating farmers in full for any stock losses and/or damage to farm infrastructure that can be linked to construction workers. This should be contained in the Code of Conduct to be signed between the proponent, the contractors and neighbouring landowners. The agreement should also cover loses and costs associated with fires caused by construction workers or construction related activities (see below); The Environmental Management Programme (EMPr) should outline procedures for managing and storing waste on site, specifically plastic waste that poses a threat to livestock if ingested; Contractors appointed by Prieska Diamond Mining (Pty) Ltd must ensure that all workers are informed at the outset of the construction phase of the conditions contained on the Code of Conduct, specifically consequences of stock theft and trespassing on adjacent farms. Contractors appointed by Prieska Diamond Mining (Pty) Ltd must ensure that construction workers who are found guilty of trespassing, stealing livestock and/or damaging farm infrastructure are dismissed and charged. This should be contained in the Code of Conduct	
	 agreement should be signed before the construction phase commences; The construction area should be fenced off prior to the commencement of the construction phase. The movement of construction workers on the site should be confined to the fenced off area; Contractors appointed by Prieska Diamond Mining (Pty) Ltd should provide daily transport for low and semi-skilled workers to and from the site. This would reduce the potential risk of trespassing on the remainder of the farm and adjacent properties; Prieska Diamond Mining (Pty) Ltd should hold contractors liable for compensating farmers in full for any stock losses and/or damage to farm infrastructure that can be linked to construction workers. This should be contained in the Code of Conduct to be signed between the proponent, the contractors and neighbouring landowners. The agreement should also cover loses and costs associated with fires caused by construction workers or construction related activities (see below); The Environmental Management Programme 	
	 (EMPr) should outline procedures for managing and storing waste on site, specifically plastic waste that poses a threat to livestock if ingested; Contractors appointed by Prieska Diamond Mining (Pty) Ltd must ensure that all workers are informed at the outset of the construction phase of the conditions contained on the Code of Conduct, specifically consequences of stock theft and trespassing on adjacent farms. Contractors appointed by Prieska Diamond Mining (Pty) Ltd must ensure that construction workers who are found guilty of trespassing, stealing livestock and/or damaging farm infrastructure are dismissed and charged. This should be contained in the Code of Conduct. All dismissals must be in accordance with South African labour legislation; The housing of construction workers on the site should be strictly limited to security personnel (if 	

<u>Increased risk of veld fires</u> - The presence of construction workers and construction-related activities on the site poses an increased risk of grass fires that could in turn pose a threat to livestock, crops, wildlife and farmsteads in the area. In the process, farm infrastructure may also be damaged or destroyed and human lives threatened. The potential risk of grass fires was heightened by the windy conditions in the area, especially during the dry, windy winter months from May to October. In terms of potential mitigation measures, a fire-break should be constructed around the perimeter of the site prior to the commencement of the construction phase. In addition, fire-fighting equipment should be provided on site during the construction phase.

Increased risk of veld fires	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Region (3)	Local (2)
Probability	Probable (3)	Probable (3)
Duration	Medium term (2)	Short term (1)
Magnitude	High (3)	Low (1)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Negligible cumulative effects compensated for.	s (1), provided losses are
Significance	Negative medium (33)	Negative low (9)
Can impacts be mitigated?	 Negligible cumulative effects (1), provided losses are compensated for. Negative medium (33) Negative low (9) The mitigation measures include: A fire-break should be constructed around the perimeter of the site prior to the commencement of the construction phase; Contractor should ensure that open fires on the site for cooking or heating are not allowed except in designated areas; Contractor to ensure that construction related activities that pose a potential fire risk, such as welding, are properly managed and are confined to areas where the risk of fires has been reduced. Measures to reduce the risk of fires include avoiding working in high wind conditions when the risk of fires is greater. In this regard special care should be taken during the high risk dry, windy winter months; Contractor to provide fire-fighting training to selected construction staff; No construction staff, with the exception of security staff, to be accommodated on site over night; 	

damage caused to their farms. The contractor
should also compensate the firefighting costs borne
by farmers and local authorities.

OPERATIONAL PHASE

Direct impacts: During the operational phase the study area will serve as an mining area and the impacts are generally associated with soil erosion, change in land use, impacts associated with the, increase in storm water runoff, increased consumption of water, visual intrusion, the generation of general waste, leakage of hazardous materials, and the change in the sense of place. The operational phase will also have a direct positive impact through the provision of permanent employment opportunities and facilitating a positive economic growth. The abovementioned impacts are discussed in more detail below:

 <u>Soil erosion</u> – The largest risk factor for soil erosion will be during the operational phase when the mining activity ensues and soil is left bare until rehabilitation is initiated. Erosion will be localised within the site. This will ultimately lead to the irretrievable commitment of this resource. The measurable effect of reducing erosion by utilizing mitigation measures may reduce possible erosion significantly.

Soil erosion	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local/Regional (2)	Local/Regional (2)
Probability	Definite (4)	Unlikely (1)
Duration	Long term (3)	Long term (3)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Significant loss of	Marginal loss of resource
	resource (3)	(2)
Cumulative impact	Medium cumulative impact (3). Should these impacts occur, there will be a cumulative impact on the air and	
Significance	Water resources in the study	/ area in terms of pollution.
Significance		Negative Low (20)
Can impacts be mitigated?	Yes, to avoid soil erosion it	will be a good practice to not
	remove all the vegetation at once but to only clear the	
	area as it becomes necessary and to implement	
	concurrent rehabilitation.	
	Also refer to section (f) of th	e EMPr.

<u>Change in land-use</u> – The use of the area for the operation of the mining activity will
result in the area not being used for livestock grazing anymore. The impact on farm
income due to the loss of grazing will be more than offset by the income from Prieska
Diamond Mining (Pty) Ltd

EIA019 –Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

Change in land use	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	medium term (2)	medium term (2)
Magnitude	Medium (2)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal loss of	Marginal loss of resource
	resource (2)	(2)
Cumulative impact	Low cumulative impacts (2).	
Significance	Negative low (15)	Negative low (14)
Can impacts be mitigated?	The proponent should establish a Rehabilitation	
	Fund to be used to reha	abilitate the area once the
	proposed facility has be	en decommissioned. The
	fund should be funded by	revenue generated during
	the operational phase of the project. The motivation	
	for the establishment of a Rehabilitation Fund is	
	based on the experience in the mining sector where	
	many mines on closure have not set aside sufficient	
	funds for closure and decommissioning.	
	Also refer to section (f) o	f the EMPr.

• <u>Generation of alternative land use income</u> – Income generated through the alluvial diamond mine will provide the farming enterprise with increased cash flow and rural livelihood, and thereby improve the financial sustainability of farming on site.

Generation of alternative land use income	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Positive	Positive
Geographical extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	Medium (2)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resources (1)	No loss of resources (1)
Cumulative impact	Low cumulative impact (2).	
Significance	Positive Low (24)	Positive Low (24)
Can impacts be mitigated?	No mitigation required.	

 Increase in storm water runoff – The development will potentially result in an increase in storm water run-off that needs to be managed to prevent soil erosion, especially where vegetation will be cleared. Not all the vegetation should be removed at once. Only the specific trench being excavated at the specific time should be cleared.

Increase in storm water runoff	Pre-mitigation impact	Post mitigation impact
Increase in storm water fution	rating	rating

Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Probable (3)	Unlikely (1)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal loss of	Marginal loss of resource
	resource (2)	(2)
Cumulative impact	Medium cumulative im	pact (3) - Should these
	impacts occur, there wil	I be a cumulative impacts
	on the wider area.	
Significance	Negative medium (30)	Negative low (13)
Can impacts be mitigated?	Yes. It is therefore impo	rtant that all management
	actions and mitigation measures included in section	
	(f) of the EMPr. are implemented to ensure that	
	these impacts do not occ	cur

• <u>Increased consumption of water</u> - Approximately 18 000 liters of water per hour will be required for the washing of the gravel in the rotary 16 feet pan. The water will be sourced from groundwater sources.

Increased consumption of water	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Region (3)	Region (3)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	Medium (2)
Reversibility	Irreversible (4)	Irreversible (4)
Irreplaceable loss of resources	Marginal loss of	Marginal loss of
	resources (2)	resources (2)
Cumulative impact	High cumulative impacts (4) - An additional demand	
	on water sources could result in a significant	
	cumulative impact with regards to the availability of	
	water.	
Significance	Negative medium	Negative medium (40)
	(40)	
Can impacts be mitigated?	Yes, management actions and mitigation measures	
	related to the use of water are included in section	
	(f) of the EMPr.	

 <u>Generation of waste</u> – Approximately 15 Workers will be present on site from 6:00 – 18:00, Monday to Saturday. Sources of general waste will be waste food, packaging, paper, etc. General waste will be stored on the site and removed on a weekly basis by a contractor.

Generation of waste	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative

Extent	Local (2)	Local (2)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Low (1)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Medium cumulative impact (3) - An additional demand for landfill space could result in significant cumulative impacts with regards to the availability of landfill space.	
Significance	Negative low (15)	Negative low (15)
Can impacts be mitigated?	Yes, management ac management are include	tions related to waste d in section (f) of the EMPr.

 <u>Leakage of hazardous materials</u> - The proposed mining activity will make use of machinery that use fuel and oil. Leakage of these oils and fuel can contaminate water supplies and must be prevented by constructing oil and diesel permeable bunds to ensure that any spills are suitably attenuated and not released into the environment.

Leakage of hazardous materials	Pre-mitigation impact	Post mitigation		
	rating	impact rating		
Status (positive or negative)	Negative	Negative		
Extent	Local (2)	Local (2)		
Probability	Possible (2)	Unlikely (1)		
Duration	Long term (3)	Long term (3)		
Magnitude	High (3)	Medium (2)		
Reversibility	Partly reversible (2)	Partly reversible (2)		
Irreplaceable loss of resources	Marginal loss of	Marginal loss of		
	resource (2)	resource (2)		
Cumulative impact	The impact would resu	ult in negligible to no		
	cumulative effects (1)			
Significance	Negative medium (36)	Negative low (22)		
Can impacts be mitigated?	Yes. It is therefore import	ant that all management		
	actions and mitigation measures included in the			
	section (f) of EMPr are implemented to ensure that			
	these impacts do not occu	ır.		

 <u>Noise disturbance</u> - Mining activities will result in the generation of noise over a period of 3-5 years. Sources of noise are likely to include vehicles, the use of machinery such as backactors, rotary pans and people working on the site, as well as occasional blasting. The noise impact is unlikely to be significant as the closest homestead is more than 1km from the site; but mining activities should be limited to normal working days and some Saturdays and hours (6:00 – 18:00).

Temporary noise disturbance	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)

EIA019 –Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

Probability	Definite (4)	Probable (3)	
Duration	Medium term (2)	Medium term (2)	
Magnitude	Medium (2)	Low (1)	
Reversibility	Completely reversible (1)	Completely reversible (1)	
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)	
Cumulative impact	The impact would result in negligible to no cumulativ		
	effects (1).		
Significance	Negative low (22)	Negative low (10)	
Can impacts be mitigated?	Yes, management actions related to noise pollution		
	are included in section (f) of the EMPr.		

Indirect impacts: The operational phase will have an indirect negative impact through the change in the sense of place and an indirect positive impact through the provision of additional electrical infrastructure.

<u>Potential impact on tourism</u> – The tourism sector is regarded as an important economic sector in the NCP. The tourism potential of the area is linked to the areas natural resources, including the relatively undisturbed scenery and landscape. The impact of the proposed mining of diamond alluvial on the areas sense of place with mitigation is likely to be low. In addition, the site will not be visible from the R357/R386. The impact of the proposed mine on the tourism potential of the area and the NCP is therefore likely to be low.

Potential impacts on tourism	Pre-mitigation impact rating	Post mitigation impact rating	
Status (positive or negative)	Negative	Negative	
Extent	Site (1)	Site (1)	
Probability	Possible (2)	Possible (2)	
Duration	Medium term (2)	Medium term (2)	
Magnitude	Low (1)	Low (1)	
Reversibility	Completely reversible (1)	Completely reversible (1)	
Irreplaceable loss of resources	N/a	N/a	
Cumulative impact	N/a		
Significance	Negative low (6)	Negative low (6)	
Can impacts be mitigated?	No mitigation required		

DECOMMISIONING PHASE (MINE CLOSURE AND REHABILITATION)

Direct impacts: Typically, the major social impacts associated with the decommissioning phase are linked to the loss of jobs and associated income. This has implications for the households who are directly affected, the communities within which they live. If infrastructures are removed after 8/10 year period, the site will be returned to its natural state. Therefore the physical environment will benefit from the closure of the mining facility.

• <u>Rehabilitation of the physical environment</u> – The physical environment will benefit from the closure of the mining facility since the site will be restored to its natural state.

Rehabilitation of the physical	Pre-mitigation impact	Post mitigation impact
Status (positivo er pogativo)	Desitive	Desitive
Status (positive of negative)	FUSILIVE	FUSILIVE
Extent	Site (1)	Site (1)
Probability	Possible (2)	Probable (3)
Duration	Long term (3)	Long term (3)
Magnitude	Low (1)	Medium (2)
Reversibility	N/A	N/A
Irreplaceable loss of resources	N/A	N/A
Cumulative impact	The impact would read	sult in negligible to no
	cumulative effects (1)	
Significance	Negative low (7)	Negative low (16)
Can impacts be mitigated?	No mitigation measures	required.

• <u>Loss of employment</u> - Given the relatively large number of people employed during the operational phase, the decommissioning of the facility has the potential to have a negative social impact on the local community.

Loss of employment	Pre-mitigation impact rating	Post mitigation impact rating	
Status (positive or negative)	Negative	Negative	
Extent	Local (2)	Local (2)	
Probability	Possible (2)	Possible (2)	
Duration	Medium term (2)	Short term (1)	
Magnitude	High (3)	Medium (2)	
Reversibility	Partly reversible (2)	Partly reversible (2)	
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)	
Cumulative impact	The impact would resu cumulative effects (1)	It in negligible to no	
Significance	Negative medium (30)	Negative low (18)	
Can impacts be mitigated?	 The following mitigarecommended: All structures and infrathe proposed facility stransported off-site on Prieska Diamond Mestablish an Environmer Fund to cover the costs rehabilitation of disturb 	ation measures are astructure associated with should be dismantled and decommissioning; lining (Pty) Ltd should tental Rehabilitation Trust s of decommissioning and bed areas.	

Indirect impacts: No indirect impacts are anticipated from the decommissioning phase of the proposed development.

vi) Methodology used in determining and ranking the nature, significance, consequences, extent, duration and probability of potential environmental impacts and risks; (Describe how the significance, probability, and duration of the aforesaid identified impacts that were identified through the consultation process was determined in order to decide the extent to which the initial site layout needs revision).

Method of environmental assessment

The environmental assessment aims to identify the various possible environmental impacts that could results from the proposed development. Different impacts need to be evaluated in terms of its significance and in doing so highlight the most critical issues to be addressed.

Significance is determined through a synthesis of impact characteristics which include context and intensity of an impact. Context refers to the geographical scale i.e. site, local, national or global whereas intensity is defined by the severity of the impact e.g. the magnitude of deviation from background conditions, the size of the area affected, the duration of the impact and the overall probability of occurrence. Significance is calculated as shown in the Table below.

Significance is an indication of the importance of the impact in terms of both physical extent and time scale, and therefore indicates the level of mitigation required. The total number of points scored for each impact indicates the level of significance of the impact.

Impact Rating System

Impact assessment must take account of the nature, scale and duration of impacts on the environment whether such impacts are positive or negative. Each impact is also assessed according to the following project phases:

- Construction
- Operation
- Decommissioning

Where necessary, the proposal for mitigation or optimisation of an impact should be detailed. A brief discussion of the impact and the rationale behind the assessment of its significance should also be included. The rating system is applied to the potential impacts on the receiving environment and includes an objective evaluation of the mitigation of the impact. In assessing the significance of each impact the following criteria is used:

Table: The rating system

NATURE

Include a brief description of the impact of environmental parameter being assessed in the context of the project. This criterion includes a brief written statement of the environmental aspect being impacted upon by a particular action or activity.

GEOGF	GEOGRAPHICAL EXTENT			
This is c	lefined as the area over which	the impact will be experienced.		
1	Site	The impact will only affect the site.		
2	Local/district	Will affect the local area or district.		
3	Province/region	Will affect the entire province or region.		
4	International and National	Will affect the entire country.		
PROBA	BILITY			
This des	scribes the chance of occurrent	ce of an impact.		
1	Unlikely	The chance of the impact occurring is extremely low (Less than a 25% chance of occurrence).		
2	Possible	The impact may occur (Between a 25% to 50% chance of occurrence).		
3	Probable	The impact will likely occur (Between a 50% to 75% chance of occurrence).		
4	Definite	Impact will certainly occur (Greater than a 75% chance of occurrence).		
DURAT	ION			
This de	scribes the duration of the impa	acts. Duration indicates the lifetime of the impact as a		
result of	the proposed activity.			
2	Short term Medium term Long term	The impact will either disappear with mitigation or will be mitigated through natural processes in a span shorter than the construction phase $(0 - 1 \text{ years})$, or the impact will last for the period of a relatively short construction period and a limited recovery time after construction, thereafter it will be entirely negated $(0 - 2 \text{ years})$. The impact will continue or last for some time after the construction phase but will be mitigated by direct human action or by natural processes thereafter $(2 - 10 \text{ years})$. The impact and its effects will continue or last for the entire operational life of the development, but will be mitigated by direct human action or by natural		
4	Permanent	processes thereafter (10 – 30 years). The only class of impact that will be non-transitory. Mitigation either by man or natural process will not		
		occur in such a way or such a time span that the impact can be considered indefinite.		
INTENS	ITY/ MAGNITUDE			
Describ	es the severity of an impact.			
1	Low	Impact affects the quality, use and integrity of the system/component in a way that is barely perceptible.		
2	Medium	Impact alters the quality, use and integrity of the system/component but system/component still continues to function in a moderately modified way and maintains general integrity (some impact on integrity).		

3	High	Impact affects the continued viability of the system/
		component and the quality, use, integrity and
		functionality of the system or component is severely
		Impaired and may temporarily cease. Figh costs of
1	Very high	Impact affects the continued viability of the
4		system/component and the quality use integrity and
		functionality of the system or component permanently
		ceases and is irreversibly impaired. Rehabilitation
		and remediation often impossible. If possible
		rehabilitation and remediation often unfeasible due to
		extremely high costs of rehabilitation and
		remediation.
REVER	SIBILITY	in a star be seen a full seen a star star seen being
I his des	scribes the degree to which an	impact can be successfully reversed upon completion
	Completely reversible	The impact is reversible with implementation of minor
I		mitigation measures
2	Partly reversible	The impact is partly reversible but more intense
	,	mitigation measures are required.
3	Barely reversible	The impact is unlikely to be reversed even with
		intense mitigation measures.
4	Irreversible	The impact is irreversible and no mitigation measures
		exist.
	ACEABLE LOSS OF RESOU	RCES
This de propose	scribes the degree to which inductivity.	resources will be irreplaceably lost as a result of a
This de propose	scribes the degree to which a activity. No loss of resource	The impact will not result in the loss of any resources.
This de propose	scribes the degree to which i d activity. No loss of resource	The impact will not result in the loss of any resources.
This de propose 1	scribes the degree to which ad activity. No loss of resource Marginal loss of resource	The impact will not result in the loss of any resources. The impact will result in marginal loss of resources.
This de propose 1 2 3	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources	The impact will result in marginal loss of resources. The impact will result in significant loss of resources.
This de propose 1 2 3	scribes the degree to which indicactivity. No loss of resource Marginal loss of resource Significant loss of resources	The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all
This de propose 1 2 3 4	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources	The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4	scribes the degree to which indicactivity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources	The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4 CUMUL	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT	The impact will result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4 CUMUL This des	scribes the degree to which is activity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of	 resources will be irreplaceably lost as a result of a The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4 CUMUL This des itself ma	scribes the degree to which is d activity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be	The impact will result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4 CUMUL This des itself ma impacts	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of	 resources will be irreplaceably lost as a result of a The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources.
This de propose 1 2 3 4 CUMUL This des itself ma impacts question	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar on.	The impact will result in the loss of any resources. The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. The impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in
This de propose 1 2 3 4 CUMUL This des itself ma impacts questior 1	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of Negligible cumulative impact	The impact will not result in the loss of any resources. The impact will not result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. The impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in The impact would result in negligible to no cumulative effects.
This de propose 1 2 3 4 CUMUL This des itself ma impacts questior 1 2	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of the significant but may be emanating from other similar of the similar of the significant but may be emanating from other similar of the similar	resources will be irreplaceably lost as a result of a The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. the impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in The impact would result in negligible to no cumulative effects. The impact would result in insignificant cumulative
This de propose 1 2 3 4 CUMUL This des itself ma impacts questior 1 2	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of Negligible cumulative impact Low cumulative impact	The impact will not result in the loss of any resources. The impact will not result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. The impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in The impact would result in negligible to no cumulative effects. The impact would result in insignificant cumulative effects.
This de propose 1 2 3 4 CUMUL This des itself ma impacts questior 1 2 3	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of the similar of the similar of the similar of the similar of the similar of the	resources will be irreplaceably lost as a result of a The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. the impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in The impact would result in negligible to no cumulative effects. The impact would result in insignificant cumulative effects. The impact would result in minor cumulative effects.
This de propose 1 2 3 4 CUMUL This des itself ma impacts questior 1 2 3 4	scribes the degree to which indicativity. No loss of resource Marginal loss of resource Significant loss of resources Complete loss of resources ATIVE EFFECT scribes the cumulative effect of ay not be significant but may be emanating from other similar of Negligible cumulative impact Low cumulative impact Medium cumulative impact	resources will be irreplaceably lost as a result of a The impact will not result in the loss of any resources. The impact will result in marginal loss of resources. The impact will result in significant loss of resources. The impact is result in a complete loss of all resources. The impacts. A cumulative impact is an effect which in ecome significant if added to other existing or potential or diverse activities as a result of the project activity in The impact would result in negligible to no cumulative effects. The impact would result in insignificant cumulative effects. The impact would result in minor cumulative effects. The impact would result in minor cumulative effects.

EIA019 –Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

SIGNIFICANCE

Significance is determined through a synthesis of impact characteristics. Significance is an indication of the importance of the impact in terms of both physical extent and time scale, and therefore indicates the level of mitigation required. The calculation of the significance of an impact uses the following formula:

(Extent + probability + reversibility + irreplaceability + duration + cumulative effect) x magnitude/intensity.

The summation of the different criteria will produce a non-weighted value. By multiplying this value with the magnitude/intensity, the resultant value acquires a weighted characteristic which can be measured and assigned a significance rating.

Points	Impact significance rating	Description
6 to 28	Negative low impact	The anticipated impact will have negligible negative effects and will require little to no mitigation.
6 to 28	Positive low impact	The anticipated impact will have minor positive effects.
29 to 50	Negative medium impact	The anticipated impact will have moderate negative effects and will require moderate mitigation measures.
29 to 50	Positive medium impact	The anticipated impact will have moderate positive effects.
51 to 73	Negative high impact	The anticipated impact will have significant effects and will require significant mitigation measures to achieve an acceptable level of impact.
51 to 73	Positive high impact	The anticipated impact will have significant positive effects.
74 to 96	Negative very high impact	The anticipated impact will have highly significant effects and are unlikely to be able to be mitigated adequately. These impacts could be considered "fatal flaws".
74 to 96	Positive very high impact	The anticipated impact will have highly significant positive effects.

vii) The positive and negative impacts that the proposed activity (in terms of the initial site layout) and alternatives will have on the environment and the community that may be affected.

(Provide a discussion in terms of advantages and disadvantages of the initial site layout compared to alternative layout options to accommodate concerns raised by affected parties)

 Increased ambient noise levels resulting from geophysic surveys site fly-overs and increased traffic movement during all prospecting phases.

- Potential water and soil pollution impacts resulting from hydrocarbon spills and soil erosion which may impact on environmental resources utilized by communities, landowners and other stakeholders.
- Potential water and soil pollution impacts resulting from hydrocarbon spills and soil erosion which may impact on ecosystem functioning.
- Increased vehicle activity with in the area resulting in the possible destruction and disturbance of fauna and flora.
- Poor access control to farms which may impact on cattle movement, breeding and grazing practices.
- Influx of persons (job seekers) to site as a result of increased activity and the possible resultant increase in opportunistic crime.
- Potential visual impacts caused by prospecting activities.
- Mining will be undertaken by specialist sub contractors and it is not anticipated that employment opportunities for local and / or regional communities will result from the prospecting activities.

viii) The possible mitigation measures that could be applied and the level of risk.

(With regard to the issues and concerns raised by affected parties provide a list of the issues raised and an assessment/ discussion of the mitigations or site layout alternatives available to accommodate or address their concerns, together with an assessment of the impacts or risks associated with the mitigation or alternatives considered).

No adverse environmental or social impacts associated with the mining activity have been identified through the Scoping & EIR process. Mitigation measures as set out in the Environmental Management Programme (EMPr) attached in Part B must be implemented in order to minimise any potential impacts.

All comments received during the review period of the Scoping and EIR report, as well as response provided is captured and recorded within the Comments and Response Report and will be attached in the final EIR.

ix) Motivation where no alternative sites were considered.

This alternative asks the question, if there is not, from an environmental perspective, a more suitable location for the proposed activity. As discussed in the previous section, based on outcomes of previous prospecting activities on the proposed site, the possibility to encounter further Diamond Reserves on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

From a local perspective, the farm Uitdraai 33 is preferred due to the sites underlying alluvial diamond bearing gravel (i.e. to facilitate the movement of machinery, equipment, infrastructure and).

x) Statement motivating the alternative development location within the overall site. (Provide a statement motivating the final site layout that is proposed)

Design alternatives were considered throughout the planning and design phase (i.e. where is the rock bed located?). In this regard discussions on the design were held between the EAP and the developer. The layout follows the limitations of the site and aspects such as, roads, site offices and workshop area as well as fencing.

i) Full description of the process undertaken to identify, assess and rank the impacts and risks the activity will impose on the preferred site (In respect of the final site layout plan) through the life of the activity. (Including (i) a description of all environmental issues and risks that erer identified during the environmental impact assessment process and (ii) an assessment of the significance of each issue and risk and an indication of the extent to which the issue and risk could be avoided or addressed by the adoption of mitigation measures.)

Process for the identification of key issues

The methodology for the identification of key issues aims, as far as possible, to provide a user-friendly analysis of information to allow for easy interpretation.

- <u>Checklist</u>: The checklist consists of a list of structured questions related to the environmental parameters and specific human actions. They assist in ordering thinking, data collection, presentation and alert against the omission of possible impacts.
- Matrix: The matrix analysis provides a holistic indication of the relationship and interaction between the various activities, development phases and the impact thereof on the environment. The method aims at providing a first order cause and effect relationship between the environment and the proposed activity. The matrix is designed to indicate the relationship between the different stressors and receptors which leads to specific impacts. The matrix also indicates the specialist studies, which will be submitted as part of the Environmental Impact Report in order to address the potentially most significant impacts.

Checklist analysis

The independent consultant conducted a site visit. The site visit was conducted to ensure a proper analysis of the site specific characteristics of the study area. The table below provides a checklist (the checklist was completed by doing a desktop study), which is designed to stimulate thought regarding possible consequences of specific actions and so assist scoping of key issues. It consists of a list of structured questions related to the environmental parameters and specific human actions. They assist in ordering thinking, data collection, presentation and alert against the omission of possible impacts. The table highlights certain issues, which are further analysed in matrix format.

Table: Environmental checklist

QUESTION	YES	NO	Un-	Description
			sure	
1. Are any of the following located on the site earmarked for the development?				

I. A river, stream, dam or wetland	×		Water tributaries, Perennial River, sand erosion and Non-perennial River. All infrastructure will be temporary and/or mobile. Where applicable a Water Use License Application will be launched for conducting mining operations in or near any water resource.
II. A conservation or open space area		×	None.
III. An area that is of cultural importance		×	The initial site desktop study concluded that there are no obvious heritage resources located on the site earmarked for development.
IV. Site of geological significance		×	None.
V. Areas of outstanding natural beauty		×	None.
VI. Highly productive agricultural land		×	None.
VII. Floodplain		×	None.
VIII. Indigenous forest		×	None.
IX. Grass land		×	None.
X. Bird nesting sites		×	None.
XI. Red data species		×	None.
XII. Tourist resort		×	None.
2. Will the project potentially result in potential?			
2. Will the project potentially result in potential? I. Removal of people		×	None.
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts	×	×	None. The visual impact will be managed
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts III. Noise pollution	×	× ×	None. The visual impact will be managed The noise impact is unlikely to be significant.
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts III. Noise pollution IV. Construction of an access road	×	×	None. The visual impact will be managed The noise impact is unlikely to be significant. None. Access will be obtained from a gravel road of the R357/R386.
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts III. Noise pollution IV. Construction of an access road V. Risk to human or valuable ecosystems due to explosion/fire/ discharge of waste into water or air.	×	x x x x x	None. The visual impact will be managed The noise impact is unlikely to be significant. None. Access will be obtained from a gravel road of the R357/R386. None.
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts III. Noise pollution IV. Construction of an access road V. Risk to human or valuable ecosystems due to explosion/fire/ discharge of waste into water or air. VI. Accumulation of large workforce (>50 manual workers) into the site.	×	x x x x x	None. The visual impact will be managed The noise impact is unlikely to be significant. None. Access will be obtained from a gravel road of the R357/R386. None. Approximately 15 employment opportunities will be created during the construction and operational phase of the project.
2. Will the project potentially result in potential? 1. Removal of people 11. Visual Impacts 11. Noise pollution 1V. Construction of an access road V. Risk to human or valuable ecosystems due to explosion/fire/ discharge of waste into water or air. VI. Accumulation of large workforce (>50 manual workers) into the site. VII. Utilisation of significant volumes of local raw materials such as water, wood etc.	×	x x x x x x	None. The visual impact will be managed The noise impact is unlikely to be significant. None. Access will be obtained from a gravel road of the R357/R386. None. Approximately 15 employment opportunities will be created during the construction and operational phase of the project. 4 x 16ft washing pans which utilise approximately 18000 L per pan per hour each from which 30% is re-used.
2. Will the project potentially result in potential? I. Removal of people II. Visual Impacts III. Noise pollution IV. Construction of an access road V. Risk to human or valuable ecosystems due to explosion/fire/ discharge of waste into water or air. VI. Accumulation of large workforce (>50 manual workers) into the site. VII. Utilisation of significant volumes of local raw materials such as water, wood etc. VIII. Job creation	×	x x x x x x x	None. The visual impact will be managed The noise impact is unlikely to be significant. None. Access will be obtained from a gravel road of the R357/R386. None. Approximately 15 employment opportunities will be created during the construction and operational phase of the project. 4 x 16ft washing pans which utilise approximately 18000 L per pan per hour each from which 30% is reused. Approximately 15 employment opportunities will be created during the construction and operational phase of the project.

X. Soil erosion	×	Only areas earmarked for prospecting will be cleared. The prospecting will be phased and the topsoil stockpiled separately. Concurrent rehabilitation will take place. The soil also has a low erosion potential.			
XI. Installation of additional bulk telecommunication transmission lines or facilities	×	None.			
3. Is the proposed project located near the following?					
I. A river, stream, dam or wetland	×	Perennial River			
II. A conservation or open space area	×	None.			
III. An area that is of cultural importance	×	None.			
IV. A site of geological significance	×	None.			
V. An area of outstanding natural beauty	×	None.			
VI. Highly productive agricultural land	×	None.			
VII. A tourist resort	×	None.			
VIII. A formal or informal settlement	×	None.			

5.1 Matrix analysis

The matrix describes the relevant listed activities, the aspects of the development that will apply to the specific listed activity, a description of the environmental issues and potential impacts, and the significance and magnitude of the potential impacts. The matrix also highlights areas of particular concern for more in depth assessment during the EIA process. Each cell is evaluated individually in terms of the nature of the impact, duration and its significance – should no mitigation measures be applied. This is important since many impacts would not be considered insignificant if proper mitigation measures were implemented. The matrix also provides an indication if mitigation measures are available.

In order to conceptualise the different impacts the matrix specify the following:

- **Stressor**: Indicates the aspect of the proposed activity, which initiates and cause impacts on elements of the environment.
- **Receptor**: Highlights the recipient and most important components of the environment affected by the stressor.
- Impacts: Indicates the net result of the cause-effect between the stressor and receptor.
- Mitigation: Impacts need to be mitigated to minimise the effect on the environment.

Matrix Analysis

LISTED ACTIVITY	ASPECTS OF THE DEVELOPMENT	POTENTIAL IMPACTS			SIG MAGNIT	SIGNIFICANCE AND MAGNITUDE OF POTENTIAL IMPACTS		MITIGATION OF POTENTIAL IMPACTS	SPECIALIST STUDIES			
(The Stressor) /ACTIVITY	ACTIVITY		Receptors	Impact description	Minor	Major	Duration	Possible Mitigation	/ INFORMATION			
			C	ONSTRUCTION PHASE		_						
<i>Listing Notice GNR 983, Activity 14</i> : "The development of facilities or infrastructure, for the storage, or the storage and	Areas earmarked for mining will need to be cleared, topsoil will be stockpiled separately.		Fauna & Flora	 Loss or fragmentation of indigenous natural vegetation. Loss of sensitive species. Loss or fragmentation of habitats. 		-	S	Yes	-			
storage occurs in containers with a combined capacity of 80 cubic metres or more but not exceeding 500 cubic metres."			Air	 Air pollution due to the increase of traffic of construction vehicles. 	-		S	Yes	-			
 The storage of dieser in builded dieser tanks, exceeding 80 000 litres. Listing Notice GNR 983, Activity 24(ii): 			DNMENT	Soil	 Soil degradation, including erosion. Loss of topsoil. Disturbance of soils and existing land use (soil compaction). 		-	S	Yes	-		
wider than 13.5 metres, or where no reserve exists where the road is wider than 8 metres." - The development of 10m wide road, with no road reserve.		SICAL ENVIR	Geology	 It is not foreseen that the removal of indigenous vegetation will impact on the geology or vice versa. 		-	S	Yes	-			
Listing Notice GNR 984, Activity 15:"The clearance of an area of 20 hectares or more, of indigenous vegetation." –		BIOPHYS	Existing services infrastructure	 Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the local sewage plant. 		-	S	Yes	-			
Random indigenous vegetation clearance over a 3695.0244 hectare area.						Ground water	Pollution due to construction vehicles.	-		S	Yes	-
"Any activity including the operation of that activity which requires a mining right as contemplated on section 22 of the Mineral and Petroleum Resources Development	T T M				Surface water	 Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams). 		-	S	Yes	-	
Act, 2002 (Act No. 28 of 2002), including associated infrastructure, structures and earthworks, directly related to the extraction of a mineral resource." – Mining right for the mining of Diamonds Conorol		MENT	Local unemployment rate	Job creation.Business opportunities.Skills development.		+	S	Yes	-			
Diamands Alluvial, Diamands and Kimberlite, including associated infrastructure, structure and earthworks.		C ENVIRON	Visual landscape	 Potential visual impact on residents of farmsteads and motorists in close proximity to proposed facility. 	-		S	Yes	-			
Listing Notice GNR 984, Activity 21: "Any activity including the operation of that activity associated with the primary processing of a mineral resource including	T/ECONOMIC	Traffic volumes	Increase in construction vehicles.	-		S	Yes	-				
winning, reduction, extraction, classifying, concentrating, crushing, screening and washing but excluding the smelting,		SOCIA	Health & Safety	 Air/dust pollution. Road safety. Increased risk of veld fires. 		-	S	Yes	-			

beneficiation, refining, calcining or gasification of the mineral resource in which case activity 6 in this Notice applies."			Noise levels	 The generation of noise as a result of construction vehicles, the use of machinery such as drills and people working on the site. 	-		S	Yes	-							
			Tourism industry	• Since there are no tourism facilities in close proximity to the site, the proposed activities will not have an impact on tourism in the area.	N/A	N/A	N/A	N/A	-							
			Heritage resources	 Removal or destruction of archaeological and/or paleontological sites. Removal or destruction of buildings, structures, places and equipment of cultural significance. Removal or destruction of graves, cemeteries and burial grounds. 		-	S	Yes	-							
Listing Notice GNR 983, Activity 14: "The development of facilities or infrastructure, for the storage, or the storage and handling, of a dangerous good, where such	Site clearing and preparation Areas earmarked for mining will need to be cleared, topsoil will be stockpiled separately. This will inevitably result in the removal of		Fauna & Flora	 Loss or fragmentation of indigenous natural vegetation. Loss of sensitive species. Loss or fragmentation of habitats. 		-	S	Yes	-							
storage occurs in containers with a combined capacity of 80 cubic metres or more but not exceeding 500 cubic metres." - The storage of diesel in bunded diesel tanks exceeding 80 000 litres	indigenous vegetation located on the site.	IAL/ECONOMIC IVIRONMENT	Air quality	Air pollution due to the increase of traffic.	-		S	Yes	-							
Listing Notice GNR 983, Activity 24(ii): "The development of a road with a reserve wider than 13.5 metres, or where no			Soll	 Soil degradation, including erosion. Disturbance of soils and existing land use (soil compaction). Loss of agricultural potential (low significance relative to agricultural potential of the site). 	-		S	Yes	-							
8 metres." - The development of 10m wide road, with no road reserve.			Geology	 It is not foreseen that the removal of indigenous vegetation will impact on the geology or vice versa. 	N/A	N/A	N/A	N/A	-							
Listing Notice GNR 984, Activity 15:" The clearance of an area of 20 hectares or more, of indigenous vegetation." – Random indigenous vegetation clearance over a 3695.0244 hectare area.			Existing services infrastructure	 Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the local sewage plant. 	-		S	Yes	-							
Listing Notice GNR 984, Activity 17: "Any activity including the operation of that activity which requires a mining right as										Ground water	Pollution due to construction vehicles.	-		S	Yes	-
contemplated on section 22 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002), including associated infrastructure, structures and			Surface water	 Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams). 	-		S	Yes	-							
earthworks, directly related to the extraction of a mineral resource." – Mining right for the mining of Diamonds General, Diamands Alluvial, Diamands and			Local unemployment rate	Job creation.Skills development.		+	S	N/A	-							
Kimberlite, including associated infrastructure, structure and earthworks. Listing Notice GNR 984, Activity 21: "Any			IAL/ECONO	IAL/ECONO	Visual landscape	• Potential visual impact on residents of farmsteads and motorists in close proximity to proposed facility due to dust.	-		S	Yes	-					
activity including the operation of that activity associated with the primary processing of a mineral resource including winning, reduction, extraction, classifying,		E SOC	Traffic volumes	Increase in construction vehicles.	-		S	Yes	-							

concentrating, crushing, screening and washing but excluding the smelting, beneficiation, refining, calcining or gasification of the mineral resource in which case activity 6 in this Notice applies."		Hea	ealth & Safety	AirRc	/dust pollution. ad safety.		-	S	Yes	-
	Noi	oise levels	• Th ve	e generation of noise as a result of construction hicles, and people working on the site.	-		S	Yes	-	
	Τοι	urism industry	• Sir to on	nce there are no tourism facilities in close proximity the site, the proposed activity will not have an impact tourism in the area.	N/A	N/A	N/A	N/A	-	
		Hei res	eritage sources	 Re pa Re an Re or or	emoval or destruction of archaeological and/or leontological sites. emoval or destruction of buildings, structures, places d equipment of cultural significance. emoval or destruction of graves, cemeteries and burial bunds.	N/A	N/A	N/A	N/A	-
	<u> </u>		(PERAT	IONAL PHASE					
Listing Nation CND 094 Activity 40, "The	The key components of the presented project are	 			amontation of hobitate					
<u>Listing Notice GNR 984, Activity 19:</u> The removal and disposal of minerals contemplated in terms of section 20 of the	described below:	Fal	una & Fiora	 Fra Es inv 	agmentation of habitats. tablishment and spread of declared weeds and alien vader plants (operations).	-		L	Yes	-
Mineral and Petroleum Resource4s Development Act (Act No. 28 of 2002), including associated infrastructure,	Vineral and Petroleum Resource4s Development Act (Act No. 28 of 2002), including • Supporting Infrastructure - A control facility with basic services such as water	Air	⁻ quality	•	Air pollution due to the mining activity, crusher plant and transport of the gravel to the designated areas.	N/A	N/A	N/A	N/A	-
 structures and earthworks, directly related to Mining of a mineral resource, including activities for which an exemption has been issued in terms of section 106 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)" <u>Roads</u> – Access will be obtained from a local gravel road off the R34. All site roads will require a width of approximately 10m. <u>Fencing</u> - For health, safety and security reasons, the facility will be required to be fenced off from the surrounding farm. 	Soi	il	•	Soil degradation, including erosion. Disturbance of soils and existing land use (soil compaction). Loss of agricultural potential (low significance relative to agricultural potential of the site).		-	L	Yes	_	
		eology		Collapsible soil. Seepage (shallow water table). Active soil (high soil heave). Erodible soil. The presence of undermined ground. Instability due to soluble rock. Steep slopes or areas of unstable natural slopes. Areas subject to seismic activity. Areas subject to flooding.		-	S	Yes	-	
		SAHdoing	isting services rastructure	•	Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increased consumption of water. Approximately 36000 L per hour		-	L	Yes	-
		Gro	ound water	•	Leakage of hazardous materials. The machinery on site require oils and fuel to function. Leakage of these oils and fuels can contaminate water supplies.	-		L	Yes	-
		Sur	rface water	•	Increase in storm water runoff. The development will potentially result in an increase in storm water run-off that needs to be managed to prevent soil erosion. Destruction of watercourses (pans/dams/streams).		-	L	Yes	-
					0.5					

				 Leakage of hazardous materials. The machinery on site require oils and fuel to function. Leakage of these oils and fuels can contaminate water supplies. 					
			Local unemployment rate	 Job creation. Security guards will be required for 24 hours every day of the week. Skills development. 		+	L	Yes	-
	NMENT	Visual landscape	 Change in land-use/sense of place. The site is characterized by open veldt with a rural agricultural sense of place. The use of the area for the mining activity will result in the area not being used for livestock grazing anymore until rehabilitated. 		-	L	Yes	-	
	: ENVIRO	Traffic volumes	 Increase in vehicles collecting gravel and bins 	-		S	Yes	-	
	CONOMIC	Health & Safety	Air/dust pollution.Road safety.	N/A	N/A	N/A	N/A	-	
	OCIAL/EC	Noise levels	 The proposed development will result in noise pollution during the operational phase. 	-	-	S	Yes	-	
	S	Tourism industry	 Since there are no tourism facilities in close proximity to the site, the decommissioning activities will not have an impact on tourism in the area. 	N/A	N/A	N/A	N/A	-	
			Heritage resources	 It is not foreseen that the proposed activity will impact on heritage resources or vice versa. 	N/A	N/A	N/A	N/A	-
DECOMMISSIONING PHASE									
			DEC	COMMISSIONING PHASE					
-	<u>Mine closure</u> During the mine closure the Mine and its		DEC Fauna & Flora	Re-vegetation of exposed soil surfaces to ensure no erosion in these areas.	+		L	Yes	-
-	<u>Mine closure</u> During the mine closure the Mine and its associated infrastructure will be dismantled.		DEC Fauna & Flora Air quality	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. 	+		L	Yes Yes	-
-	<u>Mine closure</u> During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	ument	DEC Fauna & Flora Air quality Soil	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill 	+ - +		L S L	Yes Yes Yes	-
-	Mine closure During the mine closure the Mine and its associated infrastructure will be dismantled. Rehabilitation of biophysical environment The biophysical environment will be rehabilitated.	IVIRONMENT	DEC Fauna & Flora Air quality Soil Geology	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. 	+ - + N/A	N/A	L S L N/A	Yes Yes Yes N/A	
-	Mine closure During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	BIOPHYSICAL ENVIRONMENT	Fauna & Flora Air quality Soil Geology Existing services infrastructure	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. Generation of waste that need to be accommodated at the local landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increase in construction vehicles. 	+ - + N/A	N/A	L S L N/A S	Yes Yes Yes N/A Yes	
-	<u>Mine closure</u> During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	BIOPHYSICAL ENVIRONMENT	Fauna & Flora Air quality Soil Geology Existing services infrastructure Ground water	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. Generation of waste that need to be accommodated at the local landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increase in construction vehicles. 	+ - + N/A -	N/A	L S L N/A S	Yes Yes Yes N/A Yes	-
-	<u>Mine closure</u> During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	BIOPHYSICAL ENVIRONMENT	Fauna & Flora Air quality Soil Geology Existing services infrastructure Ground water Surface water	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. Generation of waste that need to be accommodated at the local landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increase in construction vehicles. Pollution due to construction vehicles. Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams). 	+ - + N/A - -	N/A	L S L N/A S S S	Yes Yes N/A Yes Yes Yes	
-	<u>Mine closure</u> During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	CONOMI NMENT BIOPHYSICAL ENVIRONMENT	Fauna & Flora Air quality Soil Geology Existing services infrastructure Ground water Surface water Local unemployment rate	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. Generation of waste that need to be accommodated at the local landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increase in construction vehicles. Pollution due to construction vehicles. Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams). Loss of employment. 	+ - + N/A - -	N/A	L S L N/A S S S L	Yes Yes N/A Yes Yes Yes Yes	- - - - - -
	Mine closure During the mine closure the Mine and its associated infrastructure will be dismantled. <u>Rehabilitation of biophysical environment</u> The biophysical environment will be rehabilitated.	CIAL/ECONOMI BIOPHYSICAL ENVIRONMENT	Fauna & Flora Air quality Soil Geology Existing services infrastructure Ground water Surface water Local unemployment rate Visual landscape	 Re-vegetation of exposed soil surfaces to ensure no erosion in these areas. Air pollution due to the increase of traffic of construction vehicles. Backfilling of all voids Placing of topsoil on backfill It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa. Generation of waste that need to be accommodated at the local landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increase in construction vehicles. Pollution due to construction vehicles. Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of water courses (pans/dams/streams). Loss of employment. 	+ - + N/A - -	N/A	L S L N/A S S S L S	Yes Yes N/A Yes Yes Yes Yes Yes Yes	

Health & Safety	 Air/dust pollution. Road safety. Increased crime levels. The presence of mine workers on the site may increase security risks associated with an increase in crime levels as a result of influx of people in the rural area. 	
Noise levels	The generation of noise as a result of construction vehicles, the use of machinery and people working on the site.	
Tourism industry	Since there are no tourism facilities in close proximity to the site, the decommissioning activities will not have an impact on tourism in the area. N/A N/A N/A N/A N/A N/A N/A	
Heritage resources	It is not foreseen that the decommissioning phase will N/A N/A N/A N/A N/A	

(N/A) No impact (+) Positive Impact (-) Negative Impact (S) Short Term (M) Medium Term (L) Long Term

a) Summary of specialist reports. (This summary must be completed if any specialist reports informed the impact assessment and final site layout process and must be in the following tabular form):-

		SPECIALIST	REFERENCE TO
LIST OF STUDIES UNDERTAKEN		RECOMMENDATION	APPLICABLE SECTION
		S THAT HAVE BEEN	OF REPORT WHERE
	RECOMMENDATIONS OF SPECIALIST REPORTS	INCLUDED IN THE	SPECIALIST
		EIA REPORT	RECOMMENDATIONS
		(Mark with an X where	HAVE BEEN
		applicable)	INCLUDED.

Specialist Report is attached as Appendix 11

j) Environmental impact statement

(i) Summary of the key findings of the environmental impact assessment;

This section provides a summary of the assessment and conclusions drawn from the proposed mining area. In doing so, it draws on the information gathered as part of the environmental impact assessment process and the knowledge gained by the environmental consultant during the course of the process and presents an informed opinion on the environmental impacts associated with the proposed project. The following conclusions can be drawn for the proposed prospecting activity:

- Potential impacts on biodiversity: There are no critical biodiversity features (aquatic ecosystems) on the site.
- Potential impacts on land use: The farm is currently utilised for low potential cattle grazing and crop production. The activity which will be subject to concurrent rehabilitation will not have any significant impact on the land use nor will it change the sense of place of the area.
- Potential social impacts: The presence of construction workers poses a potential risk to family structures and social networks. While the presence of construction workers does not in itself constitute a social impact, the manner in which construction workers conduct themselves can impact on local communities. The most significant negative impact is associated with the disruption of existing family structures and social networks.
- Potential negative impacts: (noise, dust, soil degradation, storm water, traffic, health and safety) associated with the operation of the facility are expected to be of low-medium impact, of medium terms and site specific. These can be mitigated or negated through the implementation of practical and appropriate mitigation measures.
- > Positive impacts: The prospecting of alluvial diamonds will have socio-economic benefit to the area.

All possible negative impacts and risks that have been identified in this report can be effectively mitigated and managed by implementing the migratory measures as set out in the Environmental Management Programme (EMPr) attached in Part B. It is therefore recommended that the environmental authorisation for the prospecting right be granted.

(ii) Final Site Map

Provide a map at an appropriate scale which superimposes the proposed overall activity and its associated structures and infrastructure on the environmental sensitivities of the preferred site indicating any areas that should be avoided, including buffers .Attach as **Appendix 4**

Refer to Locality Map attached in Appendix 3.

(iii)Summary of the positive and negative implications and risks of the proposed activity and identified alternatives;

There are regional socio economic benefits due to the alluvial diamonds and general diamonds being prospected in the North West Province and greater knowledge is gained on the mineralogy of South Africa. All possible negative impacts and risks that have been identified in this report can be effectively mitigated and managed by implementing the mitigation measures as set out in the

Environmental Management Programme (EMPr) attached in Part B. No significantly adverse social or environmental impacts are anticipated.

k) Proposed impact management objectives and the impact management outcomes for inclusion in the EMPr; Based on the assessment and where applicable the recommendations from specialist reports, the recording of proposed impact management objectives, and the impact management outcomes for the development for inclusion in the EMPr as well as for inclusion as conditions of authorisation.

Management objectives include:

- Ensure that the mining activity does not cause pollution to the environment or harm to persons.
- Minimise production of waste.
- All mining activities must be conducted in a manner that minimises noise impact, litter, environmental degradation and health hazards i.e. injuries.
- The mine must be kept neat and tidy during waste handling to prevent unsightliness and accidents.

Expected outcomes include:

- Minimum impacts on the environment as a result of alluvial diamond mining.
- Compliance with legislative requirements.
- Mine is neat and tidy and well managed.

I) Final proposed alternatives.

(Provide an explanation for the final layout of the infrastructure and activities on the overall site as shown on the final site map together with the reasons why they are the final proposed alternatives which respond to the impact management measures, avoidance, and mitigation measures identified through the assessment)

This alternative asks the question, if there is not, from an environmental perspective, a more suitable location for the proposed activity. No other properties have been secured by Prieska Diamond Mining (Pty) Ltd in the Prieska area to potentially mine for alluvial diamonds. From a local perspective, the farm Uitdraai 33 is preferred due to the sites underlying alluvial diamond bearing gravel (i.e. to facilitate the movement of machinery, equipment, and infrastructure). No alternative have been identified.

m) Aspects for inclusion as conditions of Authorisation.

Any aspects which have not formed part of the EMPr that must be made conditions of the Environmental Authorisation

- The operational activities and relevant rehabilitation of disturbed areas should be monitored against the improved EMPr and all other relevant environmental legislation.
- A copy of the EMP should be made available onsite at all times.
- Implementation of the proposed mitigation measures set out in the EMPr.
- n) Description of any assumptions, uncertainties and gaps in knowledge.

(Which relate to the assessment and mitigation measures proposed)

The uncertainties in results are mostly related to the availability of information, time available to gather the relevant information as well as the sometimes subjective nature of the assessment methodology. In terms of addressing the key issues the EAP is satisfied that there are no major gaps in knowledge and that the specialist reports provide sufficient information to conduct the significance rating and provide the environmental authority with sufficient information to make an informed decision.

o) Reasoned opinion as to whether the proposed activity should or should not be authorised

i) Reasons why the activity should be authorized or not.

It is the opinion of the EAP that the activity may be authorised.

Based on the outcomes of other diamond mines in the area, the possibility to encounter further Diamond Reserves were identified.

The proposed mining area is targeted as, historically, several alluvial diamond and diamond general occurrences are known in the area, and a number of these have been exploited in the past. There are also various alluvial diamond operations within the vicinity of the exploration area.

No other properties have been secured by the applicant and the site is therefore regarded as the preferred site, and alternatives are not considered.

The option of not approving the activities will result in a significant loss to valuable diamond deposits being exploited. And all economic benefits will be lost.

ii) Conditions that must be included in the authorisation

- The operational activities and relevant rehabilitation of disturbed areas should be monitored against the improved EMPr and all other relevant environmental legislation.
- > A copy of the EMP should be made available onsite at all times.
- > Implementation of the proposed mitigation measures set out in the EMPr.

The EMPr should be binding on all managers and contractors operating/utilizing the site.

(1) Specific conditions to be included into the compilation and approval of EMPr

(2) Rehabilitation requirements

All cleared, disturbed or exposed areas must be re-vegetated as soon as practically possible to prevent the formation of additional sources of dust. Rehabilitation Plan is attached as **appendix 8**

p) Period for which the Environmental Authorisation is required.

For a minimum of 10 years.

q) Undertaking

- Confirm that the undertaking required to meet the requirements of this section is provided at the end of the EMPr and is applicable to both the Basic assessment report and the Environmental Management Programme report.
- The undertaking required to meet the requirements of this section is provided at the end of the EMPr and is applicable to both the Environmental Impact Assessment report and the Environmental Management Programme report.

r) Financial Provision

State the amount that is required to both manage and rehabilitate the environment in respect of rehabilitation.

<mark>XXXXXXXXXXXXXXXX</mark>

i) Explain how the aforesaid amount was derived.

The closure cost estimate provided above is aligned with the Guideline Document for the Evaluation of Quantum of Closure related Financial Provision Provided by a Mine, by the DMR (January, 2005). The amount was calculated by Milnex 189 CC.

ii) Confirm that this amount can be provided for from operating expenditure. (Confirm that the amount, is anticipated to be an operating cost and is provided for as such in the Mining work programme, Financial and Technical Competence Report or Mining Work Programme as the case may be).

Financial Guarantee

The financial guarantee for the rehabilitation for land disturbed by Prieska Diamond Mining (Pty) Ltd was submitted together with the application for a mining right.

Rehabilitation Fund

Prieska Diamond Mining (Pty) Ltd will also make provision for rehabilitation during closure by establishing a rehabilitation trust.

s) Deviations from the approved scoping report and plan of study.

i) Deviations from the methodology used in determining the significance of potential environmental impacts and risks.

(Provide a list of activities in respect of which the approved scoping report was deviated from, the reference in this report identifying where the deviation was made, and a brief description of the extent of the deviation).

ii) Motivation for the deviation.

- t) Other Information required by the competent Authority
 - i) Compliance with the provisions of sections 24(4)(a) and (b) read with section 24 (3) (a) and (7) of the National Environmental Management Act (Act 107 of 1998). the EIA report must include the:-
 - (1) Impact on the socio-economic conditions of any directly affected person. (Provide the results of Investigation, assessment, and evaluation of the impact of the mining, bulk sampling or alluvial diamond prospecting on any directly affected person including the landowner, lawful occupier, or, where applicable, potential beneficiaries of any land restitution claim, attach the investigation report as Appendix 2.19.1 and confirm that the applicable mitigation is reflected in 2.5.3; 2.11.6.and 2.12.herein).

The alluvial diamond mine will not impact directly on any socio-economic aspects. Indirect socioeconomic benefits are expected to be associated with the creation of employment.

- (2) Impact on any national estate referred to in section 3(2) of the National Heritage Resources Act. (Provide the results of Investigation, assessment, and evaluation of the impact of the mining, bulk sampling or alluvial diamond prospecting on any national estate referred to in section 3(2) of the National Heritage Resources Act, 1999 (Act No. 25 of 1999) with the exception of the national estate contemplated in section 3(2)(*i*)(vi) and (vii) of that Act, attach the investigation report as **Appendix 2.19.2** and confirm that the applicable mitigation is reflected in 2.5.3; 2.11.6.and 2.12.herein).
- u) Other matters required in terms of sections 24(4)(a) and (b) of the Act. (the EAP managing the application must provide the competent authority with detailed, written proof of an investigation as required by section 24(4)(b)(i) of the Act and motivation if no reasonable or feasible alternatives, as contemplated in sub-regulation 22(2)(h), exist. The EAP must attach such motivation as Appendix 4).

From a local perspective, Remainder of Portion 1 of the farm Uitdraai 33, preferred due to the site's mineral resources. No other properties have been secured by Prieska Diamond Mining (Pty) Ltd for the purpose of mining. The specific site has been chosen for its mineral resources thus making an alternative site selection null and void.

PART B

ENVIRONMENTAL MANAGEMENT PROGRAMME REPORT

1) Draft environmental management programme.

a) **Details of the EAP,** (Confirm that the requirement for the provision of the details and expertise of the EAP are already included in PART A, section 1(a) herein as required).

It is hereby confirmed that the requirements for the provision of the details and expertise of the EAP are contained in Part A, section 1(a) as required. The Curriculum Vitae for the responsible EAP is contained in **Appendix 1 and 2**.

b) **Description of the Aspects of the Activity** (Confirm that the requirement to describe the aspects of the activity that are covered by the draft environmental management programme is already included in PART A, section (1)(h) herein as required).

It is hereby confirmed that the requirements to describe the aspects of the activity that are required by the draft EMP is already included in Part A, section 1(h).

c) Composite Map

(Provide a map (Attached as an Appendix) at an appropriate scale which superimposes the proposed activity, its associated structures, and infrastructure on the environmental sensitivities of the preferred site, indicating any areas that any areas that should be avoided, including buffers)

Refer to Locality Map, attached as in Appendix 4.

- d) Description of Impact management objectives including management statements
 - i) **Determination of closure objectives.** (ensure that the closure objectives are informed by the type of environment described in 2.4 herein)

Closure objectives for the alluvial diamond and general diamond mine will aim to ensure that the residual post-closure impacts be minimized and be acceptable to relevant parties. To achieve these closure objectives, the following will be implemented:

All mining related infrastructure, foundations and concrete areas will be decommissioned, removed from the site and appropriately disposed of. Reclaimable structures such as metal, electrical installations or equipment will be sold for re-use or as scrap.
- All disturbed areas within the site not already vegetated will be re-vegetated with appropriate indigenous, ecologically adapted species appropriate to the area and the final land use as soon as possible after operation ceases. Progress of vegetation growth/establishment, stability and drainage/erosion will be monitored and, in the event of adverse trends being identified, corrective measures will be implemented.
- Vegetation monitoring will consider, inter alia, the establishment of perennial ground cover and infestation by alien invasive plant species. The encroachment of indigenous vegetation into the area will be used as an indication of a stable, self-sustaining vegetation cover with little risk of retrogressing to a situation where are and water pollution may occur.
- ii) The process for managing any environmental damage, pollution, pumping and treatment of extraneous water or ecological degradation as a result of undertaking a listed activity.
- iii) **Potential risk of Acid Mine Drainage**. (Indicate whether or not the mining can result in acid mine drainage).

The mining activities applied for will not result in acid mine drainage. These activities and methods can be seen as a clean process.

- iv) Steps taken to investigate, assess, and evaluate the impact of acid mine drainage.
- v) Engineering or mine design solutions to be implemented to avoid or remedy acid mine drainage.
- vi) Measures that will be put in place to remedy any residual or cumulative impact that may result from acid mine drainage.

vii) Volumes and rate of water use required for the mining, trenching or bulk sampling operation.

18 000 L per hour required for the rotary pans to operate at the wash plant.

viii) Has a water use licence has been applied for?

A water use license application will be applied for, if required.

ix) Impacts to be mitigated in their respective phases

Measures to rehabilitate the environment affected by the undertaking of any listed activity

ACTIVITIES	PHASE	SIZE AND SCALE of	MITIGATION MEASURES	COMPLIANCE WITH STANDARDS	TIME PERIOD FOR IMPLEMENTATION
 (E.g. For prospecting - drill site, site camp, ablution facility, accommodation, equipment storage, sample storage, site office, access route etcetcetc E.g. For mining,- excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetc.) 	(of operation in which activity will take place. State; Planning and design, Pre-Construction' Construction, Operational, Rehabilitation, Closure, Post closure).	disturbance (volumes, tonnages and hectares or m ²)	(describe how each of the recommendations in herein will remedy the cause of pollution or degradation and migration of pollutants)	(A description of how each of the recommendations herein will comply with any prescribed environmental management standards or practices that have been identified by Competent Authorities)	Describe the time period when the measures in the environmental management programme must be implemented Measures must be implemented when required. With regard to Rehabilitation specifically this must take place at the earliest opportunity. With regard to Rehabilitation, therefore state either: Upon cessation of the individual activity Or. Upon the cessation of mining, bulk sampling or alluvial diamond prospecting as the case may be.
Clearance of vegetation	Pitting and trenching phase- (construction and operation phase)	3695.0244ha – The active mining site will be restricted to only 5ha at any given time in order for rehabilitation to take place.	 Site clearing must take place in a phased manner, as and when required. Areas which are not to be mined on within two months must not be cleared to reduce erosion risks. The area to be cleared must be clearly demarcated and this footprint strictly maintained. Spoil that is removed from the site must be removed to an approved spoil site or a licensed landfill site. The necessary silt fences and erosion control measures must be implemented in areas where these risks are more prevalent. 	Compliance with Duty of Care as detailed within NEMA	Duration of operations on the mining activities.
Construction of roads	Pitting and trenching phase- (construction and operation phase)	+- 500m	 Planning of access routes to the site for construction/mining purposes shall be done in conjunction with the Contractor and the Landowner. All agreements reached should be documented and no verbal agreements should be made. The Contractor shall clearly mark all access roads. Roads not to be used shall be marked with a "NO ENTRY for mining vehicles" sign. Construction routes and required access roads must be clearly defined. 	Compliance with Duty of Care as detailed within NEMA	Duration of operations on the mining activities.

			3. 4. 5. 6. 7.	be implemented to reduce dust and nuisance. Soils compacted by construction/mining activities shall be deep ripped to loosen compacted layers and re-graded to even running levels. The contractor must ensure that damage caused by related traffic to the gravel access road off the R34 is repaired continuously. The costs associated with the repair must be borne by the contractor; Dust suppression measures must be implemented for heavy vehicles such as wetting of gravel roads on a regular basis and ensuring that vehicles used to transport the gravel are fitted with tarpaulins or covers; All vehicles must be road-worthy and drivers must be qualified and made aware of the potential road safety issues and need for strict speed limits.		
Mining of Alluvial Diamonds – Soils and geology	Pitting and trenching phase- (construction and operation phase)	3695.0244ha – The active mining site will be restricted to only 5ha at any given time in order for rehabilitation to take place.	1. 2. 3. 4. 5.	The Contractor should, prior to the commencement of earthworks determine the average depth of topsoil (If topsoil exists), and agree on this with the ECO. The full depth of topsoil should be stripped from areas affected by construction and related activities prior to the commencement of major earthworks. This should include the building footprints, working areas and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. Care must be taken not to mix topsoil and subsoil during stripping. The topsoil must be conserved on site in and around the pit/trench area. Subsoil and overburden in the mining area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further	Compliance with Duty of Care as detailed within NEMA	Duration of operations on the mine

				be made at a loss the construction of bound		
				be protected by the construction of berms,		
				trenches or low brick walls around their bases.		
			6.	Stockpiles should be kept clear of weeds and		
				alien vegetation growth by regular weeding.		
			7.	Where contamination of soil is expected,		
				analysis must be done prior to disposal of soil		
				to determine the appropriate disposal route.		
				Proof from an approved waste disposal site		
				where contaminated soils are dumped if and		
				when a spillage/leakage occurs should be		
				attained and given to the project manager.		
			8.	The impact on the geology will be permanent.		
				There is no mitigation measure.		
Mining Alluvial Diamonds – excavations	Pitting and	3695.0244ha – The active	1.	The mining activities must aim to adhere to the	Compliance with Duty of Care as	Duration of operations on the mining area
and blasting	trenching phase-	mining site will be		relevant noise regulations and limit noise to	detailed within NFMA	.
	(construction and	restricted to only 5ha at		within standard working hours in order to		
	operation phase)	any given time in order for		reduce disturbance of dwellings in close		
	oporation phase)	rehabilitation to take place		provimity to the development		
		renabilitation to take place.	2	Mine nane workshone and other noisy fixed		
			۷.	facilities should be leasted well swew from		
				acinities should be located well away north		
				house sensitive areas. Once the proposed final		
				layouts are made available by the		
				Contractor(s), the sites must be evaluated in		
				detail and specific measures designed in to the		
				system.		
			3.	Truck traffic should be routed away from noise		
				sensitive areas, where possible.		
			4.	Noise levels must be kept within acceptable		
				limits.		
			5.	Noisy operations should be combined so that		
				they occur where possible at the same time.		
			6.	Mine workers to wear necessary ear protection		
				dear		
			7	Noisy activities to take place during allocated		
				hours.		
			8	Noise from labourers must be controlled		
			۵. ۵	Noise suppression measures must be applied		
			5.	to all equipment. Equipment must be applied		
				and working order and where appropriate		1
				fitted with eileneers which are kest in seed		
				working order. Should the webiles or		
				working order. Should the vehicles of		
				equipment not be in good working order, the		
				Contractor may be instructed to remove the		
				ottending vehicle or machinery from the site.		1

	 The Contractor must take measures to discourage labourers from loitering in the area and causing noise disturbance. Where possible labour shall be transported to and from the site by the Contractor or his Sub- Contractors by the Contractors own transport. Implementation of enclosure and cladding of processing plants. Applying regular and thorough maintenance schedules to equipment and processes. An increase in noise emission levels very often is 	
	a sign of the imminent mechanical failure of a machine.	

e) Impact Management Outcomes

(A description of impact management outcomes, identifying the standard of impact management required for the aspects contemplated in paragraph ();

ACTIVITY	POTENTIAL IMPACT	ASPECTS	PHASE	MITIGATION	STANDARD TO BE ACHIEVED
(whether listed or not listed). (E.g. Excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetc).	(e.g. dust, noise, drainage surface disturbance, fly rock, surface water contamination, groundwater contamination, air pollution etcetc)	AFFECTED	In which impact is anticipated (e.g. Construction, commissioning, operational Decommissioning, closure, post-closure)	TYPE (modify, remedy, control, or stop) through (e.g. noise control measures, storm-water control, dust control, rehabilitation, design measures, blasting controls, avoidance, relocation, alternative activity etc. etc) E.g. • Modify through alternative method. • Control through noise control • Control through management and monitoring • Remedy through rehabilitation. •	(Impact avoided, noise levels, dust levels, rehabilitation standards, end use objectives) etc.
Clearance of vegetation	Loss or fragmentation of habitats	Fauna & flora	Pitting and trenching phase-(construction and operation phase)	 Existing vegetation Vegetation removal must be limited to the mining area. Vegetation to be removed as it becomes necessary rather than removal of all vegetation throughout the site in one step. No vegetation to be used for firewood without permission. Exotic and invasive plant species should not be allowed to establish, if the development is approved. 	Minimisation of impacts to acceptable limits

	Rehabilitation
	5 All damaged areas shall be rehabilitated upon
	o. In damaged aloue orthogen to to tabilitated upon
	completion of the contract.
	6. Re-vegetation of the disturbed site is aimed at
	approximating as near as possible the natural
	approximating as possible the natural
	vegetative conditions prevailing prior to
	construction.
	7 All natural areas impacted during
	7. All induital areas impacted during
	construction/mining must be renabilitated with
	locally indigenous grasses typical of the
	representative botanical unit
	8. Renabilitation must take place in a phased
	approach as soon as possible.
	9 Rehabilitation process must make use of
	o. reconciliation process that make use of
	species indigenous to the area. Seeds from
	surrounding seed banks can be used for re-
	seeding
	10 Dehabilitation must be evented in such a
	To. Renabilitation must be executed in such a
	manner that surface run-off will not cause
	erosion of disturbed areas
	11 Dianting of indiagnaus trace appages in groop not
	11. Flanting of indigenous tiee species in aleas not
	to be cultivated or built on must be encouraged.
	12.
	Demarcation of mining area
	 All plants not interfering with mining operations.
	shall be left undisturbed clearly marked and
	Shall be left unusuitbed cleany marked and
	indicated on the site plan.
	14. The mining area must be well demarcated and
	no construction/mining activities must be
	no construction/iniming activities must be
	allowed outside of this demarcated footprint.
	15. Vegetation removal must be phased in order to
	reduce impact of construction/mining
	10. Cite and budget of contained to the share much the share's
	ib. Site office and laydown areas must be clearly
	demarcated and no encroachment must occur
	beyond demarcated areas
	17 Otrigit and request audition of the mining
	17. Strict and regular auditing of the mining
	process to ensure containment of the mining
	and lavdown areas.
	18 Solid must be kent free of patrophomical
	to. Solis must be kept nee of perioditerinical
	solutions that may be kept on site during
	construction/mining. Spillage can result in a
	loss of soil functionality thus limiting the re-
	at the line of the filler
	establishment of flora.

			1	F F F F F F F F F F F F F F F F F F F
				Utilisation of resources
				19. Gathering of firewood, fruit, muti plants, or any
				other natural material onsite or in areas
				adjacent to the site is prohibited unless with
				prior approval of the ECO.
				P
				Exotic vegetation
				20 Alien vegetation on the site will need to be
				anter led
				21 The Contractor should be reconcicial for
				21. The Contractor should be responsible for
				implementing a programme of weed control
				(particularly in areas where soil has been
				disturbed); and grassing of any remaining
				stockpiles to prevent weed invasion.
				22. The spread of exotic species occurring
				throughout the site should be controlled.
				Herbicides
				23 Herbicide use shall only be allowed according
				to contract execting the application shall
				be according to get encoding the application and under
				supervision of a qualified technician. The
				possibility of leaching into the surrounding
				environment shall be properly investigated and
				only environmentally friendly herbicides shall
				be used.
				24. The use of pesticides and herbicides on the
				site must be discouraged as these impact on
				important pollinator species of indigenous
				vegetation.
				Fauna
				25. Rehabilitation to be undertaken as soon as
				possible after the mining activities have been
				completed.
				26. No trapping or snaring to fauna on the
				construction/mining site should be allowed.
				27. No faunal species must be disturbed, trapped,
				hunted or killed by maintenance staff during
				any routine maintenance at the development
Mining Alluvial Diamonds and diamonds	Loss of topsoil	Soil	Pitting and trenching	1. The Contractor should, prior to the Minimisation of impacts to acceptable limits
general – excavations and blasting			phase-(construction	commencement of earthworks determine the
			and operation phase)	average denth of tonsoil and agree on this with
				the ECO. The full denth of tonsoil should be
				stringed from areas affected by construction
				and related activities prior to the
				and related activities phot to the

commencement of major earthworks. This
should include the building footprints, working
areas and storage areas. Topsoil must be
reused where possible to rehabilitate disturbed
2. Care must be taken not to mix topsoil and
subsoil during stripping.
3. The topsoil must be conserved on site in and
around the pit/trench area.
4 Subsoil and overburden in the mining area
abault ha stackailed constrainty to be acturated
should be stockpiled separately to be returned
tor backfilling in the correct soil horizon order.
5. If stockpiles are exposed to windy conditions or
heavy rain, they should be covered either by
vegetation or geofabric, depending on the
duration of the project. Stockniles may further
be protocial by the contraction of horms or
low brick walls around their bases.
6. Stockpiles should be kept clear of weeds and
alien vegetation growth by regular weeding.
7. Where contamination of soil is expected.
analysis must be done prior to disposal of soil
to determine the appropriate disposal route
to determine the appropriate disposal folde.
Proof from an approved waste disposal site
where contaminated soils are dumped if and
when a spillage/leakage occurs should be
attained and given to the project manager.
Establish an effective record keeping system for each area
where soil is disturbed for mining purposes. These records
should be included in environmental performance reports,
and should include all the records below.
Record the GPS coordinates of each area.
Becord the date of topsoil stripping
Provide the CDS coordinates of where the tensoil
Record the GFS cooldinates of where the topson
is stockpiled.
Record the date of cessation mining activities at
the particular site.
Photograph the area on cessation of mining
activitias
activities.
Record date and depth of re-spreading of topsoli.
 Photograph the area on completion of
rehabilitation and on an annual basis thereafter to

			show vegetation establishment and evaluate	
			progress of restoration over time.	
Erosion	Soil Air Water	Pitting and trenching phase-(construction and operation phase)	 An effective system of run-off control should be implemented, where it is required, that collects and safely disseminates run-off water from all hardened surfaces and prevents potential down slope erosion. Periodical site inspection should be included in environmental performance reporting that inspects the effectiveness of the run-off control system and specifically records the occurrence of any erosion on site or downstream. Wind screening and stormwater control should be undertaken to prevent soil loss from the site. The use of silt fences and sand bags must be implemented in areas that are susceptible to erosion. Other erosion control measures that can be implemented are as follows: Brush packing with cleared vegetation Mulch or chip packing Planting of vegetation Hydroseeding/hand sowing Sensitive areas need to be identified prior to construction/mining so that the necessary precautions can be implemented. All erosion control mechanisms need to be regularly maintained. Seeding of topsoil and subsoil stockpiles to prevent wind and water erosion of soil surfaces. Retention of vegetation where possible to avoid soil erosion. Vegetation clearance should be phased to ensure that the minimum area of soil is exposed to potential erosion at any one time. Re-vegetation of disturbed surfaces should occur immediately after construction/mining activities are completed. This should be done through seeding with indigenous grasses. 	Minimisation of impacts to acceptable limits

1		1	
Air Dellution	Air		 12. No impediment to the natural water flow other than approved erosion control works is permitted. 13. To prevent stormwater damage, the increase in stormwater run-off resulting from construction/mining activities must be estimated and the drainage system assessed accordingly. 14. Stockpiles not used in three (3) months after stripping must be seeded or backfilled to prevent dust and erosion.
Air Pollution	Air	Pitting and trenching phase-(construction and operation phase)	 Dust control 1. Wheel washing and damping down of unsurfaced and un-vegetated areas. 2. Retention of vegetation where possible will reduce dust travel. 3. Clearing activities must only be done during agreed working times and permitting weather conditions to avoid drifting of sand and dust into neighbouring areas. 4. Damping down of all exposed soil surfaces with a water bowser or sprinklers when necessary to reduce dust. 5. The Contractor shall be responsible for dust control on site to ensure no nuisance is caused to the neighbouring communities. 6. A speed limit of 30km/h must not be exceeded on site. 7. Any complaints or claims emanating from the lack of dust control shall be attended to immediately by the Contractor. 8. Any dirt roads that are utilised by the workers must be regularly maintained to ensure that dust levels are controlled. Odour control 9. Regular servicing of vehicles in order to limit gaseous emissions. 10. Regular servicing of onsite toilets to avoid potential odours.
L	l		

		11. The Contractor should commence rehabilitation of exposed soil surfaces as soon as practical after completion of earthworks.	
		_ , , ,	
		Fire prevention	
		12. No open fires shall be allowed on site under	
		any circumstance. All cooking shall be done in	
		demarcated areas that are safe and cannot	
		cause runaway fires.	
		13. The Contractor shall have operational fire-	
		fighting equipment available on site at all times	
		The level of firefighting equipment must be	
		assessed and evaluated through a typical risk	
		assessed and evaluated infough a typical lisk	
Naiaa	Ditting and tranship	assessinent process.	Minimization of imposts to appontable limits
INDISE	Pluing and trenching	iy i. The mining activities must aim to adhere to the	winimisation of impacts to acceptable limits
	phase-(construction	n relevant hoise regulations and limit hoise to	
	and operation phase	se) within standard working hours in order to	
		reduce disturbance of dwellings in close	
		proximity to the development.	
		2. Mine, crushers, workshops and other noisy	
		fixed facilities should be located well away from	
		noise sensitive areas. Once the proposed final	
		layouts are made available by the	
		Contractor(s), the sites must be evaluated in	
		detail and specific measures designed in to the	
		system.	
		3. Truck traffic should be routed away from noise	
		sensitive areas, where possible	
		4 Noise levels must be kept within acceptable	
		limite	
		5 Noisy operations should be combined so that	
		5. Noisy operations should be combined so that	
		Mine workers to wear possible at the same time.	
		year. 7 Naiss activities to take place during all sector	
		7. Noisy activities to take place during allocated	
		nours.	
		8. Noise from labourers must be controlled.	
		9. Noise suppression measures must be applied	
		to all equipment. Equipment must be kept in	
		good working order and where appropriate	
		fitted with silencers which are kept in good	
		working order. Should the vehicles or	
		equipment not be in good working order, the	

	Impact on potential cultural and heritage artefacts	Heritage	Pitting and trenching phase-(construction and operation phase)	 Contractor may be instructed to remove the offending vehicle or machinery from the site. 10. The Contractor must take measures to discourage labourers from loitering in the area and causing noise disturbance. Where possible labour shall be transported to and from the site by the Contractor or his Sub-Contractors by the Contractors own transport. 11. Implementation of enclosure and cladding of processing plants. 12. Applying regular and thorough maintenance schedules to equipment and processes. An increase in noise emission levels very often is a sign of the imminent mechanical failure of a machine. 1. Any finds must be reported to the nearest National Monuments office to comply with the National Heritage Resources Act (Act No 25 of 1999) and to DEA. 2. Local museums as well as the South African Heritage Resource Agency (SAHRA) should be informed if any artefacts are uncovered in the affected area. 3. The Contractor must ensure that his workforce is aware of the necessity of reporting any possible historical or archaeological finds to the ECO so that appropriate action can be taken. 4. Any discovered artefacts shall not be removed under any circumstances. Any destruction of a site can only be allowed once a permit is obtained and the site has been mapped and
				noted. Permits shall be obtained from the SAHRA should the proposed site affect any world heritage sites or if any heritage sites are to be destroyed or altered.
Waste management		Pollution	Pitting and trenching phase-(construction and operation phase)	Litter management Minimisation of impacts to acceptable limits 1. Refuse bins must be placed at strategic positions to ensure that litter does not accumulate within the construction site. Minimisation of impacts to acceptable limits 2. The Contractor shall supply waste collection bins where such is not available and all solid waste collected shall be disposed of at registered/licensed landfill. Minimisation of impacts to acceptable limits

3. Good housekeeping practices should be
implemented to regularly maintain the litter and
rubble situation on the construction site.
4. If possible and feasible, all waste generated on
site must be separated into glass, plastic,
paper, metal and wood and recycled. An
independent contractor can be appointed to
conduct this recycling
5 Littering by the complexees of the Contractor
5. Littering by the employees of the Contractor
snall not be allowed under any circumstances.
The ECO shall monitor the neatness of the
work sites as well as the Contractor campsite.
6. Skip waste containers should be maintained on
site. These should be kept covered and
arrangements made for them to be collected
regularly.
7 All waste must be removed from the site and
transported to a landfill site promptly to ensure
that it does not attract vermin or produce
8. Where a registered waste site is not available
close to the construction site, the Contractor
shall provide a method statement with regard
to waste management.
9. A certificate of disposal shall be obtained by
the Contractor and kept on file, if relevant
10 Under no circumstances may solid waste be
burnt no site
11 All watte must be removed promotivite opeuro
The All waste must be removed prohibition to ensure
that it does not attract vermin or produce
odours.
Hazardous waste
12. All waste hazardous materials must be
carefully stored as advised by the ECO, and
then disposed of offsite at a licensed landfill
site, where practical. Incineration may be used
where relevant
13 Contaminants to be stored safely to avoid
spiritage.
14. Machinery must be properly maintained to
keep oil leaks in check.
15. All necessary precaution measures shall be
taken to prevent soil or surface water pollution
from hazardous materials used during

construction and any spills shall immediately	
be cleaned up and all affected areas	
Sanitation	
16. The Contractor shall install mobile chemical	
toilets on the site	
17 Stoff shall be sensitized to the fast that they	
17. Stall shall be sensitised to the fact that they	
should use these facilities at all times. No	
indiscriminate sanitary activities on site shall be	
allowed.	
18 Toilets shall be serviced regularly and the ECO	
abali inspect to the regulation and the EOO	
sitali inspect tonets regularity.	
19. I ollets should be no closer than 50m or above	
the 1:100 year flood line from any natural or	
manmade water bodies or drainage lines or	
alternatively located in a place approved of by	
the Engineer	
20. Under no circumstances may open areas,	
neighbours fences or the surrounding bush be	
used as a toilet facility.	
21 The construction of "I ong Drop" toilets is	
forbidden but other toiles connected to the	
ionidadei, but fallet foilets connected to the	
sewage treatment plant.	
22. Potable water must be provided for all	
construction staff.	
Remedial actions	
22 Depending on the nature and extent of the shill	
20. Depending on the nature and extent of the symptomic	
contaminated soil must be eitner excavated or	
treated on-site.	
24. Excavation of contaminated soil must involve	
careful removal of soil using appropriate	
tools/machinery to storage containers until	
tooton do may to good be to licensed based	
ianonii site.	
25. The ECO must determine the precise method	
of treatment for polluted soil. This could involve	
the application of soil absorbent materials as	
wall as oil-directive nowders to the	
contaminated soil.	
26. If a spill occurs on an impermeable surface	
such as cement or concrete, the surface spill	
must be contained using oil absorbent material.	

				21. If necessary, oil absorbent sneets of pads must
				infractructure
				0. Materials used for the second store of
				20. Iviaterials used for the remediation of
				petrochemical spills must be used according to
				product specifications and guidance for use.
				29. Contaminated remediation materials must be
				carefully removed from the area of the spill so
				as to prevent further release of petrochemicals
				to the environment, and stored in adequate
				containers until appropriate disposal.
Water Use and Quality	Water pollution	Water	Pitting and trenching	Water Use
			phase-(construction	1. Develop a sustainable water supply
			and operation phase)	management plan to minimise the impact to
			····· • • • • • • • • • • • • • • • • •	natural systems by managing water use
				avoiding depletion of aquifers and minimising
				impacts to water users
				2 Water must be reused requeled or treated
				2. Water must be reused, recycled of treated
				Water Quality
				3 The quality and quantity of effluent streams
				discharged to the environment including
				stormwater should be engaged and treated to
				mont applicable offluent discharge quidelings
				Disclarge guide intern discharge guidelines.
				4. Discharge to surface water should not result in
				contaminant concentrations in excess of local
				ambient water quality criteria outside a
				scientifically established mixing zone.
				5. Efficient oil and grease traps or sumps should
				be installed and maintained at refueling
				facilities, workshops, fuel storage depots, and
				containment areas and spill kits should be
				available with emergency response plans.
				Stormwater
				6. The site must be managed in order to prevent
				pollution of drains, downstream watercourses
				or groundwater, due to suspended solids and
				silt or chemical pollutants.
				Silt fences should be used to prevent any soil
				entering the stormwater drains.
				8. Temporary cut off drains and berms may be
				required to capture stormwater and promote
				infiltration.
	I	I	I	

 9. Promote availer saving mind set with contraction/minut govincers in order to Contractor ensure less water watages. 10. Hazardous sublateness must be stored at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies on sub to avoid at least 40m from any water bodies as store as possible to attenuate as the oparation phase. 11. Their bodies as store as possible to attenuate as the oparation phase. 12. Each, store and nubble is to be properly disposed of or utilized on site so as not to obtain the attenuate phare system the sale. 13. There should be a pendic checking of the sale saving attenuate neares that the vater frow is unobstructed. 14. If a tachting path is necessary, run off should be managed effectively to avoid contamination of other areas of the site. Unreated runnol from the should be a managed effectively to avoid contamination of other areas of the site. Unreated runnol from the should be a managed effectively to avoid contamination of other areas of the site. Unreated runnol from the should be managed effectively to avoid contamination of other areas of the site. Unreated runnol from the should be managed effectively to avoid contamination of other areas of the site. Unreated runnol from the should be a store or another to be attenue to avoid at a store and the site of the store on the site of the store on the should be a manage of the store on the should be leaded be leaded be leaded be leaded be leaded be attenue to avoid at the store on on-traited process effluents should be avoid at and the equiped with sufficient wells to enable the mather should be avoid for the should be a store on on-traited process effluent				
 Contractor ensure less water vestage. Hazardius substances must be storikances must be storikances must be storikances must be storikances must be storikance and the storikance of the storikan		9.	Promote a water saving mind set with construction/mining workers in order to	
 10. Heardous substancies must be stored at least ovoid pollution. 11. The installation of the stormwater poises on site to avoid pollution. 11. The installation of the stormwater system must take place as soon as possible to attenuate as the operation phase. 12. Earth, store and rubble is to be properly disposed of, or utilized on site so as not to obstruct natural water path ways over the site. 12. Earth, store and rubble is to be properly disposed of, or utilized on site so as not to obstruct natural water path ways over the site. 13. There shuld be a periodic checking of the site's drainage system to ensure that water flow is unobstructed. 14. If a batching pass the is necessary. run-off shuld be managed effectively to avoid contamination of other areas of the site. Unitated number flow is unobstructed. 14. If a batching passed number system on site. 15. Process solutions strates protection 16. Process solutions strates shuld be lead of and other impoundments designed to hold non free may called process fluctures shuld be lead and be equipped with sufficient wells to enable monoting of water levels and quality. Sanitation 16. Adoquate santary facilities and abultions must be readily solvided. 17. The facilities in discusses of our solution workers (1 to left per every 15 workers). 17. The facilities must be required to make and the rule pollution. 			Contractor ensure less water wastage.	
 40m from any water bodies on site to avoid pollution. 11. The installation of the stormwater system must take place as soon as possible to attenuate stormwater from the construction phase as well as the operation phase. 12. Earth, stone and rubble is to be properly disposed of or utilized on site so as not to obstruct natural water path ways over the site. i.e. these materials must not be placed in stormwater channels, drainage lines or nivers. 13. There should be a periodic characteristic of the site's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid to any storem the site is drainage system or nearly streams, nives or croased to hold, non fresh impoundment designed to hold non fresh		10.	Hazardous substances must be stored at least	
 pollution. 11. The installation of the storwater system must take place as soon as possible to afteruule storwater from the construction phase as well as the operation phase. 12. Earth, store and rubble is to be properly disposed of or utilized on site so as not to obstruct anally water park ways over the site. 13. There should be a pendicic checking of the site storwater from the construction inso or the site stormater instead in the stormater instead in the stormater is stormater is stormater instead in the stormater is stormater instead			40m from any water bodies on site to avoid	
 11. The installation of the stormwater system must take place as soon as possible to attenuate stormwater from the construction phase as well as the operation phase. 12. Earth, store and rubble is to be properly disposed of, store and rubble is to be properly disposed of, well and the stormwater of the site. 13. There should be a periodic checking of the site o			nollution	
 take place as soon as possible to attenuate sommater from the construction phase as well as the operation phase. 12. Earth, store and nubble is to be properly disposed of or utilized of or utilized of or utilized of the obstruct natural ways over the site. 13. There should be a periodic checking of the site some number of the site of the		11	The installation of the stormwater system must	
stormwater from the construction phase as well as the operation phase. 12. Earth, stone and rubble is to be properly disposed of, or utilized not alk so as not to odStruct natural water path ways over the site. i.e. these materials must not be placed in stormwater channels, dranage integer or reves. 13. There should be a periodic checking of the site's strandor be apenied in the water flow is unobstructed. 14. If a backing glant is necessary, run-off should be managed effectively to avoid contamination of other areas of the site. Untrested runoff from the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not batch plant stond into fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and abutions must be provided for construction workers (1 tollet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			take place as soon as possible to attenuate	
 as the operation phase. 12. Earth, stone and rubble is to be properly disposed of, or utilized on site so as not to obstruct natural water path ways over the site. i.e. these materials must not be placed in stormwater channels, drainage lines or rivers. 13. There should be a periodic checking of the site's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be manged effectively to avoid contamination of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or recision channels or dongas. Coroundwater resource protection 15. Process solution storage ponds and other improved the and be equipped to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable montoring of water and water and rule should be lined and be equipped with sufficient wells to enable be income the store of coroundwater resource protection 16. Adequate samitary facilities and ablutions must be provided for construction workers (1 bilet, per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			stormwater from the construction phase as well	
 12. Earth, stone and nubble is to be properly disposed of, or utilized on site so as not to obstruct natural water path ways over the site. i.e. these materials must not be placed in stormwater channels, drainage lines or rivers. 13. There should be a periodic checking of the site's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of other areas of the site. Untreaded nuonf from the batch plant must not be allowed to get into the storm water system or means the unoff the site or or resonance of the storm and systemes and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with site/initiation water system. 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with site/initiation water system. 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toliet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater general process (1 toliet per every 15 workers). 			as the operation phase	
 La chain solid a fair factor is to be a so as not to obstruct natural water path ways over the site. i.e. these materials must not be placed in stormwater channels, drainage lines or ivers. There should be a periodic checking of the site's drainage system to ensure that the water flow is unobstructed. If a batching plant is necessary, run-off should be managed effectively to avvid contamination of other areas of the site's drainage system to ensure that the water flow is unobstructed. If a batching plant is necessary, run-off should be managed effectively to avvid contamination of other areas of the site. Unbeaded runoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or donges. Groundwater resource protection Services or erosion channels or donges. Groundwater devices and the sufficient wells to be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 tollet per every 15 workers). The facilities must be regularly serviced to reduce the risk of sufficience or groundwater pollution. 		12	Earth stone and rubble is to be properly	
 disboard of, of diatual water path ways over the sile. i.e. these materials must not be placed in substrat natural water path ways over the sile. i.e. these materials must not be placed in substrat natural water path ways over the sile. ii.e. these materials must not be placed in substrat natural water path ways over the sile. ii.e. these materials must not be placed in substrat natural water path ways over the sile. ii.e. these materials must not be placed in substrat natural water path ways over the sile. iii.e. these materials must not be placed in substrat natural water path water flow is unobstructed. iii.e. the should be a periodic chacking of the substrated nunoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or ension channels or dinage path sile. iii.e. the storm water system or nearby streams, rivers or ension channels or dongas. Groundwater resource protection iii.e. Process solution storage ponds and other impoundments designed to hold on fresh water or non-treated process effuents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation iii. Adequate sanitary facilities and ablutions must be provided for constration workers of to its bid. iiii. Adequate sanitary facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 		12.	disposed of or utilized on site so as not to	
 Let these materials must be placed in stormwater channels, drainage lines or rivers. 13. Three should be a periodic checking of the site's drainage system to ensure that the water flow is unostructed. 14. If a batching plant is necessary, nun-off should be a managed effectively to avoid contamination of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process Solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be line dat be equiped with sufficient wells to enable montoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per very 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			abstruct natural water not hyper over the site	
 b. Use materials that how the pactor in stormwater channels, draitage lites or invers. 13. There should be a periodic checking of the sile's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of other areas of the sile. Untreated runoff from the batch plant must not be alloved to get into the storm water system or nearby streams, rivers or erosion channels or of host on fresh water impoundments designed to hold not fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers), 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			obstruct flatural water path ways over the site.	
 Subinitivate charmer, during these of notes. 13. There should be a periodic checking of the site's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of of ther areas of the site. Untreated numoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to anable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			i.e. these materials must not be placed in	
 So There should be a product checking of the site's drainage system to ensure that the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or ensoin channels or dongars. Groundwater resource protection Process solution storage ponds and other impoundments designed to hold non fresh water or non-tracted process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). The facilities must be regularly serviced to reduce the risk of surface or groundwater polition. 		10	Stormwater channels, orainage lines of fivers.	
 Site's dialage system to this the water flow is unobstructed. 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to get into the batch plant must not be allowed to not fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 tollet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 		13.	ite's drainage system to ensure that the water	
 14. If a batching plant is necessary, run-off should be managed effectively to avoid contamination of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			site s drainage system to ensure that the water	
 14. If a backing plant is hecessary, fun-off should be managed effectively to avoid containation of other areas of the site. Untreated runoff from the batch plant must not be allowed to get into the storm water system or nearly streams, rivers or erosion channels or dongas. Groundwater resource protection Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			liow is unopstructed.	
 be managed effectively to avoid contamination of ofther areas of the site. Untreated numbif from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 		14.	If a batching plant is necessary, run-off should	
of other areas of the site. Untreated runom from the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			be managed effectively to avoid contamination	
 the batch plant must not be allowed to get into the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			of other areas of the site. Untreated runoff from	
the storm water system or nearby streams, rivers or erosion channels or dongas. Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			the batch plant must not be allowed to get into	
Image: Second			the storm water system or nearby streams,	
Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			rivers or erosion channels or dongas.	
 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 		Groundw	vater resource protection	
impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.		15.	Process solution storage ponds and other	
 water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			impoundments designed to hold non fresh	
 be lined and be equipped with sufficient wells to enable monitoring of water levels and quality. Sanitation Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			water or non-treated process effluents should	
to enable monitoring of water levels and quality. Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			be lined and be equipped with sufficient wells	
Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			to enable monitoring of water levels and	
 Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 			quality.	
 Sanitation 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 				
 16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 		Sanitatio	n	
be provided for construction workers (1 toilet per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.		16.	Adequate sanitary facilities and ablutions must	
per every 15 workers). 17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			be provided for construction workers (1 toilet	
17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.			per every 15 workers).	
reduce the risk of surface or groundwater pollution.		17.	The facilities must be regularly serviced to	
pollution.			reduce the risk of surface or aroundwater	
			pollution.	
			F	
Concrete mixing		Concrete	emixing	
18. Concrete contaminated water must not enter		18.	Concrete contaminated water must not enter	
soil or any natural drainage system as this			soil or any natural drainage system as this	

disturbs the natural acidity of the soil and affects plant growth.
Public areas 19. Food preparation areas should be provided with adequate washing facilities and food refuse should be stored in sealed refuse bins which should be removed from site on a regular basis. 20. The Contractor should take steps to ensure that littering by construction/mining workers does not occur and persons should be employed on site to collect litter from the site and immediate surroundings, including litter accumulating at fence lines. 21. No washing or servicing of vehicles on site.

f) Impact Management Actions

(A description of impact management actions, identifying the manner in which the impact management objectives and outcomes contemplated in paragraphs (c) and (d) will be achieved).

ACTIVITY Whether listed or not listed. (E.g. Excavations, blasting, stockpiles, discard	POTENTIAL IMPACT (e.g. dust, noise, drainage	MITIGATION TYPE	TIME PERIOD FOR IMPLEMENTATION Describe the time period when the measures in the	COMPLIANCE WITH STANDARDS
dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetc).	surface disturbance, fly rock, surface water contamination, groundwater contamination, air pollution etcetc)	 (modify, remedy, control, or stop) through (e.g. noise control measures, storm-water control, dust control, rehabilitation, design measures, blasting controls, avoidance, relocation, alternative activity etc. etc) E.g. Modify through alternative method. Control through noise control Control through management and monitoring Remedy through rehabilitation 	environmental management programme must be implemented Measures must be implemented when required. With regard to Rehabilitation specifically this must take place at the earliest opportunityWith regard to Rehabilitation, therefore state either: Upon cessation of the individual activity or. Upon the cessation of mining, bulk sampling or alluvial diamond prospecting as the case may be.	(A description of how each of the recommendations in 2.11.6 read with 2.12 and 2.15.2 herein will comply with any prescribed environmental management standards or practices that have been identified by Competent Authorities)
Clearance of vegetation	Loss or fragmentation of habitats	Existing vegetation1.Vegetation removal must be limited to the mining site.	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable

 Vegetation to be removed as it becomes necessary rather than removal of all vegetation throughout the site in one step. No vegetation to be used for firewood. Exotic and invasive plant species should not be allowed to establish, if the development is approved. Thorn trees shall not be removed or damaged without prior approval and permits. 	standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.
Rehabilitation	
 6. All damaged areas shall be rehabilitated upon completion of the contract. 7. Re-vegetation of the disturbed site is aimed at approximating as near as possible the natural vegetative conditions prevailing prior to construction. 8. All natural areas impacted during construction/mining must be rehabilitated with locally indigenous grasses typical of the representative botanical unit. 9. Rehabilitation must take place in a phased approach as soon as possible. 10. Rehabilitation process must make use of species indigenous to the area. Seeds from surrounding seed banks can be used for re-seeding. 11. Rehabilitation must be executed in such a manner that surface run-off will not cause erosion of disturbed areas. 12. Planting of indigenous tree species in areas not to be 	
Demarcation of mining area 13. All plants not interfering with mining operations shall be	
left undisturbed clearly marked and indicated on the site plan. 14. The mining area must be well demarcated and no construction activities must be allowed outside of this	
demarcated footprint	
15 Vegetation removal must be phased in order to reduce	
impact of construction/mining.	
16. Site office and laydown areas must be clearly demarcated	
and no encroachment must occur beyond demarcated	
areas.	
17. Strict and regular auditing of the mining process to ensure	
containment of the mining and laydown areas.	
10. Solis must be kept tree of petrochemical solutions that	
may be kept on site during construction/mining. Splitage	

		can result in a loss of soil functionality thus limiting the re- establishment of flora.		
		 Utilisation of resources 19. Gathering of firewood, fruit, muti plants, or any other natural material onsite or in areas adjacent to the site is prohibited unless with prior approval of the ECO. 		
		 Exotic vegetation 20. Alien vegetation on the site will need to be controlled. 21. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any remaining stockpiles to prevent weed invasion. 22. The spread of exotic species occurring throughout the site should be controlled. 		
		 Herbicides 23. Herbicide use shall only be allowed according to contract specifications. The application shall be according to set specifications and under supervision of a qualified technician. The possibility of leaching into the surrounding environment shall be properly investigated and only environmentally friendly herbicides shall be used. 24. The use of pesticides and herbicides on the site must be discouraged as these impact on important pollinator species of indigenous vegetation. (Avi) Fauna 25. Rehabilitation to be undertaken as soon as possible after mining has been completed. 26. No trapping or snaring to fauna on the construction/mining 		
		 site should be allowed. 27. No faunal species must be disturbed, trapped, hunted or killed by maintenance staff during any routine maintenance at the development. 28. No impacts on bats are expected since mining will be taking place during the day and not at night, also no cave like structures are found on site. 		
Mining of Alluvial Diamonds and Diamonds General (D) – excavations and blasting	Loss of topsoil	 The Contractor should, prior to the commencement of earthworks determine the average depth of topsoil, and agree on this with the ECO. The full depth of topsoil should be stripped from areas affected by construction/mining and related activities prior to the commencement of major 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with

	 earthworks. This should include the building footprints, working areas and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. Care must be taken not to mix topsoil and subsoil during stripping. The topsoil must be conserved on site in and around the pit/trench area. Subsoil and overburden in the mining area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. 		NEMA and Duty of Care as prescribed by NEMA.
	 Establish an effective record keeping system for each area where soil is disturbed for mining purposes. These records should be included in environmental performance reports, and should include all the records below. Record the GPS coordinates of each area. Record the date of topsoil stripping. Record the GPS coordinates of where the topsoil is stockpiled. Record the date of cessation mining activities at the particular site. Photograph the area on cessation of mining activities. Record date and depth of re-spreading of topsoil. Photograph the area on completion of rehabilitation and on an annual basis thereafter to show vegetation establishment and evaluate progress of restoration over time. 		
Erosion	 An effective system of run-off control should be implemented, where it is required, that collects and safely disseminates run-off water from all hardened surfaces and prevents potential down slope erosion. 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with

	 Periodical site inspection should be included in environmental performance reporting that inspects the effectiveness of the run-off control system and specifically records the occurrence of any erosion on site or downstream. Wind screening and stormwater control should be undertaken to prevent soil loss from the site. The use of silt fences and sand bags must be implemented in areas that are susceptible to erosion. Other erosion control measures that can be implemented are as follows: Brush packing with cleared vegetation Mulch or chip packing Planting of vegetation Hydroseeding/hand sowing Sensitive areas need to be identified prior to construction/mining so that the necessary precautions can be implemented. All erosion control mechanisms need to be regularly maintained. Seeding of topsoil and subsoil stockpiles to prevent wind and water erosion of soil surfaces. Retention of vegetation where possible to avoid soil erosion. Vegetation clearance should be phased to ensure that the minimum area of soil is exposed to potential erosion at any one time. Re-vegetation of disturbed surfaces should occur immediately after construction/mining activities are completed. This should be done through seeding with indigenous grasses. No impediment to the natural water flow other than approved erosion control works is permitted. To prevent stormwater damage, the increase in stormwater run-off resulting from construction/mining activities must be estimated and the drainage system assessed accordingly. A drainage plan must be submitted to the Engineer for approval and must include the location and design criteria of any temporary stream crossings. 		NEMA and Duty of Care as prescribed by NEMA.
	and design criteria of any temporary stream crossings.		
	14. Stockpiles not used in three (3) months after stripping		
	must be seeded/backfilled to prevent dust and erosion.		
Air Pollution	Dust control	Duration of operation	The implementation of the recommended
	vegetated areas.		minimisation of impacts to acceptable standards, thereby ensuring compliance with

	15. Retention of vegetation where possible will reduce dust	NEMA and Duty of Care as prescribed by
	16 Clearing activities must only be done during agreed	
	working times and permitting weather conditions to avoid	
	drifting of sand and dust into neighbouring areas.	
	17. Damping down of all exposed soil surfaces with a water	
	bowser or sprinklers when necessary to reduce dust.	
	18. The Contractor shall be responsible for dust control on site	
	to ensure no nuisance is caused to the neighbouring	
	10 A speed limit of 20km/h must not be exceeded on site	
	20 Any complaints or claims emanating from the lack of dust	
	control shall be attended to immediately by the Contractor.	
	21. Any dirt roads that are utilised by the workers must be	
	regularly maintained to ensure that dust levels are	
	controlled.	
	Odour control	
	22. Regular servicing of vehicles in order to limit gaseous	
	emissions.	
	23. Regular servicing of onsite toilets to avoid potential	
	odours.	
	Rehabilitation	
	24. The Contractor should commence rehabilitation of	
	exposed soil surfaces as soon as practical after	
	completion of earthworks.	
	Fire prevention	
	25. No open fires shall be allowed on site under any	
	circumstance. All cooking shall be done in demarcated	
	areas that are safe and cannot cause runaway fires.	
	20. The Contractor shall have operational tire-tighting	
	firefighting equipment must be assessed and evaluated	
	through a typical risk assessment process.	
Noise	1. The mining activities must aim to adhere to the relevant Duration of operation	The implementation of the recommended
	noise regulations and limit noise to within standard	mitigation measures will result in the
	working hours in order to reduce disturbance of dwellings	minimisation of impacts to acceptable
	In close proximity to the development.	Standards, thereby ensuring compliance with
	fixed facilities should be located well away from noise	NEMA.
	sensitive areas. Once the proposed final layouts are made	

	 available by the Contractor(s), the sites must be evaluated in detail and specific measures designed in to the system. Truck traffic should be routed away from noise sensitive areas, where possible. Noise levels must be kept within acceptable limits. Noise yoperations should be combined so that they occur where possible at the same time. Mine workers to wear necessary ear protection gear. Noise from labourers must be controlled. Noise suppression measures must be controlled. Noise suppression measures must be applied to all equipment. Equipment must be kept in good working order and where appropriate fitted with silencers which are kept in good working order. Should the vehicles or equipment not be in good working order, the Contractor may be instructed to remove the offending vehicle or machinery from the site. The Contractor must take measures to discourage labourers from loitering in the area and causing noise disturbance. Where possible labour shall be transported to and from the site by the Contractor or his Sub- Contractors by the Contractors own transport. Implementation of enclosure and cladding of processing plants. Applying regular and thorough maintenance schedules to equipment and processes. An increase in noise emission levels very often is a sign of the imminent mechanical fielder of evanctions 	
Impact on potential cultural and heritage artefacts	 Any finds must be reported to the nearest National Monuments office to comply with the National Heritage Resources Act (Act No 25 of 1999) and to DEA. Local museums as well as the South African Heritage Resource Agency (SAHRA) should be informed if any artefacts are uncovered in the affected area. The Contractor must ensure that his workforce is aware of the necessity of reporting any possible historical or archaeological finds to the ECO so that appropriate action can be taken. Any discovered artefacts shall not be removed under any circumstances. Any destruction of a site can only be allowed once a permit is obtained and the site has been mapped and noted. Permits shall be obtained from the SAHRA should the proposed site affect any world heritage sites or if any heritage sites are to be destroyed or altered. 	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

Waste Management	Litter management	Duration of operation	The implementation of the recommended
	1. Refuse bins must be placed at strategic positions to		mitigation measures will result in the
	ensure that litter does not accumulate within the		minimisation of impacts to acceptable
	construction/nining site.		standards, thereby ensuring compliance with
	2. The Contractor shall supply waste collection bins where		NEMA and Duty of Care as prescribed by
	such is not available and all solid waste collected shall be		NEMA.
	disposed of at registered/licensed landfill.		
	3. Good housekeeping practices should be implemented to		
	regularly maintain the litter and rubble situation on the		
	construction/mining site.		
	4. If possible and reasible, all waste generated on site must		
	be separated into glass, plastic, paper, metal and wood		
	and recycled. An independent contractor can be		
	5 Littering by the employees of the Contractor shall not be		
	allowed under any circumstances. The ECO shall monitor		
	the neatness of the work sites as well as the Contractor		
	campsite.		
	6. Skip waste containers should be maintained on site.		
	These should be kept covered and arrangements made		
	for them to be collected regularly.		
	7. All waste must be removed from the site and transported		
	to a landfill site promptly to ensure that it does not attract		
	vermin or produce odours.		
	8. Where a registered waste site is not available close to the		
	construction/mining site, the Contractor shall provide a		
	method statement with regard to waste management.		
	9. A certificate of disposal shall be obtained by the		
	Contractor and kept on file, if relevant.		
	10. Under no circumstances may solid waste be burnt on site.		
	11. All waste must be removed promptly to ensure that it does		
	not attract vermin or produce odours.		
	Hazardous waste		
	12. All waste hazardous materials must be carefully stored as		
	advised by the ECO, and then disposed of offsite at a		
	licensed landfill site, where practical. Incineration may be		
	used where relevant.		
	13. Contaminants to be stored safely to avoid spillage.		
	14. Machinery must be properly maintained to keep oil leaks		
	in check.		
	15. All necessary precaution measures shall be taken to		
	prevent soil or surface water pollution from hazardous		
	materials used during construction/mining and any spills		

shall immediately be shared up and all affected areas	
shall immediately be cleaned up and all affected areas	
rehabilitated.	
Sanitation	
16 The Contractor shall install mobile chemical toilets on the	
17. Staff shall be sensitised to the fact that they should use	
these facilities at all times. No indiscriminate sanitary	
activities on site shall be allowed.	
18 Toilets shall be serviced regularly and the ECO shall	
inspect toilets regulately and the Lee of an	
inspect tonets regularly.	
19. Tollets should be no closer than 50m or above the 1:100	
year flood line from any natural or manmade water bodies	
or drainage lines or alternatively located in a place	
approved of by the Engineer.	
20 Under no circumstances may open areas neighbours	
fonce ar the current line has upon a real to a training hours	
The sub-out of the su	
21. The construction of Long Drop tollets is forbidden, but	
rather toilets connected to the sewage treatment plant.	
22. Potable water must be provided for all construction staff.	
Remedial actions	
23 Depending on the nature and extent of the shill	
20. Depending on the nature and extend of the spin,	
site.	
24. Excavation of contaminated soil must involve careful	
removal of soil using appropriate tools/machinery to	
storage containers until treated or disposed of at a	
licensed hazardous landfill site	
25 The ECO must determine the precise method of treatment	
for polluted call. This could involve the application of could	
ior ponded son. This could involve the application of son	
absorbent materials as well as oil-digestive powders to the	
contaminated soil.	
26. If a spill occurs on an impermeable surface such as	
cement or concrete, the surface spill must be contained	
using oil absorbent material.	
27 If necessary oil absorbent sheets or pads must be	
attached to leaky machinery or infrastructure	
28 Materials used for the remodulition of netrophamical spills	
20. Induction used to the termediation of petrochemical splits	
must be used according to product specifications and	
guidance for use.	
29. Contaminated remediation materials must be carefully	
removed from the area of the spill so as to prevent further	
release of petrochemicals to the environment, and stored	
in adequate containers until appropriate disposal	

Water Use and Quality	Water pollution	Waterlise
Water Ose and Quality		1 Develop a sustainable water supply management plan to
		minimise the impact to natural systems by managing
		water use avoiding depletion of aquifers and minimising
		impacts to water users
		2 Water must be reused recycled or treated where possible
		Water Quality
		3. The guality and guantity of effluent streams discharged to
		the environment including stormwater should be managed
		and treated to meet applicable effluent discharge
		guidelines.
		4. Discharge to surface water should not result in
		contaminant concentrations in excess of local ambient
		water quality criteria outside a scientifically established
		mixing zone.
		5. Efficient oil and grease traps or sumps should be installed
		and maintained at refueling facilities, workshops, fuel
		storage depots, and containment areas and spill kits
		should be available with emergency response plans.
		Stormustor
		Stormwater 6 The site must be managed in order to provent pollution of
		o. The site must be managed in order to prevent politicitor of designs, downstream watercourses or groupdwater, due to
		suspended solids and silt or chemical pollutants
		7 Silt fences should be used to prevent any soil entering the
		stormwater drains
		8 Temporary cut off drains and berms may be required to
		capture stormwater and promote infiltration.
		9. Promote a water saving mind set with construction/mining
		workers in order to Contractor ensure less water wastage.
		10. New stormwater construction must be developed strictly
		according to specifications from engineers in order to
		ensure efficiency.
		11. Hazardous substances must be stored at least 20m from
		any water bodies on site to avoid pollution.
		12. The installation of the stormwater system must take place
		as soon as possible to attenuate stormwater from the
		construction phase as well as the operation phase.
		13. Earth, stone and rubble is to be properly disposed of, or
		utilized on site so as not to obstruct natural water path
		ways over the site. I.e. these materials must not be placed
		in stormwater channels, drainage lines or rivers.

14. There should be a periodic checking of the site's drainage
system to ensure that the water flow is unobstructed.
15. If a batching plant is necessary, run-off should be
managed effectively to avoid contamination of other areas
of the site. Untreated runoff from the batch plant must not
he allowed to get into the storm water system or nearby
strame rivers or arreston dannels or dange
streams, nyers of erosion channels of doligas.
Groundwater resource protection
16. Process solution storage ponds and other impoundments
designed to hold non fresh water or un-treated process
effluents should be lined and be equipped with sufficient
wells to enable monitoring of water levels and quality.
Sanitation
17. Adequate sanitary facilities and ablutions must be
provided for construction workers (1 toilet per every 15
workers).
18 The facilities must be regularly serviced to reduce the risk
of surface or groundwater pollution
Concrete mixing
10 Concrete contaminated water must not enter soil or any
13. Controller containing water must not enter soil of any
natural drainage system as this disturbs the natural activity
of the soil and affects plant growth.
runic aleas
20. rood preparation areas should be provided with adequate
wasning facilities and food refuse should be stored in
sealed refuse bins which should be removed from site on
a regular basis.
21. The Contractor should take steps to ensure that littering
by construction workers does not occur and persons
should be employed on site to collect litter from the site
and immediate surroundings, including litter accumulating
at fence lines.
22. No washing or servicing of vehicles on site.
 Concrete mixing Concrete contaminated water must not enter soil or any natural drainage system as this disturbs the natural acidity of the soil and affects plant growth. Public areas Food preparation areas should be provided with adequate washing facilities and food refuse should be stored in sealed refuse bins which should be removed from site on a regular basis. The Contractor should take steps to ensure that littering by construction workers does not occur and persons should be employed on site to collect litter from the site and immediate surroundings, including litter accumulating at fence lines. No washing or servicing of vehicles on site.

i) Financial Provision

- (1) Determination of the amount of Financial Provision.
 - (a) Describe the closure objectives and the extent to which they have been aligned to the baseline environment described under Regulation 22 (2) (d) as described in 2.4 herein.
 - Final landforms must be resilient to perturbation and also be self-sustaining to obviate/limit further/ongoing interventions and maintenance by Prieska Diamond Mining (Pty) Ltd
 - The remaining impacts be of an acceptable nature with minimal deterioration over time.
 - The final outcome of the mine site rehabilitation would be productive systems, where required sustaining either cattle or wildlife.
 - Environmental and human quality of life, including health and safety requirements in general, would not be compromised; and
 - Closure is achieved in an efficient and cost-effective manner as possible and with minimum socioeconomic changes.

The above goal is underpinned by more specific objectives listed below.

1. Upfront planning/development

To provide overall guidance and direction to closure planning and/or the implementation of progressive closure measures over the remaining over the mining life.

2. Physical stability

To ensure that surface infrastructure and mining residue and/or disturbances that are present at processing plant decommissioning will be removed and/or stabilised in a manner that these will not compromise post-closure land use and be sustainable long-term landforms.

- Closure, removal and disposal of all surface infrastructure that has no beneficial post-closure use.
- Shaping and vegetating the remaining earth embankments, trenches, etc. to stabilise slopes and integrate with surrounding topography.

3. Environmental quality

To ensure that local environmental quality is not adversely affected by possible physical effects arising from mining operations and the mining site after closure. This will be achieved by:

- Avoiding and/or limiting the following during mining operations which could result in adverse effects that could not be readily addressed and/or mitigated at mine closure.
 - Dust fall-out areas surrounding the mining site.
 - Wash-off and/or mobilisation of chemically contaminated soils and sediments from the mining site that could have long term adverse effects on local aquatic health and/or other water uses.
 - Possible shallow groundwater contamination adversely affecting the quality of the local water resource and its beneficial use.
- Limiting the potential for dust generation on the rehabilitated mining site that could cause nuisance and/or health effects to surrounding landowners;

- Limiting the possible adverse water quality and quantity effects arising from the rehabilitated mining site to ensure that long term beneficial use of local resources is not compromised;
- Conducting soil clean-up/remediation to ensure that the planned land use could be implemented and maintained;

4. Health and safety

To limit the possible health and safety treats due to terrain hazards to humans and animals utilizing the rehabilitated mining site after closure by:

- Demonstrating through upfront soil testing that any resultant inorganic and organic pollution present on the site is acceptable;
- Removal of potential contaminants such as hydrocarbons and chemicals off site;
- Shaping of embankments and trenches to safe slopes and reintegrating of these into surrounding topography.
- Ensuring that the environmental quality as reflected above is achieved.

5. Land capability / land use

To ensure that the required land capability to achieve and support the planned land use can be achieved over the mining site by:

- Clean-up and reclamation of contaminated soil areas in order not to compromise the above land use planning earmarked for implementation;
- To ensure that the overall rehabilitated mining site is free draining
- Transferring mining related surface infrastructure to third parties for beneficial use after closure.

6. Aesthetic quality

To ensure that the rehabilitated mining site will display, at a minimum, an acceptable aesthetic appearance that would not compromise the planned land use by leaving behind:

- A mining area that is properly cleared-up with no fugitive/scattered waste piles
- Rehabilitated mining area that is free draining and disturbed areas that are suitably vegetated.
- Rehabilitated mining residues that are suitably landscaped, blending with the surrounding environment as far as possible.
- Shaped and rehabilitated terrace and hard stand areas, roughly emulating the local natural surface topography.

7. Landscape viability

To create a landscape that is self-sustaining and over time will evolve/converge to the desired ecosystem structure, function and composition by:

- Conducing surface profiling, with associated material movement optimisation, to
 obtain a landscape resembling the natural landscapes to support the succession
 trajectory towards a climax ecological system.
- Establishing woody patches and create "rough and loose" areas for pioneer specie establishment around the respective patches.
- Establishing pioneer species as follows:
- Collected and prepared seeds for broad casting;
- Seedlings grown on on-site nursery;
- Cuttings collected from surrounding veld areas;
- Conducting rehabilitation monitoring and corrective action as required.

8. Biodiversity

To encourage, where appropriate, the re-establishment of native vegetation on the rehabilitated mine site such the terrestrial biodiversity is largely re-instated over time, by:

- Stabilising disturbed areas to prevent erosion in the short- to medium term until a suitable vegetation cover has established; and
- Establishing viable self-sustaining vegetation communities of local fauna, as far as possible.
- (b) Confirm specifically that the environmental objectives in relation to closure have been consulted with landowner and interested and affected parties.
- (c) Closure objectives within the EMPr have been presented to the public as part of the public participation process and on-going closure planning for mining.
- (d) Provide a rehabilitation plan that describes and shows the scale and aerial extent of the main mining activities, including the anticipated mining area at the time of closure.
- (e) The Rehabilitation Plan is attached as Appendix 8.
- (f) Explain why it can be confirmed that the rehabilitation plan is compatible with the closure objectives.

The rehabilitation plan relates to each closure objective identified for the mine. Therefore, the rehabilitation plan is considered to be compatible with the closure objectives.

(g) Calculate and state the quantum of the financial provision required to manage and rehabilitate the environment in accordance with the applicable guideline.

XXXXXXXXXXXXXXXX

(h) Confirm that the financial provision will be provided as determined.

Financial Guarantee

The financial guarantee for the rehabilitation for land disturbed by Prieska Diamond Mining (Pty) Ltd was submitted together with the application for the mining right.

Rehabilitation Fund

Prieska Diamond Mining (Pty) Ltd will also make provision for rehabilitation during closure by establishing a rehabilitation trust.

EIA019 – Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

Mechanisms for monitoring compliance with and performance assessment against the environmental management programme and reporting thereon, including

- g) Monitoring of Impact Management Actions
- h) Monitoring and reporting frequency
- i) Responsible persons
- j) Time period for implementing impact management actions
- k) Mechanism for monitoring compliance

SOURCE ACTIVITY	IMPACTS REQUIRING MONITORING PROGRAMMES	FUNCTIONAL REQUIREMENTS FOR MONITORING	ROLES AND RESPONSIBILITIES (FOR THE EXECUTION OF THE MONITORING PROGRAMMES)	MONITORING AND REPORTING FREQUENCY and TIME PERIODS FOR IMPLEMENTING IMPACT MANAGEMENT ACTIONS
Clearance of vegetation	Loss or fragmentation of habitats	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.
Mining of Alluvial Diamonds– excavations	Loss of topsoil Erosion Air Pollution Noise Impact on potential cultural and heritage artefacts	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.
Waste management	Pollution	Conduct regular internal auditsConduct regular external audits	Environmental ManagerSuitable qualified environmental auditor	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6

EIA019 – Mining Right Application for Diamonds, Diamonds General, Diamonds Alluvial and Kimberlite near Prieska on Remainder of Portion 1 of the farm Uitdraai 33, Registration Division Prieska RD, Northern Cape Province.

				months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.
Water Use and Quality	Water pollution	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.

I) Indicate the frequency of the submission of the performance assessment report.

External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the Competent Authority if required.

m) Environmental Awareness Plan

(1) Manner in which the applicant intends to inform his or her employees of any environmental risk which may result from their work.

Prieska Diamond Mining (Pty) Ltd will implement an Environmental Awareness Plan which will include various mechanisms for informing employees of environmental risks resulting from their work, including:

- Induction training for full –time staff and contractors;
- In-house training sessions to be held with relevant employees;
- On the job training regarding environmental issues
- Training and skills development

The above measures will be implemented through an Environmental Communication Strategy to be implemented.

(2) Manner in which risks will be dealt with in order to avoid pollution or the degradation of the environment.

Prieska Diamond Mining (Pty) Ltd will implement an incident reporting and reporting procedure in order to identify risks timeously and implement actions to avoid or minimise environmental impacts.

n) Specific information required by the Competent Authority (Among others, Confirm that the financial provision will be reviewed annually).

No specific information requirements have been detailed by the Competent Authority.

2) UNDERTAKING

The EAP herewith confirms

- a) the correctness of the information provided in the reports \boxtimes
- b) the inclusion of comments and inputs from stakeholders and I&APs ; \boxtimes
- c) the inclusion of inputs and recommendations from the specialist reports where relevant; ⊠and
- d) the acceptability of the project in relation to the finding of the assessment and level of mitigation proposed; ⊠

Signature of the environmental assessment practitioner:

Milnex 189 CC – Environmental Consultants Name of company:

09-06-2016

Date: