

ENVIRONMENTAL IMPACT ASSESSMENT REPORT & ENVIRONMENTAL MANAGEMENT PROGRAMME REPORT FOR:

THE PROSPECTING RIGHT APPLICATION FOR A PROSPECTING RIGHT OF DIAMOND ALLUVIAL (DA), DIAMONDS GENERAL (D) & DIAMONDS IN KIMBERLITE PROSPECTING RIGHT, COMBINED WITH A WASTE LICENCE APPLICATION, NEAR POSTMASBURG ON A PORTION OF THE REMAINING EXTENT OF PLAAS 467, REGISTRATION DIVISION: HAY, NORTHERN CAPE PROVINCE.

NAME OF APPLICANT	KIMSWA MINING (PTY) LTD
PREPARED BY	Milnex 189 CC
TEL NO	(018) 011 1925
FAX NO	087 231 7021
POSTAL ADDRESS:	P.O. Box 1086, Schweizer-Reneke, 2780
PHYSICAL ADDRESS:	4 Botha Street, Schweizer-Reneke, 2780
REFERENCE NUMBER:	NC30/5/1/1/2/12286PR

DISCLAIMER

This report has been compiled by Milnex CC, using information provided by Kimswa Mining (Pty) Ltd the client as well as third parties, which information has been presumed to be correct. While Milnex CC have made every endeavour to supply accurate information, and exercised all care, skill and diligence in the drafting of this report, errors and omissions may occur. Accordingly, Milnex CC does not warrant the accuracy or completeness of the materials in this report. Milnex CC does not accept any liability for any loss or damage which may directly or indirectly result from any advice, opinion, information, representation or omission, whether negligent or otherwise, contained in this report. Milnex CC does not accept any liability for any loss or damage, whether direct, indirect or consequential, arising out of circumstances beyond the control of Milnex CC, including the use and interpretation of this report by the client, its officials or their representatives or agents. This document contains information proprietary to Milnex CC and as such should be treated as confidential unless specifically identified as a public document by law. Milnex CC owns all copyright and all other intellectual property rights in this report. The document may not be copied, reproduced in whole or in part, or used for any manner without prior written consent from Milnex CC. Copyright is specifically reserved in terms of the Copyright Act 98 of 1987 including amendments thereto. By viewing this disclaimer and by accepting this document, you acknowledge that you have read and accepted these Terms of Use and undertake to keep the information contained herein confidential and not to do any act or allow any act which is in breach of these Terms of Use.

IMPORTANT NOTICE

In terms of the Mineral and Petroleum Resources Development Act (Act 28 of 2002 as amended), the Minister must grant a prospecting or mining right if among others the mining "will not result in unacceptable pollution, ecological degradation or damage to the environment".

Unless an Environmental Authorisation can be granted following the evaluation of an Environmental Impact Assessment and an Environmental Management Programme report in terms of the National Environmental Management Act (Act 107 of 1998) (NEMA), it cannot be concluded that the said activities will not result in unacceptable pollution, ecological degradation or damage to the environment.

In terms of section 16(3)(b) of the EIA Regulations, 2014, any report submitted as part of an application must be prepared in a format that may be determined by the Competent Authority and in terms of section 17 (1) (c) the competent Authority must check whether the application has taken into account any minimum requirements applicable or instructions or guidance provided by the competent authority to the submission of applications.

It is therefore an instruction that the prescribed reports required in respect of applications for an environmental authorisation for listed activities triggered by an application for a right or permit are submitted in the exact format of, and provide all the information required in terms of, this template. Furthermore please be advised that failure to submit the information required in the format provided in this template will be regarded as a failure to meet the requirements of the Regulation and will lead to the Environmental Authorisation being refused.

It is furthermore an instruction that the Environmental Assessment Practitioner must process and interpret his/her research and analysis and use the findings thereof to compile the information required herein. (Unprocessed supporting information may be attached as appendices). The EAP must ensure that the information required is placed correctly in the relevant sections of the Report, in the order, and under the provided headings as set out below, and ensure that the report is not cluttered with un-interpreted information and that it unambiguously represents the interpretation of the applicant.

ENVIRONMENTAL IMPACT ASSESSMENT PROCESS

(1) The environmental impact assessment process must be undertaken in line with the approved plan of study for environmental impact assessment.

(2) The environmental impacts, mitigation and closure outcomes as well as the residual risks of the proposed activity must be set out in the environmental impact assessment report.

OBJECTIVE OF THE ENVIRONMENTAL IMPACT ASSESSMENT PROCESS

2. The objective of the environmental impact assessment process is to, through a consultative process-

(a) determine the policy and legislative context within which the activity is located and document how the proposed activity complies with and responds to the policy and legislative context;

(b) describe the need and desirability of the proposed activity, including the need and desirability of the activity in the context of the preferred location;

(c) identify the location of the development footprint within the preferred site based on an impact and risk assessment process inclusive of cumulative impacts and a ranking process of all the identified development footprint alternatives focusing on the geographical, physical, biological, social, economic, heritage and cultural aspects of the environment;

(d) determine the--

(i) nature, significance, consequence, extent, duration and probability of the impacts occurring to inform identified preferred alternatives; and

(ii) degree to which these impacts-

(aa) can be reversed;

(bb) may cause irreplaceable loss of resources, and

(cc) can be avoided, managed or mitigated;

(e) identify the most ideal location for the activity within the preferred site based on the lowest level of environmental sensitivity identified during the assessment;

(f) identify, assess, and rank the impacts the activity will impose on the preferred location through the life of the activity;

(g) identify suitable measures to avoid, manage or mitigate identified impacts; and

(h) identify residual risks that need to be managed and monitored.

SCOPE OF ASSESSMENT AND CONTENT OF ENVIRONMENTAL IMPACT ASSESSMENT

REPORTS

- 3. Contact Person and correspondence address
 - **A.** Details of:
 - i) The EAP who prepared the report
 - ii) Expertise of the EAP

Name of Practitioner	Qualifications	Contact details
Ms. Percy Sehaole Pr.Sci.Nat	Master's Degree in	Tel No.: (018) 011 1925
	Environmental Science (refer	Fax No. : (053) 963 2009
	to Appendix 1)	e-mail address: <u>percy@milnex-sa.co.za</u>
Danie Labuschagne	Master's Degree in	Tel No.: (018) 011 1925
	Environmental Management	Fax No. : (053) 963 2009
	and Geography (refer to	e-mail address: <u>danie@milnex-sa.co.za</u>
	Appendix 1)	
Lizanne Esterhuizen	Honours Degree in	Tel No.: (018) 011 1925
	Environmental Science (refer	Fax No. : (053) 963 2009
	to Appendix 1)	e-mail address: <u>lizanne@milnex-sa.co.za</u>

Summary of the EAP's past experience. (Attach the EAP's curriculum vitae as Appendix 2)

Milnex CC was contracted by **Kimswa Mining (Pty) Ltd** as the independent environmental consultant to undertake the Scoping and EIA process for a Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province.

Milnex CC is a specialist environmental consultancy with extensive experience in the mining industry which provides a holistic environmental management service, including environmental assessment and planning to ensure compliance with relevant environmental legislation. Milnex CC benefits from the pooled resources, diverse skills and experience in the environmental and mining field held by its team that has been actively involved in undertaking environmental studies for a wide variety of mining related projects throughout South Africa. The Milnex CC team has considerable experience in environmental impact assessment and environmental management, especially in the mining industry.

Danie Labuschagne, Percy Sehaole & Lizanne Esterhuizen have experience consulting in the environmental field. Their key focus is on environmental assessment, advice and management and ensuring compliance to legislation and guidelines. They are currently involved in undertaking EIAs for several projects across the country (refer to **Appendix 2** for CV)

B. DESCRIPTION OF THE PROPERTY.

Farm Name:	A portion of the remaining extent of farm 467
Application area (Ha)	734.4887 hectares
Magisterial district:	Siyanda District Municipality.
Distance and direction	The property is located approximately 31km East of Postmasburg in the
from nearest town	Northern Cape Province.
21 digit Surveyor	C031000000046700000
General Code for each	
farm portion	
Minerals applied for	Diamonds Alluvial (DA)
	Diamonds General (D)
	Diamonds in Kimberlite

iii. Farms Co-ordinates:

Farms		Longitude	Latitude
	0	23° 24' 7,640"" E	28° 20' 18,770"" S
	1	23° 24' 29,285"" E	28° 20' 29,469"" S
	2	23° 24' 52,622"" E	28° 20' 40,672"" S
A portion of the remaining extent of farm 467	3	23° 24' 56,273"" E	28° 20' 42,587"" S
	4	23° 24' 56,978"" E	28° 20' 42,836"" S
	5	23° 24' 56,273"" E	28° 20' 43,948"" S
	6	23° 24' 58,717"" E	28° 20' 45,158"" S
	7	23° 24' 59,430"" E	28° 20' 44,038"" S
	8	23° 25' 55,569"" E	28° 21' 11,783"" S
	9	23° 25' 19,775"" E	28° 22' 7,452"" S
	10	23° 24' 16,371"" E	28° 21' 49,255"" S
	11	23° 23' 35,825"" E	28° 21' 37,609"" S

C. LOCALITY MAP

(show nearest town, scale not smaller than 1:250000 attached as **Appendix 3**).

A Locality map is attached in **Appendix 3** and on figure 1 below.




Figure 1: Locality Map

Refer to Site Plan included within Appendix 4.




Figure 2: Site Plan

D. DESCRIPTION OF THE SCOPE OF THE PROPOSED OVERALL ACTIVITY.

i) LISTED AND SPECIFIED ACTIVITIES

Description of the overall activity. (Indicate Mining Right, Mining Permit, Prospecting right, Bulk Sampling, Production Right, Exploration Right, Reconnaissance permit, Technical co-operation permit, Additional listed activity)

- 1. **Listing Notice GNR 325, Activity 15:**"The clearance of an area of 20 hectares or more, of indigenous vegetation."
- 2. Listing Notice GNR 325, Activity 19: "The removal and disposal of minerals contemplated in terms of section 20 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002), including—
- (a) associated infrastructure, structures and earthworks, directly related to prospecting of a mineral resource [,] ; or
- (b) [including activities for which an exemption has been issued in terms of section 106 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)] the primary processing of a mineral resource including winning, extraction, classifying, concentrating, crushing, screening or washing;
- **3. Listing Notice GNR 327, Activity 20:** "Any activity including the operation of that activity which requires a prospecting right in terms of section 16 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002), including—
- (a) associated infrastructure, structures and earthworks, directly related to prospecting of a mineral resource[,]; or [including activities for which an exemption has been issued in terms of section 106 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)]
- (b) the primary processing of a mineral resource including winning, extraction, classifying, concentrating, crushing, screening or washing; – Prospecting right with bulk samples for the mining of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite including associated infrastructure, structure and earthworks.

NEM:WA 59 of 2008

Residue stockpiles or residue deposits

Category A: (15) The establishment or reclamation of a residue stockpile or residue deposit resulting from activities which require a prospecting right or mining permit, in terms of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002).

NAME OF ACTIVITY	Aerial extent of the	LISTED	APPLICABLE	WASTE
(Der Den gesensetting deill eite eite eenen aktetien fasilite	Activity	ACTIVITY	LISTING	MANAGEMENT
(E.g. For prospecting - drill site, site camp, ablution facility, accommodation, equipment storage, sample storage, site office, access route	Ha or m²		NOTICE	AUTHORISATION
etcetc				
E.g. for mining ,- excavations, blasting, stockpiles, discard dumps or dams,		(Mark with an	(GNR 324,	(Indicate whether an
Loading, hauling and transport, Water supply dams and boreholes,		X where	GNR 325 or	authorisation is
accommodation, offices, ablution, stores, workshops, processing plant, storm		applicable or	GNR 326)	required in terms of
water control, berms, roads, pipelines, power lines, conveyors, etcetc.)		affected).		the Waste Management Act) (Mark with an X)
Prospecting:	734.4887 Ha Total			-
BULK SAMPLING:	hectares to be disturbed			
734.4887 Ha – 3m x 2m x 4m (100 pits),				
30m x 20m x 2.5m (26 trenches)				
Listing Notice GNR 325, Activity 19:				
"The removal and disposal of minerals contemplated in terms of section 20 of			Listing Notice	
the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28		Х	GNR 325,	
of 2002), including—			Activity 19:	
(a) associated infrastructure, structures and earthworks, directly related to prospecting of a mineral resource [,]; or			notivity 15.	
(b) [including activities for which an exemption has been issued in terms of				
section 106 of the Mineral and Petroleum Resources Development Act,				
2002 (Act No. 28 of 2002)] the primary processing of a mineral resource				
including winning, extraction, classifying, concentrating, crushing,				
screening or washing				
Clearance of indigenous vegetation:	734.4887 Ha Total			-
BULK SAMPLING:	hectares to be disturbed		Listing Notice	
734.4887 Ha – 3m x 2m x 4m (100 pits),	Concurrent backfilling	х	GNR 325,	
30m x 20m x 2.5m (26 trenches)	will take place in order		Activity 15	
	to rehabilitate.		Activity 15	
Listing Notice GNR 325, Activity 15:				

"The clearance of an area of 20 hectares or more, of indigenous vegetation." -					
Random indigenous vegetation clearance of over a 734.4887 hectares area.					
Prospecting Right:	734.4887 Ha	Total			
BULK SAMPLING:	hectares to be dist	urbed			
734.4887 Ha – 3m x 2m x 4m (100 pits),					
30m x 20m x 2.5m (26 trenches)					
1 x 16 feet washing pan with 102 960 tons to be washed, conveyors, screens, etc.				Listing Notice	
Listing Notice GNR 325, Activity 20: "Any activity including the operation			Х	Listing Notice GNR 325,	
of that activity which requires a prospecting right in terms of section 16 of			Λ	Activity 20:	
the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of				Activity 20.	
2002), including—					
(a) associated infrastructure, structures and earthworks, directly related to					
prospecting of a mineral resource; or [including activities for which an					
exemption has been issued in terms of section 106 of the Mineral and					
Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)]					
(b) the primary processing of a petroleum resource including winning,					
extraction, classifying, concentrating or water removal					
Residue stockpiles or residue deposits: The establishment or reclamation				NEM:WA 59 of	
of a residue stockpile or residue deposit resulting from activities which				2008	
require a prospecting right or mining permit, in terms of the Mineral and					
Petroleum Resources Development Act, 2002 (Act No. 28 of 2002).				Category A:	
				(15)	

ii) <u>DESCRIPTION OF THE ASSOCIATED STRUCTURES AND INFRASTRUCTURE RELATED TO</u> THE DEVELOPMENT

(Describe Methodology or technology to be employed, and for a linear activity, a description of the route of the activity

Kimswa Mining (Pty) Ltd has embarked on a process for applying for a prospecting right for the prospecting of Diamonds (Alluvial, General & in Kimberlite) near Postmasburg on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province is preferred due to the sites mineral resources. **Kimswa Mining (Pty) Ltd** requires a prospecting right in terms of NEMA and the Mineral and Petroleum Resources Development Act to mine diamonds alluvial within the Kgatelopele Local Municipality, Northern Cape Province (refer to a locality map attached in **Appendix 3**).

DESCRIPTION OF PLANNED NON-INVASIVE ACTIVITIES:

(These activities do not disturb the land where prospecting will take place e.g. aerial photography, desktop studies, aeromagnetic surveys, etc)

PHASE 1: Site Visit (Month 0-2)

A trial pit / test pit or inspection pit investigation is a highly effective way of obtaining data on the sub surface soil and rock conditions which underlie a prospecting sight. It allows for the various soils and rock types to be locked, the soil to be sampled and a preliminary assessment to be made.

Pits shall be dug, locked, sampled and backfilled.

To dig the pits, the applicant shall make use of the systems of Dr Deon Tobias Vermaakt, the appointed project geologist.

The applicant shall at the end of the pitting process have locked the pits with the following information:

- A description of the soil and rock types from ground level to the base of the pits;
- Record of rock head depth and refusal depth, a list of where the samples will be taken, a record of where ground water seepage will be recorded;
- A general note of the geology and conditions in the vicinity of the test pits
- Pitting will be done within the period of 24 months once the prospecting right has been granted.

It is planned that **100 pits** will be dug (it may be less depending on the results) at an extent of **3m (length) x 2m (breath) x 4m (depth).**

- (100 pits / 24 months) x 12 months = 49.99 pits dug per year
- Total area to be disturbed per year = 49.99 pits x (3 m x 2 m) / 10 000 = 0.0299 Ha disturbed per year
- Total area disturbed for 24 months = 100 pits x (3 m x 2 m) / 10 000 = 0.06 Ha disturbed for 24 months

Phase 2: Trenches

The plant/ bulk sampling technique shall be that of a typical South African alluvial diamond mining operation. The method is a strip mining process with oversize material and tailings

recovered from the plant will be used as backfill material prior to final rehabilitation. Gravels are excavated, loaded and transported to the treatment facility using dump trucks.

The bulk sampling operation will be conducted using a fleet of conventional open pit mining equipment compromising of dump trucks supported by appropriate excavators and front-end-loaders. All equipment is planned to be diesel driven.

Before excavation commences vegetation shall be cleared from the proposed bulk sampling block. These shall be done as per environmental regulations. Top soil will then be removed and stored separately for later used for rehabilitation.

The bulk samples will be made in the form of box cuts whereby the dimensions of these individual box cuts on average are to be **30m wide x 20m long x 5m deep**.

Gravel will be removed by excavators and will be loaded directly into dump trucks. Ore will be hauled to the screening plant. The material will be screened where after the screened material will be moved to the processing plant where the gravel will be processed. Concentrate will be moved to the sorting plant were the concentrate will be sorted. It is estimated that the bulk sampling shall take approximately **24 months consisting of about 26 trenches** to be excavated.

- Total area to be disturbed for 24 months = 26 trenches x (30 m x 20 m) / 10 000 = 1.56 Ha disturbed per 24 months
- 0.78 Ha disturbed per year

Rehabilitation:

Since 100 pits & 26 Trenches are anticipated to be made over the period of 48 Months, concurrent rehabilitation need to take place. It should be noted that 0.78ha would be disturbed at any given time.

Phase 3: Consolidation and interpretation of results data

The prospecting activities will be conducted to determine an inferred diamond resource and an indicated diamond resource. An inferred diamond resource has a lower level of confidence then that applying to an indicated diamond resource. The inferred resource indication shall be where the geological and or grade continuity could not be confidently interpreted. It cannot be assumed that an inferred resource will necessarily be upgraded to an indicated resource. Such a resource is normally also not sufficient to enable an evaluation of economic viability.

To obtain an indicated resource the confidence level of information obtained from the prospecting will have to be sufficient for the information to be applied to mine design, mine planning to enable an evaluation of economic viability.

The project geologist, Dr Deon Tobias Vermaakt, shall monitor the program and consolidate and process the data and amend the program depending on the results received after each phase of prospecting. The DMR shall be updated of any amendments made. This shall be a continuous process throughout the prospecting work program.

Each physical phase of prospecting shall be followed by desktop studies involving interpretation and modeling of all data gathered. These studies will determine the manner in which the work programme is to be proceeded with in terms of the activity, quantity, resources, expenditure and duration. A GIS data base will be constructed capturing all the exploration data. All data shall be consolidated and processed to determine the diamond bearing resource on the property.

Water uses:

Water uses under section 21 a-k of the NWA may be triggered, thus a Water Use Licence Application (WULA) will needed in cases there will be encroachment on any watercourses. When needed WULA will be lodged with the department of Water & Sanitation (DWS).

Table 1: Water Use Pan Size specifications for Alluvial Diamond Mining (DWS NC & FS, 2001).

Pan size	Water/hour (m ³)	Water/day(m ³)	Gravel/hour (tons)	Gravel/day (ton)
16	17	170	60	600

Since 1 x 16 feet washing pans will be used, the amount of water for the pans will be 17 000 L/hour from which 30% is re-used.

<u>Ablution</u>

Chemical toilets shall be used, no french drains and pits shall be permitted.

Storage of dangerous goods

During the prospecting activities, limited quantities of diesel and fuel, oil and lubricants will be stored on site. These goods should be placed in a bunded area one and a half times the volume of the total amount of goods to be stored.

Prospecting activities and phases

Please find the Prospecting Work Programme attached as **Appendix 8**.

B. POLICY AND LEGISLATIVE CONTEXT

APPLICABLE LEGISLATION AND GUIDELINES USED TO COMPILE THE REPORT (a description of the policy and legislative context within which the development is proposed including an identification of all legislation, policies, plans, guidelines, spatial tools, municipal development planning frameworks and instruments that are applicable to this activity and are to be considered in the assessment process);	REFERENCE WHERE APPLIED
The Constitution of South Africa (Act No. 108 of 1996)	-
The National Environmental Management Act (Act No. 107 of 1998)	S24(1) of NEMA S28(1) of NEMA
The National Water Act (Act No. 36 of 1998)	S21 (a)(b) of NWA
The National Water Act (Act No. 36 of 1998) GN704 – Regulation on use of water for mining and related activities aimed at the protection of water resources.	
Management: Air Quality Act (Act No. 39 of 2004)	S21
The National Heritage Resources Act (Act No. 25 of 1999)	-
Conservation of Agricultural Resources Act (Act No. 85 of 1983)	-
Mineral and Petroleum Resources Development Act (Act No. 28 of 2002)	-
National Infrastructure Plan	-
National Forests Acts, Act 84 of 1998	Chap 3 (Part 1) 1998 S12(1) S15(1)
National Veld & Forest Fires Act (Act 101 of 1998)	
Mine, Health and Safety Act 29 of 1996	
National Environmental Management: Waste Act 59 of 2008	
National Environmental Management: Biodiversity Act 10 of 2004	
ZF Mgcawu District Municipality Integrated Development Plan (IDP)	-
Kgatelopele Local Municipality Integrated Development Plan (IDP)	-
Tsantsabane Local Municipality Integrated Development Plan (IDP)	

TABLE 4: POLICY AND LEGISLATIVE CONTEXT

Legislation/Policy	Description
The Convention of Biological Diversity (Rio de Janeiro, 1992).	The purpose of the Convention on Biological Diversity is to conserve the variability among living organisms, at all levels (including diversity between species, within species and of ecosystems). Primary objectives include (i) conserving biological diversity, (ii) using biological diversity in a sustainable manner and (iii) sharing the benefits of biological diversity fairly and equitably.
South African Constitution 108 of 1996	The Constitution is the supreme law of the land and includes the Bill of rights which is the cornerstone of democracy in South Africa and enshrines the rights of people in the country. It includes the right to an environment which is not harmful to human health or well-being and to have the environment protected for the benefit of present and future generations through reasonable legislative and other measures.
Strategic Framework for Sustainable Development in South Africa	The development of a broad framework for sustainable development was initiated to provide an overarching and guiding National Sustainable Development Strategy. The Draft Strategic Framework for Sustainable Development (SFSD) in South Africa (September 2006) is a goal orientated policy framework aimed at meeting the Millennium Development Goals. Biodiversity has been identified as one of the key crosscutting trends in the SFSD. The lack of sustainable practices in managing natural resources, climate change effects, loss of habitat and poor land management practices were raised as the main threats to biodiversity.
National Environmental Management Act 107 of 1998	This is a fundamentally important piece of legislation and effectively promotes sustainable development and entrenches principles such as the 'precautionary approach', 'polluter pays' principle, and requires responsibility for impacts to be taken throughout the life cycle of a project NEMA provides the legislative

	backing (Including Impact Assessment Regulations) for regulating development and ensuring that a risk- averse and cautious approach is taken when making decisions about activities.
Environmental Impact Assessment (EIA) regulations	New regulations have been promulgated in terms of Chapter 5 of NEMA and were published on 08 December 2014 in Government Notice No. R. 985. Development and land use activities which require Environmental Authorisation in terms of the NEMA EIA Regulations, 2014, are in Listing Notice 3 (GG No. R.983, LN3) identified via geographic areas with the intention being that activities only require Environmental Authorisation when located within designated sensitive areas. These sensitive/geographic areas were identified and published for each of the nine (9) Provinces.
National Environmental Management: Biodiversity Act No 10 of 2004	The Biodiversity Act provides listing threatened or protected ecosystems, in one of four categories: Critically Endangered (CR), Endangered (EN), Vulnerable (VU) or Protected (Government Gazette, 2011). The main purpose of listing threatened ecosystems is to reduce the rate of ecosystem and species extinction and includes the prevention of further degradation and loss of structure, function and composition of threatened ecosystems.
Conservation of Agricultural Resources Act 43 of 1967	The intention of this Act is to control the over-utilization of South Africa's natural agricultural resources, and to promote the conservation of soil and water resources and natural vegetation. The CARA has categorised a large number of invasive plants together with associated obligations of the land owner, including the requirement to remove categorised invasive plants and taking measures to prevent further spread of alien plants.
National Forest Act 84 of 1998	The protection, sustainable management and use of forests and trees within South Africa are provided for under the National Forests Act (Act 84 of 1998). Prohibition on destruction of trees in natural forests

	(1) No person may -
	(a) cut, disturb, damage or destroy any indigenous tree in a natural forest; or
	(b) possess, collect, remove, transport, export, purchase, sell, donate or in any other manner acquire or dispose of any tree, or any forest product derived from a tree contemplated in paragraph (a), except in terms of-
	(i) a licence issued under subsection (4) or section 23; or
	(ii) an exemption from the provisions of this subsection published by the Minister in the <i>Gazette</i> on the advice of the Council.
National Environmental Management: Protected Areas Act 57 of 2003	This Act provides for the protection and conservation of ecologically viable areas representative of South Africa's biological diversity and its natural landscapes and seascapes. It also seeks to provide for the sustainable utilization of protected areas and to promote participation of local communities in the management of protected areas.
Mine, Health and Safety Act 29 of 1996	The Mine Health and Safety Inspectorate was established in terms of the Mine Health and Safety Act, 1996 (Act No. 29 of 1996), as amended, for the purpose of executing the statutory mandate of the Department of Mineral Resources to safeguard the health and safety of mine employees and communities affected by mining operations.
National Environmental Management: Waste Act 59 of 2008	The Act reform the law regulating waste management in order to protect health and the environment by providing reasonable measures for the prevention of pollution and ecological degradation and for securing ecologically sustainable development; to provide for institutional arrangements and planning matters; to provide for national norms and standards for regulating the management of waste by all spheres of

	government; to provide for specific waste management measures; to provide for the licensing and control of waste management activities; to provide for the remediation of contaminated land; to provide for the national waste information system; to provide for compliance and enforcement; and to provide for matters connected
National Environmental Management: Biodiversity Act 10 of 2004	therewith. This Act provides for the management and conservation of South Africa's biodiversity within the framework of the National Environmental Management Act, 1998; the protection of species and ecosystems that warrant national protection; the sustainable use of indigenous biological resources; the fair and equitable sharing of benefits arising from bioprospecting involving indigenous biological resources; the establishment and functions of a South African National Biodiversity Institute; and for matters connected therewith
National Environmental Management: Waste Act, 2008 (Act No. 59 of 2008)	Section 24S of NEMA deals with the management of residue stockpiles and residue deposits and provides that Residue stockpiles and residue deposits must be deposited and managed in accordance with the provisions of the National Environmental Management: Waste Act, 2008 (Act No. 59 of 2008), on any site demarcated for that purpose in the environmental management plan or environmental management programme in question
	The management of residue stockpiles and residue deposits must be done in accordance with any conditions set out and any identified measures in the environmental authorisation issued in terms of NEMA, an environmental management programme and a waste management licence issued in terms of NEMA (Regulation 3(2)).
National Environmental Management: Waste Act, 2008 (Act No. 59 Of 2008) Regulations regarding the Planning & Management of	The purpose of these Regulations is to regulate the planning and management of residue stockpiles and residue deposits from a prospecting, mining, exploration or production operation.

Residue Stockpiles & Residue Deposits from a	
Prospecting, Mining, Exploration or Production	
Operation	
Mine Residue Deposits (MRD's) are legislated in	In order to ensure that a waste management plan covers all aspects applicable to the management of mine
terms of the Regulations 527 of the Minerals	residue, an example of a checklist has been generated which the authorities can use to evaluate Mine Residue
and Petroleum Resources Development Act, Act	Waste Management Plans
No. 28 of 2002 (MPRDA).	

E. NEED AND DESIRABILITY OF THE PROPOSED ACTIVITIES.

(Motivate the need and desirability of the proposed development including the need and desirability of the activity in the context of the preferred location).

Mining has played a vital role in the economy of South Africa for over 100 years. In 2015 the mining industry contributed R286 billion towards South African Gross Domestic Product (GDP) representing 7.1% of overall GDP. Mining is a significant contributor to employment in the nation, with 457 698 individuals directly employed by the sector in 2015. This represents just over 3% of all employed nationally. Diamond mining has 17 885 direct employees.

Diamonds, arguably the ultimate luxury mineral, comprise an intricate lattice of carbon atoms, a crystalline structure that makes them harder than any other form in nature. This characteristic makes diamonds not only popular in jewellery, but also desirable in high-tech cutting, grinding and polishing tools (Chamber of Mines, South Africa, 12:2016).

According to the Chamber of Mines the country's diamond sector is far from reaching the end of its life even though diamond mining has been taking place in South Africa for almost a century and a half. The primary sources of all of South Africa's diamonds are kimberlites in ancient, vertically dipping volcanic pipes most of which were located in the vicinity of the city of Kimberley and which were initially amenable to open-cast.

<u>Economic growth</u> - South Africa's total reserves remain some of the world's most valuable, with an estimated worth of R20.3-trillion. Overall, the country is estimated to have the world's fifth-largest mining sector in terms of GDP value.

It has the world's largest reserves of manganese and platinum group metals (PGMs), according to the <u>US Geological Survey</u>, and among the largest reserves of gold, diamonds, chromite ore and vanadium.

With South Africa's economy built on gold and diamond mining, the sector is an important foreign exchange earner, with gold accounting for more than one-third of exports. In 2009, the country's diamond industry was the fourth largest in the world.

Mining is a cornerstone of the economy, making a significant contribution to economic activity, job creation and foreign exchange earnings. Mining and its related industries are critical to South Africa's socio-economic development.

F. Motivation for the preferred development footprint within the approved site including a full description of the process followed to reach the proposed development footprint within the approved site.

NB!! – This section is about the determination of the specific site layout and the location of infrastructure and activities on site, having taken into consideration the issues raised by interested and affected parties, and the consideration of alternatives to the initially proposed site layout.

Location of the site

The location of the site is preferred due to the presence of shallow diamond. Access will be obtained from the D3381 gravel road off the R385

Preferred activity

The prospecting of Diamonds (Alluvial, General & in Kimberlite) is the optimum preferred activity for the site. The shallow diamond deposits makes the site ideal for alluvial diamond

mining. The mine will provide significantly more job opportunities than what is providing currently.

The site is currently used for livestock grazing.

G. A FULL DESCRIPTION OF THE PROCESS FOLLOWED TO REACH THE PROPOSED DEVELOPMENT FOOTPRINT WITHIN THE APPROVED SITE, INCLUDING:

i. details of the development footprint alternatives considered;


• <u>Consideration of alternatives</u>

The DEAT 2006 guidelines on 'assessment of alternatives and impacts' proposes the consideration of four types of alternatives namely, the no-go, site, activity, and technology alternatives. It is however, important to note that the regulation and guidelines specifically state that only 'feasible' and 'reasonable' alternatives should be explored. It also recognizes that the consideration of alternatives is an iterative process of feedback between the developer, the EAP and Interested and affected parties, which in some instances culminates in a single preferred project proposal. The following sections explore each type of alternative in relation to the proposed activity.

• <u>Location alternatives</u>

This alternative asks the question, if there is not, from an environmental perspective, a more suitable location for the proposed activity. It is expected that the diamonds (Alluvial, General & in Kimberlite) been deposited on this farm and therefore the applicant would like to commence with their prospecting activities.

Land capability is the combination of soil suitability and climate factors. The site and surrounds has a land capability classification, on the 8 category scale, of Class 5 & Class 8 (refer to Land capability map attached as Appendix 5.



Refer to Land capability map attached as Appendix 5 & figure 3 below.

Figure 3: Land capability

• <u>Activity alternatives</u>

The environmental impact assessment process also needs to consider if the development of a diamonds (Alluvial, General & in Kimberlite) mine would be the most appropriate land use for the particular site.

Prospecting of other commodities – From the surface and desktop assessment there are no indications that there are other commodities to be mined on the site, except diamonds (Alluvial, General & in Kimberlite).

If the proposed prospecting right is not granted the proposed area will still be used for livestock grazing.

• Design and layout alternatives

Design alternatives were considered throughout the planning and design phase (i.e. where is the diamond bearing gravel located?). In this regard discussions on the design were held between the EAP and the developer. The layout follows the limitations of the site and aspects such as, roads, site offices and workshop area as well as fencing- refer **Appendix 3**.

• **Operational alternatives**

Due to the nature of the prospecting activities, no permanent services in terms of water supply, electricity, or sewerage services are required.

The activities will commence with a site investigation and desktop studies, which will comprise of non-invasive techniques. This manner of survey will ensure that the applicant can clearly delineate areas which are suitable for further investigation and no unnecessary surface disturbance will be undertaken.

Based on the outcome of the desktop studies and site investigation, pits will be dug by an excavator for the purpose of soil sampling. If gravel is found, the applicant will determine the composition and quality of the gravel.

The applicant will proceed with this way of prospecting by means of the open cast/trenching method, simultaneously or after pitting depending on the information obtained from the earlier work done. The trenches will be dug to remove and wash the gravel. It will be washed by a 10-18 feet washing pan to determine diamond proceeds per 100 tons of gravel.

All data will be consolidated and processed to determine the diamond bearing resources on the property. This will be a continuous process throughout the prospecting work programme.

No feasible alternatives to the pitting and trenching method currently exists. Impacts associated with the prospecting operations will be managed through the implementation of a management plan, developed as part of the application for authorisation.

• <u>No-go alternative</u>

This alternative considers the option of 'do nothing' and maintaining the status quo. The description provided in section H of this report could be considered the baseline conditions (status quo) to persist should the no-go alternative be preferred. The site is currently zoned for agricultural land uses. Should the proposed activity not proceed, the site will remain unchanged and will continue to be used for low density cattle and game grazing.

Technology alternatives

In terms of the technologies proposed, these have been chosen based on the long term success of their prospecting history. The prospecting activities proposed in the Prospecting Works Programme (**Appendix 9**) is dependent on the preceding phase as previously discussed,

therefore no alternatives are indicated, but rather a phased approach of trusted prospecting techniques.

The preferred technology for the proposed mining activity, will be to remove the diamond bearing gravel with an excavator, depositing it in the 10 - 18 feet rotary pan(s) to be washed and sorted. Please find the Prospecting Work Programme attached as **Appendix 9**.

Pros & Cons of the alternative **Dense Media Separation (DMS)**

Advantages	Disadvantages
DMS plants is used mostly for kimberlite	10 times more expensive than Rotary pan
deposits	
	Water consumption is high
	Operating costs are expensive

In a Dense Media Separation (DMS) plant, powdered ferrosilicon (an alloy of iron and silicone) is suspended in water to form a fluid near the density of diamond (3.52 g/cm3), to which the diamond bearing material is added to begin the separation process of the heavier minerals from the lighter material. Additional separation of the denser material occurs by centrifuge in "cyclones" that swirl the mixture at low and high speeds, forcing the diamonds and other dense minerals to the walls and then out the bottom of the cyclone. Waste water rises at the center of the cyclones and is sucked out and screened to remove waste particles. The DMS process results in a concentrate that generally weighs less than one percent of the original material fed into the plant at the beginning of the process.

Pros & Cons of the alternative **Rotary Pan Plants**

Advantages	Disadvantages
More cost effective	The industry perception that Rotary Pan Plants
	yield poorer diamond recoveries
Readily available	
Generate more work opportunities	
Consume less water	
Rotary Pan Plants are most often used	
when mining alluvial deposits	

In a Rotary Pan plant, crushed ore, when mining kimberlite, or alluvial gravel and soil is mixed with water to create a liquid slurry called "puddle" which has a density in the 1.3 to 1.5 g/cm3 range. The mix is stirred in the pan by angled rotating "teeth". The heavier minerals, or "concentrate", settle to the bottom and are pushed toward an extraction point, while lighter waste remains suspended and overflows out of the centre of the pan as a separate stream of material. The concentrate, representing just a small percentage of the original kimberlite ore or alluvial gravels, is drawn off for final recovery of the diamonds.

Both methods are in actual fact used for bulk material reduction and require a further process for the final diamond recovery however, for this project the Rotary Pan will be used.

When it comes to dust suppression two main methods were considered, namely molasses stillage and the wetting (water) of roads. The table below provides a short summary of the advantages and disadvantages of each.

Water	Molasses stillage
More cost effective	Much more expensive
Could lead to the depleting of water resources	Requires less water
No damage (only if used excessively)	The product may be toxic to aquatic organisms. (As this product could have physical effects on aquatic organisms for e.g. floating, osmotic damage)

No harm to humans or animals(Only a high quantity will have harm to	Not Hazardous or toxic. Could cause irritation to eyes, skin or when
humans or animals) Non-flammable	ingested and inhaled. Non-flammable
Eye-wash fountains not needed	Eye-wash fountains in the work place are strongly recommended
	Working procedures should be designed to minimize worker exposure to this product.
Basic storing methods	Storing methods are a bit more complicated. Should be stored in a plastic, plastic lined or stainless steel, tight closed containers between 5 and 40 degrees Centigrade.

Considering the above mentioned information, water will be used for dust suppression purposes.

ii. Details of the Public Participation Process Followed

Describe the process undertaken to consult interested and affected parties including public meetings and one on one consultation. NB the affected parties must be specifically consulted regardless of whether or not they attended public meetings. (Information to be provided to affected parties must include sufficient detail of the intended operation to enable them to assess what impact the activities will have on them or on the use of their land.

Advertisement and Notices

Newspaper advertisement

An advertisement was placed in English in the local newspaper (**Die Ghaap**) on **18 January 2019** (see **Appendix 6**) notifying the public of the EIA process and requesting Interested and Affected Parties (I&APs) to register with, and submit their comments to Milnex 189 CC. I&APs were given the opportunity to raise comments within 30 days of the advertisement.

Site notices

Site notices were placed (as anticipated on the coordinates below) on site in English to inform surrounding communities and immediately adjacent landowners of the proposed development. I&APs will be given the opportunity to raise comments. Photographic evidence of the site notices will be included in **Appendix 6**. Below are the coordinates where the site notices will placed.



Figure 4: Site notice co-ordinates

Direct notification and circulation of Scoping Report to identified I&APs

Identified I&APs, including key stakeholders representing various sectors, are directly informed of the proposed development and the availability of the Scoping Report via registered post on **7 December 2018** and were requested to submit comments by **29 January 2019**. A copy of the report is also available at the Milnex offices in Schweizer-Reneke, 4 Botha Street, Schweizer-Reneke and Potchefstroom (Waterberry Street, Waterberry Square, 1st floor, Office 5B, Potchefstroom), between 7:30AM and 5PM, Monday to Friday. For a complete list of stakeholder details and for proof of registered post see **Appendix 6**. The consultees included:

- Northern Cape Department of Environmental Affairs and Nature Conservation (DENC)
- The Department of Water and Sanitation
- The Department of Mineral Resources
- NC Department of Agriculture, Forestry and Fisheries (DAFF)
- Northern Cape Department of Agriculture, Land Reform & Rural Development
- Department of Roads and Public Works (DRPW)
- Northern Cape Department of Rural Development & Land Reform,
- ZF Mgcawu District Municipality
- WESSA
- Kgatelopele Local Municipality: Municipal Manager
- Kgatelopele Local Municipality: Ward 5 Councillor

Direct notification of surrounding land owners and occupiers

Written notices and the availability of the Scoping Report are also provided to all surrounding land owners and occupiers on **7 December 2018.** The surrounding land owners were given the opportunity to raise comments by **29 January 2019**. For a list of surrounding land owners see **Appendix 6**.

2. Consultation

The Public Meeting was scheduled for **22 January 2019 at 13:00pm-14:00pm** 8.5km on the D3381 road near Lime Acres approximately 25km from Postmasburg alongside the road, at the coordinates named below. The coordinates and directions (figure1) of the public meeting follows below.

Coordinates

28°20'24.32"S 23°24'5.34"E

Directions to Public Meeting

• In Postmasburg head towards Metsimatala on the R385

- Drive for 25km on the R385 and turn right onto the D3381 road heading towards Lime Acres

• Drive on the D3381 for approximately 8.5km until where Milnex personnel will be waiting



Figure 5: Directions to the public meeting

The public meeting is an opportunity to share information regarding the proposed development and provide I&APs with an opportunity to raise any issues and provide comments. The following key stakeholders and surrounding land owners were also directly informed of the public meeting via registered post **7 December 2018**:

Stakeholders	Land owners	Surrounding Land owner
Northern Cape Department of Environmental Affairs and Nature Conservation (DENC)	Jovicube Pty Ltd Mr Chris Strauss	Transnet Ltd
DMR Department of Mineral Resources, Northern Cape		Department of Rural Development And Land Reform
The Department of Water & Sanitation (DWS)		PPC Lime Ltd
NC Department of Agriculture, Forestry and Fisheries (DAFF)		Johannes Jacobus Lambrechts
Northern Cape Department Of Agriculture, Land Reform & Rural Development		
Department of Public Works, Roads and Transport in NW (DPWRT)		
Northern Cape Department of Rural Development & Land Reform,		
The Wildlife and Environment Society of South Africa (WESSA)		
ZF Mgcawu District Municipality		
The Municipal Manager at the Kgatelopele Local Municipality		

Table 5: List of Stakeholders, Land owners, & surrounding land owners

Stakeholders	Land owners	Surrounding Land owner
The Local Councilor at the Kgatelopele		
Local Municipality		

Public meeting:

NB: The interested and affected parties were given an opportunity to register via site notice, press advert and letters.

A meeting was held on 22 January 2019 & it was attended by Mr Strauss, Mr A.J de Klerk, Mr J.J Lambrechts & Milnex representative Mr. Mandi Sibanyoni. The attendees mentioned that the property owners request an access control agreement to be set up before commencement of any activity.

The farm owners request a study to be done to calculate all the flora in the area, in order for rehabilitation to be done properly.

The attendees mentioned that the method to be used should be addressed in terms of topsoil removal and how long the topsoil will be outside until returned.

Mr Chris Strauss mentioned that there is no water in the area, the applicant should explain where water is going to come from

Direct notification and circulation of EIR & EMPr to identified I&APs

Identified I&APs, including key stakeholders representing various sectors, are directly informed of the proposed development and the availability of the EIR & EMPr via registered post on **27 March 2019** and were requested to submit comments by **29 April 2019**. A copy of the report is also available at the Milnex offices in Schweizer-Reneke, 4 Botha Street, Schweizer-Reneke and Potchefstroom (Waterberry Street, Waterberry Square, 1st floor, Office 5B, Potchefstroom), between 7:30AM and 5PM, Monday to Friday. For a complete list of stakeholder details and for proof of registered post see **Appendix 6**. The consultees included:

Issues Raised by Interested and Affected Parties

Comments received during this period are attached as comment & response report as well as populated in the table of summary of issues raised.

iii. SUMMARY OF ISSUES RAISED BY I&APS

(Complete the table summarising comments and issues raised, and reaction to those responses)

Interested and Affe	octed Parties	· •		Section and
List the names of persons consulted in this column, and Mark with an X where those who must be consulted were in fact consulted. Organisation Contact person		Issues raised	EAPs response to issues as mandated by the applicant	paragraph reference in this report where the issue and or response where incorporated
Land Owner				
Land Owner Farm RE/467 Jovicube Pty Ltd Mr Chris Strauss		No comments received yet	Emil was sent to Mr Strauss the Land owner containing Final SR on 04/02/2019 stating "Please find the attached Scoping report for perusal & commenting purposes for Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province with DMR ref: NC30/5/1/1/2/12286PR" Emil was sent to Mr Strauss the Land owner containing PWP, Final SR & a letter of consultation on 08/03/2019	
Surrounding Land Owners				
FARM RE/467 & 4/467	Transnet Ltd	No comments received yet		
FARM RE/468 & FARM 3/467	Department of Rural Development And Land Reform	No comments received yet		
FARM 4/458	PPC Lime Ltd	Letter received dated 1/01/2019 from Mr Mashudu stating "No inputs"	Email sent on 15/01/19 stating "Thank you Mashudu, received".	

		Email dated 11/04/2019 stated "Kindly add us as I&Aps in addition to PPC Sandton. Details are as per		
FARM 1/467 Johannes Jacobus Lambrechts		the attached" No comments received yet	Emil was sent to Mr Strauss the Land owner & other registered surrounding land owner containing Final SR on 04/02/2019 stating " Please find the attached Scoping report for perusal & commenting purposes for Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province with DMR ref: NC30/5/1/1/2/12286PR"	
The Municipality in which juris	sdiction the developmen	nt is located		
Kgatelopele Local Municipality	Municipal Manager: Mr Monde Alistair January	No comments received yet		
Municipal councilor of the war	d in which the site is lo	cated		
Kgatelopele Local Municipality	Ward 4 Councillor	No comments received yet		
Organs of state having jurisd	iction			
Northern Cape Department of Environmental Affairs and Nature Conservation (DENC)	Mrs. Doreen Werth	No comments received yet		
DMR Department of Mineral Resources, Northern Cape. (DMR)	Mr. Pieter Swart	 letter dated 04/03/2019 stated the application is accepted and also mentions the following: 1) In terms of section 12 (d) of the Act, you are directed to comply with the following instructions: a Notify and consult with the landowner, lawful occupier and any interested and affected party and include the result of the consultation in the environmental reports. Lodge an application in terms of National Water Act No.36 of 1998 with the Department of Water Affairs with immediate effect. 		

		BEE documents are needed by 16 April 2019		
		Letter dated 04/02/2019 acknowledged the receipt		
		of the application.		
		Acknowledgement does not grant permission to		
		commence with Prospecting activities		
The Department of Water &	Mr. Abe Abrahams	No comments received yet		
Sanitation (DWS)				
NC Department of	To whom it may	No comments received yet		
Agriculture, Forestry and	concern			
Fisheries (DAFF)				
Northern Cape Department		No comments received yet		
Of	Mr. W.J.J. de Bruyn			
Agriculture, Land Reform &				
Rural Development				
NC Department of		No comments received yet		
Agriculture, Forestry and	Mr. Harm Vorster			
Fisheries (DAFF)				
		No comments received yet		
Department of Roads and	HOD: Ms. Ruth	5		
Public Works (DRPW)	Palm			
	Mr Tshiamo Pitso			
	Land Claims	Letter dated $21/01/2019$ states that there is no land	Enquiry sent 18/01/2019 to Ms.	
Northern Cape Department	Commissioner:	claim on the database in respect of the properties.	Nqabisa Mkalipi inquiring if the	
of Rural Development & Land	Regional Offices	This includes the database for claims lodged by 31		
Reform,		December 1998; and those lodged between 1 July	properties on the application area has claims on them	
	Ms' Mkalipi	2014 and 27 July 2016.	has claims on them	
Other-				
ZF Mgcawu District	Municipal Manager:	No comments received yet		
Municipality	Mr Elias Ntoba			
WESSA (National Office)	To whom it may	No comments received yet		
	concern			
			Emil was sent to Mr Strauss the	
			Land owner & other registered	
			surrounding land owner containing	
Mr A.J de Klerk			Final SR on 04/02/2019 stating "	
			Please find the attached Scoping	
			report for perusal & commenting	
			purposes for Prospecting Right of	

Diamond Alluvial (DA), Diamonds General (D) & Diamonds in
Kimberlite combined with a Waste
Licence Application on a Portion of
the Remaining Extent of Plaas 467,
Registration Division: Hay, Northern
Cape Province with DMR ref:
NC30/5/1/1/2/12286PR"

iv. THE ENVIRONMENTAL ATTRIBUTES ASSOCIATED WITH THE SITES

Baseline Environment

The baseline environment is described with specific reference to geotechnical conditions, ecological habitat and landscape features, Soil, land capability and agricultural potential, climate and the visual landscape.

From google earth & site visit there are houses identified on site. The area is adjacent Lime Acres

Lime Acres is a mining village, and there are rich limestone deposits in the area. It is home to both PPC Lime and Petra Diamonds, was named by Eric Lowther, general manager of Northern Lime. The Finsch diamond mine is situated 2km from Lime Acres, and its employees live in the town



Figure 6: Neighbouring activities: Lime Acres

Table 6: Wind and Solar developments with an approved Environmental Authorisation or applications under consideration within 30 km of the proposed area

No	EIA Reference	Classification	Status of	Distance from proposed
	No		application	area (km)
1	12/12/20/2252/1	Solar CSP	Approved	7.2
2	12/12/20/2252/2	Solar CSP	Approved	7
3	12/12/20/1944	Solar PV	Approved	9.2
4	12/12/20/2613	Solar PV	Approved	9.2
5	12/12/20/2316	Solar CSP	Approved	3.2
6	12/12/20/1903/1	Solar PV	Approved	3.3
7	12/12/20/2675	Solar PV	Approved	9.2
8	14/12/16/3/3/2/371	Solar PV	Approved	20.1

Protected species

Dr, P.J du Preez was appointed to conduct an Ecological & Wetland Assessment Report for the proposed area. Some of his findings was extracted from the report, see blow. Please see Appendix 12 for the specialist study.

Trees / shrubs	Grasses/reeds/bulrushes	Forbs
Vachellia erioloba		
Vachellia haematoxylon		

Table 7:	Protected	species	noted	on the	e project site.
Table 7.	Induction	species	notcu		

Visual indication of and impact on terrestrial fauna (mammals)	The potential diversity of mammals within the study area is low because it is a disturbed area and most natural habitats have been transformed. There are several factors which will reduce the actual number of species present within the project site. The presence of humans and roads, the destruction of natural vegetation, noise etc., has had a major impact on the natural animal populations in the project area.
	 During the site visit the following faunal species were confirmed within the project site: Single rodent burrows (most likely Four-striped Grass Mouse (Rabdomys pumilo). Relative large burrows (likely to have been made and utilized by Aardwolf (Proteles cristatus), Porcupine (Hystrix africae-australis). and/or Aardvark - (Orycteropus afer). Smaller burrows were noted and were probably made by Ground squirrel (Geosciurus inauris), Yellow Mongoose (Cunictis penicillata) and Zorilla (Ictonyx striatus) None of these species noted within the project site are listed and or protected species.

It is noted that protected tree species under the National Forests Act No. 84 of 1998 are listed in Table 4.9. In terms of a part of section 51(1) of Act No. 84 of 1998, no person may cut, disturb, damage or destroy any protected tree or possess, collect, remove, transport, export, purchase, sell, donate or in any other manner acquire or dispose of any protected tree, except under a license granted by the Minister.

In cases where the trees will need to be cut, disturbed, damaged or destroyed or possessed, collected, removed, transported, exported, purchased, sold or donated a flora permit will be applied for.

(a) Type of environment affected by the proposed activity.

(its current geographical, physical, biological, socio- economic, and cultural character).

Geology and Soils

Griqualand Sequence

Ghaapplato (Vgl - Chert and breccia)

Classification

The structural basins in which the Transvaal and Griqualand West Sequence occur either side of the complex Vryburg arch. The lower parts of the thick successions are represented by the predominately dolomitic sediments and associated iron formations of the Ghaap group. The geology of the area is partly attributed to high stream velocities and rapid deposition. Clasts of Ventersdorp lava predominate, with significant (if variable) amounts of banded iron formation (BIF), chert, quartzite and quartz also present.

Ecological habitat and landscape features

The proposed area falls within vegetation unit SVk13 and SVk10, which is known as the Olifantshoek Plains Thornveld and Kuruman Mountain Bushveld. The Olifantshoek Plains Thornveld is part of the Eastern Kalahari Bushveld Bioregion, which is a sub-bioregion for the Savanna Biome. This Kuruman Mountain Bushveld is part of the Eastern Kalahari Bushveld which is a sub-bioregion for the Savanna Biome.

Olifantshoek Plains Thornveld

According to Mucina and Rutherford (2006:522) the Olifantshoek Plains Thornveld is distributed across the Northern Cape Province plains including most of the pediment areas of the Korannaberg, Langeberg and Asbestos Mountains as well as those of some ridges to the west of the Langeberg. From the vicinity of Sonstraal in the north, past Olifantshoek to areas north of Niekerkshoop between Volop and Griekwastad in the south. Also from Griekwastad northwards to the flats west of the Lime Acres area. Altitude 1 000–1 500 m.

Vegetation and landscape features can be described as a very wide and diverse unit on plains with usually open tree and shrub layers with, for example, *Acacia luederitzii*, *Boscia albitrunca* and *Rhus tenui-nervis* and with a usually sparse grass layer.

<u>Kuruman Mountain Bushveld</u>

According to Mucina and Rutherford (2006:520) the Kuruman Mountain Bushveld is distributed across the Northern Cape and North West Provinces. From the Asbestos Mountains southwest and northwest of Griekwastad, along the Kuruman Hills north of Danielskuil, passing west of Kuruman town and re-emerging as isolated hill, i.e. Makhubung and the hills around Pomfret in the north. This bushveld is situated on an altitude of 1100m – 1800m.

Vegetation and landscape features can be described as rolling hills with generally gentle to moderate slopes and hill pediment areas with an open shrubveld with *Lebeckia macrantha* prominent in place, with well-developed grass layers.




Figure 7: Vegetation Unit Map

Specialist study was conducted by Dr P.J du Preez for the proposed area. Some of his findings was extracted from the report, see blow. Please see **Appendix 12** for the specialist study.

FINDINGS:

Table 8: Description of the assessment of the terrestrial vegetation on project site.

Site features	Comments	
Landscape features	Some undulating rocky ridges occur on the upper parts of the project site. These areas are covered by an open savanna dominated by the Swarthaak (<i>Senegalia mellifera</i>) and Umbrella Thorn (<i>Vachellia</i> <i>tortilis</i>) and Shepherd's Tree (<i>Boscia albitrunca</i>). The landscape is more dissected and numerous seasonal drainage lines occur.	
	The deeper sandy plains between the rocky outcrops are dominated by two protected trees namely Camel Thorn (<i>Vachellia erioloba</i>) and Grey Camel Thorn (<i>Vachellia haematoxylon</i>).	
Land use of the project site		
Condition of the vegetation (pristine / degraded / totally transformed) The character of this area's vegetation is an open savanna land. The area on low-lying areas are in a transformed state due to a activities. The remaining natural veld is subjected to invast Swarthaak (Senegalia mellifera), Driedoring (Rhigozum trichot Aristida congesta, Aristida bipartita, Hyparrhenia hirta and This is a sign of extensive grazing practices.		
Protected plant species noted	On the deeper sandy drainage lines between the rocky outcrops (northern portion of farm) are numerous individuals of Camel Thorn (<i>Vachellia erioloba</i>) and Grey Camel Thorn (<i>Vachellia haematoxylon</i>).	

Visual indication of and impact on terrestrial fauna (herpetofauna)	Of the many reptilian species that have been recorded with the region none of these species are listed as Red Data species.	
	Fifteen amphibian species have been recorded within the region and of these 15 species eight species were recorded within close proximity of the project site. One near threatened species namely the Giant Bullfrog (<i>Pyxicephalus adspersus</i>) has been recorded for the quarter degree grid square (QDGS). Although this species was not found on site (not a suitable habitat), it is still likely for this species to occur near the project site as potential suitable habitat (drainage lines) is available in the vicinity of the project site.	
Visual indication of and impact on terrestrial fauna (birds)	Of the more than 320 bird species that have been recorded in the region a few species occur on the study area. Birds such as, Crowned Lapwing, Blacksmith Lapwing, Orange River Francolin, Helmeted Guineafowl, Thick-knee, Northern Black Korhaan, Cattle Egrets, Black-headed Heron, Turtle Doves, Rock Pigeons, and Hadeda and others could occur in the project site.	
Signs of pollution	No obvious signs of pollution are present on the site except along the roads and railway line	
Erosion potential	There are signs of disturbance and clearance of the vegetation. Some erosion gullies are present.	
Ecosystem function	The remaining natural vegetation provides nesting areas for avifauna and occasional shelter for terrestrial fauna. Niche habitats for fauna – providing sheltered burrows and nesting sites. Micro-climate i created by the shrubs and trees housing species sensitive to direct sunlight or frost	
Landowner concerns	 Prospecting could damage drainage lines and affecting the hydrology negatively Prospecting could damage the pans' hydrology negatively 	

Alien Invasive Plants (AIPs) confirmed during the survey

Due to the previous mining and agricultural activities disturbance of the natural vegetation occurred. Several alien species and pioneer species were noted on these disturbed areas. On the project site are the trees *Prosopis glandulosa, Tamarix ramosissima,* and forbs such as *Atriplex semibaccata, Bidens bipinnata. Chenopodium album, Chenopodium schraderianum, Datura ferox, Salsola kali, Schkuhria pinnata,* and *Tagetes minuta,* are present on heaps of disturbed soil.

Land capability and agricultural potential

• <u>Climate</u>

Postmasburg normally receives about 241mm of rain per year, with most rainfall occuring mainly during summer. The chart below (lower left) shows the average rainfall values for Postmasburg per month. It receives the lowest rainfall (0mm) in July and the highest (57mm) in March. The monthly distribution of average daily maximum temperatures (centre chart below) shows that the average midday temperatures for Postmasburg range from 17°C in June to 32°C in January. The region is the coldest during July when the mercury drops to 0°C on average during the night. Consult the chart below (lower right) for an indication of the monthly variation of average minimum daily temperatures.

Description of the socio-economic environment

<u>Socio-economic conditions</u>

Kgatelopele Local Municipality

Kgatelopele Local Municipality is situated in the 1ZF Mgcawu District Municipality. The municipality is surrounded by the following municipalities: Ga-Segonyana Local Municipality

(LM), Dikgatlong LM, Tsantsabane LM and Siyancuma LM. The administrative town of the municipality is Danielskuil. Kgatelopele Local Municipality consist of Danielskuil, Kuilsville, Tlhakalatlou, Lime Acres and the surrounding farms. The municipality's name Kgatelopele is a Setswana name which means moving forward. The municipality is situated 154 km west of Kimberley and 91 km to Kuruman.

Population

The Kgatelopele Local Municipality has a total population of 20691, 52.5% of the population being male, while 47.5% are female as per census Statistics for 2016. The population growth rate has been 3.49% between 2011 and 2016. The municipality has 6206 households, with 3.49% of households being female-headed (Stats SA, Census, 2011 and 2016). The average household size is 3.5. The majority of people residing in the municipal area are Black Africans, followed by Coloured people. The two least represented racial groups are Whites and Indian/Asians. The most commonly spoken language is Afrikaans at 58%, followed by Setswana at 33%

Employment levels

The number of those economically active is slightly greater than those not economically active, hence the dependency ratio of 50.6% which is very high. Stats SA (2011) indicates that the unemployment rate is at 22.3% while 29.1% of the total unemployed people are young people. There is need to address the challenges of those not employed particularly the youth.

The municipality has relatively high levels of basic services, partially integrated society, medical facilities in Douglas and Griekwastad, one of the biggest correctional services in the province and is the neighbour to Kimberley, the provincial and legislative capital of the province. It still has major inequalities to overcome and in common with the rest of the country, a skew and sluggish economy to transform and speed up.

<u>Economy</u>

The following economic sectors that contributed the most to the DRSMDM Gross Domestic Product (GDP):

- Community services (33.1%),
- Agriculture (17.1%)
- Finance 16.2%
- Trade (12.7%),
- Transport (9%),
- Manufacturing (4%)
- Mining (3.2%),
- Construction (3.2%)

Protected Areas

According to the data for protected areas the proposed area does not fall within a Formally Protected Area nor Threatened Ecosystem.




Figure 8: Protected Areas Map

Critical Biodiversity Area

According to the data for Critical Biodiversity Areas, the proposed area falls within Critical Biodiversity Area One, Ecological Support Area and Other Natural Areas.




Figure 9: Critical Biodiversity Areas Map.

Sensitive area for Mine

According to the Mining of Biodiversity Guidelines, biodiversity priority areas sensitive to the impacts of mining are categorized into four categories (please see the table below).

Category	Description
А	Legally protected
В	Highest biodiversity importance
С	High biodiversity importance
D	Moderate biodiversity importance

The purpose is to identify and categorize biodiversity priority areas sensitive to the impacts of mining in order to support mainstreaming of biodiversity issues in decision making in the mining sector.

According to the mine guide map, a certain area of the proposed area falls within category B. The biodiversity priority areas are as follows:

Highest biodiversity importance (B)

These areas are viewed as necessary to ensure protection of biodiversity, environmental sustainability, and human well-being. The Biodiversity priority areas is as follows:

- Critically endangered and endangered ecosystems
- Critical Biodiversity Areas (or equivalent areas) from provincial spatial biodiversity plans
- River and wetland Freshwater Ecosystem Priority Areas (FEPAs), and a 1km buffer around these FEPAs
- Ramsar Sites




Figure 10: Sensitive area for mine

Wetland Areas

Wetland is defined as land which is transitional between terrestrial and aquatic systems where the water table is usually at or near the surface, or the land is periodically covered with shallow water, and which land in normal circumstances supports or would support vegetation typically adapted to life in saturated soil (from the South African National Water Act; Act No. 36 of 1998).

The maps below depict all wetland areas on the proposed area, there are Depressions and a Seep on the proposed area and the wetland vegetation type falls within the Eastern Kalahari Bushveld Group 3 and 4.

According to the 2013 SANBI Biodiversity Series 22 a:

<u>Depression</u> is a wetland or aquatic ecosystem with closed (or near-closed) elevation contours, which increases in depth from the perimeter to a central area of greatest depth and within which water typically accumulates. Although they may at times have a river flowing into or out of them, depressions are especially characterised by their closed (or at least near-closed) contour shape, which makes them relatively easy to identify on topographic maps.

<u>Seep</u> is a wetland area located on gently to steeply sloping land and dominated by colluvial (i.e. gravity-driven), unidirectional movement of water and material down-slope. Seeps are often located on the side-slopes of a valley but they do not, typically, extend onto a valley floor. Seeps are characterised by their association with geological formations (lithologies) and topographic positions that either cause groundwater to discharge to the land surface or rain-derived water to 'seep' down-slope as subsurface interflow.




Figure 11: Wetland types present on site




Figure 12: Wetland vegetation type

River Ecosystem Status

There is a watercourse running through and adjacent to the proposed portions, which is classified as being Class C: Moderately Modified. The figure below depicts the river ecosystem status.




Figure 13: River Ecosystem Status

During the site assessment of the banks of the drainage lines were assessed. It should be noted that although the wetland and riparian features identified may extend beyond the project site, only portions located within the study area (including the 500m buffer) were assessed and ground-truthed. Furthermore, the study focused on features located within the study area and features located outside of this area were delineated using digital satellite imagery with limited field verification. Nonetheless, the potential impacts of activities such as crop production, erosion and clearing of natural vegetation within the greater catchment were taken into consideration during the assessment.

All wetland and watercourse/riparian features identified within the study area were classified as Inland Systems falling within the Highveld Aquatic Ecoregion. The table below presents the classification on level 3 and 4 of the wetland classification system.

System	Level 3: 1 unit	Landscape	Level 4: Hydro-geomorphic Unit			
			HGM type	Longitudinal landform / Inflo	zonation ow drainage	/

Ephemeral lines	drainage	Valley without	– chan	bottom nel	Watercourse	Lowland channel 8		active
Pans		Endorrh	eic w	retland	Pans	Endorrhe	ic	

<u>Wetland habitat</u> is land which is transitional between terrestrial and aquatic systems where the water table is usually at or near the surface, or the land is periodically covered with shallow water, and which land in normal circumstances supports or would support vegetation typically adapted to life in saturated soil (NWA; Act No. 36 of 1998).

<u>Riparian habitat</u> includes the physical structure and associated vegetation of the areas associated with a watercourse which are commonly characterised by alluvial soils, and which are inundated or flooded to an extent and with a frequency sufficient to support vegetation of species with a composition and physical structure distinct from those of adjacent land areas.

The rivers and non-perennial drainage lines with riparian characteristics are defined as watercourses, whilst the smaller ephemeral drainage lines without riparian zones are not considered wetlands or systems with an associated riparian zone but may still be defined as watercourses if the features have floodlines applicable to them.

FINDINGS:

Table 9: Description of the assessment of the pans and watercourses

Site features	Comments		
Upstream and catchment features	The catchment area is small and a mixture of natural shrubland. A broad plains occur on the project site A railway line and dirt roads are present in the catchment area		
Type of wetland (Ephemeral / perennial)	The watercourses are ephemeral streams and only become inundated when these watercourses burst its banks during floods.		
Other sources of input (e.g. springs etc.)	None		
Downstream significance	None. The voids have no outflow.		
Riparian zone characteristics	The riparian zone is poorly developed on the plains. In the mountainous areas the riparian zone is dominated by a mix of trees, shrubs, grasses, reeds, and sedges		
Presence of algae	At the time of the assessment the area was dry		
Visual indication of and impacts on aquatic fauna	At the time of the assessment the area was dry		
Depth characteristics	At the time of the assessment the area was dry		
Flow conditions	At the time of the assessment the area was dry		
Water clarity	At the time of the assessment the area was dry		
Water odour	No odours were noted		
Erosion potential	The potential is high because large areas are barren and the slopes towards the Vaal River. The slopes are relatively steep in places. There is thus a high erosion potential.		

Much of the functionality of the pans and watercourses and its riparian features has been altered due to anthropogenic activities such as impounding them with dams and weirs, stream bank disturbance by clearing the riparian vegetation and some agricultural activities close to the river

such as trampling of the plains. Currently, the systems are dry and not have a real value for the local.

Riparian Vegetation Response Index (VEGRAI)

The VEGRAI method was applied in order to assess the impacts of modifications to the system on the riparian vegetation of the river. The riparian zones located along the river have been impacted by the growth of alien vegetation. The resultant encroachment of alien vegetation has led to an impediment of water flow and displacement of indigenous floral and faunal species within the riparian areas. Furthermore, all of these systems have been impacted upon by previous prospecting and agriculture (grazing of domestic livestock) activities.

The riparian features found along the seasonal drainage lines and the pans received a score of 27%, and 39 respectively indicating that the VEGRAI Ecological Category falls in Category E which means that these systems are seriously modified systems where the loss of natural habitat, biota, and basis ecosystem functions is extensive.

Index of Habitat Integrity (IHI)

The Index of Habitat Integrity (IHI) as described by the DWA (2007) was utilised to assess the present Habitat Integrity state of the wetlands on the properties.

Wetland health is defined as a measure of the similarity of a wetland to a natural or reference condition. "Deviations" from this natural or reference state, particularly the extent of human impacts which may have caused the wetland to differ from this natural state, are considered when ascertaining the "health" of a wetland (Macfarlane et al., 2008).

The Index of Habitat Integrity (IHI) was applied to the pans and drainage lines to assess the Present Ecological State (PES). The table below provides a summary of the IHI results for each group of features and the river which are discussed in detail in the sub-sections that follow.

Drainage lines (watercourses)

These drainage lines have an ephemeral character. Impacts from the catchment areas and disturbance of the drainage lines within the project site are the predominant modifiers to these systems. These factors have resulted in a reduction of indigenous riparian vegetation with the resultant influx of alien vegetation contributing to some change in the natural functioning of the riparian zones of the drainage lines.

The WET-IHI category for the drainage lines is a D meaning that which means that these systems are seriously modified systems where the loss of natural habitat, biota, and basis ecosystem functions is extensive.

Larger depressions (pans)

These depressions have an ephemeral character. Impacts from the catchment areas and disturbance of the depressions within the project site are the predominant modifiers to these systems. These factors have resulted in a reduction of indigenous riparian vegetation with the resultant influx of alien vegetation contributing to some change in the natural functioning of the riparian zones of the depressions.

The WET-IHI category for the large depressions is a D meaning that which means that these systems are seriously modified systems where the loss of natural habitat, biota, and basis ecosystem functions is extensive. The pans are in raining seasons used as watering points for the cattle and game which are present on the project site.

Wet-Health Assessment (Overall PES)

A Level 1 Wet-Health assessment of the floodplain HGM Units was undertaken. Three modules, namely hydrology, geomorphology and vegetation, were assessed as a single unit for the HGM Units and subsequently an area weighted score was obtained for the HGM Units. The potential impacts of activities such as agriculture, altered hydrological functions and clearing of natural vegetation within the greater catchment were taken into consideration during the assessment. These results are summarised in the table below.

Table 10: Summary of results of the WET-Health assessments conducted on the pans and
seasonal drainage lines of the project site.

Feature	Hydrology		Geomorphology		Vege	Overall	
	Impact	Change	Impact	Change	Impact	Change	PES
	score	score	score	score	score	score	Category
Pans	D	→	D	→	D	→	D
Drainage lines (watercourse)	С	→	D	→	D	→	D

The overall PES Category for the pans and drainage lines is a D which means that the system is a largely modified system where a large change in ecosystem processes and loss is natural habitat and biota has occurred.

What needs to be considered is that if the disturbance and spread of alien invasive plants are allowed to continue unchecked and prospecting and mining activities are not planned for properly, and without proper rehabilitation it is highly likely that the floodplain areas in the project site will be further degraded and it will suppress the wetland function capabilities.

• Cultural and heritage aspects

Heritage Impact Assessment

Dr. David Morris from the McGregor Museum in Kimberley was appointed to conduct a Heritage Impact Assessment (Archaeology) on the proposed area. However, he could not access the site & will do it as soon as he has access to site.

Palaeontological Desktop Assessment

Elize Butler from Banzai Environmental (Pty) Ltd was appointed to conduct a Palaeontological Desktop Assessment for the proposed area. Please find the specialist report attached under **Appendix 12.** Some of the findings

Geological and Palaeontological Heritage

The proposed development is completely underlain by the Ongeluks Formation, Postmasburg Group and the Asbestos Hills Subgroup, Ghaap Group of the Transvaal Supergroup (Figure 4).

The Transvaal Supergroup is preserved in three structural basins on the Kaapvaal Craton of South Africa namely the Griqualand West Basin, Transvaal Basin, as well as the Kanye Basin in Botswana. The Griqualand West Basin can be subdivided into the Ghaap Plateau and Prieska subbasins. The geometry of the three basins is basically stratiform with the exception of the volcanic precursor of the Kanye Basin and parts of the Griqualand West Basin. Extensive deformation has taken place in the south-western portion of the Griqualand West Basin.

Rocks of the Transvaal Supergroup in the Transvaal Basin were intruded by the Bushveld Complex approximately 2060 million years ago. The Transvaal Supergroup overlays the Archaean basement as well as the Witwatersrand and Ventersdorp Supergroups. In the far western and Kanye Basin

rocks belonging to the Kanye Formation and Gaborone Granite Suite is also overlain by the Transvaal Supergroup




Figure 14: Surface geology of the proposed Kimswa development

The Asbestos Hill Subgroup is located in the **Griqualand West Basin**, Northern Cape Province which consists of clastic sediments as well as volcanic rocks, diamictites and banded iron formations. Manganese deposits is present in the Hotazel Formation, upper Postmasburg Group (approximately 2222 Ma). The Vryburg Formation is the basal unit and overlies unconformably the granite and rocks of the Ventersdorp Supergroup. The Campbell Group overlies the Vryburg Formation and consists of the Schmidtsdrif Formation and the upper Ghaap Plateau Formation. The Griquatown Group is divided into two formations namely the Asbestos Hills and Koegas Formations. The Gamagara Formation. The Cox Group comprises of the lower Ongeluk Formation and the upper Voëlwater Formation. The Ongeluk Formation was deposited under water and is approximately 400 to 900 m thick. This Formation is basal and is mainly volcanic (Visser 1989). Manganese is present in the upper Voëlwater Formation (Snyman 1996). According to Kent (1980) and Snyman (1996) Griqualand West Basin attains a maximum thickness of 4500 m.

Fossils known from the Transvaal Supergroup are algal structures which are also known as stromatolites. Stromatolites are layered mounds, columns and sheet-like sedimentary rocks. These structures were originally formed by the growth of layer upon layer of cyanobacteria, a single-celled photosynthesizing microbe. Cyanobacteria are prokaryotic cells (simplest form of modern carbon-bases life). Stromatolites are first found in Precambrian rocks and are known as the earliest known fossils. The oxygen atmosphere that we depend on today was generated by numerous cyanobacteria photosynthesizing during the Archaean and Proterozoic Era.

Subgroup/ sequence		Group	Formation	Fossil Heritage	Comment
Griqualand W	7est	Griquastad	Asbestos	Stromatolites	Cynanobacterial
Super Group			Hills		microfossils are present

Table 11: Table modified from Palaeotechnical Report (Almond and Pether 2009).

Stromatolites and oolites from the Transvaal Supergroup have been described by various authors (Eriksson and Altermann, 1998). Detailed descriptions of South African Archaean stromatolites are available in the literature (Altermann, 2001; Buick, 2001; and Schopf, 2006). Literature on the Malmani stromatolites, includes articles by Button (1973), Truswell and Eriksson (1972, 1973, 1975), Eriksson and MacGregor (1981), Eriksson and Altermann (1998), Sumner (2000), Schopf (2006).

The lower parts of the thick successions are represented by the predominately dolomitic sediments and associated iron formations of the Ghaap group. The geology of the area is partly attributed to high stream velocities and rapid deposition. Clasts of Ventersdorp lava predominate, with significant (if variable) amounts of banded iron formation (BIF), chert, quartzite and quartz also present.

Findings and Recommendations

The proposed Kimswa Mine development is completely underlain by the Ongeluks Formation, Postmasburg Group and the Asbestos Hills Subgroup, Ghaap Group of the Transvaal Supergroup. According to the PalaeoMap of South African Heritage Resources Information System the Palaeontological Sensitivity of the Ongeluks Formation as well as the Asbestos Hills Subgroup is moderate. It is therefore considered that the prospecting right application near near Postmasburg Northern Cape Province is deemed appropriate and feasible and will not lead to detrimental impacts on the palaeontological resources of the area. Thus, the construction and operation of the facility may be authorised as the whole extent of the development footprint is not considered sensitive in terms of palaeontological resources.

In the event that fossil remains are discovered during any phase of construction, either on the surface or exposed by fresh excavations, is essential that the ECO in charge for these developments must be informed immediately. These discoveries must be protected (preferably *in situ*) and the ECO must alert SAHRA (South African Heritage Research Agency) so that mitigation (recording and collection) can be under taken by a paleontologist.

The specialist would need a collection permit from SAHRA. Fossil material must be curated in an approved collection (museum or university) and all fieldwork and reports must adhere to the minimum standards for palaeontological impact studies developed by SAHRA.

(b) Description of the current land uses.

Below is the land cover of the proposed area, the proposed area is covered in natural vegetation and waterbodies according to the landcover map.

Attendees at the public meeting said the proposed area is used of agriculture activities such as livestock grazing.




Figure 15: Land cover

v. IMPACTS AND RISKS IDENTIFIED INCLUDING THE NATURE, SIGNIFICANCE, CONSEQUENCE, EXTENT, DURATION AND PROBABILITY OF THE IMPACTS, INCLUDING THE DEGREE TO WHICH THESE IMPACTS

Significance of potential impacts

The following sections present the outcome of the significance rating exercise. The results suggest that almost none of the key issues identified as part of the EIR process had a negative high environmental significance. Instead the overall score indicate a low environmental significance score.

INITIAL CLEARANCE AND SITE PREPARATION PHASE

Direct impacts: During this phase minor negative impacts are foreseen over the short term. The latter refers to a period of weeks. The site preparation may result in the loss or fragmentation of indigenous natural fauna and flora, loss or fragmentation of habitats, soil erosion, hydrology, and temporary noise disturbance, generation of waste, visual intrusions, increase in heavy vehicle traffic, and risk to safety, livestock and farm infrastructure, and increased risk of veld fires. The abovementioned impacts are discussed in more detail below:

Loss or fragmentation of indigenous natural fauna and flora:

The proposed area falls within vegetation units SVk13 and SVk10, which is known as the Olifantshoek Plains Thornveld and Kuruman Mountain Bushveld. Olifantshoek Plains Thornveld and Kuruman Mountain Bushveld are part of the Eastern Kalahari Bushveld which is a subbioregion for the Savanna Biome.

Olifantshoek Plains Thornveld

According to Mucina and Rutherford (2006:522) the Olifantshoek Plains Thornveld is distributed across the Northern Cape Province plains including most of the pediment areas of the Korannaberg, Langeberg and Asbestos Mountains as well as those of some ridges to the west of the Langeberg. From the vicinity of Sonstraal in the north, past Olifantshoek to areas north of Niekerkshoop between Volop and Griekwastad in the south. Also from Griekwastad northwards to the flats west of the Lime Acres area. Altitude 1 000–1 500 m.

Vegetation and landscape features can be described as a very wide and diverse unit on plains with usually open tree and shrub layers with, for example, *Acacia luederitzii*, *Boscia albitrunca* and *Rhus tenui-nervis* and with a usually sparse grass layer.

Kuruman Mountain Bushveld

According to Mucina and Rutherford (2006:520) the Kuruman Mountain Bushveld is distributed across the Northern Cape and North West Provinces. From the Asbestos Mountains southwest and northwest of Griekwastad, along the Kuruman Hills north of Danielskuil, passing west of Kuruman town and re-emerging as isolated hill, i.e. Makhubung and the hills around Pomfret in the north. This bushveld is situated on an altitude of 1100m – 1800m.

Vegetation and landscape features can be described as rolling hills with generally gentle to moderate slopes and hill pediment areas with an open shrubveld with *Lebeckia macrantha* prominent in place, with well-developed grass layers.

Loss or fragmentation of indigenous natural fauna and flora	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	Medium term (2)	Medium term (2)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Significant loss of resource (3)	Marginal loss of resource (2)
Cumulative impact	Medium cumulative impac	cts (3),
Significance	Negative Medium (45)	Negative low (28)
Can impacts be mitigated?	 ensure that no mammali trapped, hunted or kille approved, every effort show footprint to the blocks allo and have the least poss surrounding area. The EM mitigation measures – refe The potential impacts asso loss of farmland should be aspects that should be con The site should be commencement of con The footprint associate related activities (acc platforms, workshop et al.) 	ociated with damage to and e effectively mitigated. The vered include: e fenced off prior to

 An Environmental Control Officer (ECO) should be appointed to monitor the establishment phase of the construction phase; All areas disturbed by construction related activities, such as access roads on the site, construction platforms, workshop area etc., should be rehabilitated at the end of the construction phase;
 The implementation of a rehabilitation programme should be included in the terms of reference for the contractor/s appointed. Specifications for the rehabilitation are provided throughout the EMPr – section (f) of the EMPr. The implementation of the Rehabilitation Programme should be monitored by the ECO.

• <u>Loss or fragmentation of habitats</u> – Given the medium probability of resident threatened species occurring at the footprint site, Water Use License Application will be lodged with the department of Water & Sanitation (DWS).

Loss or fragmentation of habitats	Pre-mitigation impact rating	Post mitigation impact rating		
Status (positive or negative)	Negative	Negative		
Extent	Local (2)	Local (2)		
Probability	Definite (4)	Definite (4)		
Duration	Medium term (2)	Medium term (2)		
Magnitude	Very High (4)	High (3)		
Reversibility	Barely reversible (3)	Barely reversible (3)		
Irreplaceable loss of resources	Significant loss of	Marginal loss of		
	resource (3)	resource (2)		
Cumulative impact	Medium cumulative impacts (3).			
Significance	Negative High (68)	Negative Medium (48)		
Can impacts be mitigated?	allowed to establish, approved. Where exotic a are found at the site should take place. If the every effort should be ma to the blocks allocated for	nt species should not be if the development is and invasive plant species continuous eradication development is approved, de to confine the footprint r development – section (f) des numerous mitigation a and flora.		

• <u>Loss of topsoil</u> – Topsoil may be lost due to poor topsoil management (burial, erosion, etc.) during construction related soil profile disturbance (levelling, excavations, disposal of spoils from excavations etc.) The effect will be the loss of soil fertility on disturbed areas after rehabilitation.

Loss of topsoil	Pre-mitigation impact rating	Post mitigation impact rating	
Status (positive or negative)	Negative	Negative	
Geographical extent	Site (1)	Site (1)	
Probability	Possible (2)	Unlikely (1)	
Duration	Medium term (2)	Medium term (2)	
Magnitude	High (3)	High (3)	
Reversibility	Partly reversible (2)	Partly reversible (2)	
Irreplaceable loss of resources	Significant (3)	Marginal (2)	
Cumulative impact	Medium cumulative im	pact (3).	
Significance	Negative Medium (39)	Negative Medium (33)	

Can impacts be mitigated?	The following mitigation or management
Can impacts be mitigated?	 measures are provided: If an activity will mechanically disturb below surface in any way, then any available topsoil should first be stripped from the entire surface and stockpiled for respreading during rehabilitation. Topsoil stockpiles must be conserved against losses through erosion by establishing vegetation cover on them. Dispose of all subsurface spoils from excavations where they will not impact on undisturbed land. During rehabilitation, the stockpiled topsoil must be evenly spread over the entire disturbed surface. Erosion must be controlled where necessary on top soiled areas. Establish an effective record keeping system for each area where soil is disturbed for constructional purposes. These records should be included in environmental performance reports, and should include all the records below. Record the GPS coordinates of each area. Record the GPS coordinates of where the topsoil is stockpiled. Record the date of cessation of constructional (or operational) activities at the particular site. Photograph the area on cessation of constructional activities. Record date and depth of re-spreading of topsoil. Photograph the area on completion of rehabilitation and on an annual basis thereafter to show vegetation establishment
	and evaluate progress of restoration over time.Section (f) of the EMPr also provide mitigation measures related to topsoil management.

• <u>Soil erosion</u> – Soil erosion due to alteration of the land surface run-off characteristics. Alteration of run-off characteristics may be caused by construction related land surface disturbance, vegetation removal and the establishment of roads. Erosion will cause loss and deterioration of soil resources. The erosion risk is low due to the low slope gradients and low to moderate erodibility of the soils.

Soil erosion	Pre-mitigation impact rating	Post mitigation impact rating	
Status (positive or negative)	Negative	Negative	
Geographical extent	Site (1)	Site (1)	
Probability	Possible (2)	Unlikely (1)	
Duration	Medium term (2)	Medium term (2)	
Magnitude	Medium (2)	Medium (2)	

Reversibility	Partly reversible (2)	Partly reversible (2)	
Irreplaceable loss of resources	Marginal (2)	Marginal (2)	
Cumulative impact	Negligible cumulative in	npact (1).	
Significance	Negative low (20)	Negative low (18)	
Can impacts be mitigated?	are provided: Implement run-off control, where in and safely disseminated	The following mitigation or management measures are provided: Implement an effective system of run-off control, where it is required, that collects and safely disseminates run-off water from all hardened surfaces and prevents potential down slope erosion.	
	Include periodical site inspection in environmental performance reporting that inspects the effectiveness of the run-off control system and specifically records the occurrence any erosion on site or downstream – refer to section (f) of the EMPr.		

• <u>Temporary noise disturbance</u> - Preparation activities will result in the generation of noise over a period of months. Sources of noise are likely to include vehicles, the use of machinery such as back actors and people working on the site. The noise impact is unlikely to be significant; but activities should be limited to normal working days and hours (6:00 – 18:00).

Temporary noise disturbance	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Definite (4)	Probable (3)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (2)	Low (1)
Reversibility	Completely reversible	Completely reversible
	(1)	(1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	The impact would result in negligible to no	
	cumulative effects (1).	
Significance	Negative low (20)	Negative low (9)
Can impacts be mitigated?	Yes, management actions related to noise	
	pollution are included in	n section (f) of the EMPr.

• <u>Generation of waste - general waste, construction waste, sewage and grey water</u> - The workers on site are likely to generate general waste such as food wastes, packaging, bottles, etc. Construction waste is likely to consist of packaging, scrap metals, waste cement, etc If any). The applicant will need to ensure that general and construction waste is appropriately disposed of i.e. taken to the nearest licensed landfill. Sufficient ablution facilities will have to be provided, in the form of portable/VIP toilets. No pit latrines, French drain systems or soak away systems shall be allowed.

Generation of waste	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local/district (2)	Local/district (2)
Probability	Definite (4)	Definite (4)
Duration	Short term (1)	Short term (1)
Magnitude	Low (1)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Medium cumulative impact (3) - An additional	
	demand for landfill space could result in	
	significant cumulative in	npacts if services become

	unstable or unavailable, which in turn would negatively impact on the local community.	
Significance	Negative medium (13) Negative low (13)	
Can impacts be mitigated?	Yes, it is therefore important that all management actions and mitigation measures included in section (f) of the EMPr are implemented.	

• <u>Impacts on heritage objects</u> –

Heritage Impact Assessment

Dr. David Morris from the McGregor Museum in Kimberley was appointed to conduct a Heritage Impact Assessment (Archaeology) on the proposed area. Note that the area could not be accessed and hence this assessment is provisional.

Palaeontological Desktop Assessment

The proposed development is completely underlain by the Ongeluks Formation, Postmasburg Group and the Asbestos Hills Subgroup, Ghaap Group of the Transvaal Supergroup. The Palaeontological Sensitivity of this formation is rated Moderate. The expected duration of the impact is assessed as potentially permanent to long term. In the absence of mitigation procedures (should fossil material be present within the affected area) the damage or destruction of any palaeontological materials will be permanent. Impacts on palaeontological heritage during the construction phase could potentially occur but are regarded as having a low possibility.

Impacts on heritage objects	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Possible (2)	Possible (2)
Duration	Short term (1)	Short term (1)
Magnitude	Medium (2)	Low (1)
Reversibility	Irreversible (4)	Irreversible (4)
Irreplaceable loss of resources	Marginal loss of resource (2)	Marginal loss of resource (2)
Cumulative impact	Low cumulative impact (2). Should these impacts occur, there may be a cumulative impact on the preservation of heritage objects in the area.	
Significance	Negative low (24)	Negative low (12)
Can impacts be mitigated?	during construction wor be reported to a heritag	or graves are exposed or graves are exposed or the should immediately a practitioner so that an ation of the finds can be on (f) of the EMPr.

Indirect impacts: The nuisance aspects generally associated with the installation of infrastructure or ground preparation will also be applicable to this development, which relates primarily to the increase in vehicle traffic associated with prospecting practices, the influx of job seekers to the area, risk to safety, livestock and farm infrastructure, and increased risk of veld fires.

• <u>Increase in vehicle traffic</u> – The movement of heavy vehicles during the clearance of vegetation and topsoil has the potential to damage local farm roads and create dust and safety impacts for other road users in the area. Access will be obtained from the D3381 gravel road off the R385. While the volume of traffic along this road is low, the movement of heavy vehicles along this road is likely to damage the road surface and impact on other road users. The contractor should be required to ensure that damage to the road is repaired periodically. The movement of additional heavy vehicle traffic is will add significantly to the current traffic load on the road. The impact on the D3381 gravel road off the R385 is therefore likely to be moderate.

Increase in vehicle traffic	Pre-mitigation impact rating	Post mitigation impact rating	
Status (positive or negative)	Negative	Negative	
Extent	Local (2)	Local (2)	
Probability	Probable (3)	Probable (3)	
Duration	Short term (1)	Short term (1)	
Magnitude	High (3)	Medium (2)	
Reversibility	Completely reversible (1)	Completely reversible (1)	
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)	
Cumulative impact	is not repaired then this activities in the area maintenance costs for ve and other road users. Th road users who were r damage.	Medium cumulative impact (3). If damage to roads is not repaired then this will affect the farming activities in the area and result in higher maintenance costs for vehicles of local farmers and other road users. The costs will be borne by road users who were no responsible for the damage	
Significance	impacts (33)	Negative low (11)	
Can impacts be mitigated?	 caused by constructing road off the R385 in associated with the rather of the contractor; Dust suppression implemented for the wetting of gravel road ensuring that vehicles and building material tarpaulins or covers; All vehicles must be must be qualified at the construction of the construction of	tively mitigated. The ide: at ensure that damage on on the D3381 gravel s repaired. The costs repair must be borne by	
	Also refer section (f) of the measures related to traffic		

• <u>Risk to safety, livestock and farm infrastructure</u> - The presence on and movement of workers on and off the site poses a potential safety threat to local famer's and farm workers in the vicinity of the site threat. In addition, farm infrastructure, such as fences and gates, may be damaged and stock losses may also result from gates being left open and/or fences being damaged or stock theft linked either directly or indirectly to the presence of farm workers on the site.

Risk to safety, livestock and farm infrastructure	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Probable (3)	Probable (3)
Duration	Medium term (2)	Medium term (2)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal resource (2)	Marginal resource (2)

• <u>Increased risk of veld fires</u> - The presence of construction workers and construction-related activities on the site poses an increased risk of grass fires that could in turn pose a threat to livestock, crops, wildlife and farmsteads in the area. In the process, farm infrastructure may also be damaged or destroyed and human lives threatened. The potential risk of grass fires was heightened by the windy conditions in the area, especially during the dry, windy winter months from May to October. In terms of potential mitigation measures, a fire-break should be constructed around the perimeter of the site prior to the commencement of the construction phase. In addition, fire-fighting equipment should be provided on site during the construction phase.

Increased risk of veld fires	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Region (3)	Local (2)
Probability	Probable (3)	Probable (3)
Duration	Medium term (2)	Short term (1)
Magnitude	High (3)	Low (1)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	Negligible cumulative effe	
Significance	Negative medium (33)	Negative low (9)
Can impacts be mitigated?	 The mitigation measures i A fire-break should be perimeter of the commencement of the Contractor should ensithe site for cooking or except in designated a Contractor to ensure the activities that pose a as welding, are propied to areas where been reduced. Measure fires include avoiding conditions when the result of this regard special during the high risk dr Contractor to provide selected construction staff security staff, to be acconstruction workers activities, the appoint compensate farmers for their farms. The commencement of a construction workers activities, the appoint compensate farmers for their farms. The commencement of the commencement of a construction workers activities are subjected construction workers activities are subjected compensate farmers for their farms. The commencement of the commencement of the commencement of the commencement of the compensate farmers for the commencement of the commenceme	nclude: constructed around the site prior to the construction phase; sure that open fires on heating are not allowed reas; hat construction related potential fire risk, such erly managed and are ere the risk of fires has res to reduce the risk of working in high wind isk of fires is greater. In care should be taken y, windy winter months; e adequate firefighting ncluding a fire fighting fire-fighting training to staff; , with the exception of commodated on site over of the Code of Conduct, fire being caused by and or construction need contractors must or any damage caused to ontractor should also ghting costs borne by

OPERATIONAL PHASE

Direct impacts: During the operational phase the study area will serve as an prospecting area and the impacts are generally associated with soil erosion, change in land use, impacts associated with the, increase in storm water runoff, increased consumption of water, visual intrusion, the generation of general waste, leakage of hazardous materials, and the change in the sense of place. The operational phase will also have a direct positive impact through the provision of permanent employment opportunities and facilitating a positive economic growth. The abovementioned impacts are discussed in more detail below:

• <u>Soil erosion</u> – The largest risk factor for soil erosion will be during the operational phase when the prospecting activity ensues and soil is left bare until rehabilitation is initiated. Erosion will

be localised within the site. This will ultimately lead to the irretrievable commitment of this resource. The measurable effect of reducing erosion by utilizing mitigation measures may reduce possible erosion significantly.

Soil erosion	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local/Regional (2)	Local/Regional (2)
Probability	Definite (4)	Unlikely (1)
Duration	Long term (3)	Long term (3)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Significant loss of	Marginal loss of
	resource (3)	resource (2)
Cumulative impact	Medium cumulative impact (3). Should these	
	impacts occur, there will be a cumulative impact	
	on the air and water resources in the study area	
	in terms of pollution.	
Significance	Negative High (51)	Negative Low (26)
Can impacts be mitigated?	Yes, to avoid soil erosion it will be a good practice	
	to not remove all the vegetation at once but to only	
	clear the area as it becomes necessary and to	
	implement concurrent rehabilitation.	
	Also refer to section (f) of the EMPr.	

• <u>Change in land-use</u> – The use of the area for the operation of the prospecting activity will not disturb any agricultural activities on most of the portions as both will be done concurrently.

Change in land use	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Province (3)	Local (2)
Probability	Definite (4)	Definite (4)
Duration	medium term (2)	medium term (2)
Magnitude	High (3)	Medium (2)
Reversibility	Barely reversible (3)	Partly reversible (2)
Irreplaceable loss of resources	Significant loss of resource (3)	resource (2)
Cumulative impact	Medium cumulative in	npacts (3).
Significance	Negative high (54)	Negative medium (30)
Can impacts be mitigated?	(30)The proponent should establish a Rehabilitation Fund to be used to rehabilitate the area once the proposed facility has been decommissioned. The fund should be funded by revenue generated during the operational phase of the project. The motivation for the establishment of a Rehabilitation Fund is based on the experience in the mining sector where many mines on closure have not set aside sufficient funds for closure and 	

• <u>Generation of alternative land use income</u> – Income generated through the alluvial diamond mine will provide the farming enterprise with increased cash flow and rural livelihood, and thereby improve the financial sustainability of farming on site.

Generation of alternative land use income	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Positive	Positive
Geographical extent	Site (1)	Site (1)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	High (3)
Reversibility	Completely reversible (1)	Completely reversible (1)
Irreplaceable loss of resources	No loss of resources (1)	No loss of resources (1)
Cumulative impact	Medium cumulative impact (3).	
Significance	Positive Low (24)	Positive medium (39)
Can impacts be mitigated?	No mitigation required.	

• <u>Increase in storm water runoff</u> – The development will potentially result in an increase in storm water run-off that needs to be managed to prevent soil erosion, especially where vegetation will be cleared. Not all the vegetation should be removed at once. Only the specific trench being excavated at the specific time should be cleared

Increase in storm water runoff	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Probable (3)	Unlikely (1)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal loss of resource (2)	Marginal loss of resource (2)
Cumulative impact	impacts occur, there wi on the wider area.	npact (3) - Should these ll be a cumulative impacts
Significance	Negative medium (30)	Negative low (13)
Can impacts be mitigated?	actions and mitigation section (f) of the EMPr. that these impacts do n	artant that all management n measures included in are implemented to ensure not occur and silt fences will be
	installed where necess	sary as to control runoff lating it and control the
	basis. It is suggested	be monitored on a regular that it be monitored on a le rainy season, and after ring the dry season.
	control of storm water	nd to be insufficient for the and sedimentation, other mediately be investigated

<u>Increased consumption of water</u> - Since $1 \ge 16$ feet washing pans will be used, the amount of water for the pans will be 17 000 L/hour from which 30% is re-used.

Increased consumption of water	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Region (3)	Region (3)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Medium (2)	Medium (2)
Reversibility	Irreversible (4)	Irreversible (4)
Irreplaceable loss of resources	Marginal loss of	Marginal loss of
	resources (2)	resources (2)
Cumulative impact		acts (4) - An additional
	demand on water so	urces could result in a
	significant cumulative	e impact with regards to
	the availability of wat	er.
Significance	Negative medium	Negative medium
	(40)	(40)
Can impacts be mitigated?	Yes, management a	ctions and mitigation
	measures related to	the use of water are
	included in section (f)	of the EMPr.

• <u>Generation of waste</u> – Approximately 15 Workers will be present on site from 6:00 – 18:00, Monday to Saturday. Sources of general waste will be waste food, packaging, paper, etc. General waste will be stored on the site and removed on a weekly basis by a contractor.

Generation of waste	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Definite (4)	Definite (4)
Duration	Long term (3)	Long term (3)
Magnitude	Low (1)	Low (1)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	No loss of resource	No loss of resource (1)
	(1)	
Cumulative impact	Medium cumulative ir	npact (3) - An additional
	demand for landfill	space could result in
		impacts with regards to
	the availability of land	fill space.
Significance	Negative low (15)	Negative low (15)
Can impacts be mitigated?	Yes, management ac	ctions related to waste
	8	uded in section (f) of the
	EMPr.	

• <u>Leakage of hazardous materials</u> - The proposed prospecting activity will make use of machinery that use fuel and oil. Leakage of these oils and fuel can contaminate water supplies and must be prevented by constructing oil and diesel permeable bunds to ensure that any spills are suitably attenuated and not released into the environment.

Leakage of hazardous materials	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Possible (2)	Unlikely (1)
Duration	Long term (3)	Long term (3)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	Marginal loss of	Marginal loss of
	resource (2)	resource (2)

Cumulative impact	The impact would result in negligible to no cumulative effects (1)	
Significance	Negative medium Negative low (22) (36)	
Can impacts be mitigated?	Yes. It is therefore important that all management actions and mitigation measures included in the section (f) of EMPr are implemented to ensure that these impacts do not occur.	

• <u>Noise disturbance</u> - Prospecting activities will result in the generation of noise over a period of 3-5 years. Sources of noise are likely to include vehicles, the use of machinery such as backactors, rotary pans and people working on the site, as well as occasional blasting. The noise impact is likely to be significant as the closest

Temporary noise disturbance	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Definite (4)	Probable (3)
Duration	Medium term (2)	Medium term (2)
Magnitude	Very high (4)	High (3)
Reversibility	Completely reversible	Completely reversible
	(1)	(1)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource (1)
Cumulative impact	The impact would resul	t in medium cumulative
	effects (3).	
Significance	Negative High (52)	Negative medium (36)
Can impacts be mitigated?		ions related to noise n section (f) of the EMPr.

Indirect impacts: The operational phase will have an indirect negative impact through the change in the sense of place and an indirect positive impact through the provision of additional electrical infrastructure.

• <u>Potential impact on tourism</u> – The impact of the proposed prospecting of diamond alluvial on the areas sense of place with mitigation is likely to be low. In addition, the site will be visible from the D3381 gravel road off the R385.

Potential impacts on tourism	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Site (1)	Site (1)
Probability	Possible (2)	Possible (2)
Duration	Medium term (2)	Medium term (2)
Magnitude	medium (2)	Low (1)
Reversibility	Completely	Completely reversible
	reversible (1)	(1)
Irreplaceable loss of resources	N/A	N/A
Cumulative impact	N/A	
Significance	Negative low (12)	Negative low (6)
Can impacts be mitigated?	No mitigation require	ed

DECOMMISIONING PHASE (MINE CLOSURE AND REHABILITATION)

Direct impacts: Typically, the major social impacts associated with the decommissioning phase are linked to the loss of jobs and associated income. This has implications for the households

who are directly affected, the communities within which they live. If infrastructures are removed after a 3/5 year period, the site will be returned to its natural state. Therefore the physical environment will benefit from the closure of the prospecting area.

• <u>Rehabilitation of the physical environment</u> – The physical environment will benefit from the closure of the prospecting area since the site will be restored to its natural state.

Rehabilitation of the physical environment	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Positive	Positive
Extent	Site (1)	Site (1)
Probability	Possible (2)	Probable (3)
Duration	Long term (3)	Long term (3)
Magnitude	Low (1)	Medium (2)
Reversibility	N/A	N/A
Irreplaceable loss of resources	N/A	N/A
Cumulative impact	The impact would recumulative effects (1)	esult in negligible to no
Significance	Negative low (7)	Negative low (16)
Can impacts be mitigated?	No mitigation measur	res required.

• <u>Loss of employment</u> - Given the relatively large number of people employed during the operational phase, the decommissioning of the facility has the potential to have a negative social impact on the local community.

Loss of employment	Pre-mitigation impact rating	Post mitigation impact rating
Status (positive or negative)	Negative	Negative
Extent	Local (2)	Local (2)
Probability	Possible (2)	Possible (2)
Duration	Medium term (2)	Short term (1)
Magnitude	High (3)	Medium (2)
Reversibility	Partly reversible (2)	Partly reversible (2)
Irreplaceable loss of resources	No loss of resource (1)	No loss of resource
		(1)
Cumulative impact	The impact would rest cumulative effects (1)	ult in negligible to no
Significance	Negative medium (30)	Negative low (18)
Can impacts be mitigated?	 recommended: All structures associated with the should be dismantle site on decommission Kimswa Mining establish an Environ Trust Fund to 	he proposed facility ed and transported off- oning;

Indirect impacts: No indirect impacts are anticipated from the decommissioning phase of the proposed development.

vi. METHODOLOGY USED IN DETERMINING AND RANKING THE NATURE, SIGNIFICANCE, CONSEQUENCES, EXTENT, DURATION AND PROBABILITY OF POTENTIAL ENVIRONMENTAL IMPACTS AND RISKS

Method of environmental assessment

The environmental assessment aims to identify the various possible environmental impacts that could results from the proposed development. Different impacts need to be evaluated in terms of its significance and in doing so highlight the most critical issues to be addressed.

Significance is determined through a synthesis of impact characteristics which include context and intensity of an impact. Context refers to the geographical scale i.e. site, local, national or global whereas intensity is defined by the severity of the impact e.g. the magnitude of deviation from background conditions, the size of the area affected, the duration of the impact and the overall probability of occurrence. Significance is calculated as shown in the Table below.

Significance is an indication of the importance of the impact in terms of both physical extent and time scale, and therefore indicates the level of mitigation required. The total number of points scored for each impact indicates the level of significance of the impact.

Impact Rating System

Impact assessment must take account of the nature, scale and duration of impacts on the environment whether such impacts are positive or negative. Each impact is also assessed according to the following project phases:

- Construction
- Operation
- Decommissioning

Where necessary, the proposal for mitigation or optimisation of an impact should be detailed. A brief discussion of the impact and the rationale behind the assessment of its significance should also be included. The rating system is applied to the potential impacts on the receiving environment and includes an objective evaluation of the mitigation of the impact. In assessing the significance of each impact the following criteria is used:

Table: The rating system

	NATURE		
cont	Include a brief description of the impact of environmental parameter being assessed in the context of the project. This criterion includes a brief written statement of the environmental aspect being impacted upon by a particular action or activity.		
	GE	OGRAPHICAL EXTENT	
This	This is defined as the area over which the impact will be experienced.		
1	Site	The impact will only affect the site.	
2	Local/district	Will affect the local area or district.	
3	Province/region	Will affect the entire province or region.	
4	International and National	Will affect the entire country.	
	PROBABILITY		
This	This describes the chance of occurrence of an impact.		
1	Unlikely	The chance of the impact occurring is extremely low (Less than a 25% chance of occurrence).	
2	Possible	The impact may occur (Between a 25% to 50% chance of occurrence).	

tween a 50% to 75%
er than a 75% chance
ime of the impact as a
with mitigation or will esses in a span shorter l years), or the impact ely short construction ne after construction, d $(0 - 2 \text{ years})$.
or some time after the mitigated by direct sses thereafter (2 – 10
ntinue or last for the elopment, but will be ction or by natural s).
rill be non-transitory. ural process will not e span that the impact
and integrity of the
is barely perceptible.
and integrity of the em/component still tely modified way and
and integrity of the em/component still
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely cease. High costs of d viability of the ity, use, integrity and mponent permanently ed. Rehabilitation and possible rehabilitation due to extremely high
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely cease. High costs of d viability of the ity, use, integrity and mponent permanently ed. Rehabilitation and possible rehabilitation due to extremely high
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely cease. High costs of d viability of the ity, use, integrity and mponent permanently ed. Rehabilitation and possible rehabilitation due to extremely high ation.
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely cease. High costs of d viability of the ity, use, integrity and mponent permanently ed. Rehabilitation and possible rehabilitation due to extremely high ation.
and integrity of the em/component still tely modified way and impact on integrity). bility of the system/ use, integrity and omponent is severely cease. High costs of d viability of the ity, use, integrity and mponent permanently ed. Rehabilitation and possible rehabilitation due to extremely high ation. ed upon completion of

IRREPLACEABLE LOSS OF RESOURCES

This d	logarihas the degree to which re	popurose will be irreplaced by last as a result of a proposed
activit	0	esources will be irreplaceably lost as a result of a proposed
1	No loss of resource	The impact will not result in the loss of any resources.
2	Marginal loss of resource	The impact will result in marginal loss of resources.
3	Significant loss of resources	The impact will result in significant loss of resources.
4	Complete loss of resources	The impact is result in a complete loss of all resources.
CUMULATIVE EFFECT		
This describes the cumulative effect of the impacts. A cumulative impact is an effect which in itself may not be significant but may become significant if added to other existing or potential impacts emanating from other similar or diverse activities as a result of the project activity in question.		
1	Negligible cumulative impact	The impact would result in negligible to no cumulative effects.
2	Low cumulative impact	The impact would result in insignificant cumulative effects.
3	Medium cumulative impact	The impact would result in minor cumulative effects.

SIGNIFICANCE

The impact would result in significant cumulative effects

4

High cumulative impact

Significance is determined through a synthesis of impact characteristics. Significance is an indication of the importance of the impact in terms of both physical extent and time scale, and therefore indicates the level of mitigation required. The calculation of the significance of an impact uses the following formula:

(Extent + probability + reversibility + irreplaceability + duration + cumulative effect) x magnitude/intensity.

The summation of the different criteria will produce a non-weighted value. By multiplying this value with the magnitude/intensity, the resultant value acquires a weighted characteristic which can be measured and assigned a significance rating.

which car	i de measureu anu assigne	u a significance rating.
Points	Impact significance rating	Description
6 to 28	Negative low impact	The anticipated impact will have negligible negative effects and will require little to no mitigation.
6 to 28	Positive low impact	The anticipated impact will have minor positive effects.
29 to 50	Negative medium impact	The anticipated impact will have moderate negative effects and will require moderate mitigation measures.
29 to 50	Positive medium impact	The anticipated impact will have moderate positive effects.
51 to 73	Negative high impact	The anticipated impact will have significant effects and will require significant mitigation measures to achieve an acceptable level of impact.
51 to 73	Positive high impact	The anticipated impact will have significant positive effects.
74 to 96	Negative very high impact	The anticipated impact will have highly significant effects and are unlikely to be able to be mitigated adequately. These impacts could be considered "fatal flaws".

74 to 96	Positive very high	The anticipated impact will have highly significant
	impact	positive effects.

vii. THE POSITIVE AND NEGATIVE IMPACTS THAT THE PROPOSED ACTIVITY (IN TERMS OF THE INITIAL SITE LAYOUT) AND ALTERNATIVES WILL HAVE ON THE ENVIRONMENT AND THE COMMUNITY THAT MAY BE AFFECTED.

(Provide a discussion in terms of advantages and disadvantages of the initial site layout compared to alternative layout options to accommodate concerns raised by affected parties)

- Increased ambient noise levels resulting from geophysic surveys site fly-overs and increased traffic movement during all prospecting phases.
- Potential water and soil pollution impacts resulting from hydrocarbon spills and soil erosion which may impact on environmental resources utilized by communities, landowners and other stakeholders.
- Potential water and soil pollution impacts resulting from hydrocarbon spills and soil erosion which may impact on ecosystem functioning.
- Increased vehicle activity with in the area resulting in the possible destruction and disturbance of fauna and flora.
- Poor access control to farms which may impact on cattle movement, breeding and grazing practices.
- Influx of persons (job seekers) to site as a result of increased activity and the possible resultant increase in opportunistic crime.
- Potential visual impacts caused by prospecting activities.
- Prospecting will be undertaken by specialist sub contractors and it is not anticipated that employment opportunities for local and / or regional communities will result from the prospecting activities.

viii. THE POSSIBLE MITIGATION MEASURES THAT COULD BE APPLIED AND THE LEVEL OF RISK.

(With regard to the issues and concerns raised by affected parties provide a list of the issues raised and an assessment/ discussion of the mitigations or site layout alternatives available to accommodate or address their concerns, together with an assessment of the impacts or risks associated with the mitigation or alternatives considered).

No adverse environmental or social impacts associated with the prospecting activity have been identified through the Scoping & EIR process. Mitigation measures as set out in the Environmental Management Programme (EMPr) attached in Part B must be implemented in order to minimise any potential impacts.

All comments received during the review period of the Scoping and EIR report, as well as response provided is captured and recorded within the Comments and Response Report and will be attached in the final EIR.

ix. MOTIVATION WHERE NO ALTERNATIVE SITES WERE CONSIDERED.

This alternative asks the question, if there is not, from an environmental perspective, a more suitable location for the proposed activity. No other properties have been secured by **Kimswa Mining (Pty) Ltd** near Postmasburg on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province is preferred due to the sites underlying diamond bearing gravel, therefore there will be no other alternative (i.e. to facilitate the movement of machinery, equipment, infrastructure).

x. STATEMENT MOTIVATING THE ALTERNATIVE DEVELOPMENT LOCATION WITHIN THE OVERALL SITE. (Provide a statement motivating the final site layout that is proposed)

Design alternatives were considered throughout the planning and design phase (i.e. where is the rock bed located?). In this regard discussions on the design were held between the

EAP and the developer. The layout follows the limitations of the site and aspects such as, roads, site offices and workshop area as well as fencing.

H. FULL DESCRIPTION OF THE PROCESS UNDERTAKEN TO IDENTIFY, ASSESS AND RANK THE IMPACTS AND RISKS THE ACTIVITY WILL IMPOSE ON THE PREFERRED SITE (IN RESPECT OF THE FINAL SITE LAYOUT PLAN) THROUGH THE LIFE OF THE ACTIVITY.

i. A description of all environmental issues and risks that are identified during the environmental impact assessment process

Process for the identification of key issues

The methodology for the identification of key issues aims, as far as possible, to provide a user-friendly analysis of information to allow for easy interpretation.

- Checklist: The checklist consists of a list of structured questions related to the environmental parameters and specific human actions. They assist in ordering thinking, data collection, presentation and alert against the omission of possible impacts.
- Matrix: The matrix analysis provides a holistic indication of the relationship and interaction between the various activities, development phases and the impact thereof on the environment. The method aims at providing a first order cause and effect relationship between the environment and the proposed activity. The matrix is designed to indicate the relationship between the different stressors and receptors which leads to specific impacts. The matrix also indicates the specialist studies, which will be submitted as part of the Environmental Impact Report in order to address the potentially most significant impacts.

Checklist analysis

The table below provides a checklist, which is designed to stimulate thought regarding possible consequences of specific actions and so assist scoping of key issues. It consists of a list of structured questions related to the environmental parameters and specific human actions. They assist in ordering thinking, data collection, presentation and alert against the omission of possible impacts. The table highlights certain issues, which are further analysed in matrix format.

Table: Environmental checklist

QUESTION	YES	NO	Un-	Description
1. Are any of the following located on the site	earma	rked f	sure for the	development?
I. A river, stream, dam or wetland	×			The proposed area consists Rietpan, dam, reservoirs & tributaries from a pan. Where applicable a Water Use License Application will be launched for conducting mining operations. All infrastructure will be temporary and/or mobile.
II. A conservation or open space area		×		None.
III. An area that is of cultural importance			×	
IV. Site of geological significance		×		
V. Areas of outstanding natural beauty		×		None.
VI. Highly productive agricultural land		×		None

VII. Floodplain		×		None
VIII. Indigenous forest		×		None.
IX. Grass land		×		None.
X. Bird nesting sites	×			Due to site having dense woodland, birds nests are expect/may be found on site.
XI. Red data species			×	
XII. Tourist resort		×		None.
2. Will the project potentially result in poter	itial?	<u> </u>	•	l
I. Removal of people		×		None.
II. Visual Impacts	×			The visual impact will be managed; however it may be difficult since the site is situated next to the road
III. Noise pollution		×		The noise impact is unlikely to be significant.
IV. Construction of an access road		×		None. Access will be obtained from gravel road off the R385
V. Risk to human or valuable ecosystems due to explosion/fire/ discharge of waste into water or air.		×		None.
VI. Accumulation of large workforce (>50 manual workers) into the site.		×		Approximately 15 employment opportunities will be created during the construction and operational phase of the project.
VII. Utilisation of significant volumes of local raw materials such as water, wood etc.	×			The application area will use 1 x 16 feet washing pans, the amount of water for the pans will be 17 000 L/hour from which 30% is re-used.
VIII. Job creation	×			Approximately 15 employment opportunities will be created during the construction and operational phase of the project.
IX. Traffic generation		×		None.
X. Soil erosion		×		Only areas earmarked for mining will be cleared. Mining will be phased and the topsoil stockpiled separately. Concurrent rehabilitation will take place. The soil also has a low erosion potential.
XI. Installation of additional bulk telecommunication transmission lines or facilities		×		None.
3. Is the proposed project located near the fe	ollowing	g?		I
I. A river, stream, dam or wetland		×		
II. A conservation or open space area		×		None.
III. An area that is of cultural importance		×		None.
IV. A site of geological significance		×		None.
V. An area of outstanding natural beauty		×		None.

VI. Highly productive agricultural land		×	Yes
VII. A tourist resort		×	None.
VIII. A formal or informal settlement	×		Lime Acres

<u>Matrix analysis</u>

The matrix describes the relevant listed activities, the aspects of the development that will apply to the specific listed activity, a description of the environmental issues and potential impacts, the significance and magnitude of the potential impacts, and the mitigation of the potential impacts. The matrix also highlights areas of particular concern, which requires more in depth assessment. Each cell is evaluated individually in terms of the nature of the impact, duration and its significance – should no mitigation measures be applied. This is important since many impacts would not be considered insignificant if proper mitigation measures were implemented. The matrix also provides an indication if mitigation measures are available.

In order to conceptualise the different impacts the matrix specify the following:

- **Stressor**: Indicates the aspect of the proposed activity, which initiates and cause impacts on elements of the environment.
- **Receptor**: Highlights the recipient and most important components of the environment affected by the stressor.
- **Impacts**: Indicates the net result of the cause-effect between the stressor and receptor.
- Mitigation: Impacts need to be mitigated to minimise the effect on the environment.

I. AN ASSESSMENT OF EACH IDENTIFIED POTENTIALLY SIGNIFICANT IMPACT AND RISK

LISTED ACTIVITY (The Stressor)	ASPECTS OF THE DEVELOPMENT /ACTIVITY			POT	ENTIAL IMPACTS	MA	IFICANCI GNITUDE NTIAL IM	OF	MITIGATION OF POTENTIAL IMPACTS Possible Mitigation	SPECIALIST STUDIES / INFORMATION
			Receptors		Impact description	Minor	Major	Durati on		
			(CONST	RUCTION PHASE			<u> </u>		
Listing Notice GNR 325, Activity 15: "The clearance of an area of 20 hectares or more, of indigenous vegetation."	need to be cleared, topsoil will be		Fauna & Flora		Loss or fragmentation of indigenous natural vegetation. Loss of sensitive species. Loss or fragmentation of habitats.		-	L	Yes	-
			Air	•	Air pollution due to the increase of traffic of construction vehicles.	-		М	Yes	-
		IRONMENT	Soil	• •	Soil degradation, including erosion. Loss of topsoil. Disturbance of soils and existing land use (soil compaction).		-	S	Yes	-
		BIOPHYSICAL ENVIRONMENT	Geology	•	It is not foreseen that the removal of indigenous vegetation will impact on the geology or vice versa.		-	S	Yes	-
			Existing services infrastructure		Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the local sewage plant.		-	S	Yes	-
		B	Ground water	•	Pollution due to construction vehicles.	-		S	Yes	-
			Surface water	•	Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams).		-	S	Yes	-
		NMENT	Local unemploymen t rate	•	Job creation. Business opportunities. Skills development.		+	S	Yes	-
			Visual landscape	•	Potential visual impact on residents of farmsteads and motorists in close proximity to proposed facility.	-		L	Yes	-
		IVIRC	Traffic volumes	•	Increase in construction vehicles.	-		S	Yes	-
		SOCIAL/ECONOMIC ENVIRONMENT	Health & Safety	• • •	Air/dust pollution. Road safety. Increased risk of veld fires.		-	S	Yes	-
			Noise levels	•	The generation of noise as a result of construction vehicles, the use of machinery such as drills, excavators, rotary pans, dumper trucks and people working on the site.	-		L	Yes	-
			Tourism industry	•	Since there are no tourism facilities in close proximity to the site, the construction activities will not have an impact on tourism in the area.	N/A	N/A	N/A	Yes	-

		Heritage resources	•	Removal or destruction of archaeological and/or paleontological sites. Removal or destruction of buildings, structures, places and equipment of cultural significance. Removal or destruction of graves, cemeteries and burial grounds.	-		S	Yes	-
Listing Notice GNR 325,Site clearing and preparationActivity 19: "The removalAreas earmarked for prospecting will need to be cleared, topsoil will be stockpiled separately.		Fauna & Flora	•	Loss or fragmentation of indigenous natural vegetation. Loss of sensitive species. Loss or fragmentation of habitats.		-	L	Yes	-
contemplated in terms of contemplated in terms of of indigenous vegetation located on the		Air quality	٠	Air pollution due to the increase of traffic.	-		М	Yes	-
section 20 of the Mineral and Petroleumsite.PetroleumResourcesDevelopment Act, 2002 (Act No. 28 of 2002), including—	BIOPHYSICAL ENVIRONMENT	Soil	•	Soil degradation, including erosion. Disturbance of soils and existing land use (soil compaction). Loss of agricultural potential (low significance relative to agricultural potential of the site).		-	М	Yes	-
Listing Notice GNR 325, Activity 20: "Any activity	CAL ENV	Geology	•	It is not foreseen that the removal of	N/A	N/A	N/A	N/A	-
including the operation of that activity which requires a prospecting right in terms of	BIOPHYSI	Existing services infrastructure	•	Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the local sewage plant.	-		М	Yes	-
section 16 of the Mineral and		Ground water	•	Pollution due to construction vehicles.			S	Yes	-
PetroleumResourcesDevelopment Act, 2002 (ActNo. 28 of 2002), including—		Surface water	•	Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams).	-		М	Yes	-
	MENT	Local unemploymen t rate	• •	Job creation.		+	S	N/A	-
	ENVIRONMENT	Visual landscape	•	Since there are no tourism facilities in close proximity to the site, the construction activities will not have an impact on tourism in the area.	-		М	Yes	-
	OMIC	Traffic volumes	•	Increase in construction vehicles.	-		S	Yes	-
	SOCIAL/ECONOMIC	Health & Safety	•	Air/dust pollution. Road safety.	-		S	Yes	-
		Noise levels	•	The generation of noise as a result of construction vehicles, and people working on the site.	-		М	Yes	-
		Tourism industry	•	Since there are no tourism facilities in close proximity to the site, the construction activities will not have an impact on tourism in the area.	N/A	N/A	N/A	N/A	-
		Heritage resources	•	Removal or destruction of archaeological and/or paleontological sites. Removal or destruction of buildings, structures, places and equipment of cultural significance.	N/A	N/A	N/A	N/A	-

				•	Removal or destruction of graves, cemeteries and burial grounds.					
				OPERA	TIONAL PHASE					
Activity 19: "The removal and disposal of minerals contemplated in terms of	The key components of the proposed project are described below:		Fauna & Flora	•	Fragmentation of habitats. Establishment and spread of declared weeds and alien invader plants (operations).		-	L	Yes	-
section 20 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002), including—	• <u>Supporting Infrastructure</u> - A control facility with basic services such as water and electricity will be constructed on the site and		Air quality	•	Air pollution due to the mining activity, crusher plant and transport of the gravel to the designated areas.	-		S	Yes	-
(a) associated infrastructure, structures and earthworks, directly related to prospecting of a mineral resource [,]; or (b) [including	will have an approximate footprint 50m ² or less. Other supporting infrastructure includes a site office and workshop area.		Soil	•	Soil degradation, including erosion. Disturbance of soils and existing land use (soil compaction). Loss of agricultural potential (low significance relative to agricultural potential of the site).		-	L	Yes	-
 activities for which an exemption has been issued in terms of section 106 of the Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)] the primary processing of a mineral resource including winning, extraction, classifying, concentrating, crushing, screening or Roads – Access will be obtained from gravel road off the R385 <u>Fencing</u> - For health, safety and security reasons, the facility will be required to be fenced off from the surrounding farm. 	NVIRONMENT	Geology	• • • • •	Collapsible soil. Seepage (shallow water table). Active soil (high soil heave). Erodible soil. The presence of undermined ground. Instability due to soluble rock. Steep slopes or areas of unstable natural slopes. Areas subject to seismic activity. Areas subject to flooding.		-	L	Yes	-	
secondary processing of a mineral resource, including the smelting, beneficiation, reduction, refining, calcining or gasification of the mineral resource in which case activity 6 in this Notice	washing; but excluding the secondary processing of a mineral resource, including the smelting, beneficiation, reduction, refining, calcining or gasification of the mineral resource in which case	BIOPHYSICAL ENVIRONMENT	Existing services infrastructure		Generation of waste that need to be accommodated at a licensed landfill site. Generation of sewage that need to be accommodated by the municipal sewerage system and the local sewage plant. Increased consumption of water. Approximately 17 000 L/hour		-	L	Yes	-
applies.			Ground water	•	Leakage of hazardous materials. The machinery on site require oils and fuel to function. Leakage of these oils and fuels can contaminate water supplies.		-	L	Yes	-
		Surface water	•	Increase in storm water runoff. The development will potentially result in an increase in storm water run-off that needs to be managed to prevent soil erosion. Destruction of watercourses (pans/dams/streams). Leakage of hazardous materials. The machinery on site require oils and fuel to function. Leakage of these oils and fuels can contaminate water supplies.	-		L	Yes	-	
		SOCIAL/ECON OMIC	Local unemploymen t rate		Job creation. Security guards will be required for 24 hours every day of the week. Skills development.		+	L	Yes	-
		SOCIA	Visual landscape		The proposed portions are used for livestock grazing which will still take place simultaneously with the prospecting		-	L	Yes	-

		Traffic		activity, however this depends on the location of the activity.					
		volumes		distribution.	-		S	Yes	-
		Health & Safety	•	Air/dust pollution. Road safety.		-	S	Yes	-
		Noise levels	•	The proposed development will result in noise pollution during the operational phase.	-	-	L	Yes	-
		Tourism industry	•	Since there are no tourism facilities in close proximity to the site, the decommissioning activities will not have an impact on tourism in the area.	N/A	N/A	N/A	N/A	-
		Heritage resources	•	It is not foreseen that the proposed activity will impact on heritage resources or vice versa.	N/A	N/A	N/A	N/A	-
		DI	COMM	ISSIONING PHASE			1		
- <u>Mine closure</u> During the mine closure the Mine		Fauna & Flora	•	Re-vegetation of exposed soil surfaces to ensure no erosion in these areas.	+		L	Yes	-
its associated infrastructure will b dismantled.	e	Air quality	•	Air pollution due to the increase of traffic of construction vehicles.	-		S	Yes	-
Rehabilitation of biophysical environment	INT	Soil		Backfilling of all voids Placing of topsoil on backfill	+		L	Yes	-
The biophysical environment will rehabilitated.	be MINON	Geology	•	It is not foreseen that the decommissioning phase will impact on the geology of the site or vice versa.	N/A	N/A	N/A	N/A	-
	8 BIOPHYSICAL ENVIRONMENT	Existing services infrastructure	•	Generation of waste that need to be accommodated at the local landfill site.	-		S	Yes	-
	BIG	Ground water	•		-		S	Yes	-
		Surface water	•	Increase in storm water run-off. Pollution of water sources due to soil erosion. Destruction of watercourses (pans/dams/streams).	-		S	Yes	-
	C	Local unemploymen t rate	•	Loss of employment.		-	L	Yes	-
	(ECONOMIC RONMENT	Visual landscape	•	receptors in close proximity to proposed facility.	-		S	Yes	-
		volumes	•		-		S	Yes	-
	SOCIAL	Health & Safety	•	Air/dust pollution. Road safety. Increased crime levels. The presence of mine workers on the site may increase security risks associated with an			L	Yes	-

	increase in crime levels as a result of influx of people in the rural area.				
Noise levels	• The generation of noise as a result of construction vehicles, the use of machinery and people working on the site.		S	Yes	-
Tourism industry	• Since there are no tourism facilities in close proximity to the site, the decommissioning activities will not have an impact on tourism in the area.	N/A	N/A	N/A	-
Heritage resources	• It is not foreseen that the decommissioning phase will impact on N/A any heritage resources.	N/A	N/A	N/A	-

(N/A) No impact (+) Positive Impact (-) Negative Impact (S) Short Term (M) Medium Term (L) Long Term

J. SUMMARY OF THE KEY FINDINGS OF THE ENVIRONMENTAL IMPACT ASSESSMENT

(This summary must be completed if any specialist reports informed the impact assessment and final site layout process and must be in the following tabular form):-

LIST OF STUDIES UNDERTAKEN	RECOMMENDATIONS OF SPECIALIST REPORTS	SPECIALIST RECOMMENDATI ONS THAT HAVE BEEN INCLUDED IN THE EIA REPORT (Mark with an X where applicable)	REPORT WHERE SPECIALIST RECOMMENDATI
Ecological & Wetland Assessment Report Prepared by: P.J du Preez (Ph.D., Pr.Sci.Nat.)	 Upon completion of the Impact Assessment, the following general conclusions were drawn: The results of the impact assessment indicate that although the impacts prior to mitigation may potentially be Moderate, strict and effective implementation of mitigation measures will reduce the impact significance to medium-low, levels. In view of the fact that large portions of the study area and the catchment of the pans and watercourses have already been impacted due to human activities such as previous mining activities, grazing of vegetation, construction of roads, dams, farm steads, etc. It is the opinion of the specialist that should the mitigation measures, be adhered to, the proposed mining activities may have a lower risk to the wetland or riparian resources or natural vegetation within the project site than without the mitigation measures. Recommendations 6.1. The proper rehabilitation of the disturbed areas. 6.2. Remove all exotic vegetation that occur on the project site 6.3. Regular monitoring of the disturbed areas must be done to inspect the regrowth of alien plants in the disturbed areas. Vegetation clearing must be done if necessary 	X	

Heritage Impact Assessment (Archaeology) Prepared by: McGregor Museum, Kimberley, Dr. David Morris	 6.4. Permits to remove protected trees must be obtained from DAFF and DENC before the removal of these species. The prospecting and mining and associated operations will have a "moderate" impact on the above-ground ecology of the site as some areas are already partly degraded. On undisturbed areas the impact will be higher. The impacts such as erosion potential, dust generation and spread of alien weeds can be lowered if mitigated properly. The project site has a low ecological sensitivity because of the presence of several man-made impacts on the site. The area proposed for prospecting was partially inspected on foot on 13-17 May 2019. Access could not be gained to the property. 		
Palaeontological Desktop Assessment Prepared by: Banzai Environmental (Pty) Ltd, Elize Butler	SUMMARY OF IMPACT TABLES The proposed development is completely underlain by the Ongeluks Formation, Postmasburg Group and the Asbestos Hills Subgroup, Ghaap Group of the Transvaal Supergroup. The Palaeontological Sensitivity of this formation is rated Moderate. The expected duration of the impact is assessed as potentially permanent to long term. In the absence of mitigation procedures (should fossil material be present within the affected area) the damage or destruction of any palaeontological materials will be permanent . Impacts on palaeontological heritage during the construction phase could potentially occur but are regarded as having a low possibility.	X	
	FINDINGS AND RECOMMENDATIONS The proposed Kimswa Mine development is completely underlain by the Ongeluks Formation, Postmasburg Group and the Asbestos Hills Subgroup, Ghaap Group of the Transvaal Supergroup. According to the PalaeoMap of South African Heritage Resources Information System the Palaeontological Sensitivity of the Ongeluks		

Formation as well as the Asbestos Hills Subgroup is moderate. It is therefore considered that the prospecting right application near near Postmasburg Northern Cape Province is deemed appropriate and feasible and will not lead to detrimental impacts on the palaeontological resources of the area. Thus, the construction and operation of the facility may be authorised as the whole extent of the development footprint is not considered sensitive in terms of palaeontological resources.	
In the event that fossil remains are discovered during any phase of construction, either on the surface or exposed by fresh excavations, is essential that the ECO in charge for these developments must be informed immediately. These discoveries must be protected (preferably <i>in situ</i>) and the ECO must alert SAHRA (South African Heritage Research Agency) so that mitigation (recording and collection) can be under taken by a paleontologist.	
The specialist would need a collection permit from SAHRA. Fossil material must be curated in an approved collection (museum or university) and all fieldwork and reports must adhere to the minimum standards for palaeontological impact studies developed by SAHRA.	

K. ENVIRONMENTAL IMPACT STATEMENT

- A. This section provides a summary of the assessment and conclusions drawn from the proposed prospecting area. In doing so, it draws on the information gathered as part of the environmental impact assessment process and the knowledge gained by the environmental consultant during the course of the process and presents an informed opinion on the environmental impacts associated with the proposed project. The following conclusions can be drawn for the proposed prospecting activity:
- Potential impacts on biodiversity: According to the critical biodiversity, the proposed farm portions falls within Ecological Support Area and Other Natural Areas. But through implementing mitigation measures, no adverse impacts are expected.
- > Potential impacts on land use: The farm is currently utilised for cattle and game. The activity which will be subject to concurrent rehabilitation will not have any significant impact on the land use nor will it change the sense of place of the area.
- > Potential social impacts: The presence of construction workers poses a potential risk to family structures and social networks. While the presence of construction workers does not in itself constitute a social impact, the manner in which construction workers conduct themselves can impact on local communities. The most significant negative impact is associated with the disruption of existing family structures and social networks.
- > Potential negative impacts: (noise, dust, soil degradation, storm water, traffic, health and safety) associated with the operation of the facility are expected to be of low-medium impact, of medium terms and site specific. These can be mitigated or negated through the implementation of practical and appropriate mitigation measures.
- > Positive impacts: The mining of alluvial diamonds will have socio-economic benefit to the area.

All possible negative impacts and risks that have been identified in this report can be effectively mitigated and managed by implementing the migratory measures as set out in the Environmental Management Programme (EMPr) attached in Part B. It is therefore recommended that the environmental authorisation for the prospecting right be granted.

B. Final Site Map

Provide a map at an appropriate scale which superimposes the proposed overall activity and its associated structures and infrastructure on the environmental sensitivities of the preferred site indicating any areas that should be avoided, including buffers.

Refer to Site layout Map attached in Appendix 4.

C. Summary of the positive and negative implications and risks of the proposed activity and identified alternatives

There are regional socio economic benefits due to the alluvial diamonds being prospected in the Northern Cape Province and greater knowledge is gained on the mineralogy of South Africa. All possible negative impacts and risks that have been identified in this report can be effectively mitigated and managed by implementing the mitigation measures as set out in the Environmental Management Programme (EMPr) attached in Part B. No significantly adverse social or environmental impacts are anticipated.

L. PROPOSED IMPACT MANAGEMENT OBJECTIVES AND THE IMPACT MANAGEMENT OUTCOMES FOR INCLUSION IN THE EMPR

Based on the assessment and where applicable the recommendations from specialist reports, the recording of proposed impact management objectives, and the impact management outcomes for the development for inclusion in the EMPr as well as for inclusion as conditions of authorisation.

Management objectives include:

- Ensure that the prospecting activity does not cause pollution to the environment or harm to persons.
- Minimise production of waste.
- > All prospecting activities must be conducted in a manner that minimises noise impact, litter, environmental degradation and health hazards i.e. injuries.
- > The mine must be kept neat and tidy during waste handling to prevent unsightliness and accidents.

Expected outcomes include:

- > Minimum impacts on the environment as a result of alluvial diamond prospecting.
- > Compliance with legislative requirements.
- > Mine is neat and tidy and well managed.

M. FINAL PROPOSED ALTERNATIVES.

(Provide an explanation for the final layout of the infrastructure and activities on the overall site as shown on the final site map together with the reasons why they are the final proposed alternatives which respond to the impact management measures, avoidance, and mitigation measures identified through the assessment)

This alternative asks the question, if there is not, from an environmental perspective, a more suitable location for the proposed activity. No other properties have been secured by **Kimswa Mining (Pty) Ltd** on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province is preferred due to the sites underlying alluvial diamond bearing gravel, therefore there will be no other alternative (i.e. to facilitate the movement of machinery, equipment, infrastructure).

N. ASPECTS FOR INCLUSION AS CONDITIONS OF AUTHORISATION.

Any aspects which have not formed part of the EMPr that must be made conditions of the Environmental Authorisation

- > The operational activities and relevant rehabilitation of disturbed areas should be monitored against the improved EMPr and all other relevant environmental legislation.
- > A copy of the EMP should be made available onsite at all times.
- > Implementation of the proposed mitigation measures set out in the EMPr.

O. DESCRIPTION OF ANY ASSUMPTIONS, UNCERTAINTIES AND GAPS IN KNOWLEDGE. (Which relate to the assessment and mitigation measures proposed)

The uncertainties in results are mostly related to the availability of information, time available to gather the relevant information as well as the sometimes subjective nature of the assessment methodology. In terms of addressing the key issues the EAP is satisfied that there are no major gaps in knowledge and that the specialist reports provide sufficient information to conduct the significance rating and provide the environmental authority with sufficient information to make an informed decision.

P. REASONED OPINION AS TO WHETHER THE PROPOSED ACTIVITY SHOULD OR SHOULD NOT BE AUTHORISED

Reasons why the activity should be authorized or not.

It is the opinion of the EAP that the activity may be authorised. Based on that the official will take into consideration all aspects of the application & the specialist inputs.

Based on the outcomes of other diamond mines in the area, the possibility to encounter further Diamond Reserves were identified.

The proposed prospecting area is targeted as, historically, several alluvial diamond occurrences are known in the area, and a number of these have been exploited in the past. There are also various alluvial diamond operations within the vicinity of the exploration area.

No other properties have been secured by the applicant and the site is therefore regarded as the preferred site, and alternatives are not considered.

The option of not approving the activities will result in a significant loss to valuable diamond deposits being exploited. And all economic benefits will be lost.

Q. CONDITIONS THAT MUST BE INCLUDED IN THE AUTHORISATION

- > The operational activities and relevant rehabilitation of disturbed areas should be monitored against the improved EMPr and all other relevant environmental legislation.
- A copy of the EMP should be made available onsite at all times.
- > Implementation of the proposed mitigation measures set out in the EMPr.

The EMPr should be binding on all managers and contractors operating/utilizing the site.

Period for which the Environmental Authorisation is required.

For a minimum of 5 years.

R. UNDERTAKING

Confirm that the undertaking required to meet the requirements of this section is provided at the end of the EMPr and is applicable to both the Basic assessment report and the Environmental Management Programme report.

The undertaking required to meet the requirements of this section is provided at the end of the EMPr and is applicable to both the Environmental Impact Assessment report and the Environmental Management Programme report.

I, Percy Sehaole (EAP) herewith confirms

- **A.** the correctness of the information provided in the reports \bigotimes
- **B.** the inclusion of comments and inputs from stakeholders and I&APs ; \square
- **C.** the inclusion of inputs and recommendations from the specialist reports where relevant; \square and
- **D.** the acceptability of the project in relation to the finding of the assessment and level of mitigation proposed;

Rehaole.

Signature of the environmental assessment practitioner:

Milnex CC – Environmental Consultants

Name of company:

27 - 05 - 2019

Date:

S. FINANCIAL PROVISION State the amount that is required to both manage and rehabilitate the environment in respect of rehabilitation.

olicant: Iluators:	KIMSWA MINING (PTY) LTD Milnex CC			Ref No.: Date:	NC30/5/1/1/2/12286PR 16/05/2019		
			Α	в	С	D	E=A*B*C*D
No.	Description	Unit	Quantity	Master Rate	Multiplication factor	-	Amount (Rands)
1	Dismantling of processing plant and related structures (including overland conveyors and pow erlines)	m3	900	14,05	1	1	12645
2 (A)	Demolition of steel buildings and structures	m2	0	195,76	1	1	0
2(B)	Demolition of reinforced concrete buildings and structures	m2	0	288,49	1	1	0
3	Rehabilitation of access roads	m2	1000	35,03	1	1	35030
4 (A)	Demolition and rehabilitation of electrified railw ay lines	m	0	340,01	1	1	0
4 (A)	Demolition and rehabilitation of non-electrified railw ay lines	m	0	185,46	1	1	0
5	Demolition of housing and/or administration facilities	m2	0	391,53	1	1	0
6	Opencast rehabilitation including final voids and ramps	ha	0,8	205242,16	0,52	1	85380,73856
7	Sealing of shafts adits and inclines	m3	0	105,09	1	1	0
8 (A)	Rehabilitation of overburden and spoils	ha	0,1	136828,1	1	1	13682,81
8 (B)	Rehabilitation of processing waste deposits and evaporation ponds (non-polluting potential)		0,06	170416,93	1	1	10225,0158
8(C)	Rehabilitation of processing waste deposits and evaporation	ha	0	494971,55	1	1	0
9	Rehabilitation of subsided areas	ha	0,06	114572,93	1	1	6874,3758
10	General surface rehabilitation	ha	0,1	108390,94	1	1	10839,094
11	River diversions	ha	0	108390,94	1	1	0
12	Fencing	m	0	123,64	1	1	0
13	Water management	ha	0	41213,28	1	1	0
14	2 to 3 years of maintenance and aftercare	ha	0,34	14424,65	1	1	4904,381
15 (A)	Specialist study	Sum	0			1	0
15 (B)	Specialist study	Sum				1	0
					Sub Tot	al 1	179581,4152
1	Preliminary and General	21549,76982 weighting fac		factor 2	21549,76982		
2	Contingencies			1795	8,14152		17958,14152
	· · · ·		-		Subtota	al 2	219089,33
					VAT (1	5%)	32863,40
					Grand T	otal	251953

Explain how the aforesaid amount was derived. А.

The closure cost estimate provided above is aligned with the Guideline Document for the Evaluation of Quantum of Closure related Financial Provision Provided by a Mine, by the DMR (January, 2005). The amount was calculated by Milnex CC.

B. Confirm that this amount can be provided for from operating expenditure. (Confirm that the amount, is anticipated to be an operating cost and is provided for as such in the Mining work programme, Financial and Technical Competence Report or Prospecting Work Programme as the case may be).

Financial Guarantee

The financial guarantee for the rehabilitation for land disturbed by **Kimswa Mining (Pty) Ltd** will be submitted

Rehabilitation Fund

Kimswa Mining (Pty) Ltd will also make provision for rehabilitation during closure by establishing a rehabilitation trust.

T. DEVIATIONS FROM THE APPROVED SCOPING REPORT AND PLAN OF STUDY.

A. Deviations from the methodology used in determining the significance of potential environmental impacts and risks.

None of the methodologies approved for the scoping report were deviated

B. Motivation for the deviation.

Not applicable

U. OTHER INFORMATION REQUIRED BY THE COMPETENT AUTHORITY

V. COMPLIANCE WITH THE PROVISIONS OF SECTIONS 24(4)(A) AND (B) READ WITH SECTION 24 (3) (A) AND (7) OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT (ACT 107 OF 1998). THE EIA REPORT MUST INCLUDE THE:

1. Impact on the socio-economic conditions of any directly affected person. (Provide the results of Investigation, assessment, and evaluation of the impact of the mining, bulk sampling or alluvial diamond prospecting on any directly affected person including the landowner, lawful occupier, or, where applicable, potential beneficiaries of any land restitution claim, attach the investigation report as **Appendix 2.19.1** and confirm that the applicable mitigation is reflected in 2.5.3; 2.11.6.and 2.12.herein).

The diamonds alluvial prospecting will not impact directly on any socio-economic aspects. Indirect socio-economic benefits are expected to be associated with the creation of employment.

2. Impact on any national estate referred to in section 3(2) of the National Heritage Resources Act. (Provide the results of Investigation, assessment, and evaluation of the impact of the mining, bulk sampling or alluvial diamond prospecting on any national estate referred to in section 3(2) of the National Heritage Resources Act, 1999 (Act No. 25 of 1999) with the exception of the national estate contemplated in section 3(2)(*i*)(vi) and (vii) of that Act, attach the investigation report as **Appendix 2.19.2** and confirm that the applicable mitigation is reflected in 2.5.3; 2.11.6.and 2.12.herein).

The diamonds alluvial prospecting will not impact on any heritage estate referred to in section 3(2) of the National Heritage Resources Act. In terms of the National Heritage Resource Act no 25 of 1999. Heritage resources including archaeological and paleontological sites over 100 years old, graves older than 60 years, structure older than 60 years are protected. They may not be disturbed without a permit from the relevant heritage resource Authority, which means that before such sites are disturbed by development it is incumbent on the developer to ensure that a heritage impact assessment is done and the Provincial Heritage Resources Authority and SAHRA will be contacted immediately and work will stop

Other matters required in terms of sections 24(4)(a) and (b) of the Act.

(the EAP managing the application must provide the competent authority with detailed, written proof of an investigation as required by section 24(4)(b)(i) of the Act and motivation if no reasonable or feasible alternatives, as contemplated in sub-regulation 22(2)(h), exist. The EAP must attach such motivation as **Appendix 4**).

From on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province is preferred due to the sites underlying geology and the shallowness of the diamond bearing gravel to the surface as well as site access (i.e. to facilitate the movement of machinery, equipment, infrastructure and people). No other properties have been secured by **Kimswa Mining (Pty) Ltd** The specific site has been chosen for its mineral resources thus making an alternative site selection null and void.

PART B

ENVIRONMENTAL MANAGEMENT PROGRAMME REPORT

1) ENVIRONMENTAL MANAGEMENT PROGRAMME

Name of Practitioner	Qualifications	Contact details
Ms. Percy Sehaole	Master's Degree in	Tel No.: (018) 011 1925
	Environmental Science (refer	Fax No. : (053) 963 2009
	to Appendix 1)	e-mail address: <u>percy@milnex-sa.co.za</u>

It is hereby confirmed that the requirements for the provision of the details and expertise of the EAP are contained in Part A, section 1(a) as required. The Curriculum Vitae for the responsible EAP is contained in **Appendix 1 and 2**.

B. **DESCRIPTION OF THE ASPECTS OF THE ACTIVITY** (Confirm that the requirement to describe the aspects of the activity that are covered by the draft environmental management programme is already included in PART A, section (1)(h) herein as required).

It is hereby confirmed that the requirements to describe the aspects of the activity that are required by the EMP is already included in Part A, section 1(h).

C. COMPOSITE MAP

(Provide a map **(Attached as an Appendix**) at an appropriate scale which superimposes the proposed activity, its associated structures, and infrastructure on the environmental sensitivities of the preferred site, indicating any areas that any areas that should be avoided, including buffers)

Refer to Locality Map, attached as in Appendix 4.

D. DESCRIPTION OF IMPACT MANAGEMENT OBJECTIVES INCLUDING MANAGEMENT STATEMENTS

i) **Determination of closure objectives.** (ensure that the closure objectives are informed by the type of environment described in 2.4 herein)

Closure objectives for the alluvial diamond mine will aim to ensure that the residual postclosure impacts be minimized and be acceptable to relevant parties. To achieve these closure objectives, the following will be implemented:

- All prospecting related infrastructure, foundations and concrete areas will be decommissioned, removed from the site and appropriately disposed of. Reclaimable structures such as metal, electrical installations or equipment will be sold for re-use or as scrap.
- All disturbed areas within the site not already vegetated will be re-vegetated with appropriate indigenous, ecologically adapted species appropriate to the area and the final land use as soon as possible after operation ceases. Progress of vegetation growth/establishment,

stability and drainage/erosion will be monitored and, in the event of adverse trends being identified, corrective measures will be implemented.

- Vegetation monitoring will consider, inter alia, the establishment of perennial ground cover and infestation by alien invasive plant species. The encroachment of indigenous vegetation into the area will be used as an indication of a stable, self-sustaining vegetation cover with little risk of retrogressing to a situation where are and water pollution may occur.
- Final landforms must be resilient to perturbation and also be self-sustaining to obviate/limit further/ongoing interventions and maintenance by **Kimswa Mining (Pty) Ltd** The remaining impacts be of an acceptable nature with minimal deterioration over time.
- The final outcome of the mine site rehabilitation would be productive systems, where required sustaining either cattle or wildlife.
- Environmental and human quality of life, including health and safety requirements in general, would not be compromised; and
- Closure is achieved in an efficient and cost-effective manner as possible and with minimum socioeconomic changes.

The above goal is underpinned by more specific objectives listed below.

1. Upfront planning/development

To provide overall guidance and direction to closure planning and/or the implementation of progressive closure measures over the remaining over the prospecting life.

2. Physical stability

To ensure that surface infrastructure and prospecting residue and/or disturbances that are present at processing plant decommissioning will be removed and/or stabilised in a manner that these will not compromise post-closure land use and be sustainable long-term landforms.

- Closure, removal and disposal of all surface infrastructure that has no beneficial post-closure use.
- Shaping and vegetating the remaining earth embankments, trenches, etc. to stabilise slopes and integrate with surrounding topography.

3. Environmental quality

To ensure that local environmental quality is not adversely affected by possible physical effects arising from prospecting operations and the prospecting site after closure. This will be achieved by:

- Avoiding and/or limiting the following during prospecting operations which could result in adverse effects that could not be readily addressed and/or mitigated at mine closure.
 - Dust fall-out areas surrounding the prospecting site.
- Wash-off and/or mobilisation of chemically contaminated soils and sediments from the prospecting site that could have long term adverse effects on local aquatic health and/or other water uses.
- Possible shallow groundwater contamination adversely affecting the quality of the local water resource and its beneficial use.
 - Limiting the potential for dust generation on the rehabilitated prospecting site that could cause nuisance and/or health effects to surrounding landowners;
 - Limiting the possible adverse water quality and quantity effects arising from the rehabilitated prospecting site to ensure that long term beneficial use of local resources is not compromised;
 - Conducting soil clean-up/remediation to ensure that the planned land use could be implemented and maintained;

4. Health and safety

- To limit the possible health and safety treats due to terrain hazards to humans and animals utilizing the rehabilitated prospecting site after closure by:
- Demonstrating through upfront soil testing that any resultant inorganic and organic pollution present on the site is acceptable;
- Removal of potential contaminants such as hydrocarbons and chemicals off site;
- Shaping of embankments and trenches to safe slopes and reintegrating of these into surrounding topography.

• Ensuring that the environmental quality as reflected above is achieved.

5. Land capability / land use

To ensure that the required land capability to achieve and support the planned land use can be achieved over the prospecting site by:

- Clean-up and reclamation of contaminated soil areas in order not to compromise the above land use planning earmarked for implementation;
- To ensure that the overall rehabilitated prospecting site is free draining
- Transferring prospecting related surface infrastructure to third parties for beneficial use after closure.

6. Aesthetic quality

To ensure that the rehabilitated prospecting site will display, at a minimum, an acceptable aesthetic appearance that would not compromise the planned land use by leaving behind:

- A prospecting area that is properly cleared-up with no fugitive/scattered waste piles
- Rehabilitated prospecting area that is free draining and disturbed areas that are suitably vegetated.
- Rehabilitated prospecting residues that are suitably landscaped, blending with the surrounding environment as far as possible.
- Shaped and rehabilitated terrace and hard stand areas, roughly emulating the local natural surface topography.

7. Landscape viability

To create a landscape that is self-sustaining and over time will evolve/converge to the desired ecosystem structure, function and composition by:

- Conducing surface profiling, with associated material movement optimisation, to obtain a landscape resembling the natural landscapes to support the succession trajectory towards a climax ecological system.
- Establishing woody patches and create "rough and loose" areas for pioneer specie establishment around the respective patches.
- Establishing pioneer species as follows:
- Collected and prepared seeds for broad casting;
- Seedlings grown on on-site nursery;
- Cuttings collected from surrounding veld areas;
- Conducting rehabilitation monitoring and corrective action as required.

8. Biodiversity

To encourage, where appropriate, the re-establishment of native vegetation on the rehabilitated mine site such the terrestrial biodiversity is largely re-instated over time, by:

- Stabilising disturbed areas to prevent erosion in the short- to medium term until a suitable vegetation cover has established; and
- Establishing viable self-sustaining vegetation communities of local fauna, as far as possible.

Provide a rehabilitation plan that describes and shows the scale and aerial extent of the main mining activities, including the anticipated mining area at the time of closure.

The Rehabilitation & Closure Plan is attached as Appendix 8.

Calculate and state the quantum of the financial provision required to manage and rehabilitate the environment in accordance with the applicable guideline.

	CALCULATION OF THE QUANTUM									
pplicant: valuators:	KIMSWA MINING (PTY) LTD Milnex CC				Ref No.: Date:	NC30/5/1/1/2 16/05/2019	/12286PR			
			Α	В	С	D	E=A*B*C*D			
No.	Description	Unit	Quantity	Master Rate	Multiplication factor	Weighting factor 1	Amount (Rands)			
1	Dismantling of processing plant and related structures (including overland conveyors and pow erlines)	m3	900	14,05	1	1	12645			
2 (A)	Demolition of steel buildings and structures	m2	0	195,76	1	1	0			
2(B)	Demolition of reinforced concrete buildings and structures	m2	0	288,49	1	1	0			
3	Rehabilitation of access roads	m2	1000	35,03	1	1	35030			
4 (A)	Demolition and rehabilitation of electrified railw ay lines	m	0	340,01	1	1	0			
4 (A)	Demolition and rehabilitation of non-electrified railw ay lines	m	0	185,46	1	1	0			
5	Demolition of housing and/or administration facilities	m2	0	391,53	1	1	0			
6	Opencast rehabilitation including final voids and ramps	ha	0,8	205242,16	0,52	1	85380,73856			
7	Sealing of shafts adits and inclines	m3	0	105,09	1	1	0			
8 (A)	Rehabilitation of overburden and spoils	ha	0,1	136828,1	1	1	13682,81			
8 (B)	Rehabilitation of processing w aste deposits and evaporation ponos (non-poliuling potential)		0,06	170416,93	1	1	10225,0158			
8(C)	Rehabilitation of processing waste deposits and evaporation	ha	0	494971,55	1	1	0			
9	Rehabilitation of subsided areas	ha	0,06	114572,93	1	1	6874,3758			
10	General surface rehabilitation	ha	0,1	108390,94	1	1	10839,094			
11	River diversions	ha	0	108390,94	1	1	0			
12	Fencing	m	0	123,64	1	1	0			
13	Water management	ha	0	41213,28	1	1	0			
14	2 to 3 years of maintenance and aftercare	ha	0,34	14424,65	1	1	4904,381			
15 (A)	Specialist study	Sum	0			1	0			
15 (B)	Specialist study	Sum				1	0			
					Sub Tot	al 1	179581,4152			
1	Preliminary and General	21549,76982		weighting factor 2		21549,76982				
2	Contingencies	1795	8,14152		17958,14152					
					Subtota	al 2	219089,33			
					VAT (15	5%)	32863,40			
					Grand T	otal	251953			

a. Confirm that the financial provision will be provided as determined.

Financial Guarantee

The financial guarantee for the rehabilitation for land disturbed **Kimswa Mining (Pty) Ltd** will be submitted

Rehabilitation Fund

Kimswa Mining (Pty) Ltd will also make provision for rehabilitation during closure by establishing a rehabilitation trust.

E. IMPACTS TO BE MITIGATED IN THEIR RESPECTIVE PHASES

Measures to rehabilitate the environment affected by the undertaking of any listed activity

ACTIVITIES	PHASE	SIZE AND	MITIGATION MEASURES	COMPLIANCE WITH	TIME PERIOD FOR	
(E.g. For prospecting - drill site, site camp, ablution facility, accommodation, equipment storage, sample storage, site office, access route	(of operation in which activity will take place.	SCALE of disturbance (volumes, tonnages and hectares or m ²)	(describe how each of the recommendations in herein will remedy the cause of pollution or degradation and migration of	STANDARDS (A description of how each of the	IMPLEMENTATION Describe the time period when the measures in the environmental management programme must be implemented Measures must be	
etcetcetc E.g. For mining,- excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetc)	State; Planning and design, Pre- Construction' Construction, Operational, Rehabilitation, Closure, Post closure).		pollutants) r h v e n s F b c c	pollutants)	recommendations herein will comply with any prescribed environmental management standards or practices that have been identified by Competent Authorities)	implemented measures indict be implemented when required. With regard to Rehabilitation specifically this must take place at the earliest opportunityWith regard to Rehabilitation, therefore state either: Upon cessation of the individual activity Or. Upon the cessation of mining, bulk sampling or alluvial diamond prospecting as the case may be.
Clearance of vegetation	Pitting and trenching phase- (construction and operation phase)	734.4887 Ha – 3m x 2m x 4m (100 pits), 30m x 20m x 2.5m (26 trenches)	 Site clearing must take place in a phased manner, as and when required. Areas which are not to be prospected on within two months must not be cleared to reduce erosion risks. The area to be cleared must be clearly demarcated and this footprint strictly maintained. Spoil that is removed from the site must be removed to an approved spoil site or a licensed landfill site. 	Compliance with Duty of Care as detailed within NEMA	Duration of operations on the prospecting activities.	

			5. The necessary silt fences and erosion control measures must be implemented in areas where these risks are more prevalent.
Construction of roads	Pitting and trenching phase- (construction and operation phase)	+- 500m	 Planning of access routes to the site for construction/prospecting purposes shall be done in conjunction with the Contractor and the Landowner. All agreements reached should be documented and no verbal agreements should be made. The Contractor shall clearly mark all access roads. Roads not to be used shall be marked with a "NO ENTRY for prospecting vehicles" sign. Construction routes and required access roads must be clearly defined. Damping down of the unsurfaced roads must be implemented to reduce dust and nuisance. Soils compacted by construction/prospecting activities shall be deep ripped to loosen compacted layers and regraded to even running levels. The contractor must ensure that damage caused by related traffic to the gravel access road off the R385 is repaired continuously. The costs associated with the repair must be borne by the contractor; Dust suppression measures must be implemented for heavy vehicles such as wetting of

			7.	gravel roads on a regular basis and ensuring that vehicles used to transport the gravel are fitted with tarpaulins or covers; All vehicles must be road-worthy and drivers must be qualified and made aware of the potential road safety issues and need for strict speed limits.		
Prospecting of Alluvial Diamonds – Soils and geology	Pitting and trenching phase- (construction and operation phase)	734.4887 Ha – 3m x 2m x 4m (100 pits), 30m x 20m x 2.5m (26 trenches)	2. 3. 4.	The Contractor should, prior to the commencement of earthworks determine the average depth of topsoil (If topsoil exists), and agree on this with the ECO. The full depth of topsoil should be stripped from areas affected by construction and related activities prior to the commencement of major earthworks. This should include the building footprints, working areas and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. Care must be taken not to mix topsoil and subsoil during stripping. The topsoil must be conserved on site in and around the pit/trench area. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric,	Compliance with Duty of Care as detailed within NEMA	Duration of operations on the mine

			depending on the duration of the project. Stockpiles may further be protected by the construction of berms, trenches or low brick walls around their bases. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an		
Prospecting Alluvial Diamonda	Ditting and	724 4997 40	approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. The impact on the geology will be permanent. There is no mitigation measure.	Compliance with	Duration of approximations on the
Prospecting Alluvial Diamonds – excavations and blasting	Pitting and trenching phase- (construction and operation phase)	734.4887 Ha – 3m x 2m x 4m (100 pits), 30m x 20m x 2.5m (26 trenches)	The prospecting activities must aim to adhere to the relevant noise regulations and limit noise to within standard working hours in order to reduce disturbance of dwellings in close proximity to the development. Mine, pans, workshops and other noisy fixed facilities should be located well away from noise sensitive areas. Once the proposed final layouts are made available by the Contractor(s), the sites must be evaluated in detail and specific measures designed in to the system.	Duty of Care as detailed within	Duration of operations on the prospecting area

equipment and processes. An increase in noise emission levels	
very often is a sign of the	
imminent mechanical failure of	
a machine.	

IMPACT MANAGEMENT OUTCOMES

(A description of impact management outcomes, identifying the standard of impact management required for the aspects contemplated in paragraph ();

ACTIVITY (whether listed or not listed). (E.g. Excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines, conveyors, etcetc).	POTENTIAL IMPACT (e.g. dust, noise, drainage surface disturbance, fly rock, surface water contamination, groundwater contamination, air pollution etcetc)	ASPECTS AFFECTED	PHASE In which impact is anticipated (e.g. Construction, commissioning, operational Decommissioning, closure, post- closure)	MITIGATION TYPE (modify, remedy, control, or stop) through (e.g. noise control measures, storm- water control, dust control, rehabilitation, design measures, blasting controls, avoidance, relocation, alternative activity etc. etc) E.g. • Modify through alternative method. • Control through noise control • Control through management and monitoring • Remedy through rehabilitation	STANDARD TO BE ACHIEVED (Impact avoided, noise levels, dust levels, rehabilitation standards, end use objectives) etc.
Clearance of vegetation	Loss or fragmentation of habitats	Fauna & flora	Pitting and trenching phase- (construction and operation phase)	 Existing vegetation Vegetation removal must be limited to the prospecting area. Vegetation to be removed as it becomes necessary rather than removal of all vegetation throughout the site in one step. No vegetation to be used for firewood. 	Minimisation of impacts to acceptable limits

4. Exotic and invasive plant species
should not be allowed to establish, if
the development is approved.
Rehabilitation
5. All damaged areas shall be
rehabilitated upon completion of the
contract.
6. Re-vegetation of the disturbed site is
aimed at approximating as near as
possible the natural vegetative
conditions prevailing prior to
construction.
7. All natural areas impacted during
construction/prospecting must be
rehabilitated with locally indigenous
grasses typical of the representative
botanical unit.
8. Rehabilitation must take place in a
phased approach as soon as
possible.
9. Rehabilitation process must make
use of species indigenous to the
area. Seeds from surrounding seed
banks can be used for re-seeding.
10. Rehabilitation must be executed in
such a manner that surface run-off
will not cause erosion of disturbed
areas.
11. Planting of indigenous tree species
in areas not to be cultivated or built
on must be encouraged.
Demarcation of prospecting area
12. All plants not interfering with
prospecting operations shall be left
undisturbed clearly marked and
indicated on the site plan.
13. The prospecting area must be well
demarcated and no
construction/prospecting activities

must be allowed outside of this	
demarcated footprint.	
14. Vegetation removal must be phased	
in order to reduce impact of	
construction/prospecting.	
15. Site office and laydown areas must	
be clearly demarcated and no	
encroachment must occur beyond	
demarcated areas.	
16. Strict and regular auditing of the	
prospecting process to ensure	
containment of the prospecting and	
laydown areas.	
17. Soils must be kept free of	
petrochemical solutions that may be	
kept on site during	
construction/prospecting. Spillage	
can result in a loss of soil	
functionality thus limiting the re-	
establishment of flora.	
Utilisation of resources	
18. Gathering of firewood, fruit, muti	
plants, or any other natural material	
onsite or in areas adjacent to the site	
is prohibited unless with prior	
is prohibited unless with prior approval of the ECO	
approval of the ECO.	
approval of the ECO.	
approval of the ECO. Exotic vegetation	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled.	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any remaining stockpiles to prevent	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any remaining stockpiles to prevent weed invasion.	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any remaining stockpiles to prevent weed invasion. 21. The spread of exotic species	
approval of the ECO. Exotic vegetation 19. Alien vegetation on the site will need to be controlled. 20. The Contractor should be responsible for implementing a programme of weed control (particularly in areas where soil has been disturbed); and grassing of any remaining stockpiles to prevent weed invasion.	

		ſ		1	1
				 Herbicides 22. Herbicide use shall only be allowed according to contract specifications. The application shall be according to set specifications and under supervision of a qualified technician. The possibility of leaching into the surrounding environment shall be properly investigated and only environmentally friendly herbicides shall be used. 23. The use of pesticides and herbicides on the site must be discouraged as these impact on important pollinator species of indigenous vegetation. Fauna 24. Rehabilitation to be undertaken as soon as possible after the prospecting activities have been completed. 25. No trapping or snaring to fauna on the construction/prospecting site should be allowed. 26. No faunal species must be disturbed, trapped, hunted or killed by maintenance staff during any routine maintenance at the development. 	
Prospecting Alluvial Diamonds– excavations	Loss of topsoil	Soil	Pitting and trenching phase- (construction and operation phase)	1. The Contractor should, prior to the commencement of earthworks determine the average depth of topsoil, and agree on this with the ECO. The full depth of topsoil should be stripped from areas affected by construction and related activities prior to the commencement of major	Minimisation of impacts to acceptable limits

earthworks. This should include the building footprints, working areas and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. 2. Care must be taken not to mix topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windly conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles should be kept clear of weeds and alien vegetation growth by rick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation of soil is experied analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be studened if and when a spillage/leakage occurs should be studened and given to the project manager.	 	
and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. 2. Care must be taken not to mix topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles should be protected by the construction of berms or low brick walls around their bases, 6. Stockpiles should be kept clear of weeds and aline vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be donne prior to disposal of soil to determine the appropriate disposal order. Proof from an approved waste disposal site where contamination of soil as expected, analysis must be donne the appropriate disposal order. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
reused where possible to rehabilitate disturbed areas. 2. Care must be taken not to mix topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If Stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berns or low brick walls around their bases. 6. Stockpiles should be key telear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal oruse. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 rehabilitate disturbed areas. 2. Care must be taken not to mix topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles should be they be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. 		
 2. Care must be taken not to mix topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geolabric, depending on the duration of the project. Stockpiles around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal route. Proof from an approved waste disposal soil to determine the appropriate disposal route. Proof from an approved waste disposal soil when a spillage/leakage occurs should be still be included in environmental 		
 topsoil and subsoil during stripping. 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of between order. 6. Stockpiles should be kept clear of weeds and aller vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal outs. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be induced in environmental 		
 3. The topsoil must be conserved on site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation or good is expected, analysis must be done prior to disposal of soil to determine the approach durated solar of the approach durated and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be induced in environmental 		2. Care must be taken not to mix
 site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of bem sor low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be in environmental 		topsoil and subsoil during stripping.
 site in and around the pit/trench area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of bem sor low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be in environmental 		3. The topsoil must be conserved on
 area. 4. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles and unter bases. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal of soil to determine the appropriate disposal of soil to determine the appropriate disposal of soil to an approver waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		site in and around the pit/trench
prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		area.
 stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and allen vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		4. Subsoil and overburden in the
 stockpiled separately to be returned for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and allen vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		prospecting area should be
for backfilling in the correct soil horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 horizon order. 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal or soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
 5. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal route. Proof from an approved waste disposal site where contaminate soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
 vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
 on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
Stockpiles may further be protected by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
by the construction of berms or low brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
brick walls around their bases. 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 6. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
 weeds and alien vegetation growth by regular weeding. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
by regular weeding. 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 7. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
 expected, analysis must be done prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
prior to disposal of soil to determine the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager.Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 the appropriate disposal route. Proof from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
from an approved waste disposal site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
 site where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental 		
dumped if and when a spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
spillage/leakage occurs should be attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
attained and given to the project manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		-
manager. Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
Establish an effective record keeping system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		
system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		manager.
system for each area where soil is disturbed for prospecting purposes. These records should be included in environmental		Establish an effective record keeping
for prospecting purposes. These records should be included in environmental		
should be included in environmental		

			 performance reports, and should include all the records below. Record the GPS coordinates of each area. Record the date of topsoil stripping. Record the GPS coordinates of where the topsoil is stockpiled. Record the date of cessation prospecting activities at the particular site. Photograph the area on cessation of prospecting activities. Record date and depth of re- spreading of topsoil. Photograph the area on completion of rehabilitation and on an annual basis thereafter to show vegetation establishment and evaluate progress of restoration over time. 	
Erosion	Soil Air Water	Pitting and trenching phase- (construction and operation phase)	 An effective system of run-off control should be implemented, where it is required, that collects and safely disseminates run-off water from all hardened surfaces and prevents potential down slope erosion. Periodical site inspection should be included in environmental performance reporting that inspects the effectiveness of the run-off control system and specifically records the occurrence of any erosion on site or downstream. Wind screening and stormwater control should be undertaken to prevent soil loss from the site. The use of silt fences and sand bags must be implemented in areas that are susceptible to erosion. 	

5. Other erosion control measures that
can be implemented are as follows:
• Brush packing with cleared
vegetation
 Mulch or chip packing
 Planting of vegetation
• Hydroseeding/hand sowing
6. Sensitive areas need to be identified
prior to construction/prospecting so
that the necessary precautions can
be implemented.
7. All erosion control mechanisms
need to be regularly maintained.
8. Seeding of topsoil and subsoil
stockpiles to prevent wind and water
erosion of soil surfaces.
9. Retention of vegetation where
possible to avoid soil erosion.
10. Vegetation clearance should be
phased to ensure that the minimum
area of soil is exposed to potential
erosion at any one time.
11. Re-vegetation of disturbed surfaces
should occur immediately after
construction/prospecting activities
are completed. This should be done
through seeding with indigenous
grasses.
12. No impediment to the natural water
flow other than approved erosion
control works is permitted.
13. To prevent stormwater damage, the
increase in stormwater run-off
resulting from
construction/prospecting activities
must be estimated and the drainage
system assessed accordingly.
14. Stockpiles not used in three (3)
months after stripping must be
seeded or backfilled to prevent dust
and erosion.

Air Pollution	Air	Pitting and	Dust control	Minimisation of
	1 111	trenching phase-	1. Wheel washing and damping down	impacts to
		(construction and	of un-surfaced and un-vegetated	acceptable limits
		operation phase)	areas.	
			2. Retention of vegetation where	
			possible will reduce dust travel.	
			3. Clearing activities must only be	
			done during agreed working times	
			and permitting weather conditions	
			to avoid drifting of sand and dust	
			into neighbouring areas.	
			4. Damping down of all exposed soil	
			surfaces with a water bowser or	
			sprinklers when necessary to reduce	
			dust.	
			5. The Contractor shall be responsible	
			for dust control on site to ensure no	
			nuisance is caused to the	
			neighbouring communities.	
			6. A speed limit of 30km/h must not	
			be exceeded on site.	
			7. Any complaints or claims emanating	
			from the lack of dust control shall be	
			attended to immediately by the	
			Contractor.	
			8. Any dirt roads that are utilised by	
			the workers must be regularly	
			maintained to ensure that dust	
			levels are controlled.	
			Odour control	
			9. Regular servicing of vehicles in order	
			to limit gaseous emissions.	
			10. Regular servicing of onsite toilets to	
			avoid potential odours.	
			Rehabilitation	
			11. The Contractor should commence	
			rehabilitation of exposed soil	
			surfaces as soon as practical after	
			completion of earthworks.	
I	<u> </u>	L	completion of cal inworks.	

		 Fire prevention 12. No open fires shall be allowed on site under any circumstance. All cooking shall be done in demarcated areas that are safe and cannot cause runaway fires. 13. The Contractor shall have operational fire-fighting equipment available on site at all times. The level of firefighting equipment must be assessed and evaluated through a typical risk assessment process. 	
Noise	Pitting and trenching phase- (construction and operation phase)	 The prospecting activities must aim to adhere to the relevant noise regulations and limit noise to within standard working hours in order to reduce disturbance of dwellings in close proximity to the development. Mine, crushers, workshops and other noisy fixed facilities should be located well away from noise sensitive areas. Once the proposed final layouts are made available by the Contractor(s), the sites must be evaluated in detail and specific measures designed in to the system. Truck traffic should be routed away from noise sensitive areas, where possible. Noise levels must be kept within acceptable limits. Noisy operations should be combined so that they occur where possible at the same time. Mine workers to wear necessary ear protection gear. Noisy activities to take place during allocated hours. 	Minimisation of impacts to acceptable limits

			 8. Noise from labourers must be controlled. 9. Noise suppression measures must be applied to all equipment. Equipment must be kept in good working order and where appropriate fitted with silencers which are kept in good working order. Should the vehicles or equipment not be in good working order, the Contractor may be instructed to remove the offending vehicle or machinery from the site. 10. The Contractor must take measures from the site. 	
	Heritege	Ditting and	 to discourage labourers from loitering in the area and causing noise disturbance. Where possible labour shall be transported to and from the site by the Contractor or his Sub-Contractors by the Contractors own transport. 11. Implementation of enclosure and cladding of processing plants. 12. Applying regular and thorough maintenance schedules to equipment and processes. An increase in noise emission levels very often is a sign of the imminent mechanical failure of a machine. 	Minimization of
Impact on potential cultural and heritage artefacts	Heritage	Pitting and trenching phase- (construction and operation phase)	 Any finds must be reported to the nearest National Monuments office to comply with the National Heritage Resources Act (Act No 25 of 1999) and to DEA. Local museums as well as the South African Heritage Resource Agency (SAHRA) should be informed if any artefacts are uncovered in the affected area. 	Minimisation of impacts to acceptable limits

			 3. The Contractor must ensure that his workforce is aware of the necessity of reporting any possible historical or archaeological finds to the ECO so that appropriate action can be taken. 4. Any discovered artefacts shall not be removed under any circumstances. Any destruction of a site can only be allowed once a permit is obtained and the site has been mapped and noted. Permits shall be obtained from the SAHRA should the proposed site affect any world heritage sites or if any heritage sites are to be destroyed or altered.
Waste management	Pollution	Pitting and trenching phase- (construction and operation phase)	 Litter management Refuse bins must be placed at strategic positions to ensure that litter does not accumulate within the construction site. The Contractor shall supply waste collection bins where such is not available and all solid waste collected shall be disposed of at registered/licensed landfill. Good housekeeping practices should be implemented to regularly maintain the litter and rubble situation on the construction site. If possible and feasible, all waste generated on site must be separated into glass, plastic, paper, metal and wood and recycled. An independent contractor can be appointed to conduct this recycling. Littering by the employees of the Contractor shall not be allowed under any circumstances. The ECO

shall monitor the neatness of the
work sites as well as the Contractor
campsite.
6. Skip waste containers should be
maintained on site. These should be
kept covered and arrangements
made for them to be collected
regularly.
7. All waste must be removed from the
site and transported to a landfill site
promptly to ensure that it does not
attract vermin or produce odours.
8. Where a registered waste site is not
available close to the construction
site, the Contractor shall provide a
method statement with regard to
waste management.
9. A certificate of disposal shall be
obtained by the Contractor and kept
on file, if relevant.
10. Under no circumstances may solid
waste be burnt on site.
11. All waste must be removed promptly
to ensure that it does not attract
vermin or produce odours.
Hazardous waste
12. All waste hazardous materials must
be carefully stored as advised by the
ECO, and then disposed of offsite at
a licensed landfill site, where
practical. Incineration may be used
where relevant.
13. Contaminants to be stored safely to
avoid spillage.
14. Machinery must be properly
maintained to keep oil leaks in
check.
15. All necessary precaution measures
shall be taken to prevent soil or
surface water pollution from

 hazardous materials used during construction and any spills shall immediately be cleaned up and all alfected areas rehabilitated. Sanitation 16. The Contractor shall install mobile chemical toilets on the site. 17. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate as anitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be regulared for a place water bodies or drainage lines or alternatively located in a place sproved of by the Engineer. 20. Under no circumstances may open area, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbiden, but rather toilets is forbiden, but rather toilets is forbiden, but rather toilets or must be provided for all construction staff. 22. Potable water must be provided for all construction staff. 23. Depending on the nature and extent of the spill, contaminated soil must they be careful removal of soil using appropriate tools/machinery 	
 construction and any spills shall immediately be cleaned up and all affected areas rehabilitated. Sanitation for The Contractor shall install mobile chemical lolets on the site. Statistical and the service of the service of the service of the service of regularly and the ECO shall inspect toilets at all times. No indiscriminate allowed. To Statif shall be serviced regularly and the ECO shall inspect toilets regularly. To or above the 1:100 year flood line from any natural or mammade water bodies or the Engineer. 20. Under no circumstances may open are real the facility. The construction of "Long Prop" to be serviced to the service of the surrounding bush be used as a toilet facility. The construction of "Long Prop" toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the servage treatment plant. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be the example tools water down and soil must be the service or the spill. Excavation of contaminate of must be restored for all construction staff. 	hazardous materials used during
 immediately be cleaned up and all affected areas rehabilitated. Sanitation The Contractor shall install mobile chemical toleties on the site. The Contractor shall install contained and up and all affected areas rehabilitated. Staff shall be sensitized to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. R Tollets shall be serviced regularly and the ECO shall inspect toilets regularly. Tollets should be no closer than Som or above the 1:00 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. Outer no circumstances may open areas, neighbours forces or the surrounding bush be used as a toilet facility. The construction of "Long Drop" tollets is forbidden, but rather tollets connected to the sawage treatment plant. Details extend for all contaminated soil must involve careful removal of soil uses the either executed or treated on site. 	
affected areas rehabilitated. Sanitation 1. The Contractor shall install mobile chemical toilets on the site. 1.7. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 1.8. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than SOm or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
 Sanitation 16. The Contractor shall install mobile chemical tolets on the site. 17. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year fload line from any natural or mammade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be tused as a toilet facility. 21. The construction of "Long Drop" toilets is corrected to the sewage treatment plant. 22. Potable water must be provided for all contaminated soil must be either excavated or treated on site. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on site. 	
 16. The Contractor shall install mobile chemical toilets on the site. 17. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or drainage lines or distensitively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the split, contaminated soil must be circum of contaminated soil must involve careful removal of soil using appropriate toils/machinery 	
 16. The Contractor shall install mobile chemical toilets on the site. 17. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or drainage lines or distensitively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the split, contaminated soil must be circum of contaminated soil must involve careful removal of soil using appropriate toils/machinery 	Sanitation
 chemical toilets on the site. 17. Staf shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:00 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets construction of "Long Drop" toilets is forbidden, but rather toilets construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must be a construct on soil. 	
 17. Staff shall be sensitised to the fact that they should use these facilities at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open arreas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be cither exavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
 that they should use these facilities at all times. No indiscriminate samitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open a reas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either exavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
at all times. No indiscriminate sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spiil, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
 sanitary activities on site shall be allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Protable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spil, contaminated soil must be either excavated or treated on-site. 24. Excavation of contaminated soil must involve careful removal of soil uust involve careful removal of soil uust involve careful removal of soil 	
allowed. 18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or mammade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
18. Toilets shall be serviced regularly and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on-site. 24. Excavation of contaminated soil must involve careful removal of soil uusing appropriate tools/machinery	
and the ECO shall inspect toilets regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
regularly. 19. Toilets should be no closer than 50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
 19. Toilets should be no closer than S0m or above the 1:100 year flood line from any natural or mamade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
50m or above the 1:100 year flood line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
 line from any natural or manmade water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
water bodies or drainage lines or alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
alternatively located in a place approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil using appropriate tools/machinery	
 approved of by the Engineer. 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
 20. Under no circumstances may open areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must be appropriate tools/machinery 	alternatively located in a place
areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	approved of by the Engineer.
areas, neighbours fences or the surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	20. Under no circumstances may open
surrounding bush be used as a toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	areas, neighbours fences or the
toilet facility. 21. The construction of "Long Drop" toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
21. The construction of "Long Drop" toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
toilets is forbidden, but rather toilets is forbidden, but rather toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
toilets connected to the sewage treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
treatment plant. 22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
22. Potable water must be provided for all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated onsite. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
all construction staff. Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
Remedial actions 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	
 23. Depending on the nature and extent of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery 	Remedial actions
of the spill, contaminated soil must be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
be either excavated or treated on- site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
site. 24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
24. Excavation of contaminated soil must involve careful removal of soil using appropriate tools/machinery	
must involve careful removal of soil using appropriate tools/machinery	
using appropriate tools/machinery	

		T	1	
				 to storage containers until treated or disposed of at a licensed hazardous landfill site. 25. The ECO must determine the precise method of treatment for polluted soil. This could involve the application of soil absorbent materials as well as oil-digestive powders to the contaminated soil. 26. If a spill occurs on an impermeable surface such as cement or concrete, the surface spill must be contained using oil absorbent material. 27. If necessary, oil absorbent sheets or pads must be attached to leaky machinery or infrastructure. 28. Materials used for the remediation of petrochemical spills must be used according to product specifications
				according to product specifications and guidance for use. 29. Contaminated remediation
				materials must be carefully removed from the area of the spill so as to prevent further release of petrochemicals to the environment,
				and stored in adequate containers until appropriate disposal.
Water Use and Quality	Water pollution	Water	Pitting and trenching phase- (construction and operation phase)	 Water Use Develop a sustainable water supply management plan to minimise the impact to natural systems by managing water use, avoiding depletion of aquifers and minimising impacts to water users. Water must be reused, recycled or treated where possible.
				Water Quality 3. The quality and quantity of effluent streams discharged to the

environment including stormwater	
should be managed and treated to	
meet applicable effluent discharge	
guidelines.	
4. Discharge to surface water should	
not result in contaminant	
concentrations in excess of local	
ambient water quality criteria	
outside a scientifically established	
mixing zone.	
5. Efficient oil and grease traps or	
sumps should be installed and	
maintained at refueling facilities,	
workshops, fuel storage depots, and	
containment areas and spill kits	
should be available with emergency	
response plans.	
Stormwater	
6. The site must be managed in order	
to prevent pollution of drains,	
downstream watercourses or	
groundwater, due to suspended	
solids and silt or chemical	
pollutants.	
7. Silt fences should be used to prevent	
any soil entering the stormwater	
drains.	
8. Temporary cut off drains and berms	
may be required to capture	
stormwater and promote	
infiltration.	
9. Promote a water saving mind set	
with construction/prospecting	
workers in order to Contractor	
ensure less water wastage.	
10. Hazardous substances must be	
stored at least 40m from any water	
bodies on site to avoid pollution.	
11. The installation of the stormwater	
system must take place as soon as	

possible to attenuate stormwater
from the construction phase as well
as the operation phase.
12. Earth, stone and rubble is to be
properly disposed of, or utilized on
site so as not to obstruct natural
water path ways over the site. i.e.
these materials must not be placed
in stormwater channels, drainage
lines or rivers.
13. There should be a periodic checking
of the site's drainage system to
ensure that the water flow is
unobstructed.
14. If a batching plant is necessary,
run-off should be managed
effectively to avoid contamination of
other areas of the site. Untreated
runoff from the batch plant must
not be allowed to get into the storm
water system or nearby streams,
rivers or erosion channels or
dongas.
The cut-off trenches and silt fences will be
installed where necessary as to control
runoff storm water by attenuating it and
control the movement of sediment on the
premises.
These structures will be monitored on a
regular basis. It is suggested that it be
monitored on a weekly basis during the
rainy season, and after possible rain events
during the dry season.
If these practices is found to be insufficient
for the control of storm water and
sedimentation, other alternatives should
immediately be investigated and
implemented.
107

	Groundwater resource protection 15. Process solution storage ponds and other impoundments designed to hold non fresh water or non-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality.
	Sanitation16. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers).17. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution.
	Concrete mixing 18. Concrete contaminated water must not enter soil or any natural drainage system as this disturbs the natural acidity of the soil and affects plant growth.
	Public areas19. Food preparation areas should be provided with adequate washing facilities and food refuse should be stored in sealed refuse bins which should be removed from site on a regular basis.20. The Contractor should take steps to ensure that littering by construction/prospecting workers does not occur and persons should
	be employed on site to collect litter from the site and immediate

Milnex CC: EIA343 -EIR & EMPr - Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province

surroundings, including litter	
accumulating at fence lines.	
21. No washing or servicing of vehicles	
on site.	

IMPACT MANAGEMENT ACTIONS

(A description of impact management actions, identifying the manner in which the impact management objectives and outcomes contemplated in paragraphs (c) and (d) will be achieved).

ACTIVITY	POTENTIAL	MITIGATION	TIME PERIOD FOR	COMPLIANCE WITH
Whether listed or not listed.	IMPACT	TYPE	IMPLEMENTATION	STANDARDS
(E.g. Excavations, blasting, stockpiles, discard dumps or dams, Loading, hauling and transport, Water supply dams and boreholes, accommodation, offices, ablution, stores, workshops, processing plant, storm water control, berms, roads, pipelines, power lines,	(e.g. dust, noise, drainage surface disturbance, fly rock, surface water contamination, groundwater contamination, air pollution		IMPLEMENTATION Describe the time period when the measures in the environmental management programme must be implemented Measures must be implemented when	(A description of how each of the recommendations in 2.11.6 read with 2.12 and 2.15.2 herein will comply with any prescribed environmental management standards or practices that
conveyors, etcetcetc.).	etcetc)	 Modify through alternative method. Control through noise control Control through management and monitoring Remedy through rehabilitation 	required. With regard to Rehabilitation specifically this must take place at the earliest opportunityWith regard to Rehabilitation, therefore state either: Upon cessation of the individual activity or.	have been identified by Competent Authorities)

			Upon the cessation of mining, bulk sampling or alluvial diamond prospecting as the case may be.	
Clearance of vegetation	Loss or fragmentation of habitats	 Existing vegetation Vegetation removal must be limited to the prospecting site. Vegetation to be removed as it becomes necessary rather than removal of all vegetation throughout the site in one step. No vegetation to be used for firewood. Exotic and invasive plant species should not be allowed to establish, if the development is approved. Rehabilitation All damaged areas shall be rehabilitated upon completion of the contract. Re-vegetation of the disturbed site is aimed at approximating as near as possible the natural vegetative conditions prevailing prior to construction. All natural areas impacted during construction/prospecting must be rehabilitated with locally indigenous grasses typical of the representative botanical unit. Rehabilitation process must make use of species indigenous to the area. Seeds from surrounding seed banks can be used for re-seeding. Rehabilitation must be executed in such a manner that surface run-off 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

will not cause erosion of disturbed	
areas.	
11. Planting of indigenous tree species in	
areas not to be cultivated or built on	
must be encouraged.	
muot se encouragear	
Demarcation of prospecting area	
12. All plants not interfering with	
prospecting operations shall be left	
undisturbed clearly marked and	
indicated on the site plan.	
13. The prospecting area must be well	
demarcated and no construction	
activities must be allowed outside of	
this demarcated footprint.	
14. Vegetation removal must be phased	
in order to reduce impact of	
construction/prospecting.	
15. Site office and laydown areas must	
be clearly demarcated and no	
encroachment must occur beyond	
demarcated areas.	
16. Strict and regular auditing of the	
prospecting process to ensure	
containment of the prospecting and	
laydown areas.	
17. Soils must be kept free of	
petrochemical solutions that may be	
1 5	
1 0	
construction/prospecting. Spillage	
can result in a loss of soil	
functionality thus limiting the re-	
establishment of flora.	
Utilisation of resources	
18. Gathering of firewood, fruit, muti	
plants, or any other natural material	
onsite or in areas adjacent to the site	
is prohibited unless with prior	
approval of the ECO.	
1	

Exotic vegetation	
19. Alien vegetation on the site will need	
to be controlled.	
20. The Contractor should be	
responsible for implementing a	
programme of weed control	
(particularly in areas where soil has	
been disturbed); and grassing of any	
remaining stockpiles to prevent weed	
invasion.	
21. The spread of exotic species	
occurring throughout the site should	
be controlled.	
Herbicides	
22. Herbicide use shall only be allowed	
according to contract specifications.	
The application shall be according to	
set specifications and under	
supervision of a qualified technician.	
The possibility of leaching into the	
surrounding environment shall be	
properly investigated and only	
environmentally friendly herbicides	
shall be used.	
23. The use of pesticides and herbicides	
on the site must be discouraged as	
these impact on important pollinator	
species of indigenous vegetation.	
Fauna	
24. Rehabilitation to be undertaken as	
soon as possible after prospecting	
has been completed.	
25. No trapping or snaring to fauna on	
the construction/prospecting site	
should be allowed.	
26. No faunal species must be disturbed,	
trapped, hunted or killed by	
maintenance staff during any routine	
maintenance at the development.	

Prospecting of Alluvial Diamonds – excavations	Loss of topsoil	 The Contractor should, prior to the commencement of earthworks determine the average depth of topsoil, and agree on this with the ECO. The full depth of topsoil should be stripped from areas affected by construction/prospecting and related activities prior to the commencement of major earthworks. This should include the building footprints, working areas and storage areas. Topsoil must be reused where possible to rehabilitate disturbed areas. Care must be taken not to mix topsoil and subsoil during stripping. The topsoil must be conserved on site in and around the pit/trench area. Subsoil and overburden in the prospecting area should be stockpiled separately to be returned for backfilling in the correct soil horizon order. If stockpiles are exposed to windy conditions or heavy rain, they should be covered either by vegetation or geofabric, depending on the duration of the project. Stockpiles may further be protected by the construction of berms or low brick walls around their bases. Stockpiles should be kept clear of weeds and alien vegetation growth by regular weeding. Where contamination of soil is expected, analysis must be done prior to disposal of soil to determine the appropriate disposal site 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

Milnex CC: EIA343 – EIR & EMPr - Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province

	for ea prospe be inc	where contaminated soils are dumped if and when a spillage/leakage occurs should be attained and given to the project manager. ish an effective record keeping system ch area where soil is disturbed for ecting purposes. These records should duded in environmental performance s, and should include all the records Record the GPS coordinates of each area. Record the date of topsoil stripping. Record the GPS coordinates of where the topsoil is stockpiled. Record the date of cessation prospecting activities at the particular site. Photograph the area on cessation of prospecting activities. Record date and depth of re- spreading of topsoil. Photograph the area on completion of rehabilitation and on an annual basis thereafter to show vegetation establishment and evaluate progress of restoration over time.		
Ero		An effective system of run-off control should be implemented, where it is required, that collects and safely disseminates run-off water from all hardened surfaces and prevents potential down slope erosion. Periodical site inspection should be included in environmental performance reporting that inspects the effectiveness of the run-off control system and specifically	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

records the occurrence of any erosion
on site or downstream.
3. Wind screening and stormwater
control should be undertaken to
prevent soil loss from the site.
4. The use of silt fences and sand bags
must be implemented in areas that
are susceptible to erosion.
5. Other erosion control measures that
can be implemented are as follows:
• Brush packing with cleared
vegetation
 Mulch or chip packing
 Planting of vegetation
 Hydroseeding/hand sowing
6. Sensitive areas need to be identified
prior to construction/prospecting so
that the necessary precautions can
be implemented.
7. All erosion control mechanisms need
to be regularly maintained.
8. Seeding of topsoil and subsoil
stockpiles to prevent wind and water
erosion of soil surfaces.
9. Retention of vegetation where
possible to avoid soil erosion.
10. Vegetation clearance should be
phased to ensure that the minimum
area of soil is exposed to potential
erosion at any one time.
11. Re-vegetation of disturbed surfaces
should occur immediately after
construction/prospecting activities
are completed. This should be done
through seeding with indigenous
grasses.
12. No impediment to the natural water
flow other than approved erosion
control works is permitted.
13. To prevent stormwater damage, the
increase in stormwater run-off

Milnex CC: EIA343 -EIR & EMPr - Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province

	resulting from construction/prospecting activities must be estimated and the drainage system assessed accordingly. A drainage plan must be submitted to the Engineer for approval and must include the location and design criteria of any temporary stream crossings. 14. Stockpiles not used in three (3) months after stripping must be seeded/backfilled to prevent dust and erosion.		
Air Pollution	 Dust control Wheel washing and damping down of un-surfaced and un-vegetated areas. Retention of vegetation where possible will reduce dust travel. Clearing activities must only be done during agreed working times and permitting weather conditions to avoid drifting of sand and dust into neighbouring areas. Damping down of all exposed soil surfaces with a water bowser or sprinklers when necessary to reduce dust. The Contractor shall be responsible for dust control on site to ensure no nuisance is caused to the neighbouring communities. A speed limit of 30km/h must not be exceeded on site. Any complaints or claims emanating from the lack of dust control shall be attended to immediately by the Contractor. 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

	 maintained to ensure that dust levels are controlled. Odour control 22. Regular servicing of vehicles in order to limit gaseous emissions. 23. Regular servicing of onsite toilets to avoid potential odours. Rehabilitation 24. The Contractor should commence rehabilitation of exposed soil surfaces as soon as practical after completion of earthworks. Fire prevention 25. No open fires shall be allowed on site under any circumstance. All cooking shall be done in demarcated areas that are safe and cannot cause runaway fires. 26. The Contractor shall have operational fire-fighting equipment available on site at all times. The level of firefighting equipment must be assessed and evaluated through a trained rest on the second seco		
Noise	 typical risk assessment process. The prospecting activities must aim to adhere to the relevant noise regulations and limit noise to within standard working hours in order to reduce disturbance of dwellings in close proximity to the development. Pans, power plants, crushers, workshops and other noisy fixed facilities should be located well away from noise sensitive areas. Once the proposed final layouts are made available by the Contractor(s), the sites must be evaluated in detail and 	Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

specific measures designed in to the
system.
3. Truck traffic should be routed away
from noise sensitive areas, where
possible.
4. Noise levels must be kept within
acceptable limits.
5. Noisy operations should be combined
so that they occur where possible at
the same time.
6. Mine workers to wear necessary ear
protection gear.
7. Noisy activities to take place during
allocated hours.
8. Noise from labourers must be
controlled.
9. Noise suppression measures must be
applied to all equipment. Equipment
must be kept in good working order
and where appropriate fitted with
silencers which are kept in good
working order. Should the vehicles or
equipment not be in good working
order, the Contractor may be
instructed to remove the offending
vehicle or machinery from the site.
10. The Contractor must take measures
loitering in the area and causing
noise disturbance. Where possible
labour shall be transported to and
from the site by the Contractor or his
Sub-Contractors by the Contractors
own transport.
11. Implementation of enclosure and
cladding of processing plants.
12. Applying regular and thorough
maintenance schedules to
equipment and processes. An
increase in noise emission levels very

		often is a sign of the imminent	
	Impact on potential cultural and heritage artefacts	 mechanical failure of a machine. 1. Any finds must be reported to the nearest National Monuments office to comply with the National Heritage Resources Act (Act No 25 of 1999) and to DEA. 2. Local museums as well as the South African Heritage Resource Agency (SAHRA) should be informed if any artefacts are uncovered in the affected area. 3. The Contractor must ensure that his workforce is aware of the necessity of reporting any possible historical or archaeological finds to the ECO so that appropriate action can be taken. 4. Any discovered artefacts shall not be removed under any circumstances. Any destruction of a site can only be allowed once a permit is obtained and the site has been mapped and noted. Permits shall be obtained from the SAHRA should the proposed site affect any world heritage sites or if any heritage sites are to be destroyed or altered. 	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.
Waste Management		Litter management Duration of operation 1. Refuse bins must be placed at strategic positions to ensure that litter does not accumulate within the construction/prospecting site. Duration of operation 2. The Contractor shall supply waste collection bins where such is not available and all solid waste collected shall be disposed of at registered/licensed landfill. Duration of operation 3. Good housekeeping practices should be implemented to regularly Duration of operation	The implementation of the recommended mitigation measures will result in the minimisation of impacts to acceptable standards, thereby ensuring compliance with NEMA and Duty of Care as prescribed by NEMA.

• , • , • • • • •	
maintain the litter and rubble	
situation on the	
construction/prospecting site.	
4. If possible and feasible, all waste	
generated on site must be separated	
into glass, plastic, paper, metal and	
wood and recycled. An independent	
contractor can be appointed to	
conduct this recycling.	
5. Littering by the employees of the	
Contractor shall not be allowed	
under any circumstances. The ECO	
shall monitor the neatness of the	
work sites as well as the Contractor	
campsite.	
6. Skip waste containers should be	
maintained on site. These should be	
kept covered and arrangements	
made for them to be collected	
regularly.	
7. All waste must be removed from the	
site and transported to a landfill site	
promptly to ensure that it does not	
attract vermin or produce odours.	
8. Where a registered waste site is not	
available close to the	
construction/prospecting site, the	
Contractor shall provide a method	
statement with regard to waste	
management.	
9. A certificate of disposal shall be	
obtained by the Contractor and kept	
on file, if relevant.	
10. Under no circumstances may solid	
waste be burnt on site.	
11. All waste must be removed promptly	
to ensure that it does not attract	
vermin or produce odours.	
Hazardous waste	

	,
12. All waste hazardous materials must	
be carefully stored as advised by the	
ECO, and then disposed of offsite at	
a licensed landfill site, where	
practical. Incineration may be used	
where relevant.	
13. Contaminants to be stored safely to	
avoid spillage.	
14. Machinery must be properly	
maintained to keep oil leaks in	
check.	
15. All necessary precaution measures	
shall be taken to prevent soil or	
surface water pollution from	
hazardous materials used during	
construction/prospecting and any	
spills shall immediately be cleaned	
up and all affected areas	
rehabilitated.	
i onuomitatou.	
Sanitation	
16. The Contractor shall install mobile	
chemical toilets on the site.	
17. Staff shall be sensitised to the fact	
that they should use these facilities	
at all times. No indiscriminate	
sanitary activities on site shall be	
allowed.	
18. Toilets shall be serviced regularly	
and the ECO shall inspect toilets	
regularly.	
19. Toilets should be no closer than 50m	
or above the 1:100 year flood line	
from any natural or manmade water	
bodies or drainage lines or	
alternatively located in a place	
approved of by the Engineer.	
20. Under no circumstances may open	
areas, neighbours fences or the	
surrounding bush be used as a toilet	
facility.	

1	
21. The construction of "Long Drop"	
toilets is forbidden, but rather toilets	
connected to the sewage treatment	
plant.	
22. Potable water must be provided for	
all construction staff.	
Remedial actions	
23. Depending on the nature and extent	
of the spill, contaminated soil must	
be either excavated or treated on-	
site.	
24. Excavation of contaminated soil	
must involve careful removal of soil	
using appropriate tools/machinery	
to storage containers until treated or	
disposed of at a licensed hazardous	
landfill site.	
25. The ECO must determine the precise	
method of treatment for polluted soil.	
This could involve the application of	
soil absorbent materials as well as	
oil-digestive powders to the	
contaminated soil.	
26. If a spill occurs on an impermeable	
surface such as cement or concrete,	
the surface spill must be contained	
using oil absorbent material.	
27. If necessary, oil absorbent sheets or	
pads must be attached to leaky	
machinery or infrastructure.	
28. Materials used for the remediation of	
petrochemical spills must be used	
according to product specifications	
and guidance for use.	
29. Contaminated remediation materials	
must be carefully removed from the	
area of the spill so as to prevent	
further release of petrochemicals to	
the environment and stored in	

		adequate containers until appropriate disposal.	
Water Use and Quality	Water pollution	Water Use 1. Develop a sustainable water supply management plan to minimise the impact to natural systems by managing water use, avoiding depletion of aquifers and minimising impacts to water users. 2. Water must be reused, recycled or treated where possible.	
		 Water Quality 3. The quality and quantity of effluent streams discharged to the environment including stormwater should be managed and treated to meet applicable effluent discharge guidelines. 4. Discharge to surface water should not result in contaminant concentrations in excess of local ambient water quality criteria outside a scientifically established mixing zone. 5. Efficient oil and grease traps or sumps should be installed and maintained at refueling facilities, workshops, fuel storage depots, and containment areas and spill kits should be available with emergency response plans. 	
		Stormwater 6. The site must be managed in order to prevent pollution of drains, downstream watercourses or groundwater, due to suspended solids and silt or chemical pollutants.	

7. Silt fences should be used to prevent	
any soil entering the stormwater	
drains.	
8. Temporary cut off drains and berms	
may be required to capture	
stormwater and promote infiltration.	
9. Promote a water saving mind set with	
construction/prospecting workers in	
order to Contractor ensure less water	
wastage.	
10. New stormwater construction must	
be developed strictly according to	
specifications from engineers in	
order to ensure efficiency.	
11. Hazardous substances must be	
stored at least 20m from any water	
bodies on site to avoid pollution.	
12. The installation of the stormwater	
system must take place as soon as	
possible to attenuate stormwater	
from the construction phase as well	
as the operation phase.	
13. Earth, stone and rubble is to be	
properly disposed of, or utilized on	
site so as not to obstruct natural	
water path ways over the site. i.e.	
these materials must not be placed in	
stormwater channels, drainage lines	
or rivers.	
14. There should be a periodic checking	
of the site's drainage system to	
ensure that the water flow is	
unobstructed.	
15. If a batching plant is necessary, run-	
off should be managed effectively to	
avoid contamination of other areas of	
the site. Untreated runoff from the	
batch plant must not be allowed to	
get into the storm water system or	
nearby streams, rivers or erosion	
channels or dongas.	

Groundwater resource protection 16. Process solution storage ponds and other impoundments designed to hold non fresh water or un-treated process effluents should be lined and be equipped with sufficient wells to enable monitoring of water levels and quality.	
Sanitation	
 17. Adequate sanitary facilities and ablutions must be provided for construction workers (1 toilet per every 15 workers). 18. The facilities must be regularly serviced to reduce the risk of surface or groundwater pollution. 	
Concrete mixing	
19. Concrete contaminated water must not enter soil or any natural drainage system as this disturbs the natural acidity of the soil and affects plant growth.	
Public areas	
 20. Food preparation areas should be provided with adequate washing facilities and food refuse should be stored in sealed refuse bins which should be removed from site on a regular basis. 21. The Contractor should take steps to ensure that littering by construction workers does not occur and persons should be employed on site to collect litter from the site and immediate surroundings, including litter 	
accumulating at fence lines.	
accumulating at fence lines.	

Milnex CC: EIA343 -EIR & EMPr - Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province

	22. No washing or servicing of vehicles	
	on site.	

Mechanisms for monitoring compliance with and performance assessment against the environmental management programme and reporting thereon, including

F. Monitoring of Impact Management Actions

G. Monitoring and reporting frequency

H. Responsible persons

I. Time period for implementing impact management actions J. Mechanism for monitoring compliance

- K.

SOURCE ACTIVITY	IMPACTS REQUIRING MONITORING PROGRAMMES	FUNCTIONAL REQUIREMENTS FOR MONITORING	ROLES AND RESPONSIBILITIES (FOR THE EXECUTION OF THE MONITORING PROGRAMMES)	MONITORING AND REPORTING FREQUENCY and TIME PERIODS FOR IMPLEMENTING IMPACT MANAGEMENT ACTIONS
Clearance of vegetation	Loss or fragmentation of habitats	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.
Prospecting of Alluvial Diamonds – excavations	Loss of topsoil Erosion Air Pollution Noise Impact on potential cultural and heritage artefacts	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to

Milnex CC: EIA343 – EIR & EMPr - Prospecting Right of Diamond Alluvial (DA), Diamonds General (D) & Diamonds in Kimberlite combined with a Waste Licence Application on a Portion of the Remaining Extent of Plaas 467, Registration Division: Hay, Northern Cape Province

				the competent authority if required.
Waste management	Pollution	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.
Water Use and Quality	Water pollution	 Conduct regular internal audits Conduct regular external audits 	 Environmental Manager Suitable qualified environmental auditor 	Monitoring should be undertaken for duration of operations. Internal audits should be undertaken at least every 6 months. External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the competent authority if required.

L. INDICATE THE FREQUENCY OF THE SUBMISSION OF THE PERFORMANCE ASSESSMENT REPORT.

External audits should be undertaken by a suitably qualified auditor on an annual basis. Reports should be made available to the Competent Authority if required.

M. ENVIRONMENTAL AWARENESS PLAN

1. Manner in which the applicant intends to inform his or her employees of any environmental risk which may result from their work.

- **Kimswa Mining (Pty) Ltd** will implement an Environmental Awareness Plan which will include various mechanisms for informing employees of environmental risks resulting from their work, including:
 - Induction training for full -time staff and contractors;
 - In-house training sessions to be held with relevant employees;
 - On the job training regarding environmental issues
 - Training and skills development

The above measures will be implemented through an Environmental Communication Strategy to be implemented.

See the attached **appendix 12** for the Awareness plan

2. Manner in which risks will be dealt with in order to avoid pollution or the degradation of the environment.

Kimswa Mining (Pty) Ltd will implement an incident reporting and reporting procedure in order to identify risks timeously and implement actions to avoid or minimise environmental impacts.

N. Specific information required by the Competent Authority (Among others, Confirm that the financial provision will be reviewed annually).

No specific information requirements have been detailed by the Competent Authority.

####