

**ENVIRONMENTAL IMPACT ASSESSMENT PROCESS  
FINAL BASIC ASSESSMENT REPORT**

**PROPOSED GILLMER SOLAR ENERGY FACILITY NEAR  
NOUPOORT, NORTHERN CAPE PROVINCE**

**(DEA REF No: 14/12/16/3/3/1/735)**

**DRAFT BASIC ASSESSMENT REPORT  
FOR SUBMISSION TO DEA  
JANUARY 2013**

**Prepared for:**

Gillmer Solar Energy (Pty) Ltd  
3 Eglin Road  
Unit B4 The Crescent East  
Sunninghill  
2157

**Prepared by:**

*Savannah Environmental Pty Ltd*

FIRST FLOOR, UNIT 10, BUILDING 2,  
5 WOODLANDS DRIVE OFFICE PARK  
CNR WOODLANDS DRIVE &  
WESTERN SERVICE ROAD,  
WOODMEAD, GAUTENG  
P.O. BOX 148, SUNNINGHILL, 2157  
TELEPHONE : +27 (0)11 656 3237  
FACSIMILE : +27 (0)86 684 0547  
EMAIL : INFO@SAVANNAHSA.COM  
WWW.SAVANNAHSA.COM



# BASIC ASSESSMENT REPORT



## environmental affairs

Department:  
Environmental Affairs  
REPUBLIC OF SOUTH AFRICA

(For official use only)

**File Reference Number:**

**Application Number:**

**Date Received:**


Basic assessment report in terms of the Environmental Impact Assessment Regulations, 2010, promulgated in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998), as amended.

### Kindly note that:

1. This **basic assessment report** is a standard report that may be required by a competent authority in terms of the EIA Regulations, 2010 and is meant to streamline applications. Please make sure that it is the report used by the particular competent authority for the activity that is being applied for.
2. This report format is current as of **1 September 2012**. It is the responsibility of the applicant to ascertain whether subsequent versions of the form have been published or produced by the competent authority
3. The report must be typed within the spaces provided in the form. The size of the spaces provided is not necessarily indicative of the amount of information to be provided. The report is in the form of a table that can extend itself as each space is filled with typing.
4. Where applicable **tick** the boxes that are applicable in the report.
5. An incomplete report may be returned to the applicant for revision.
6. The use of "not applicable" in the report must be done with circumspection because if it is used in respect of material information that is required by the competent authority for assessing the application, it may result in the rejection of the application as provided for in the regulations.
7. This report must be handed in at offices of the relevant competent authority as determined by each authority.
8. No faxed or e-mailed reports will be accepted.
9. The signature of the EAP on the report must be an original signature.
10. The report must be compiled by an independent environmental assessment practitioner.
11. Unless protected by law, all information in the report will become public information on receipt by the competent authority. Any interested and affected party should be provided with the information contained in this report on request, during any stage of the application process.

## BASIC ASSESSMENT REPORT

---

12. A competent authority may require that for specified types of activities in defined situations only parts of this report need to be completed.
13. Should a specialist report or report on a specialised process be submitted at any stage for any part of this application, the terms of reference for such report must also be submitted.
14. Two (2) colour hard copies and one (1) electronic copy of the report must be submitted to the competent authority.
15. Shape files (.shp) for maps must be included on the electronic copy of the report submitted to the competent authority.

---

## PROJECT DETAILS

---

<b>DEA Reference No.</b>	:	14/12/16/3/3/1/735
<b>Title</b>	:	Environmental Assessment Process Final Basic Assessment Report for the Proposed Gillmer Solar Energy Facility near Noupoot, Northern Cape Province
<b>Authors</b>	:	Savannah Environmental Lusani Rathanya Ravisha Ajodhapersadh Karen Jodas
<b>Sub-consultants</b>	:	Eduplan cc Zone Land Solutions Skaab cc Albany Museum Wildskies Ecological Services
<b>Client</b>	:	Gillmer Solar Energy (Pty) Ltd
<b>Report Status</b>	:	Final Basic Assessment Report for submission to Department of Environmental Affairs
<b>Review Period</b>	:	25 January 2012

When used as a reference this report should be cited as: Savannah Environmental (2013) Final Basic Assessment Report: Proposed Gillmer Solar Energy Facility near Noupoot, Northern Cape Province.

**COPYRIGHT RESERVED**

This technical report has been produced for Gillmer Solar Energy (Pty) Ltd. The intellectual property contained in this report remains vested in Savannah Environmental and Gillmer Solar Energy (Pty) Ltd. No part of the report may be reproduced in any manner without written permission from Gillmer Solar Energy (Pty) Ltd or Savannah Environmental (Pty) Ltd.

## TABLE OF CONTENTS

<b>PROJECT DETAILS</b> .....	<b>i</b>
<b>TABLE OF CONTENTS</b> .....	<b>ii</b>
<b>APPENDICES</b> .....	<b>iv</b>
<b>SUMMARY AND OVERVIEW OF THE PROPOSED PROJECT</b> .....	<b>6</b>
1.1 Summary of the Proposed Development.....	8
1.2 Requirement for an Environmental Impact Assessment Process .....	11
1.3 Details of an Environmental Assessment Practitioner and Expertise to conduct the Basic Assessment Process .....	12
<b>SECTION A: ACTIVITY INFORMATION</b> .....	<b>15</b>
1. PROJECT DESCRIPTION.....	15
a) Describe the project associated with the listed activities applied for.....	15
<b>a) Conduct Surveys</b> .....	15
<b>b) Establishment of Access Roads to the Site</b> .....	15
<b>c) Undertake Site Preparation</b> .....	16
<b>d) Transport of Components and Equipment to Site</b> .....	16
<b>e) Establishment of Laydown Areas on Site</b> .....	16
<b>f) Erect PV Cells</b> .....	16
<b>g) Establishment of Ancillary Infrastructure (Power line and office)</b> .....	17
<b>h) Undertake Site Rehabilitation</b> .....	17
<b>Activities to be undertaken during the Operational Phase of the PV Facility</b> .....	17
<b>Activities to be undertaken during the Decommissioning Phase of the PV Facility</b> .....	17
<b>a) Site Preparation</b> .....	18
<b>b) Disassemble Components</b> .....	18
b) Provide a detailed description of the listed activities associated with the project as applied for.....	18
2. FEASIBLE AND REASONABLE ALTERNATIVES .....	19
a) Site alternatives .....	20
b) Lay-out alternatives .....	22
c) Technology alternatives .....	22
d) Other alternatives (e.g. scheduling, demand, input, scale and design alternatives) N/A	23
e) No-go alternative.....	23
3. PHYSICAL SIZE OF THE ACTIVITY .....	24
a) Indicate the physical size of the preferred activity/technology as well as alternative activities/technologies (footprints):.....	24
b) Indicate the size of the alternative sites or servitudes (within which the above footprints will occur) N/A.....	24
4. SITE ACCESS .....	24
5. LOCALITY MAP.....	25
6. LAYOUT/ROUTE PLAN .....	25
7. SENSITIVITY MAP .....	26
8. SITE PHOTOGRAPHS .....	26
9. FACILITY ILLUSTRATION .....	26
10. ACTIVITY MOTIVATION .....	27
11. APPLICABLE LEGISLATION, POLICIES AND/OR GUIDELINES .....	34
12. WASTE, EFFLUENT, EMISSION AND NOISE MANAGEMENT.....	46

a)	<i>Solid waste management</i> .....	46
b)	<i>Liquid effluent</i> .....	47
c)	<i>Emissions into the atmosphere</i> .....	48
d)	<i>Waste permit</i> .....	48
e)	<i>Generation of noise</i> .....	48
13.	WATER USE .....	49
14.	ENERGY EFFICIENCY .....	49
<b>SECTION B: SITE/AREA/PROPERTY DESCRIPTION</b> .....		<b>50</b>
1.	GRADIENT OF THE SITE .....	51
2.	LOCATION IN LANDSCAPE .....	51
3.	GROUNDWATER, SOIL AND GEOLOGICAL STABILITY OF THE SITE .....	51
4.	GROUND COVER .....	52
5.	SURFACE WATER .....	53
6.	LAND USE CHARACTER OF SURROUNDING AREA .....	53
7.	CULTURAL/HISTORICAL FEATURES .....	55
8.	SOCIO-ECONOMIC CHARACTER .....	56
a)	<i>Local Municipality</i> .....	56
b)	<i>Socio-economic value of the activity</i> .....	58
9.	BIODIVERSITY .....	58
a)	<i>Indicate the applicable biodiversity planning categories of all areas on site and indicate the reason(s) provided in the biodiversity plan for the selection of the specific area as part of the specific category</i> .....	59
c)	<i>Complete the table to indicate:</i> .....	60
d)	<i>Please provide a description of the vegetation type and/or aquatic ecosystem present on site, including any important biodiversity features/information identified on site (e.g. threatened species and special habitats)</i> .....	60
<b>SECTION C: PUBLIC PARTICIPATION</b> .....		<b>62</b>
1.	ADVERTISEMENT AND NOTICE .....	62
2.	DETERMINATION OF APPROPRIATE MEASURES .....	62
3.	ISSUES RAISED BY INTERESTED AND AFFECTED PARTIES .....	63
4.	COMMENTS AND RESPONSE REPORT .....	64
5.	AUTHORITY PARTICIPATION .....	65
6.	CONSULTATION WITH OTHER STAKEHOLDERS .....	68
<b>SECTION D: IMPACT ASSESSMENT</b> .....		<b>69</b>
1.	IMPACTS THAT MAY RESULT FROM THE PLANNING AND DESIGN, CONSTRUCTION, OPERATIONAL, DECOMMISSIONING AND CLOSURE PHASES AS WELL AS PROPOSED MANAGEMENT OF IDENTIFIED IMPACTS AND PROPOSED MITIGATION MEASURES .....	69
2.	ENVIRONMENTAL IMPACT STATEMENT .....	80
<b>SECTION E. RECOMMENDATION OF PRACTITIONER</b> .....		<b>85</b>
<b>SECTION F: APPENDICES</b> .....		<b>90</b>

## APPENDICES

---

- Appendix A:** Maps
- Appendix B:** Photographs
- Appendix C:** Facility Illustration(s)
- Appendix D:** Specialist(s) Reports
- Appendix E:** Record of Public Involvement Process
- » *Appendix E1: Adverts and Notices*
  - » *Appendix E2: Stakeholder Letter*
  - » *Appendix E3: Comments*
  - » *Appendix E4: Proof from Authorities*
  - » *Appendix E5: Registered I & APs*
  - » *Appendix E6: Minutes of Meetings*
- Appendix F:** Impact Assessment
- Appendix G:** Draft Environmental Management Programme
- Appendix H:** Details of EAP & expertise
- Appendix I:** Specialist Declarations
- Appendix J:** Additional Information
- » J1: *List of Co-Ordinates for Power Line*

## **INVITATION TO COMMENT ON THE DRAFT BASIC ASSESSMENT REPORT**

The **Draft Basic Assessment Report** was made available for public review at the following place, which lie in the vicinity of the proposed project area from 30 November 2012- 17 January 2013:

- » Noupoot Public Library
- » The report was also made available for download on: [www.savannahsa.com](http://www.savannahsa.com)



---

## SUMMARY AND OVERVIEW OF THE PROPOSED PROJECT

---

Due to the exploitation of and large scale reliance on non-renewable resources and the potential subsequent impacts on climate, there is increasing pressure globally to increase the share of renewable energy generation. South Africa currently depends on fossil fuels for the supply of approximately 90% of its primary energy needs. With economic development over the next several decades resulting in an ever increasing demand for energy, there is some uncertainty as to the availability of economically extractable coal reserves for future use. Furthermore, several of South Africa's power stations are nearing the end of their economic life, require refurbishment, or have been recently returned to service (re-commissioned) at great expense (i.e. the Camden, Komati, and Grootvlei Power Stations).

The current electricity imbalances in South Africa highlight the significant role that renewable energy can play in terms of power supplementation. Given that renewables can generally be deployed in a decentralised manner close to consumers, they offer the opportunity for improving grid strength and supply quality, while reducing expensive transmission and distribution losses. At present, South Africa is some way off from exploiting the diverse gains from renewable energy and from achieving a considerable market share in the industry. In order to meet the long-term goal of a sustainable renewable energy industry, a target of 17.8 GW of renewables by 2030 has been set by the Department of Energy (DoE) within the Integrated Resource Plan (IRP) 2010 and incorporated in the IPP Procurement Programme. This energy will be produced from various renewable energy technologies including solar energy facilities (i.e. such as PV or CPV technology). The proposed project is to contribute towards this goal for renewable energy.

The purpose of the proposed Gillmer Solar facility is to sell the electricity generated to Eskom as part of the Renewable Energy Independent Power Producers (IPP) Procurement Programme. The IPP Procurement Programme has been introduced by the Department of Energy (DoE) to promote the development of renewable power generation facilities by IPPs. Selling of electricity according to the IPP Procurement Programme has the advantage of giving developers long-term stability and predictability, as well as providing the opportunity for the South African Government to introduce renewable energy into the power generation technology mix within the country, as per the aims of the Integrated Resource Plan (IRP) for the period 2010 – 2030.

Gillmer Solar Energy (Pty) Ltd has identified a site for consideration and evaluation through a Basic Environmental Assessment process. In terms of the Environmental Impact Assessment (EIA) Regulations published in terms of Section 24(5) of the National Environmental Management Act (NEMA, Act No. 107 of 1998), Gillmer Solar Energy (Pty) requires authorisation from the National Department of Environmental Affairs (DEA) (in

consultation with the Northern Cape Department of Environmental and Nature Conservation (NC-DENC)-for the construction and operation of the proposed Gillmer Solar Energy Facility Project. This project has been registered with the National DEA under application Reference Number **14/12/16/3/3/1/735**. In terms of Sections 24 and 24D of NEMA, as read with the EIA Regulations of GN R543 - R546, a Basic Assessment Process is required to be undertaken for this proposed project. This is due to the fact that the facility development area covers an area of less than 20 hectares and will have the generation capacity of the facility of up to 20 MW. In order to obtain authorisation, comprehensive and independent environmental studies must be undertaken in accordance with the EIA Regulations.

Gillmer Solar Energy (Pty) Ltd has appointed Savannah Environmental as the independent environmental consultants to undertake the required Basic Assessment and to identify and assess all the potential environmental impacts associated with the proposed project and propose appropriate mitigation and management measures in an Environmental Management Programme (EMP). As part of these environmental studies, I&APs have been actively involved through the public involvement process.

## 1.1 Summary of the Proposed Development

Gillmer Solar Energy (Pty) Ltd is proposing the establishment of a commercial solar energy facility near Noupoot, Northern Cape (Fig. 1). The purpose of the facility is to generate electricity from a renewable resource (i.e. sun) to provide power to the national electricity grid. The proposed development site is located within the Umsobomvu Local Municipality, approximately west of Noupoot town, Northern Cape.


The site is proposed to accommodate PV panels and associated infrastructure which is required for such a facility, including:

- » Arrays of photovoltaic (PV) panels with a capacity of 20 MW;
- » Cabling between the project components, to be laid underground where practical;
- » A new 66kV/132kV overhead power line of ~ 334m to connect the solar facility to the New Gate Substation or a 104 m power line to connect to the existing Eskom power line which traverses the site;
- » Internal access roads, fencing and
- » Workshop area for maintenance and storage.


A layout of the proposed PV facility is shown in Figure 2.

The developer (under separate Special Purpose Vehicles (SPVs) is also proposing several other solar energy facilities on farm portions around the Nourpoort area. These facilities are being considered within separate Basic Assessment processes under the following applications:

- » Wonderheuvel Solar Energy Facility DEA REF NO.: 14/12/16/3/3/1/731
- » Allemans Solar Energy Facility DEA REF NO.: 14/12/16/3/3/1/730
- » Damfontein Solar Energy Facility DEA REF NO.: 14/12/16/3/3/1/728.
- » Carolus Poort Solar Energy Facility DEA REF NO : 14/12/16/3/3/1/729



**Figure 1:** Locality map for the proposed Gillmer Solar Energy Facility, near Noupoort.



**Figure 2:** Map showing the Layout for the Gillmer Solar Energy Facility



## 1.2 Requirement for an Environmental Impact Assessment Process

In terms of the EIA Regulations published in terms of Section 24(5) of the National Environmental Management Act (NEMA, Act No. 107 of 1998), authorisation is required from DEA as the competent authority, in consultation with DENC, for the establishment of the proposed solar energy facility. In terms of sections 24 and 24D of NEMA, as read with the EIA Regulations of GN R543 – R546, a Basic Assessment process is required to be undertaken for the proposed project. The project has been registered with the National Department of Environmental Affairs as the competent authority under application reference number (14/12/16/3/3/1/735).

Relevant Notice & Activity number	Description of the Listed Activity	Applicability to the proposed project
GN 544, 18 JUNE 2010	1	<p>The construction of facilities or infrastructure for the generation of infrastructure for the generation of electricity where;</p> <p>i. the electricity output is more than 10 megawatts but less than 20 megawatts; or</p> <p>ii. The output is 10 megawatts or less but the total extent of the facility covers an area in excess of 1 hectare.</p> <p><b>The proposed facility will have a generation capacity of ~ 20 MW and will be constructed over an area larger than 1 ha.</b></p>
GN 544, 18 JUNE 2010	10	<p>The construction of facilities or infrastructure for the transmission and distribution of electricity-</p> <p>(i)outside urban areas or industrial complexes with a capacity of more than 33 but less than 275 kilovolts;</p> <p><b>The facility will require the construction of a 66kV/132kV overhead distribution power line, which will connect to the <i>New gate substation</i>.</b></p>
GN 544, 18 JUNE 2010	22	<p>The construction of a road, outside urban areas;</p> <p>(i)with a reserve wider than 13.5 meters</p> <p><b>The facility will require the upgrade of the existing road and construction of a new access roads within the site.</b></p>
GN 544, 18	23	The transformation of undeveloped, vacant or

JUNE 2010		derelict land to- (ii)residential, retail, commercial, recreational, industrial or institutional use, outside an urban area and where the total area to be transformed is bigger than 1 hectare but less than 20 hectares.  <b>The solar energy facility will involve transforming agricultural land-use to industrial land-use of an area outside an urban area and where the total area to be transformed is larger than 1 hectare but less than 20 hectares.</b>
GN 546, 18 JUNE 2010	14(a)(i)	The clearance of an area of 5 hectares or more of vegetation 75% or more of the vegetation cover constitutes indigenous vegetation  <b>The site is approx. 20ha and constitutes natural vegetation which will be cleared.</b>

### 1.3 Details of an Environmental Assessment Practitioner and Expertise to conduct the Basic Assessment Process

Savannah Environmental has been appointed as the independent environmental consultant, to undertake the Environmental Basic Assessment to identify and assess the potential environmental impacts associated with the proposed facility. Neither savannah Environmental nor any of its specialist sub-consultants on this project are subsidiaries of or are affiliated to Gillmer Solar Energy (Pty) Ltd. In addition, Savannah Environmental does not have any interest in secondary developments that may arise out of the authorisation of the proposed project.

Savannah Environmental is a specialist environmental consulting company providing holistic environmental management services, including environmental impact assessment and planning to ensure compliance and evaluate the risk of development and the development and implementation of environmental management tools. Savannah Environmental benefits from the pooled resources, diverse skills and experience in the environmental field held by its team that has been actively involved in undertaking environmental studies for a wide variety of projects throughout South Africa and neighbouring countries. Strong competencies have been developed in project management of environmental processes, as well as strategic environmental assessment and compliance advice, and the assessment of environmental impacts, the identification of environmental management solutions and mitigation/risk minimising measures.

The Savannah Environmental team has considerable experience in environmental impact assessments and environmental management, and have been actively involved in

undertaking environmental studies, for a wide variety of projects throughout South Africa, including those associated with electricity generation.

The EAP's from Savannah Environmental who are responsible for this project are:

- » *Karen Jodas* is a registered Professional Natural Scientist and holds a Master of Science degree. She has 14 years of experience consulting in the environmental field. Her key focus is on strategic environmental assessment and advice; management and co-ordination of environmental projects, which includes integration of environmental studies and environmental processes into larger engineering-based projects and ensuring compliance to legislation and guidelines; compliance reporting; the identification of environmental management solutions and mitigation/risk minimising measures; and strategy and guideline development. She is currently responsible for the project management of EIAs for several renewable energy projects across the country.
- » *Ravisha Ajodhapersadh*, the co-author of this report, holds an Honours Bachelor of Science degree in Environmental Management and has 5 years' experience in environmental management. She has undertaken EIAs for other proposed solar energy facilities in South Africa and has been involved in other projects in this area.
- » *Lusani Rathanya* - the principle author of this report holds an Honours Bachelor of Science degree in Environmental Management and analysis. Her key focus is on environmental impact assessments, public participation, environmental management plans and programmes, as well as mapping for a variety of environmental projects. She is currently the responsible EAP for several renewable energy projects EIAs across the country.
- » *Gabrielle Wood* - the public participation consultant for this project, hold an Honours Bachelor degree in Anthropology and has 5 years' experience in Public Participation and Social consultancy including professional execution of public participation consulting for a variety of projects as well as managing and coordinating public participation processes for Environmental Impact Assessments (EIA).

Savannah Environmental has gained extensive knowledge and experience on potential environmental impacts associated with electricity generation projects through their involvement in related EIA processes. Savannah Environmental has completed the EIA process and received environmental authorisations for numerous solar energy facilities.

Curricula vitae for the Savannah Environmental project team consultants are included in **Appendix H**.

In order to adequately identify and assess potential environmental impacts, several specialists have been appointed to conduct specialist studies, as required:

- » Ecology: Marianne Strohbach (of Savannah Environmental)
- » Soil & Agricultural Potential: Louis Di Pisani (of Eduplan cc)
- » Heritage resources: Celeste Booth (of the Albany Museum)



- » Visual: Johan Claassen (of Zone Land Solutions)
- » Palaeontology: Francois Durand (of Skarab cc)
- » Avifauna: Jon Smallie ( Wildskies Ecological Services)

Specialist's declaration of interest and CVs are included in the **Appendix I.**

## SECTION A: ACTIVITY INFORMATION

Has a specialist been consulted to assist with the completion of this section?  NO ✓

If YES, please complete the form entitled "Details of specialist and declaration of interest" for the specialist appointed and attach in Appendix I.

### 1. PROJECT DESCRIPTION

#### a) Describe the project associated with the listed activities applied for

The Gillmer project is proposed to be located within the Umsobomvu Local municipality in the Northern Cape. The Solar Energy Facility is proposed to be located on the Farm Noupoort No. 306 which is situated approximately west of Noupoort. The site is accessible via existing road from the R389 road.

The site is proposed to accommodate PV panels and associated infrastructure including:

- » Arrays of photovoltaic (PV) panels with a capacity of 20 MW;
- » Cabling between the project components, to be lain underground where practical;
- » A new 66kV/132kV overhead power line of ~ 334m to connect the solar facility to the New gate substation or a 104m power line to connect to the existing Eskom power line which traverses the site;
- » Internal access roads, fencing and
- » Workshop area for maintenance and storage.

#### **Activities to be undertaken during the Construction phase of the PV Facility:**

In order to construct the proposed PV solar energy facility and associated infrastructure, a series of activities will need to be undertaken. The construction process is discussed in more detail below.

#### **a) Conduct Surveys**

Prior to initiating construction, a number of surveys will be required including, but not limited to, a geotechnical survey, site survey and road servitudes.

#### **b) Establishment of Access Roads to the Site**

Access to the site (directly from the R389 via existing access road) will be required. Existing road on the farm portion will be used and upgraded where necessary (little to no clearing will be required). Within the site itself, access will be required to the

individual facility components for construction purposes (and later limited access for maintenance). Upgrade of access roads within the site will be required and new access roads will be required. Access track construction would normally comprise of compacted rock-fill with a layer of higher quality surfacing stone on top. The strength and durability properties of the rock strata at the proposed site are not known at this stage; this will need to be assessed via a geotechnical study to be conducted by the project proponent. Depending on the results of these studies, it may be possible, in some areas, to strip off the existing vegetation and ground surface and level the exposed formation to form an access track surface. The final layout of the access roads will be determined following the identification of site related sensitivities.

**c) Undertake Site Preparation**

Site preparation activities will include clearance of vegetation at the footprint of each support structure, if required. Vegetation will be kept undisturbed as far as possible in and between the support structures. These activities will require the stripping of topsoil which will need to be stockpiled, backfilled and/or spread on site.

**d) Transport of Components and Equipment to Site**

The components and equipment required for the construction of the proposed facility will be brought to site in sections by means of national and provincial roads and then proposed internal access road. Some of the components (i.e. transformer) may be defined as abnormal loads in terms of the Road Traffic Act (Act No. 29 of 1989)<sup>1</sup> by virtue of the dimensional limitations (i.e. weight).

Typical civil engineering construction equipment will need to be brought to the site (e.g. excavators, trucks, graders, compaction equipment, cement trucks, etc.) as well as components required for the upgrade of the substation and site preparation.

**e) Establishment of Laydown Areas on Site**

Laydown and storage areas will be required for the typical construction equipment which will be required on site, and within the development footprint.

**f) Erect PV Cells**

The PV cells will be arranged in arrays. The frames will be fixed onto the ground with the use of concrete / rammed into the ground, depending on the soil conditions, depending on the soil conditions at the site. This will make the installation of the plant less invasive for the territory and facilitate the decommissioning at the end of its production cycle. The height of the PV panel structure will be up to 4 m.

<sup>1</sup> A permit will be required for the transportation of these abnormal loads on public roads.

Inverters will be installed to facilitate the connection between the solar energy facility and the Eskom electricity grid via the New gate substation. The position of the inverters within the footprint of the broader site will be informed by the final positioning of the PV components.

**g) Establishment of Ancillary Infrastructure (Power line and office)**

Ancillary infrastructure includes an overhead power line feeding into the Eskom electricity network via the New Gate substation workshop, storage areas as well as a temporary contractor's equipment camp.

The establishment of the above ancillary infrastructure will require the clearing of vegetation and levelling of the development site and the excavation of foundations prior to construction. A laydown area for building materials and equipment associated with these buildings will also be required.

**h) Undertake Site Rehabilitation**

Once construction is completed and once all construction equipment is removed, the site must be rehabilitated where practical and reasonable. On full commissioning of the facility, any access points to the site which are not required during the operational phase must be closed and rehabilitated.

**Activities to be undertaken during the Operational Phase of the PV Facility**

The electricity that is generated from the PV panels will be stepped up through the on-site inverters and feed into the New Gate Substation which will be located on a nearby farm, via an overhead power line.

It is anticipated that a full-time security, maintenance and control room staff will be required on site. Each component within the solar energy facility will be operational except under circumstances of mechanical breakdown, unfavourable weather conditions or maintenance activities. Maintenance activities for the PV plant will include cleaning of the PV Panel's (using water), trimming of vegetation (underneath the panels) and maintenance of the infrastructure. Water will be required for construction and cleaning the PV panels, as and when needed to remove dust that may collect on the panels. Approximately 21 -43.25 m<sup>3</sup>/wash cycle, 1-2 times per annum will be required during operations for cleaning the PV panels. Gillmer Solar Energy (Pty) Ltd is looking into purchasing water from Umsobomvu Local Municipality to supply water for the cleaning of the panels over the life of the solar park or the use of on-site bore holes (if sufficient water available).

**Activities to be undertaken during the Decommissioning Phase of the PV**

**Facility**

The solar energy facility is expected to have a lifespan of more than 20 years (with maintenance) and the power plant infrastructure would only be decommissioned once it has reached the end of its economic life. If economically feasible/desirable the decommissioning activities would comprise the disassembly and replacement of the individual components with more appropriate technology/ infrastructure available at that time. However, if not deemed so, then the facility would be completely decommissioned which would include the following decommissioning activities.

**a) Site Preparation**

Site preparation activities will include confirming the integrity of the access to the site to accommodate the required equipment (e.g. lay down areas) and the mobilisation of decommissioning equipment.

**b) Disassemble Components**

The components would be disassembled, and reused and recycled (where possible), or disposed of in accordance with regulatory requirements.

**c) Rehabilitation**

Disturbed area (where infrastructure has been removed) will be rehabilitated, if required, depending on the future land-use of the facility.

**b) Provide a detailed description of the listed activities associated with the project as applied for**

Listed activity as described in GN R.544, 545 and 546	Description of project activity
GN 544, 18 JUNE 2010: 1(i)  The construction of facilities or infrastructure for the generation of electricity where: i. the electricity output is more than 10 megawatts but less than 20 megawatts;	Construction of a Photovoltaic Solar Energy Facility with a maximum generating capacity of up to 20MW in an area covering approximately 20 ha. Inverters, Step-Up transformers, reticulation cables, medium voltage connection and protection equipment and mounting structures are ancillary infrastructure for this facility.
GN 544, 18 JUNE 2010: 10 (i)  The construction of facilities or infrastructure for the transmission and distribution of electricity: i. Outside urban areas or industrial complexes with a capacity of more than 33 but less than 275 kilovolts;	The construction of a 66kV/132kV overhead power line from the solar facility to the Eskom electricity grid.

GN 544, 18 JUNE 2010: 22	The facility will require the upgrade of existing roads and construction of new access roads to the site.
GN 544, 18 JUNE 2010: 23  The transformation of undeveloped, vacant or derelict land to: i. Residential, retails, commercial, recreational, industrial, or institutional use, outside an urban area, and where the total area to be transformed is bigger than 1 hectare but less than 20 hectares.	The solar energy facility will involve transforming agricultural land-use to industrial land-use of an area outside an urban area and where the total area to be transformed is bigger than 1 hectare but less than 20 hectares. The area to be developed for the solar facility will be less than 20 hectares but more than 1 hectare.
GN 546, 18 JUNE 2010: 14(a)(i)  The clearance of an area of 5 hectares or more of vegetation where 75% or more of the vegetative cover constitutes indigenous vegetation i. All areas outside urban areas.	These constitute natural vegetation that will be cleared for construction of the PV panels and associated infrastructure.

## 2. FEASIBLE AND REASONABLE ALTERNATIVES

**“alternatives”**, in relation to a proposed activity, means different means of meeting the general purpose and requirements of the activity, which may include alternatives to—

- (a) the property on which or location where it is proposed to undertake the activity;
- (b) the type of activity to be undertaken;
- (c) the design or layout of the activity;
- (d) the technology to be used in the activity;
- (e) the operational aspects of the activity; and
- (f) the option of not implementing the activity.

Describe alternatives that are considered in this application as required by Regulation 22(2)(h) of GN R.543. Alternatives should include a consideration of all possible means by which the purpose and need of the proposed activity (NOT PROJECT) could be accomplished in the specific instance taking account of the interest of the applicant in the activity. The no-go alternative must in all cases be included in the assessment phase as the baseline against which the impacts of the other alternatives are assessed.

The determination of whether site or activity (including different processes, etc.) or both is appropriate needs to be informed by the specific circumstances of the activity and its environment. After receipt of this report the, competent authority may also request the

applicant to assess additional alternatives that could possibly accomplish the purpose and need of the proposed activity if it is clear that realistic alternatives have not been considered to a reasonable extent.

The identification of alternatives should be in line with the Integrated Environmental Assessment Guideline Series 11, published by the DEA in 2004. Should the alternatives include different locations and lay-outs, the co-ordinates of the different alternatives must be provided. The co-ordinates should be in degrees, minutes and seconds. The projection that must be used in all cases is the WGS84 spheroid in a national or local projection.

**a) Site alternatives**

<b>Alternative 1 (preferred alternative)</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)
<p>A site alternative refers to the identification of more than one potential site which may be suitable for the establishment of a proposed facility. However, the nature of the site required for renewable energy generation projects often means that assessment of the site alternative is not possible. This site has been selected based on the following preferences:</p> <ul style="list-style-type: none"> <li>» The solar resource (i.e. the daily normal irradiance for the Noupoort town is 7.21 KW/h); Site access (i.e. the site is accessible via existing road off the R389.</li> <li>» Site slope and topography (i.e. the proposed site for the placement of the PV panels is flat with no hills/mountains in the immediate vicinity that would cause shading issues or the need for excessive earthworks);</li> <li>» Access to the national electricity grid for power evacuation (i.e. 66/132 kV line will convey the power from the PV units, through the transformers, to the switchgear and directly to the New Gate Substation).</li> </ul> <p>As such, no site alternatives have been proposed for the establishment of the proposed solar energy facility.</p>	311044.504	245633.598
<b>Alternative 2</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)

<b>Alternative 3</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)

In the case of linear activities:

**Alternative:**

**Latitude (S):**

**Longitude (E):**

Alternative S1 (preferred) (Power line)

- Starting point of the activity
- Middle/Additional point of the activity
- End point of the activity

311032.91	245627.43
311033.20	245629.38
311.33.59	2455630.98

Alternative S2 (if any)

- Starting point of the activity
- Middle/Additional point of the activity
- End point of the activity

311033.59	245630.98
311031.53	245633.62
311025.15	245638.20

Alternative S3 (if any)

- Starting point of the activity
- Middle/Additional point of the activity
- End point of the activity


For route alternatives that are longer than 500m, please provide an addendum with co-ordinates taken every 250 meters along the route for each alternative alignment.

**See Appendix J1.**

In the case of an area being under application, please provide the co-ordinates of the corners of the site as indicated on the lay-out map provided in Appendix A.



**b) Lay-out alternatives**

<b>Alternative 1 (preferred alternative)</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)
Design and Layout alternatives were not assessed during the compilation of the DBAR. However, due to findings of the DBAR the initial layout was revised based on environmental sensitivities as indicated by the ecologist. The revised layout (see appendix <b>Figure 2</b> ) is therefore the recommended site layout alternative. The revised layout does not require further assessment as the changes are still within the initial footprint assessed during the Basic Assessment process and the potential impacts of the facility based on both layouts is the same.	311044.504	245633.598
<b>Alternative 2</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)
<b>Alternative 3</b>		
Description	Lat (DDMMSS)	Long (DDMMSS)

**c) Technology alternatives**

<b>Alternative 1 (preferred alternative)</b>
<p>Few technological options exist in as far as PV technologies are concerned; those that are available are usually differentiated by weather and temperature conditions that prevail – so that optimality is obtained by the final choice. The impacts of any of the PV technology choices are the same. Therefore, the choice of technology does not affect the environmental impact of the proposed development. The construction, operation and decommissioning of the facility will also be the same irrespective of the technology chosen. Therefore, no alternatives were assessed in this regard.</p> <p>No activity alternatives were assessed because the site has been identified by Gillmer Solar Energy and is being highly desirable for the establishment of a photovoltaic plant and not any other development or renewable technologies such as wind or concentrated solar power (CSP).</p>

Wind energy installations were not considered as a feasible and reasonable alternative as the proposed developmental area does not have the required wind resource.

CSP installations were not considered as a feasible and reasonable alternative as they require a large amount of water for cooling, unlike PV where water is only required for cleaning purposes (considering the fact that the site is in an arid area.). PV is also relatively easier to construct as opposed to CSP.

Therefore, a PV facility is considered by Gillmer Solar Energy to be the only feasible activity for the proposed site.

Alternative 2

Alternative 3

**d) Other alternatives (e.g. scheduling, demand, input, scale and design alternatives) N/A**

**Alternative 1 (preferred alternative)**

Description:

***Operating Alternatives***

This refers to the manner in which a proposed facility would function. For example, should a wind energy facility prove problematic for avifauna during migrating periods, an operating alternative of switching off certain turbines during those times could be proposed. No operating alternatives would be applicable to the proposed solar energy facility as there are no feasible means of alternative operation for a facility of this nature.

Alternative 2

Alternative 3

**e) No-go alternative**

This option is assessed as the "no go alternative" in this Basic Assessment Report.

**Paragraphs 3 – 13 below should be completed for each alternative.**

### 3. PHYSICAL SIZE OF THE ACTIVITY

**a) Indicate the physical size of the preferred activity/technology as well as alternative activities/technologies (footprints):**

**Alternative:**

Alternative A1<sup>2</sup> (preferred activity alternative)

Alternative A2 (if any)

Alternative A3 (if any)

**Size of the activity:**

140 000 m <sup>2</sup>
m <sup>2</sup>
m <sup>2</sup>

or, for linear activities:

**Alternative:**

Alternative A1 (preferred activity alternative)

Alternative A2 (if any)

Alternative A3 (if any)

**Length of the activity:**

104m
334m
m

**b) Indicate the size of the alternative sites or servitudes (within which the above footprints will occur) N/A**

**Alternative:**

Alternative A1 (preferred activity alternative)

Alternative A2 (if any)

Alternative A3 (if any)

**Size of the site/servitude:**

30m servitude (power line)
m <sup>2</sup>
m <sup>2</sup>

### 4. SITE ACCESS

Does ready access to the site exist?

If NO, what is the distance over which a new access road will be built

YES ✓	
m	

<sup>2</sup> "Alternative A.." refer to activity, process, technology or other alternatives.

Describe the type of access road planned:

The site is accessible via existing road from the R389 road. This existing road on the farm portion will be used and upgraded where necessary.

Include the position of the access road on the site plan and required map, as well as an indication of the road in relation to the site.

## 5. LOCALITY MAP

An A3 locality map must be attached to the back of this document, as **Appendix A**. The scale of the locality map must be relevant to the size of the development (at least 1:50 000. For linear activities of more than 25 kilometres, a smaller scale e.g. 1:250 000 can be used. The scale must be indicated on the map.). The map must indicate the following:

- an accurate indication of the project site position as well as the positions of the alternative sites, if any;
- indication of all the alternatives identified;
- closest town(s);
- road access from all major roads in the area;
- road names or numbers of all major roads as well as the roads that provide access to the site(s);
- all roads within a 1km radius of the site or alternative sites; and
- a north arrow;
- a legend; and
- locality GPS co-ordinates (Indicate the position of the activity using the latitude and longitude of the centre point of the site for each alternative site. The co-ordinates should be in degrees and decimal minutes. The minutes should have at least three decimals to ensure adequate accuracy. The projection that must be used in all cases is the WGS84 spheroid in a national or local projection).

An A3 Locality Map is attached as **Appendix A**.

## 6. LAYOUT/ROUTE PLAN

A detailed site or route plan(s) must be prepared for each alternative site or alternative activity. It must be attached as **Appendix A** to this document.

The site or route plans must indicate the following:

- the property boundaries and numbers of all the properties within 50 metres of the site;

- the current land use as well as the land use zoning of the site;
- the current land use as well as the land use zoning each of the properties adjoining the site or sites;
- the exact position of each listed activity applied for (including alternatives);
- servitude(s) indicating the purpose of the servitude;
- a legend; and
- a north arrow.

A detailed plan (s) for each alternative activity is attached as **Appendix A**.

## 7. SENSITIVITY MAP

The layout/route plan as indicated above must be overlain with a sensitivity map that indicates all the sensitive areas associated with the site, including, but not limited to:

- watercourses;
- the 1:100 year flood line (where available or where it is required by DWA);
- ridges;
- cultural and historical features;
- areas with indigenous vegetation (even if it is degraded or infested with alien species); and
- critical biodiversity areas.

The sensitivity map must also cover areas within 100m of the site and must be attached in **Appendix A**.

A sensitivity map covering areas 100m of the site is attached in **Appendix A**.

## 8. SITE PHOTOGRAPHS

Colour photographs from the centre of the site must be taken in at least the eight major compass directions with a description of each photograph. Photographs must be attached under **Appendix B** to this report. It must be supplemented with additional photographs of relevant features on the site, if applicable.

Colour photographs have been taken from the centre of the proposed site in the eight major compass directions. Annotated photographs are included in **Appendix B**.

## 9. FACILITY ILLUSTRATION

A detailed illustration of the activity must be provided at a scale of at least 1:200 as **Appendix C** for activities that include structures. The illustrations must be to scale and must represent a realistic image of the planned activity. The illustration must give a representative view of the activity.

A facility illustration which represents a realistic image of the planned solar energy facility is attached within **Appendix C**.

## 10. ACTIVITY MOTIVATION

Motivate and explain the need and desirability of the activity (including demand for the activity):

<b>1. Is the activity permitted in terms of the property's existing land use rights?</b>		NO ✓	Please explain
The site is zoned agricultural. An application will be required to be made to change the land use rights to accommodate the solar energy facility			
<b>2. Will the activity be in line with the following?</b>			
<b>(a) Provincial Spatial Development Framework (PSDF)</b>		YES ✓	Please explain
The Northern Cape Province Spatial Development Framework (NCPSDF) makes reference to the need to ensure the availability of inexpensive energy. The section notes that in order to promote economic growth in the Northern Cape the availability of electricity to key industrial users at critical localities at rates that enhance the competitiveness of their industries must be ensured. At the same time, the development of new sources of energy through the promotion of the adoption of energy applications that display a synergy with the province's natural resource endowments must be encouraged. In this regard the NCPSDF notes "the development of energy sources such as solar energy, the natural gas fields, bio-fuels, etc., could be some of the means by which new economic opportunity and activity is generated in the Northern Cape". The NCPSDF also highlights the importance of close co-operation between the public and private sectors in order for the economic development potential of the Northern Cape to be realised.			
<b>(b) Urban edge / Edge of Built environment for the area</b>		NO ✓	Please explain
The site lies west of the urban edge related to the town of Noupoort. The site is proposed outside an urban area. The Farm Noupoort is currently utilised for farming (grazing of livestock). Addition of a PV Facility on the Farm Noupoort will not significantly alter the urban edge of Noupoort or the Umsobomvu Local Municipality, as the current farming activities will continue on areas of the Farm which will not be occupied by infrastructure for the solar energy facility. Therefore the project is compatible with the farming activities in a rural area which is outside the urban edge of			

the Umsobomvu Local Municipality.		
<b>(c) Integrated Development Plan (IDP) and Spatial Development Framework (SDF) of the Local Municipality (e.g. would the approval of this application compromise the integrity of the existing approved and credible municipal IDP and SDF?).</b>		NO ✓ Please explain
The main IDP and SDP objective of the Pixley ka Seme District Municipality is to provide access to electricity to all households in the district by 2014. To achieve this, the district aims at fast-tracking the delivery of free basic electricity and co-ordinate the maintenance and upgrading of existing electricity infrastructure. The construction of the proposed PV solar panels will be meeting the objective.		
<b>(d) Approved Structure Plan of the Municipality</b>	YES ✓	Please explain
The municipality aims at ensuring that all citizens have access to basic services such as electricity, and this project will be addressing such issues in the local municipality.		
<b>(e) An Environmental Management Framework (EMF) adopted by the Department (e.g. Would the approval of this application compromise the integrity of the existing environmental management priorities for the area and if so, can it be justified in terms of sustainability considerations?)</b>		NO ✓ Please explain
The Municipality does not have an EMF, however an Integrated Environmental Management Programme was compiled by the District Municipality to ensure that land use decision making must be taken with adequate environmental resource information is available in other to ensure sustainable and appropriate environmental management to the benefit of its residents. One of the set goals for the Plan is ensuring that all environmental issues are appropriately addressed.		
Renewable energy projects such the proposed Gillmer Solar Energy project will contribute to clean energy generation as a sustainable resource and holds huge benefits for the local region and the country as a whole. Renewable resources generally operate from an unlimited resource base and, as such, can increasingly contribute towards a long-term sustainable energy future, the project aims on achieving the set goals for the Plan through addressing all possible environmental issues associated with the development and address measure to mitigate environmental issues.		
<b>(f) Any other Plans (e.g. Guide Plan) N/A</b>		Please explain

<p><b>3. Is the land use (associated with the activity being applied for) considered within the timeframe intended by the existing approved SDF agreed to by the relevant environmental authority (i.e. is the proposed development in line with the projects and programmes identified as priorities within the credible IDP)?</b></p>	<p>YES ✓</p>		<p>Please explain</p>
<p>The main IDP and SDP objective of the Pixley ka Seme District Municipality is to provide access to electricity to all households in the district by 2014. To achieve this, the district aims at fast-tracking the delivery of free basic electricity and co-ordinate the maintenance and upgrading of existing electricity infrastructure. The construction of the proposed PV solar panels will be meeting the objective.</p>			
<p><b>4. Does the community/area need the activity and the associated land use concerned (is it a societal priority)? (This refers to the strategic as well as local level (e.g. development is a national priority, but within a specific local context it could be inappropriate.)</b></p>	<p>YES ✓</p>		<p>Please explain</p>
<p>The evacuation of additional power into the Eskom grid will serve to improve the stability of the grid for the immediate area, assist the government in achieving the goal of 17GW renewable energy as part of the electricity generation technology mix by 2030, and assist in the reduction in the need to mine non-renewable resources such as coal for conventional power generation.</p> <p>The proposed activity is not a necessarily a societal priority for the community; however the development will benefit the local community through jobs creation, skills development opportunities and training which will in turn reduce poverty level that the area is currently facing; strengthen electricity supply for the area.</p>			
<p><b>5. Are the necessary services with adequate capacity currently available (at the time of application), or must additional capacity be created to cater for the development? (Confirmation by the relevant Municipality in this regard must be attached to the final Basic Assessment Report as Appendix I.)</b></p>	<p>YES ✓</p>		<p>Please explain</p>



<p><b>6. Is this development provided for in the infrastructure planning of the municipality, and if not what will the implication be on the infrastructure planning of the municipality (priority and placement of services and opportunity costs)? (Comment by the relevant Municipality in this regard must be attached to the final Basic Assessment Report as Appendix I.)</b></p>		<p>NO ✓</p>	<p>Please explain</p>
<p>The proposed project is to be developed by a private developer (i.e. Gillmer Solar Energy) and not the municipality. It therefore does not fall within the infrastructure planning of the municipality. The project will not have any implications for the municipality but assist them in their infrastructural planning priorities through the increasing electricity capacity.</p>			
<p><b>7. Is this project part of a national programme to address an issue of national concern or importance?</b></p>	<p>YES ✓</p>		<p>Please explain</p>
<p>The current electricity imbalances in South Africa highlight the significant role that renewable energy can play in terms of power supplementation. Given that renewables can generally be deployed in a decentralised manner close to consumers, they offer the opportunity for improving grid strength and supply quality, while reducing expensive transmission and distribution losses. At present, South Africa is some way off from exploiting the diverse gains from renewable energy and from achieving a considerable market share in the industry. In order to meet the long-term goal of a sustainable renewable energy industry, a target of 17.8 GW of renewables by 2030 has been set by the Department of Energy (DoE) within the Integrated Resource Plan (IRP) 2010 and incorporated in the IPP Procurement Programme. This energy will be produced from various renewable energy technologies including solar energy facilities (i.e. such as PV or CPV technology). The proposed project is to contribute towards this goal through generation of renewable energy.</p>			
<p><b>8. Do location factors favour this land use (associated with the activity applied for) at this place? (This relates to the contextualisation of the proposed land use on this site within its broader context.)</b></p>	<p>YES ✓</p>		<p>Please explain</p>
<p><i>Site access</i> The site can be accessed easily via existing access roads from R389 road.</p> <p><i>Climatic Conditions</i> The economic viability of a photovoltaic plant is directly dependent on the annual direct solar irradiation values. A study of available radiation data shows that the proposed site is uniformly irradiated by the sun. In addition, compared to other areas in the country with similar irradiation, the site experiences moderate temperatures which are suitable for PV technology.</p> <p><i>Gradient</i> A level surface area (i.e. with a minimal gradient in the region of 1%) is preferred for</p>			

the installation of PV panels and specifically for PV technologies (Fluri, 2009). This reduces the need for extensive earthworks associated with the levelling of a site, thereby minimising environmental impacts. The proposed area for the proposed PV plant is generally on a flat location with slopes less than 5 degrees.

*Grid Connection*

The proposed facility is in a close proximity (approx. 334 m) to the proposed New Gate substation, the new substation will have enough capacity to accommodate the proposed PV Solar energy facility.

<b>9. Is the development the best practicable environmental option for this land/site?</b>	YES ✓		Please explain
--	-------	--	----------------

The proposed activity which will occupy an area less than 20 ha will represent a change in land use and land form to what is currently the status quo. However the proposed development is for proposed PV solar energy; this is a renewable energy project, which is the best practicable environmental option for the type of land since the proposed development can allow the current land-use to continue on the rest of the farm portion (i.e. the rest of the land which is not utilised for the facility).

<b>10. Will the benefits of the proposed land use/development outweigh the negative impacts of it?</b>	YES ✓		Please explain
--	-------	--	----------------

- » This basic assessment report identified that no environmental fatal flaws are associated with the project. The potential negative impacts for the project include:
  - Clearing of natural vegetation for the proposed footprint area, increasing the potential for soil erosion, deterioration of the biotic, abiotic and economic properties of soil, and the long-term loss of natural vegetation;
  - Possible destruction of stone artefact occurrences and scatters. That are scattered over the extent of the proposed Gillmer Solar Energy Facility area and within the existing site access that is proposed to be used as the access road for the project.
- » Most of these impacts can be managed and mitigated as outlined in the Impact Assessment and Environmental Management Programme. Below are some of the benefits associated with the development:
  - Pollution reduction: The releases of by-products through the burning of fossil fuels for electricity generation have a particularly hazardous impact on human health and contribute to ecosystem degradation.
  - Support for international agreements: The effective deployment of renewable energy provides a tangible means for South Africa to demonstrate its commitment to its international agreements under the Kyoto Protocol, and for cementing its status as a leading player within the international community.
  - Employment creation: The sale, development, installation, maintenance, and management of renewable energy facilities have significant potential for job

<p>creation in South Africa.</p> <ul style="list-style-type: none"> <li>○ Acceptability to society: Renewable energy offers a number of tangible benefits to society including reduced pollution concerns, improved human, and ecosystem health.</li> <li>○ Support to a new industry sector: The development of renewable energy offers the opportunity to establish a new industry within the South African economy.</li> <li>○ Support to local community: Since the local community will acquire some ownership in the facility, some of the revenue generated by the facility will be utilised for upliftment of the local community.</li> </ul> <p>The negative impacts referred to above could also result from activities associated with the current land use. This is not true of the positive impacts. It is considered reasonable that the benefits of the proposed land use/development will outweigh the negative impacts.</p>			
<b>11. Will the proposed land use/development set a precedent for similar activities in the area (local municipality)?</b>	YES ✓		Please explain
<p>There are similar developments being proposed in the Umsobomvu Local Municipality which have received environmental authorisations; however no solar projects have been developed yet in the area. It is considered that the precedent for the development of renewable energy projects in this area and within this Municipality has already been set, and local support has been shown by landowners, and the Municipality.</p>			
<b>12. Will any person's rights be negatively affected by the proposed activity/ies?</b>		NO ✓	Please explain
<p>The proposed project will be taking place in a privately owned land and will not in any way infringe on any person's rights.</p>			
<b>13. Will the proposed activity/ies compromise the "urban edge" as defined by the local municipality?</b>		NO ✓	Please explain
<p>The site is located west of the urban edge related to the town of Noupoort. The site is proposed outside an urban area. The Farm Noupoort 306 is currently utilised for farming (grazing of livestock). Addition of a PV Facility on the Farm Noupoort will not significantly alter the urban edge of Noupoort or the Umsobomvu Local Municipality, as the current farming activities will continue on areas of the Farm which will not be occupied by infrastructure for the solar energy facility. Therefore the project compatible with the farming activities in a rural area which is outside the urban edge of the Umsobomvu Local Municipality.</p>			
<b>14. Will the proposed activity/ies contribute to any of the 17 Strategic Integrated Projects (SIPS)?</b>	YES ✓		Please explain
<p>One of the 17 Strategic Integrated Project (SIPS) is to address issues of electricity infrastructure, unemployment and climate change. The proposed project will be addressing these issues.</p>			

<b>15. What will the benefits be to society in general and to the local communities?</b>	Please explain
Job opportunities, albeit limited, will be created during the construction and operation of the proposed facility. In addition, local and regional economic benefits would be realised through the additional revenue generated as a result of the proposed project (through direct and indirect job opportunities, local spend, local procurement, etc.).	
<b>16. Any other need and desirability considerations related to the proposed activity?</b>	Please explain
The area is in need of infrastructure which will benefit the municipal economy.	
<b>17. How does the project fit into the National Development Plan for 2030?</b>	Please explain
One of the National Development Plan for 2030 is the transition to low carbon energy through speeding up and expanding renewable energy. This project will fit into this vision since it aims on increasing electricity supply through carbon-free methods.	
<b>18. Please describe how the general objectives of Integrated Environmental Management as set out in section 23 of NEMA have been taken into account.</b>	
The general objectives of Integrated Environmental Management have been taken into account for this Basic Assessment report by means of identifying, predicting and evaluating the actual and potential impacts on the environment, socio-economic conditions and cultural heritage component. The risks, consequences, alternatives as well as options for mitigation of activities have also been considered with a view to minimise negative impacts, maximise benefits, and promote compliance with the principles of environmental management.	
<b>19. Please describe how the principles of environmental management as set out in section 2 of NEMA have been taken into account.</b>	
<p>The principle of environmental management as set out in section of NEMA states that:</p> <ul style="list-style-type: none"> <li>» Environmental management must place people and their needs at the forefront of its concern, and serve their physical, psychological, developmental, cultural and social interests equitably;</li> <li>» Development must be sustainable socially (people), environmentally (planet) and economically (prosperity);and</li> <li>» Sustainable development requires the consideration of all the relevant factors,</li> </ul> <p>These principles have been taken into account for this Basic Assessment report by means of identifying, predicting and evaluating the actual and potential impacts on the environment, socio-economic conditions and cultural heritage component. The risks, consequences, alternatives as well as options for mitigation of activities have also been considered with a view to minimise negative impacts, maximise benefits, and promote compliance with the principles of environmental management.</p>	

## **11. APPLICABLE LEGISLATION, POLICIES AND/OR GUIDELINES**

List all legislation, policies and/or guidelines of any sphere of government that are applicable to the application as contemplated in the EIA regulations, if applicable:

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
<b>National Legislation</b>			
National Environmental Management Act (Act No 107 of 1998)	<p>The Basic Assessment Regulations have been promulgated in terms of Chapter 5 of the Act. Listed activities which may not commence without an environmental authorisation are identified within these Regulations.</p> <p>In terms of S24(1) of NEMA, the potential impact on the environment associated with these listed activities must be assessed and reported on to the competent authority charged by NEMA with granting of the relevant environmental authorisation.</p> <p>In terms of GN R543, R544, R545 and R546 of 18 June 2010, a Basic Assessment Process is required to be undertaken for the proposed project.</p>	<p>Department of Environmental Affairs – competent authority</p> <p>Department of Environmental and Nature Conservation (DENC)- commenting authority</p>	<p>The listed activities triggered by the proposed solar energy facility have been identified and assessed in the Basic Assessment Process being undertaken. This Basic Assessment Report will be submitted to the competent and commenting authority in support of the application for authorisation.</p>
National Environmental Management Act (Act No 107 of 1998)	<p>In terms of the Duty of Care Provision in S28(1) the project proponent must ensure that reasonable measures are taken throughout the life cycle of this project to ensure that any pollution or degradation of the environment associated with this project is avoided, stopped or minimised.</p> <p>In terms of NEMA, it has become the legal duty of a project proponent to consider a project holistically, and to consider the cumulative effect of a variety of impacts.</p>	<p>Department of Environmental Affairs</p>	<p>While no permitting or licensing requirements arise directly by virtue of the proposed project, this section has found application during the Basic Assessment Process through the consideration of potential impacts (cumulative, direct, and indirect). It will continue to apply throughout the life</p>

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
<p>Environment Conservation Act (Act No 73 of 1989)</p>	<p>National Noise Control Regulations (GN R154 dated 10 January 1992)</p>	<p>Department of Environmental Affairs                       Department of Environmental and Nature Conservation (DENC)-                       Local Authorities</p>	<p>cycle of the project.</p> <p>Noise impacts are expected to be associated with the construction phase of the project and are not likely to present a significant intrusion to the local community. Therefore is no requirement for a noise permit in terms of the legislation.</p> <p>On-site activities should be limited to 6:00am - 6:00pm, Monday – Saturday (excluding public holidays).</p> <p>Should activities need to be undertaken outside of these times, the surrounding communities will need to be notified and appropriate approval will be obtained from DEA and the Local Municipality.</p>
<p>National Water Act (Act No 36 of 1998)</p>	<p>Water uses under S21 of the Act must be licensed, unless such water use falls into one of the categories listed in S22 of the Act or falls under the general</p>	<p>Department of Water Affairs</p>	<p>A water use license (WUL) is required to be obtained if wetlands or drainage</p>

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	<p>authorisation (and then registration of the water use is required).</p> <p>Consumptive water uses may include the taking of water from a water resource - Sections 21a and b.</p> <p>Non-consumptive water uses may include impeding or diverting of flow in a water course - Section 21c; and altering of bed, banks or characteristics of a watercourse - Section 21i.</p>	<p>Provincial Department of Water Affairs</p>	<p>lines are impacted on, or if infrastructure lies within 500m of such features. Pans occur on the project site, but outside of the development footprint.</p> <p>Should water be abstracted from ground water/ a borehole on site for use within the facility, a water use license may be required.</p>
<p>Minerals and Petroleum Resources Development Act (Act No 28 of 2002)</p>	<p>A mining permit or mining right may be required where a mineral in question is to be mined (e.g. materials from a borrow pit) in accordance with the provisions of the Act.</p> <p>Requirements for Environmental Management Programmes and Environmental Management Plans are set out in S39 of the Act.</p> <p>S53 Department of Mineral Resources: Approval from the Department of Mineral Resources (DMR) may be required to use land surface contrary to the objects of the Act in terms of section 53 of the Mineral and Petroleum Resources Development Act, (Act No 28 of 2002): In terms of the Act approval from the Minister of Mineral Resources is required to ensure that proposed activities do not sterilise a mineral resources that might</p>	<p>Department of Mineral Resources</p>	<p>As no borrow pits are expected to be required for the construction of the facility, no mining permit or right is required to be obtained.</p> <p>A Section 53 application will be submitted the Northern Cape DMR office.</p>



Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
National Environmental Management: Air Quality Act (Act No 39 of 2004)	occur on site.  Measures in respect of dust control (S32) - no regulations promulgated yet.  Measures to control noise (S34) - no regulations promulgated yet.	Department of Environmental Affairs	No permitting or licensing requirements arise from this legislation.  The Act provides that an air quality officer may require any person to submit an atmospheric impact report if there is reasonable suspicion that the person has failed to comply with the Act.
National Heritage Resources Act (Act No 25 of 1999)	<ul style="list-style-type: none"> <li>» Stipulates assessment criteria and categories of heritage resources according to their significance (S7).</li> <li>» Provides for the protection of all archaeological and paleontological sites, and meteorites (S35).</li> <li>» Provides for the conservation and care of cemeteries and graves by SAHRA where this is not the responsibility of any other authority (S36).</li> <li>» Lists activities which require developers any person who intends to undertake to notify the responsible heritage resources authority and furnish it with details regarding the location, nature, and extent of the proposed development (S38).</li> <li>» Requires the compilation of a Conservation Management Plan as well as a permit from SAHRA for the presentation of archaeological sites as part of</li> </ul>	South African Heritage Resources Agency	An HIA and PIA has been undertaken as part of the Basic Assessment Process to identify heritage sites.(See Appendix D2).

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
National Environmental Management: Biodiversity Act (Act No 10 of 2004)	tourism attraction (S44). » Provides for the MEC/Minister to identify any process or activity in such a listed ecosystem as a threatening process (S53) » A list of threatened and protected species has been published in terms of S 56(1) - Government Gazette 29657. » Three government notices have been published, i.e. GN R 150 (Commencement of Threatened and Protected Species Regulations, 2007), GN R 151 (Lists of critically endangered, vulnerable and protected species) and GN R 152 (Threatened or Protected Species Regulations). » Provides for listing threatened or protected ecosystems, in one of four categories: critically endangered (CR), endangered (EN), and vulnerable (VU) or protected. The first national list of threatened terrestrial ecosystems has been gazetted, together with supporting information on the listing process including the purpose and rationale for listing ecosystems, the criteria used to identify listed ecosystems, the implications of listing ecosystems, and summary statistics and national maps of listed ecosystems (National Environmental Management: Biodiversity Act: National list of ecosystems that are threatened and in need of protection, (G 34809, GN 1002), 9 December 2011). » This Act also regulates alien and invader species.	Department of Environmental Affairs	As the applicant will not carry out any restricted activity, as is defined in S1 of the Act, no permit is required to be obtained in this regard.  Specialist flora and fauna studies have been undertaken as part of the Basic Assessment Process. As such the potentially occurrence of critically endangered, endangered, vulnerable, and protected species and the potential for them to be affected has been considered.

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	<ul style="list-style-type: none"> <li>» Under this Act, a permit would be required for any activity which is of a nature that may negatively impact on the survival of a listed protected species.</li> </ul>		
<p>Conservation of Agricultural Resources Act (Act No 43 of 1983)</p>	<ul style="list-style-type: none"> <li>» Prohibition of the spreading of weeds (S5)</li> <li>» Classification of categories of weeds &amp; invader plants (Regulation 15 of GN R1048) &amp; restrictions in terms of where these species may occur.</li> <li>» Requirement &amp; methods to implement control measures for alien and invasive plant species (Regulation 15E of GN R1048).</li> </ul>	<p>Department of Agriculture</p>	<p>This Act will find application throughout the life cycle of the project. In this regard, soil erosion prevention and soil conservation strategies must be developed and implemented. In addition, a weed control and management plan must be implemented.</p> <p>The permission of agricultural authorities will be required if the Project requires the draining of vleis, marshes or water sponges on land outside urban areas.</p>
<p>National Forests Act (Act No. 84 of 1998)</p>	<p>According to this act, the Minister has declared a tree, group of trees, woodland or a species of trees as protected. The prohibitions provide that 'no person may cut, damage, disturb, destroy or remove any protected tree, or collect, remove, transport, export, purchase, sell, donate or in any other manner acquire or dispose of any protected tree, except under a licence granted by</p>	<p>National Department of Forestry</p>	<p>They are no protected trees in the study area.</p>

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
National Veld and Forest Fire Act (Act 101 of 1998)	<p>the Minister’.</p> <p>In terms of S12 the applicant must ensure that the firebreak is wide and long enough to have a reasonable chance of preventing the fire from spreading, not causing erosion, and is reasonably free of inflammable material.</p> <p>In terms of S17, the applicant must have such equipment, protective clothing, and trained personnel for extinguishing fires.</p>	Department of Agriculture, Forestry and Fisheries (DAFF)	While no permitting or licensing requirements arise from this legislation, this act will find application during the construction and operational phase of the project.
Hazardous Substances Act (Act No 15 of 1973)	<p>This Act regulates the control of substances that may cause injury, or ill health, or death due to their toxic, corrosive, irritant, strongly sensitising or inflammable nature or the generation of pressure thereby in certain instances and for the control of certain electronic products. To provide for the rating of such substances or products in relation to the degree of danger; to provide for the prohibition and control of the importation, manufacture, sale, use, operation, modification, disposal or dumping of such substances and products.</p> <p>Group I and II: Any substance or mixture of a substance that might by reason of its toxic, corrosive etc., nature or because it generates pressure through decomposition, heat or other means, cause extreme risk of injury etc., can be declared as Group I or Group II substance</p> <p>Group IV: any electronic product; and</p>	Department of Health	It is necessary to identify and list all the Group I, II, III, and IV hazardous substances that may be on the site and in what operational context they are used, stored or handled. If applicable, a license is required to be obtained from the Department of Health.

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	Group V: any radioactive material. The use, conveyance, or storage of any hazardous substance (such as distillate fuel) is prohibited without an appropriate license being in force.		
Development Facilitation Act (Act No 67 of 1995)	Provides for the overall framework and administrative structures for planning throughout the Republic. S (2 - 4) provides general principles for land development and conflict resolution.	Local Municipality	The applicant must submit a land development application in the prescribed manner and form as provided for in the Act. A land development applicant who wishes to establish a land development area must comply with procedures set out in the Act.
Subdivision of Agricultural Land Act (Act No 70 of 1970)	Details land subdivision requirements and procedures. Applies for subdivision of all agricultural land in the Province.	Department of Agriculture	Subdivision will have to be in place prior to any subdivision approval in terms of S24 and S17 of the Act.
National Environmental Management: Waste Act, 2008 (Act No. 59 of 2008)	The Minister may by notice in the <i>Gazette</i> publish a list of waste management activities that have, or are likely to have, a detrimental effect on the environment.  The Minister may amend the list by –  » Adding other waste management activities to the list. » Removing waste management activities from the	National Department of Water and Environmental Affairs  Provincial Department of Environmental Affairs (general waste)	As no waste disposal site is to be associated with the proposed project, no permit is required in this regard.  Waste handling, storage and disposal during construction and operation

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	<p>list.</p> <ul style="list-style-type: none"> <li>» Making other changes to the particulars on the list.</li> </ul> <p>In terms of the Regulations published in terms of this Act (GN 718), A Basic Assessment or Environmental Impact Assessment is required to be undertaken for identified listed activities.</p> <p>Any person who stores waste must at least take steps, unless otherwise provided by this Act, to ensure that:</p> <ul style="list-style-type: none"> <li>» The containers in which any waste is stored, are intact and not corroded or in</li> <li>» Any other way rendered unfit for the safe storage of waste.</li> <li>» Adequate measures are taken to prevent accidental spillage or leaking.</li> <li>» The waste cannot be blown away.</li> <li>» Nuisances such as odour, visual impacts and breeding of vectors do not arise; and</li> <li>» Pollution of the environment and harm to health are prevented.</li> </ul>		<p>is required to be undertaken in accordance with the requirements of the Act, as detailed in the EMP (refer to Appendix G).</p> <p>The volumes of waste to be generated and stored on the site during construction and operation of the facility will not require a waste license (provided these remain below the prescribed thresholds).</p>
<p>National Road Traffic Act (Act No 93 of 1996)</p>	<ul style="list-style-type: none"> <li>» The technical recommendations for highways (TRH 11): "Draft Guidelines for Granting of Exemption Permits for the Conveyance of Abnormal Loads and for other Events on Public Roads" outline the rules and conditions which apply to the transport of abnormal loads and vehicles on public roads and the detailed procedures to be followed in applying for</li> </ul>	<ul style="list-style-type: none"> <li>» South African National Roads Agency Limited (national roads)</li> <li>» Provincial Department of Transport</li> </ul>	<p>An abnormal load/vehicle permit may be required to transport the various components to site for construction. These include route clearances and permits will be</p>

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	<p>exemption permits are described and discussed.</p> <ul style="list-style-type: none"> <li>» Legal axle load limits and the restrictions imposed on abnormally heavy loads are discussed in relation to the damaging effect on road pavements, bridges, and culverts.</li> <li>» The general conditions, limitations, and escort requirements for abnormally dimensioned loads and vehicles are also discussed and reference is made to speed restrictions, power/mass ratio, mass distribution, and general operating conditions for abnormal loads and vehicles. Provision is also made for the granting of permits for all other exemptions from the requirements of the National Road Traffic Act and the relevant Regulations.</li> </ul>		<p>required for vehicles carrying abnormally heavy or abnormally dimensioned loads.</p> <p>Transport vehicles exceeding the dimensional limitations (length) of 22m. Depending on the trailer configuration and height when loaded, some of the power station components may not meet specified dimensional limitations (height and width).</p>
<p>Promotion of Access to Information Act (Act No 2 of 2000)</p>	<p>All requests for access to information held by state or private body are provided for in the Act under S11.</p>	<p>Department of Environmental Affairs</p>	<p>No permitting or licensing requirements.</p>
<p>Promotion of Administrative Justice Act (Act No 3 of 2000)</p>	<p>In terms of S3 the government is required to act lawfully and take procedurally fair, reasonable, and rational decisions.</p> <p>Interested and affected parties have a right to be heard.</p>	<p>Department of Environmental Affairs</p>	<p>No permitting or licensing requirements.</p>
<p><b>Provincial Legislation</b></p>			
<p>Northern Cape Nature Conservation Act, Act No. 9 of 2009</p>	<p>This Act provides for the sustainable utilisation of wild animals, aquatic biota and plants; provides for the implementation of the Convention on International Trade in Endangered Species of Wild Fauna and Flora;</p>	<p>Provincial Department of Environmental Affairs</p>	<p>Permitting or licensing requirements arise from this legislation for the proposed activities to be</p>

Legislation	Applicable Requirements	Relevant Authority	Compliance Requirements
	<p>provides for offences and penalties for contravention of the Act; provides for the appointment of nature conservators to implement the provisions of the Act; and provides for the issuing of permits and other authorisations. Amongst other regulations, the following may apply to the current project:</p> <ul style="list-style-type: none"> <li>» Boundary fences may not be altered in such a way as to prevent wild animals from freely moving onto or off of a property;</li> <li>» Aquatic habitats may not be destroyed or damaged;</li> <li>» The owner of land upon which an invasive species is found (plant or animal) must take the necessary steps to eradicate or destroy such species.</li> <li>» The Act provides lists of protected species for the Province.</li> </ul>		<p>undertaken for the proposed project as there are succulent plants species on the proposed development site. A permit is required to remove the plants.</p>



## 12. WASTE, EFFLUENT, EMISSION AND NOISE MANAGEMENT

### a) Solid waste management

Will the activity produce solid construction waste during the construction/initiation phase?

YES ✓	<input checked="" type="checkbox"/>
-------	-------------------------------------

If YES, what estimated quantity will be produced per month?

± 4m <sup>3</sup>
-------------------

± 4m<sup>3</sup> of solid construction waste consisting mainly of vegetation, spoil material from clearing activities and metal and cabling off cuts. Therefore minimal quantities of packaging materials for the various components, excess concrete spillage and excess building materials will be produced on site during the construction phase. The quantity would be readily handled by contractors on site.

How will the construction solid waste be disposed of (describe)?

It is anticipated that construction waste will be comprised mainly of spoil material from cleaning activities as well as metal and cabling off-cuts. Non-recyclable waste will be trucked to the nearest registered waste disposal facility for appropriate disposal.

Where will the construction solid waste be disposed of (describe)?

In order to comply with legal requirements should there be excess solid construction waste after recycling options have been exhausted, the waste will be trucked to the nearest registered waste disposal facility for appropriate disposal.

Will the activity produce solid waste during its operational phase?

<input type="checkbox"/>	NO ✓
--------------------------	------

If YES, what estimated quantity will be produced per month?

--

How will the solid waste be disposed of (describe)?

--

If the solid waste will be disposed of into a municipal waste stream, indicate which registered landfill site will be used.

--

Where will the solid waste be disposed of if it does not feed into a municipal waste stream (describe)?

Waste that does not feed into the municipal stream will be transported to the nearest landfill site.

*If the solid waste (construction or operational phases) will not be disposed of in a registered landfill site or be taken up in a municipal waste stream, then the applicant should consult with the competent authority to determine whether it is necessary to change to an application for scoping and EIA.*

Can any part of the solid waste be classified as hazardous in terms of the NEM:WA?  NO ✓

If YES, inform the competent authority and request a change to an application for scoping and EIA. An application for a waste permit in terms of the NEM:WA must also be submitted with this application.

Is the activity that is being applied for a solid waste handling or treatment facility?  NO ✓

If YES, then the applicant should consult with the competent authority to determine whether it is necessary to change to an application for scoping and EIA. An application for a waste permit in terms of the NEM:WA must also be submitted with this application.

**b) Liquid effluent**

Will the activity produce effluent, other than normal sewage, that will be disposed of in a municipal sewage system?  NO ✓

If YES, what estimated quantity will be produced per month?

m<sup>3</sup>

Will the activity produce any effluent that will be treated and/or disposed of on site?  NO ✓

*If YES, the applicant should consult with the competent authority to determine whether it is necessary to change to an application for scoping and EIA.*

Will the activity produce effluent that will be treated and/or disposed of at another facility?  NO ✓

If YES, provide the particulars of the facility:

<b>Facility name:</b>			
<b>Contact person:</b>			
<b>Postal address:</b>			
<b>Postal code:</b>			
<b>Telephone:</b>		<b>Cell:</b>	
<b>E-mail:</b>		<b>Fax:</b>	

Describe the measures that will be taken to ensure the optimal reuse or recycling of waste water, if any:

--

**c) Emissions into the atmosphere**

Will the activity release emissions into the atmosphere other than exhaust emissions and dust associated with construction phase activities?

	NO ✓

If YES, is it controlled by any legislation of any sphere of government?

If YES, the applicant must consult with the competent authority to determine whether it is necessary to change to an application for scoping and EIA.

If NO, describe the emissions in terms of type and concentration:

Solar energy installations operate by converting solar energy into electricity. This is characterised as a non-consumptive use of a natural resource and consumes no fuel for its continuing operation. Solar power produces an insignificant quantity of greenhouse gases over its lifecycle as compared to conventional coal-fired power stations. The operational phase of a solar facility does not produce carbon dioxide, sulphur dioxide, mercury, particulates, or any other type of pollution.
---

**d) Waste permit**

Will any aspect of the activity produce waste that will require a waste permit in terms of the NEM:WA?

	NO ✓
--	------

If YES, please submit evidence that an application for a waste permit has been submitted to the competent authority

**e) Generation of noise**

Will the activity generate noise?

	NO ✓

If YES, is it controlled by any legislation of any sphere of government?

If YES, the applicant should consult with the competent authority to determine whether it is necessary to change to an application for scoping and EIA.

If NO, describe the noise in terms of type and level:

Minimal noise will be made during construction phase by moving vehicles; this is not regarded as significant noise source/ impact and will most likely not constitute a "disturbing noise".
---

### 13.WATER USE

Please indicate the source(s) of water that will be used for the activity by ticking the appropriate box(es):

<b>Municipal</b> ✓	Water board	Groundwater	River, stream, dam or lake	Other	The activity will not use water
--------------------	-------------	-------------	----------------------------	-------	---------------------------------

*Water will be used to clean the PV panels twice per annum every three months, or more frequently if deemed necessary. Water will be trucked in (i.e. likely from Umsobomvu Local Municipality) and high pressure hoses will be used to clean the panels. It is estimated that for every cleaning session 13 tankers of water will be required (i.e. where each tanker is assumed to hold 30 000 l).*

If water is to be extracted from groundwater, river, stream, dam, lake or any other natural feature, please indicate the volume that will be extracted per month:

Does the activity require a water use authorisation (general authorisation or water use license) from the Department of Water Affairs?

	NO ✓

If YES, please provide proof that the application has been submitted to the Department of Water Affairs.

### 14.ENERGY EFFICIENCY

Describe the design measures, if any that have been taken to ensure that the activity is energy efficient:

The activity will use very little of the energy it produces and is in itself an activity that is proposed to generate electricity from a cleaner alternative energy source (i.e. solar radiation).

Describe how alternative energy sources have been taken into account or been built into the design of the activity, if any:

The purpose of a PV installation is to utilise an alternative energy source (i.e. solar radiation) for the production of electricity. Therefore it is not required to consider any additional alternative energy sources.

**SECTION B: SITE/AREA/PROPERTY DESCRIPTION**

**Important notes:**

- For linear activities (pipelines, etc) as well as activities that cover very large sites, it may be necessary to complete this section for each part of the site that has a significantly different environment. In such cases please complete copies of Section B and indicate the area, which is covered by each copy No. on the Site Plan.

Section B Copy No. (e.g. A):

- Paragraphs 1 - 6 below must be completed for each alternative.

- Has a specialist been consulted to assist with the completion of this section? 

YES ✓	
----------	--

If YES, please complete the form entitled "Details of specialist and declaration of interest" for each specialist thus appointed and attach it in Appendix I. All specialist reports must be contained in Appendix D.

<b>Property description/physical address:</b>	<b>Province</b>	Northern Cape Province
	<b>District Municipality</b>	Pixley ka Seme District Municipality
	<b>Local Municipality</b>	Umsobomvu Local Municipality
	<b>Ward Number(s)</b>	Ward 2
	<b>Farm name and number</b>	Noupoort 306
	<b>Portion number</b>	0
	<b>SG Code</b>	C0210000000003060000

Where a large number of properties are involved (e.g. linear activities), please attach a full list to this application including the same information as indicated above.

<b>Current land-use zoning as per local municipality IDP/records:</b>	Agriculture, used for grazing of livestock
---	--

In instances where there is more than one current land-use zoning, please attach a list of current land use zonings that also indicate which portions each use pertains to, to this application.

Is a change of land-use or a consent use application required?

YES	<input type="checkbox"/>
✓	<input checked="" type="checkbox"/>

**1. GRADIENT OF THE SITE**

Indicate the general gradient of the site.

**Alternative S1:**

Flat ✓	1:50	-	1:20	-	1:15	-	1:10	-	1:7,5	-	Steeper than 1:5
	1:20		1:15		1:10		1:7,5		1:5		

**Alternative S2 (if any):**

Flat	1:50	-	1:20	-	1:15	-	1:10	-	1:7,5	-	Steeper than 1:5
	1:20		1:15		1:10		1:7,5		1:5		

**Alternative S3 (if any):**

Flat	1:50	-	1:20	-	1:15	-	1:10	-	1:7,5	-	Steeper than 1:5
	1:20		1:15		1:10		1:7,5		1:5		

**2. LOCATION IN LANDSCAPE**

Indicate the landform(s) that best describes the site:

2.1 Ridgeline	<input type="checkbox"/>	2.4 Closed valley	<input type="checkbox"/>	<b>2.7 Undulating plain / low hills</b>	<input checked="" type="checkbox"/>
2.2 Plateau	<input type="checkbox"/>	2.5 Open valley	<input type="checkbox"/>	2.8 Dune	<input type="checkbox"/>
2.3 Side slope of hill/mountain	<input type="checkbox"/>	<b>2.6 Plain</b>	<input checked="" type="checkbox"/>	2.9 Seafront	<input type="checkbox"/>

**3. GROUNDWATER, SOIL AND GEOLOGICAL STABILITY OF THE SITE**

Is the site(s) located on any of the following?

	<b>Alternative S1:</b>	<b>Alternative S2 (if any):</b>	<b>Alternative S3 (if any):</b>
Shallow water table (less than 1.5m deep)	<input type="checkbox"/> NO <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Dolomite, sinkhole or doline areas	<input type="checkbox"/> NO <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Seasonally wet soils (often close to water bodies)	<input type="checkbox"/> NO <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Unstable rocky slopes or steep slopes with loose soil	<input type="checkbox"/> NO <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Dispersive soils (soils that dissolve in water)	YES ✓				
Soils with high clay content (clay fraction more than 40%)	YES ✓				
Any other unstable soil or geological feature		NO ✓			
An area sensitive to erosion	YES ✓				

If you are unsure about any of the above or if you are concerned that any of the above aspects may be an issue of concern in the application, an appropriate specialist should be appointed to assist in the completion of this section. Information in respect of the above will often be available as part of the project information or at the planning sections of local authorities. Where it exists, the 1:50 000 scale Regional Geotechnical Maps prepared by the Council for Geo Science may also be consulted.

#### 4. GROUND COVER

Indicate the types of groundcover present on the site. The location of all identified rare or endangered species or other elements should be accurately indicated on the site plan(s).

Natural veld - good condition <sup>E</sup>	<b>Natural veld with scattered aliens<sup>E</sup> ✓</b>	Natural veld with heavy alien infestation <sup>E</sup>	Veld dominated by alien species <sup>E</sup>	Gardens
Sport field	Cultivated land	Paved surface	Building or other structure	Bare soil

If any of the boxes marked with an "E" is ticked, please consult an appropriate specialist to assist in the completion of this section if the environmental assessment practitioner doesn't have the necessary expertise.

Two vegetation units could be identified:

- » Unit 1: The *Ruschia axthelmiana* – *Felicia muricata* low open shrublands cover most of the study area (sensitivity medium low). Species composition and density of herbs vs. low shrubs varies significantly within this vegetation unit, mostly due to past and current land use of the area.
- » Unit 2: The *Pentzia incana* – *Cynodon incompletus* sparse dwarf shrublands are mostly in slight depression adjacent to larger drainage lines and the Noupoort Spruit (sensitivity low). The vegetation of this vegetation unit is expected to be very dynamic, with the density of especially the herb layer varying significantly between years and even seasons within years.

Both vegetation units are part of the Eastern Upper Karoo vegetation.

The two vegetation units identified on the study area are not limited occurrences, but part of a larger distribution of similar habitats. The integrity of each vegetation unit may greatly influence the integrity of surrounding habitats, and developments should thus be kept as close as possible together and as far away as possible from Noupoort Spruit to minimise the areal extent of the impacts on the environment.

## 5. SURFACE WATER

Indicate the surface water present on and or adjacent to the site and alternative sites?

Perennial River		NO ✓	
Non-Perennial River	YES ✓		
Permanent Wetland		NO ✓	
Seasonal Wetland		NO ✓	
Artificial Wetland		NO ✓	
Estuarine / Lagoonal wetland		NO ✓	

If any of the boxes marked YES or UNSURE is ticked, please provide a description of the relevant watercourse.

Drainage lines occur in the proposed site but do fall within the development area of the PV panels.

## 6. LAND USE CHARACTER OF SURROUNDING AREA

Indicate land uses and/or prominent features that currently occur within a 500m radius of the site and give description of how this influences the application or may be impacted upon by the application:

<b>Natural area ✓</b>	Dam or reservoir	Polo fields
Low density residential (Nouppoot)	Hospital/medical centre	Filling station <sup>H</sup>
Medium density residential	School	Landfill or waste treatment site
High density residential	Tertiary education facility	Plantation
Informal residential <sup>A</sup>	Church	<b>Agriculture ✓</b>
Retail commercial & warehousing	Old age home	River, stream or wetland
Light industrial	Sewage treatment plant <sup>A</sup>	Nature conservation area



Medium industrial <sup>AN</sup>	Train station or shunting yard <sup>N</sup>	Mountain, koppie or ridge
Heavy industrial <sup>AN</sup>	Railway line <sup>N</sup>	Museum
Power station	Major road (4 lanes or more) <sup>N</sup>	Historical building
Office/consulting room	Airport <sup>N</sup>	Protected Area
Military or police base/station/compound	Harbour	Graveyard
Spoil heap or slimes dam <sup>A</sup>	Sport facilities	Archaeological site
Quarry, sand or borrow pit	Golf course	<b>Other:</b>

If any of the boxes marked with an "N" are ticked, how will this impact / be impacted upon by the proposed activity?

If any of the boxes marked with an "AN" are ticked, how will this impact / be impacted upon by the proposed activity? Specify and explain:

If any of the boxes marked with an "H" are ticked, how will this impact / be impacted upon by the proposed activity? Specify and explain:

Does the proposed site (including any alternative sites) fall within any of the following:

Critical Biodiversity Area (as per provincial conservation plan)		<b>NO</b> ✓
Core area of a protected area?		<b>NO</b> ✓
Buffer area of a protected area?		<b>NO</b> ✓
Planned expansion area of an existing protected area?		<b>NO</b> ✓
Existing offset area associated with a previous Environmental Authorisation?		<b>NO</b> ✓
Buffer area of the SKA?		<b>NO</b> ✓

If the answer to any of these questions was YES, a map indicating the affected area must be included in Appendix A.

## 7. CULTURAL/HISTORICAL FEATURES

Are there any signs of culturally or historically significant elements, as defined in section 2 of the National Heritage Resources Act, 1999, (Act No. 25 of 1999), including Archaeological or paleontological sites, on or close (within 20m) to the site? If YES, explain:

<b>YES</b> ✓	

The heritage study of the proposed site showed that there are two stone artefacts documented are of a low cultural significance as they are in a secondary context, however, owing to lack of surface visibility, it is possible that stone artefacts may occur underneath the vegetation cover. The distribution of historical artefacts incorporates and relative large area in the south-eastern section of farm Noupoot306. These have been considered as having a medium-low cultural significance owing to the interpretation historical landscape of Noupoot. Unfortunately the remains of the built structures, that may have part of that landscape have collapsed, and are considered as a low cultural significance owing to the state of disrepair.

The palaeontological study of the proposed site showed that the area is characterised by fossiliferous mudstones and sandstones. Several dolerite sills and dykes occur in the region and are often found capping hills and forming ridges. Care should be given however to constructions such as access routes, construction facilities, substations, pylons and buildings which are not limited to dolerite. There is a high probability that fossils would occur on the Gilmer site where construction is proposed due to the mudstone which dominates the study site.

The specialist heritage report contained in **Appendix D** provides further details.

If uncertain, conduct a specialist investigation by a recognised specialist in the field (archaeology or palaeontology) to establish whether there is such a feature(s) present on or close to the site. Briefly explain the findings of the specialist:

The heritage study of the proposed site showed that there are two stone artefacts on the site. Which are of a low cultural significance as they are in a secondary context, however, owing to lack of surface visibility, it is possible that stone artefacts may occur underneath the vegetation cover. The distribution of historical artefacts incorporates and relative large area in the south-eastern section of Noupoot 306. These have been considered as having a medium-low cultural significance owing to the interpretation historical landscape of Noupoot. Unfortunately the remains of the built structures, that may have part of that landscape have collapsed, and are considered as a low cultural significance owing to the state of disrepair.

Will any building or structure older than 60 years be affected in any way?

	<b>NO</b> ✓
--	-------------

Is it necessary to apply for a permit in terms of the National Heritage Resources Act, 1999 (Act 25 of 1999)?

	<b>NO</b> ✓
--	-------------

If YES, please provide proof that this permit application has been submitted to SAHRA or the relevant provincial authority.

## 8. SOCIO-ECONOMIC CHARACTER


### a) Local Municipality

Please provide details on the socio-economic character of the local municipality in which the proposed site(s) are situated.

#### ***Level of unemployment:***

In 2001 the level of unemployment in the Umsobomvu (UM) LM was 31.12%, which decreased to 25% in 2007. The IDP indicates however, that unemployment is more than 30% in most of the areas and people survive on subsistence farming, pension/welfare payments and labour intensive jobs. The UM IDP notes the level of unemployment the high unemployment rate has serious repercussions on the ability of the residents of Umsobomvu to pay for service and meet their daily needs.

The agricultural sector is the most important sector in terms of employment, followed by the community, social and personal services including government associations and institutions (Figure 3.4). The IDP also notes that there are a large number of pensioners and retired people are in the urban areas.



**Figure 4: Key economic sectors in terms of employment**

***Economic profile of local municipality:***

The Umsobomvu Local municipality is characterised by the following:

- » High levels of poverty and low levels of education
- » Declining economy that is largely on sheep farming
- » An economy that was too dependent on Spoornet in Noupoort, which has since declined because of the withdrawal of Spoornet
- » Promising growth in tourism in Colesberg Area.
- » Rapid population growth in Colesberg because of the migration from other parts of the municipal are, which puts a heavy burden on the infrastructure.

***Level of education:***

In terms of education levels 15.1 % of the population had no education at all, while 71.3% have primary or secondary education. Those with higher educational qualification accounted for 3.7 % of the population. These figures indicate an increase in all categories since 1996, except for the no schooling category, which decreased by 4.9 % indicating a higher percentage of people attending school. In general there has been an improvement in the educational qualifications of the labour force that has a secondary and tertiary education. This would appear to be result of an increase in access to education since 1994, particular, amongst new entrants to the labour force.

**b) Socio-economic value of the activity**

What is the expected capital value of the activity on completion?	R390 million	
What is the expected yearly income that will be generated by or as a result of the activity?	R54 million/ year	
Will the activity contribute to service infrastructure?	YES ✓	
Is the activity a public amenity?		NO ✓
How many new employment opportunities will be created in the development and construction phase of the activity/ies?	60-80	
What is the expected value of the employment opportunities during the development and construction phase?	This will become known after an initial total price has been calculated for the project	
What percentage of this will accrue to previously disadvantaged individuals?	The developer will, as far as possible, ensure maximum opportunities are given to the local community to participate in the construction phase	
How many permanent new employment opportunities will be created during the operational phase of the activity?	Two	
What is the expected current value of the employment opportunities during the first 10 years?	R40 000	
What percentage of this will accrue to previously disadvantaged individuals?	75%	

**9. BIODIVERSITY**

Please note: The Department may request specialist input/studies depending on the nature of the biodiversity occurring on the site and potential impact(s) of the proposed activity/ies. To assist with the identification of the biodiversity occurring on site and the ecosystem status consult <http://bgis.sanbi.org> or [BGIShelp@sanbi.org](mailto:BGIShelp@sanbi.org). Information is also available on compact disc (cd) from the Biodiversity-GIS Unit, Ph (021) 799 8698. This information may be updated from time to time and it is the applicant/ EAP's responsibility to ensure that the latest version is used. A map of the relevant biodiversity information (including an indication of the habitat conditions as per (b) below) and must be provided as an overlay map to the property/site plan as Appendix D to this report.

Refer to Figure 3 in **Appendix D1**

a) Indicate the applicable biodiversity planning categories of all areas on site and indicate the reason(s) provided in the biodiversity plan for the selection of the specific area as part of the specific category)

Systematic Biodiversity		Planning		If CBA or ESA, indicate the reason(s) for its selection in biodiversity plan
Category				
Critical Biodiversity Area (CBA)	Ecological Support Area (ESA)	<b>Other Natural Area (ONA)</b> ✓	No Natural Area Remaining (NNR)	

b) Indicate and describe the habitat condition on site

Habitat Condition	Percentage of habitat condition class (adding up to 100%)	Description and additional Comments and Observations (including additional insight into condition, e.g. poor land management practises, presence of quarries, grazing, harvesting regimes etc).
Natural		
<b>Near Natural (includes areas with low to moderate level of alien invasive plants)</b> ✓	<b>98%</b>	Relatively good condition
Degraded (includes areas heavily invaded by alien plants)	%	
<b>Transformed (includes cultivation, dams, urban, plantation, roads, etc)</b> ✓	<b>2%</b>	Cultivation, roads, homestead

**c) Complete the table to indicate:**

- (i) the type of vegetation, including its ecosystem status, present on the site; and
- (ii) whether an aquatic ecosystem is present on site.

Terrestrial Ecosystems		Aquatic Ecosystems						
<b>Ecosystem threat status as per the National Environmental Management: Biodiversity Act (Act No. 10 of 2004)</b>	Critical	<b>Wetland (including rivers, depressions, channelled and unchanneled wetlands, flats, seeps pans, and artificial wetlands)</b>		Estuary		Coastline		
	Endangered							
	Vulnerable							
	<b>Least Threatened</b> ✓							
		<b>YES</b> ✓				<b>NO</b> ✓		<b>NO</b> ✓

**d) Please provide a description of the vegetation type and/or aquatic ecosystem present on site, including any important biodiversity features/information identified on site (e.g. threatened species and special habitats)**

The study site falls within the Eastern Upper Karoo as described by Mucina and Rutherford (2006). It runs adjacent to the Noupoort Spruit, which is covered by the azonal Southern Karoo Riviere vegetation. The Eastern Upper Karoo landscapes, as described in Mucina and Rutherford (2006) consist of gently sloping plains and flats, interspersed with hills, rocky areas, and drainage lines of various sizes. Vegetation is dominated by dwarf microphyllous shrubs and a very variable cover of grasses, dominated by the genera *Aristida* and *Eragrostis*. Local grass cover depends on soil properties (preferring sandier soils), and rainfall. As rainfall is very variable in the Karoo, grass cover within one area can vary significantly from one year to the next.

Prominent tall shrubs include *Lycium cinereum* and *L. horridum*; prominent low shrubs include *Eriocephalus ericoides*, *E. spinescens*, *Pentzia* species, *Chrysocoma ciliata*, *Phymaspermum parvifolium*, and *Pteronia* and *Selago* species. The succulent shrub *Ruschia intricata* is widely spread and may reach high localised densities. A wide variety of geophytes occurs in the area, although only visible for short periods after sufficient rains and thus often overlooked or not detected during surveys.

Overall, this vegetation type is regarded as least threatened and is the largest mapped vegetation unit within South Africa, with up to date an estimated 2% of the vegetation being transformed due to various developments (Mucina and Rutherford 2006), but larger areas may be in various states of degradation (Hoffman and Ashwell 2001, Esler *et al.* 2006). A large factor contributing to this widespread degradation is erosion, with up to 60% of landscapes within the vegetation type being affected by moderate erosion, the remainder by high erosion rates, thus also leading to changes in vegetation composition and requiring active management to combat and reverse

degradation.

Southern Karoo Riviere vegetation that does occur adjacent to the study area is too small to have been mapped by Mucina and Rutherford (2006). It generally covers narrow riverine flats. The vegetation is dominated wither by a mixture of *Acacia karroo* and *Tamarix usneoides*, or tall *Salsola*-dominated shrublands. Sandy drainage lines are occasionally dominated by *Stipagrostis namaquensis*. Other prominent species include *Searsia lancea*, *Diospyros lycioides*, *Euclea undulata*, *Pentzia incana*, and *Salsola* species. The vegetation unit is regarded least threatened, but prone to invasion by alien invasive plants and various degrees of erosion (Mucina and Rutherford 2006).



## SECTION C: PUBLIC PARTICIPATION

### 1. ADVERTISEMENT AND NOTICE

<b>Publication name</b>	Volksblad and De Aar Echo	
<b>Date published</b>	26 October 2012 and 02 November 2012 (Project announcement) 09 November 2012 (announcement of Public Open Day)	
<b>Site notice position</b>	<b>Latitude</b>	<b>Longitude</b>
	-31.15673	24.81955
<b>Date placed</b>	29/10/2012	

Include proof of the placement of the relevant advertisements and notices in **Appendix E1**.

### 2. DETERMINATION OF APPROPRIATE MEASURES

Provide details of the measures taken to include all potential I&APs as required by Regulation 54(2)(e) and 54(7) of GN R.543.

The public consultation process has included the publishing of notices regarding the proposed project as well as the distribution of notification letters to identify I & APs. Affected and neighbouring landowners were consulted through one-on-one consultation sessions and via telephone. A public open day was held within the study area during the review period of the draft Basic Assessment report in order to provide feedback regarding the findings of the study; this was advertised in the local and regional press. All identifies I & APs were invited to attend. All identified I & APs will be invited to attend.

Key stakeholders (other than organs of state) identified in terms of Regulation 54(2)(b) of GN R.543:

<b>Title, Name and Surname</b>	<b>Affiliation/ key stakeholder status</b>	<b>Contact details (tel number or e-mail address)</b>
Christiaan Philippus	Adjacent Landowner	
Jim De Villiers	Adjacent Land Owner	
Handre Nieuwoudt	Adjacent Land Owner	
Hendrikus Visser	Adjacent Land Owner	
Henk Du Toit	Adjacent Land Owner	
Andries Keun	Adjacent Land Owner	
Jim De Villiers	Adjacent Land Owner	

Anita Geldenhuis	Adjacent Landowner	
Septimus Van Dyk	Adjacent Landowner	
Fauntleroy Gillmer	Impacted Land Owner	
Jim De Villiers	Adjacent Land Owner	
Dykie De Villiers	Adjacent Land Owner	
Colin Bowes	Adjacent Land Owner	
Jim De Villiers	Adjacent Land Owner	
Pieter Langenhoven	Adjacent Landowner	
Pam Barret	I&AP	
Suzanne Erasmus	I&AP	

Include proof that the key stakeholder received written notification of the proposed activities as **Appendix E2**. This proof may include any of the following:

- e-mail delivery reports;
- registered mail receipts;
- courier waybills;
- signed acknowledgements of receipt; and/or
- or any other proof as agreed upon by the competent authority.

### 3. ISSUES RAISED BY INTERESTED AND AFFECTED PARTIES

Summary of main issues raised by I&APs	Summary of response from EAP
SKA assessed the project location of the proposed site and determined that it is of a low risk to the SKA infrastructure because the solar energy project is more than 100 km away from the SKA project infrastructure.	Comment noted, no response required
Department of Agriculture, Forestry & Fisheries commented that since they are no protected trees that will be affected by the proposed development; the Department has no objection against the proposed development as long as the necessary permits are obtained from the provincial Department of Environment and Nature conservation for the disturbance of specially protected fauna and flora.	If permit for the disturbance of specially protected fauna and floras is required, it will be obtained from DENC

<p>BirdLife South Africa commented that the powerlines associated with Gilmer should be regularly checked and avifaunal collisions must be recorded. If high numbers of avifaunal mortality are observed, suitable mitigation measures must be put in place.</p>	<p>Comment noted, no response required</p>
<p>The general community of Noupoort were concerned about job prospects which the development of the solar energy facility would bring to the area.</p>	<p>The project will create employment opportunities. Approximately 60-80 jobs will be created per project during the construction phase. Twenty permanent jobs would be created during the operational phase.</p>
<p>Umsobomvu Local Municipality queried whether the proposed substation would still be constructed regardless of all the various Terra-Solar projects being developed.</p>	<p>The alternative would be to connect to the existing power line. This would, however, depend on the grid capacity and Eskom. Detailed grid integration studies are being undertaken by the developer. It is possible, that the Newgate substation to accommodate all 5 projects, therefore a new substation is proposed. At this point the aim is to secure the land for development of the substation and obtain Environmental Authorisation, in the event that is required, this is also dependent on Eskom's input.</p>
<p>Mr Marais raised issues with regard to the visual impact and property value that the proposed project will have on his property</p>	<p>The comment was noted and response was written to address his issues</p>
<p>Mr Langenhoven raised issues with regard to the visual impact that the proposed project will have on his property</p>	<p>Utilise visual screening and landscaping on adjacent landowner homesteads in order to mitigate the visual impact upon adjacent landowners.</p>

#### 4. COMMENTS AND RESPONSE REPORT

The practitioner must record all comments received from I&APs and respond to each comment before the Draft BAR is submitted. The comments and responses must be captured in a comments and response report as prescribed in the EIA regulations and be attached to the Final BAR as **Appendix E3**.

## 5. AUTHORITY PARTICIPATION

Authorities and organs of state identified as key stakeholders:

Authority/Organ of State	Title	Contact person (Name and Surname)	Tel No	Fax No	e-mail
Council for Scientific and Industrial Research	Mr.	Paul Lochner	021-888-2486		plochner@csir.co.za
Department of Agriculture, Forestry & Fisheries	Ms	Thoko Buthelezi	012-319-7634		thokob@daff.gov.za
Department of Agriculture, Forestry & Fisheries	Ms	Jacoline Mans	054-338-5909	054-334-0030	jacolinema@daff.gov.za
Department of Energy	M	The Director: Northern Cape	053-807-1752	086-562-7065	
Department of Energy		DDG: Programmes and Projects	012-406-7568		
Department of Mineral Resources	Mr	Ntsundeni Ravhugoni	053-807-1700	053-830-0827	Ntsundeni.Ravhugoni@dmr.gov.za
Department of Rural Development and Land Reform	Ms	Debbie Khan	012-312-9490	012-323-6072	dkhan@ruraldevelopment.gov.za
Department of Water Affairs	Mr	A Abrahams		053-831-4534	abrahamsa@dwa.gov.za
Department of Water Affairs	Ms.	Tocky Ngobeni	012-336-7488		ngobenit@dwa.gov.za
Eskom	Mr.	John Geeringh	011-516-7233	086-661-4064	john.geeringh@eskom.co.za
Eskom	Mr.	Andrea van Gensen	051-404-2040		andrea.vangensen@eskom.co.za

Northern Cape Department of Agriculture, Land Reform & Rural Development	Mr.	Ali Diteme	053-838-9106	053-832-4328	aditeme@agri.ncap e.gov.za
Northern Cape Department of Environment and Nature Conservation	Ms.	J Mutyorauta	053-807-7431		jmutyorauta@ncpg. gov.za
Northern Cape Department of Environment and Nature Conservation	Mr	Denver van Heerden	053-807-7305	053-807-7367	jriddles@ncpg.gov.z a
Northern Cape Department of Environment and Nature Conservation	Ms	Christene Pienaar	053-807-7437	053-807-7416	
Northern Cape Department of Roads and Public Works	Ms	Kholikile Nogwili	053-838-2109	053-838-2117	lucindavanwyk@ncp g.gov.za
Northern Cape Department of Roads and Public Works	Mr.	Kenneth Markman	053-631-1355	053-631-1357	kenneth.markman@ vodamail.co.za
Northern Cape Provincial Heritage Resources Agency	Mr.	Andrew Timothy	053-831-2537	053-833-1435	ratha.timothy@gma il.com
Northern Cape Rock Art Trust (NCRA) McGregor Museum	Ms.	David Morris	053-839-2706	053-842-1433	dmorris@inext.co.z a
Pixely Ka Seme District Municipality	Mr.	Simphiwe Naude	053-631-0891	053-631-0891	
Pixely Ka Seme District Municipality	Mr.	Maccollan Jack	053-631-0891	053-631-2529	mackjack@vodamai l.com
Pixely Ka Seme District Municipality	Mr.	Sandisile Madayo	053-632-9100	052-631-0105	pixley@telkomsa.ne t
South African Civil Aviation Authority	Mr.	Chris Isherwood	011-545-1028	011-545-1282	isherwoodc@caa.co. za
South African Heritage Resources Agency (SAHRA)	Mr.	Kathryn Smuts	021-462-4502	021-462-4509	ksmuts@sahra.org. za
South African Heritage Resources Agency (SAHRA)	Ms	Mariagrazia Galimberti	021-462-4502	021-462-4509	mgalimberti@sahra. org.za
South African National Parks	Mr.	Peter Novellie	012-426-5066		peter.novellie@sanp

					arks.org
South African National Parks	Mr.	Paul Daphne	012-426-5066	012-343-2832	pauld@sanparks.org
South African National Roads Agency Limited	Ms.	Rene de Kock	021-957-4607	021-946-1630	Dekockr@nra.co.za
South African National Roads Agency Limited	Ms.	Colene Runkel		021-946-1630	runkelc@nra.co.za
Square Kilometre Array (SKA): South Africa	Dr.	Adrian Tiplady	011-442-2434		atiplady@ska.ac.za
Transnet	Mr.	Krishna Reddy	011-308-1065	011-308-2638	krishna.reddy@transnet.net
Umsobomvu Local Municipality	Mr.	Mzawandile Toto	049-843-1056	049-843-1947	mzwandiletoto@gmail.com
Umsobomvu Local Municipality	Mr.	MA Sestile	049-843-1165	049-843-1165	ma.sestile@webmail.co.za
Umsobomvu Local Municipality	Mr.	Manne Rossouw	051-753-0574	051-753-0574	manne@umsobomvumun.co.za
Umsobomvu Local Municipality	Mr.	Ben Malherbe	051-753-0777	051-753-0574	faith@umsobomvumun.co.za
Umsobomvu Local Municipality	Cllr	Annie Fritz	049-843-1219		
Umsobomvu Local Municipality	Cllr	Amos China Mpela	051-753-0777	051-753-1918	
Wildlife and Environment Society of South Africa (WESSA)	Ms	Suzanne Erasmus	053-839-2717	053-842-1433	wessanc@yahoo.com

Include proof that the Authorities and Organs of State received written notification of the proposed activities as **Appendix E4**.

In the case of renewable energy projects, Eskom and the SKA Project Office must be included in the list of Organs of State.

## 6. CONSULTATION WITH OTHER STAKEHOLDERS

Note that, for any activities (linear or other) where deviation from the public participation requirements may be appropriate, the person conducting the public participation process may deviate from the requirements of that sub-regulation to the extent and in the manner as may be agreed to by the competent authority.

Proof of any such agreement must be provided, where applicable. Application for any deviation from the regulations relating to the public participation process must be submitted prior to the commencement of the public participation process.

<b>See Appendix E5</b>
------------------------

A list of registered I&APs must be included as **Appendix E5**.

Copies of any correspondence and minutes of any meetings held must be included in **Appendix E6**.

**SECTION D: IMPACT ASSESSMENT**

The assessment of impacts must adhere to the minimum requirements in the EIA Regulations, 2010, and should take applicable official guidelines into account. The issues raised by interested and affected parties should also be addressed in the assessment of impacts.

**1. IMPACTS THAT MAY RESULT FROM THE PLANNING AND DESIGN, CONSTRUCTION, OPERATIONAL, DECOMMISSIONING AND CLOSURE PHASES AS WELL AS PROPOSED MANAGEMENT OF IDENTIFIED IMPACTS AND PROPOSED MITIGATION MEASURES**

Provide a summary and anticipated significance of the potential direct, indirect and cumulative impacts that are likely to occur as a result of the planning and design phase, construction phase, operational phase, decommissioning and closure phase, including impacts relating to the choice of site/activity/technology alternatives as well as the mitigation measures that may eliminate or reduce the potential impacts listed. This impact assessment must be applied to all the identified alternatives to the activities identified in Section A (2) of this report.

Activity	Impact summary	Significance	Proposed mitigation
<b>Alternative 1 (preferred alternative)</b>			
Construction of PV array, access roads and associated infrastructure.	<p><b>Direct impacts:</b></p> <p><b>Ecology</b></p> <ul style="list-style-type: none"> <li>» Loss of vegetation, increase in runoff and erosion through upgrading of access road.</li> <li>» Loss of vegetation and living soil crusts, loss of and alteration of microhabitats, altered vegetation cover, altered distribution of rainfall and resultant runoff patterns, increase in runoff and</li> </ul>	Medium-Low	<ul style="list-style-type: none"> <li>» Make use of existing tracks as far as possible</li> <li>» Ensure an adequate plant search and rescue program prior to commencement of activity</li> <li>» Minimise area affected, especially during construction</li> <li>» Use topsoils removed for redistribution outside the lowest borders of the development to stop erosion off the cleared areas</li> </ul>



Activity	Impact summary	Significance	Proposed mitigation
	<p>accelerated erosion during construction and operation of PV panels.</p> <ul style="list-style-type: none"> <li>» Loss of vegetation, loss of micro-habitat, increase in runoff and erosion, window of opportunity for the establishment of alien invasive species, absence of living soil crusts, altered topsoil characteristics with low moisture infiltration capacity and increased runoff during fencing area of the area.</li> <li>» Loss of vegetation, increase in runoff and erosion during the construction of power line to substation.</li> <li>» Potential collision and electrocution of the blue cranes species found in the area with overhead power line.</li> </ul>		<ul style="list-style-type: none"> <li>» Remove and collect all succulent and bulbous plants from cleared areas and transplant onto the newly redistributed topsoils</li> <li>» Ensure bird-friendly tower designs are implemented to minimise the risk of electrocutions. Fit overhead power lines with appropriate flappers to increase the visibility thereof to avifauna. Notes of electrocution and collision events must be sent to a qualified Ornithologist for the recommendation of further mitigation measures if necessary.</li> <li>» Install bird diverters on the power line.</li> </ul>
	<p><b>Indirect impacts:</b></p> <ul style="list-style-type: none"> <li>» Ecological degradation/loss of and ecological integrity.</li> </ul>	Medium	<ul style="list-style-type: none"> <li>» Prevent pollution of the environment;</li> <li>» Re-establish vegetation where possible and in so doing increasing habitat capabilities;</li> <li>» Implement an invasive/exotic species eradication programme.</li> </ul>
	<p><b>Cumulative impacts:</b></p> <ul style="list-style-type: none"> <li>» Possible erosion of areas lower than the access road, possible contamination of lower-lying drainage lines due to oil or other spillage.</li> </ul>	Low-Medium	<ul style="list-style-type: none"> <li>» Cumulative impacts of developments on population viability of species can be reduced significantly if new developments are kept as close as possible to existing developed areas or, where such is not possible, different</li> </ul>

Activity	Impact summary	Significance	Proposed mitigation
	<ul style="list-style-type: none"> <li>» Possible spread and establishment of alien invasive species</li> <li>» Possible excessive fragmentation and thus reduction of core habitats that may negatively influence species population viability.</li> </ul>		<p>sections of a development be kept as close together as possible. Thus new power lines should follow routes of existing servitudes if such exist, renewable energy facilities should be constructed as close as possible to existing infrastructure or substations, and if several developments are planned within close proximity, these developments should be situated as close together as possible, not scattered throughout the landscape.</p>
Placement of solar panels; underground cabling; overhead power line; additional internal access roads, and the workshop area	<p><b>Direct impacts:</b>  <b>Heritage Impacts</b></p> <ul style="list-style-type: none"> <li>» The destruction stone artefact occurrences and scatters.</li> </ul>	Medium	<ul style="list-style-type: none"> <li>» If concentrations of archaeological heritage material and human remains are uncovered during construction, all work must cease immediately and be reported to the Albany Museum and/or the South African Heritage Resources Agency (SAHRA) so that systematic and professional investigation/ excavation can be undertaken.</li> <li>» Construction managers/foremen should be informed before construction starts on the possible types of heritage sites and cultural material they may encounter and the procedures to follow when they find sites.</li> </ul>
	<p><b>Indirect impacts:</b></p> <ul style="list-style-type: none"> <li>» Irreplaceable loss of archaeological heritage resources.</li> </ul>	Low	Same as above

Activity	Impact summary	Significance	Proposed mitigation
	<p><b>Cumulative impacts:</b></p> <ul style="list-style-type: none"> <li>» Irreplaceable loss of archaeological heritage resources.</li> </ul>	Low	Same as above
<p>Construction and operation of the PV array, access roads and associated infrastructure.</p>	<p><b>Direct impacts:</b></p> <p><b>Visual Impacts</b></p> <ul style="list-style-type: none"> <li>» Potential visual impact on the sensitive receptors in the background. (i.e. within 3km of the facility).</li> <li>» Potential visual impact on the intrinsic value and sense of place of the Noupoort region.</li> <li>» Potential visual impact of artificial lighting as a result of the activity.</li> </ul>	Low	<ul style="list-style-type: none"> <li>» Keep disturbed areas to a minimum.</li> <li>» No clearing of land to take place outside the demarcated footprint.</li> <li>» Institute a planting regime around the boundaries of the project site to shield the PV plant from any potential views onto it from the view corridors. Only indigenous plant species to be introduced and planted in such a manner and location which would not cast shadows on the PV arrays.</li> <li>» Buildings and similar structures must be in keeping with regional planning policy documents, especially the principles of critical regionalism, namely sense of place, sense of history, sense of nature, sense of craft and sense of limits.</li> <li>» Utilise existing roads and tracks to the extent possible. Where new roads are required, they should be two-track gravel roads, maintained to prevent dust and erosion.</li> </ul>
	<p><b>Indirect impacts:</b></p> <ul style="list-style-type: none"> <li>» The proposed infrastructure is of such a nature that the status quo could be regained after decommissioning of the plant.</li> </ul>	Low	Providing that the site is rehabilitated to its current state, the visual impact will also be removed.

Activity	Impact summary	Significance	Proposed mitigation
	<p><b>Cumulative impacts:</b></p> <ul style="list-style-type: none"> <li>» The introduction of the PV plant, coupled with the transmission lines and proposed substation will contribute to an increased cumulative visual impact.</li> </ul>	Medium	<p>Provided that the footprint of the individual sites is not enlarged and their positions remain as planned, the cumulative impact of the proposed activity is regarded to be insignificant.</p>
<p>Construction of the PV array, access roads and associated infrastructure.</p>	<p><b>Direct impacts:</b></p> <p><b>Soil &amp; Agricultural Impacts</b></p> <ul style="list-style-type: none"> <li>» Siltation of watercourses and other natural resources downstream as a result of improper storm water management and soil erosion due to increased and concentrated water run-off</li> <li>» Dust production and dust pollution of grazing plants</li> <li>» Soil erosion on construction sites during and after the construction phase due to decreased vegetation cover and increased water run-off</li> </ul>	Medium-Low	<p>Care must be taken with the ground cover during and after construction on the site. If it is not possible to retain a good plant cover during construction, techniques should be employed to keep the soil covered by other means, i.e. straw, mulch, erosion control mats, etc., until a healthy plant cover is again established. Care should also be taken to control and contain stormwater run-off. Rehabilitate construction sites by establishing it with indigenous grasses.</p>
	<p><b>Indirect impacts:</b></p> <p>Limited with the necessary mitigation in place</p>	Low	<p>See mitigation of direct impacts</p>
	<p><b>Cumulative impacts:</b></p> <ul style="list-style-type: none"> <li>» The site is located outside wetland areas, but runoff does accumulate on lower-lying areas where it may remain without draining further after smaller rainfall events. During such time soils of these</li> </ul>	Low	<p>Care must be taken with the ground cover during and after construction on the site. If it is not possible to retain a good plant cover during construction, techniques should be employed to keep the soil covered by other means, i.e. straw, mulch, erosion control mats, etc., until a healthy</p>

Activity	Impact summary	Significance	Proposed mitigation
	clay-rich valleys become almost marshy and impossible to cross by vehicle, until the soils have dried out again.		plant cover is again established.
<b>Construction phase</b> (Including all related infrastructure such as transmission lines, access roads, office and warehouse components) and <b>Operational phase</b>	<b>Direct impacts:</b> <b>Positive social impacts:</b> <ul style="list-style-type: none"> <li>» Creation of employment and business opportunities (Based on information from the developer 2 fulltime and 18 part time employment opportunities for the 20 year life of the project). The operational phase will also create opportunities for skills development and training.</li> <li>» Benefits associated with the establishment of a local community trust;</li> <li>» The establishment of renewable energy infrastructure.</li> </ul> <b>Potential negative impacts:</b> <ul style="list-style-type: none"> <li>» The visual impacts and associated impact on sense of place</li> <li>» Influx of construction workers employed on the project;</li> <li>» Increased risk of stock theft, poaching and damage to farm infrastructure associated with construction workers;</li> <li>» Increased risk of veld fires associated with construction related activities;</li> <li>» Impact of heavy vehicles, including</li> </ul>	Low	<ul style="list-style-type: none"> <li>» Where possible, Gillmer Solar Energy should make it a requirement for contractors to implement a 'locals first' policy for construction jobs, specifically semi and low-skilled job categories. This will reduce the potential impact that this category of worker could have on local family and social networks;</li> <li>» Maximise the use of local labour for low – semi skilled jobs far as possible.</li> </ul>

Activity	Impact summary	Significance	Proposed mitigation
	damage to roads, safety, noise and dust; » Loss of agricultural land associated with construction related activities.		
	<b>Indirect impacts:</b> » Once the construction phase is complete, locals may not be able to find future employment. » Alternatively local employed during the construction phase may learn new skills thereby making them more employable in the future.	Low	The developer should implement a training and skills development programme for locals during the first 5 years of the operational phase. The aim of the programme should be to maximise the number of South African's and locals employed during the operational phase of the project.
	<b>Cumulative impacts:</b> » The development of additional renewable energy facilities in the region may serve to increase the potential for job creation. » Impacts on family and community relations that may, in some cases, persist for a long period of time. Also in cases where unplanned / unwanted pregnancies occur or members of the community are infected by an STD, specifically HIV and or AIDS, the impacts may be permanent and have long term to permanent cumulative impacts on the affected individuals and/or their families and the community.	Low	» Attention should be given to the extension and improvement of the existing HIV/Aids awareness programmes.

Activity	Impact summary	Significance	Proposed mitigation
<b>Alternative 2</b>			
	<i>Direct impacts:</i>		
	<i>Indirect impacts:</i>		
	<i>Cumulative impacts:</i>		
<b>Alternative 3</b>			
	<i>Direct impacts:</i>		
	<i>Indirect impacts:</i>		
	<i>Cumulative impacts:</i>		
<b>No-go option</b>			
Construction, operation and decommissioning phase of the solar energy facility	<p><b>Direct impacts:</b></p> <p>The negative impacts for the project include:</p> <ul style="list-style-type: none"> <li>» Clearing of natural vegetation for the proposed footprint area, increasing the potential for soil erosion, deterioration of the biotic, abiotic and economic properties of soil, and the long-term loss of natural vegetation;</li> <li>» Possible destruction of stone artefact occurrences and scatters. That are scattered over the extent of the proposed GillmerSolar Energy Facility area and</li> </ul>	Low	None

Activity	Impact summary	Significance	Proposed mitigation
	<p>within the existing site access that is proposed to be used as the access road for the project.</p> <p>The positive impacts for the project include:</p> <ul style="list-style-type: none"> <li>» Pollution reduction: The releases of by-products through the burning of fossil fuels for electricity generation have a particularly hazardous impact on human health and contribute to ecosystem degradation.</li> <li>» Support for international agreements: The effective deployment of renewable energy provides a tangible means for South Africa to demonstrate its commitment to its international agreements under the Kyoto Protocol, and for cementing its status as a leading player within the international community.</li> <li>» Employment creation: The sale, development, installation, maintenance, and management of renewable energy facilities have significant potential for job creation in South Africa.</li> <li>» Acceptability to society: Renewable energy offers a number of tangible benefits to society including reduced</li> </ul>		



Activity	Impact summary	Significance	Proposed mitigation
	<p>pollution concerns, improved human, and ecosystem health.</p> <ul style="list-style-type: none"> <li>» Support to a new industry sector: The development of renewable energy offers the opportunity to establish a new industry within the South African economy.</li> <li>» Support to local community: Since the local community will acquire some ownership in the facility, some of the revenue generated by the facility will be utilised for upliftment of the local community.</li> </ul> <p>Also referred to as the 'Do nothing' option, this refers to Gillmer Solar Energy (Pty) Ltd not constructing the proposed solar energy facility on the identified site. In this scenario the potential positive and negative environmental and social impacts as described in this Basic Assessment Report will not occur and the status quo will be maintained. There are no insurmountable environmental or social constraints that prevent the establishment of the proposed Gillmer Solar Energy Facility; therefore the No-Go option is not supported.</p>		

Activity	Impact summary	Significance	Proposed mitigation
	<p><b>Indirect impacts:</b>                      The No-Development option would represent a lost opportunity for South Africa to supplement its current energy needs with clean, renewable energy. Given South Africa's position as one of the highest per capita producer of carbon emissions in the world, this would represent a high negative social cost.</p>	Low	None
	<p><b>Cumulative impacts:</b>                      Contributing to further unemployment and unsustainable ways to produce electricity.</p>	Low	None

A complete impact assessment in terms of Regulation 22(2)(i) of GN R.543 must be included as **Appendix F**.

## 2. ENVIRONMENTAL IMPACT STATEMENT

Taking the assessment of potential impacts into account, please provide an environmental impact statement that summarises the impact that the proposed activity and its alternatives may have on the environment after the management and mitigation of impacts have been taken into account, with specific reference to types of impact, duration of impacts, likelihood of potential impacts actually occurring and the significance of impacts.

### Alternative A (preferred alternative)

This section provides a summary of the environmental assessment and conclusions drawn for the proposed solar energy facility. In doing so, it draws on the information gathered as part of the Basic Assessment process and the knowledge gained by the environmental consultants during the course of the process and presents an informed opinion of the environmental impacts associated with the proposed project.

The following conclusions can be drawn from the studies undertaken within this Basic Assessment:

- » The overall impacts based on the **ecology** for the proposed development is **low**. The extent to which the vegetation will be impacted is small compared to its overall distribution, thus the planned development will not likely have a significant impact on the overall conservation status of the Eastern Upper Karoo, of which it is part. Rather, clearing of alien invasive plants and rubble from the site will constitute a positive impact. None of these areas fall within critical biodiversity areas (BGIS), but, being in close proximity to Noupoot Spruit, due care must be taken to ensure the long-term stability of the vegetation. This is even more important when considering that soils are relatively erodible and vegetation slow to re-establish due to the unpredictability and general low levels of rainfall. This objective should be achievable by following recommended mitigation measures.
- » The area is, however, in close proximity to the Noupootspruit with eroded banks, and care must thus be taken to curb erosion as much as possible, prevent any pollution of the site and its surroundings, and retain a suitable buffer zone of a minimum of 50 m, preferably up to 100 m, from the banks of the Noupoot Spruit. Minimising the negative impact of the development and enhancing its positive impact should be achievable by following recommended mitigation measures. Nevertheless, as soils are relatively erodible and vegetation slow to re-establish due to the unpredictability and general low levels of rainfall, due care should be taken to retain a basic functionality of the ecosystem, instead of creating a window of opportunity for degradation, including the establishment of alien invasive species that are up to date absent from the site. This objective should be achievable by following recommended mitigation measures as contained in the EMP (Appendix G).

No infrastructure is proposed in the Noupootspruit, however the power line will be strung across the Noupootspruit and should be done carefully during construction of pylons and stringing of the powerline. No pylons will be placed in the Noupootspruit.

- » The overall impacts on **soil and agricultural potential** for the proposed site is **low**. The size of the site on the agricultural production and the food security of the region and the country are regarded as small. The reasons for this conclusion is (ii) the small size of the site and (iii) the fact that it is currently primarily in disuse regarding agricultural production due to its close proximity to the town of Noupoot and the consequent theft of most agricultural products that can be produced on the site.

The site is relatively well endowed with good quality deep soil which is well suited for cultivation. Its proximity to the town of Noupoot and the consequent theft of agricultural products that can be produced, though, makes the site almost useless for agricultural production. The site does not consist of unique agricultural land and its conservation status is regarded as least threatened. A small part of the site is currently rented to a neighbor and under lucerne cultivation.

Apart from a windmill and a water reservoir, there are no agricultural infrastructure (i.e. silos, irrigation lines, pivot points, channels, feeding structures, grazing camps, animal housing, farm roads, etc.) or any conservation works (i.e. contour banks, waterways, etc.) that will be interfered with. Due to the fact that the site has fallen in disuse, the windmill and reservoir is seldom used for agricultural production. The site is virtually flat with no slopes in excess of 20%. The site has a moderate susceptibility to wind and water erosion.

- » The overall impacts of the proposed facility on **heritage** resources is **low**. : The proposed area for development is situated on the outskirts of the small town of Noupoot. Historical archaeological artefacts and the remains of building structures were documented in the southern portion of the proposed area for development. The distribution of historical artefacts extends along the Noupoot Spruit situated on the eastern border of the development. Two Middle Stone Age stone artefacts were documented also documented on the banks of the Noupoot Spruit. No archaeological heritage remains, features, or sites were documented in the northern half of the proposed area for development.
- » The overall impact of the proposed facility on **palaeontology** is **low**. The area is characterised by fossiliferous mudstones and sandstones. Several dolerite sills and dykes occur in the region and are often found capping hills and forming ridges. Care should be given however to constructions such as access routes, construction facilities, substations, pylons and buildings which are not limited to dolerite. There is a high probability that fossils would occur on the Gillmer site where construction is proposed due to the mudstone which dominates the study site.
- » The overall **visual impacts** of the PV panels and associated infrastructure is **low**. . All of the potential impacts therefore relate to the *middle-* and *background* zone

of visual influence. The visual analysis and assessment from all of these observation points found that the proposed activity is rarely visible from the relevant Observation Points. The results of the Visual Impact Assessment for the proposed Gillmer Solar Energy Facility therefore found that the proposed activity will have a **low** impact from all key Observation Points including the town of Noupoort.

- » The overall **social impact** of the project is likely to be of a predominantly **low significance (positive impacts and negative impacts)** with the implementation of appropriate enhancement measures. The project will create employment and business opportunities for locals during both the construction and operational phase of the project. The majority of the potential negative impacts can therefore be effectively mitigated if the recommended mitigation measures are implemented. However, the impact on individuals who are directly impacted on by construction workers and or job seekers (i.e. contract HIV/ AIDS) was assessed to be of Medium-High negative significance. In addition, due to the low population density of the area and the relatively small size of the labour force the potential risk to local family structures and social networks are regarded as low. The establishment of a Community Trust also creates an opportunity to support local economic development in the area. The proposed development also represents an investment in clean, renewable energy infrastructure, which, given the challenges created by climate change, represents a positive social benefit for society as a whole.
- » The overall impact on **avifauna** is likely to carry **low significance** due to the limited area that is taken up by the facilities and the relative uniformity of the habitat in the broader area. It will be necessary to check for such breeding just prior to the onset of construction. It is recommended that a final avifaunal walk-through be conducted as part of the site specific EMP for the projects.

Based on the findings of the studies undertaken, in terms of environmental constraints and opportunities identified through the Environmental Basic Assessment process, no environmental impacts of high significance, and no fatal flaws were identified to be associated with the establishment of the proposed Gillmer Solar Energy (Pty) Ltd and associated infrastructure.

The significance levels of the majority of identified negative impacts can generally be reduced by implementing the recommended mitigation measures. With reference to the information available at this planning approval stage in the project cycle, the confidence in the environmental assessment undertaken is regarded as acceptable.

Therefore, it is recommended that the project should be authorised. However, a number of issues requiring mitigation have been highlighted in the impact assessment (Appendix F). In response to these potential environmental impacts, environmental specifications for the management of these issues / impacts are detailed within the draft Environmental Management Programme (EMP) included within Appendix G.

**Alternative B: N/A**

**Alternative C: N/A**

**No-go alternative (compulsory)**

The 'do-nothing' alternative is the option of not constructing the Gillmer Solar Energy Facility on the identified site. This alternative would result in no environmental impacts on the site or surrounding area. However, failure to add the proposed electricity to the national grid would most likely result in additional consumption of fossil fuels to achieve the same level of electrical generation at other locations in the country. This is because the electricity demand in South Africa is placing increasing pressure on the country's existing power generation capacity. There is therefore a need for additional electricity generation options to be developed throughout the country.

The support for renewable energy policy is guided by the need to address climate change as well as a rationale that South Africa has a very attractive range of renewable resources, particularly solar and wind and that renewable applications are in fact the least-cost energy service in many cases - and more so when social and environmental costs are taken into account.

The generation of electricity from renewable energy in South Africa offers a number of socio-economic and environmental benefits. These benefits are explored in further detail in the South Africa Renewable Energy Feed-in Tariff (REFIT) Regulatory Guideline published by NERSA (March 2009), and include:

- » *Support for international agreements:* The effective deployment of renewable energy provides a tangible means for South Africa to demonstrate its commitment to its international agreements under the Kyoto Protocol, and for cementing its status as a leading player within the international community.
- » *Exploitation of our significant renewable energy resource:* At present, valuable national resources including biomass by-products, solar radiation and solar power remain largely unexploited. The use of these energy flows will strengthen energy security through the development of a diverse energy portfolio.
- » *Increased energy security:* The current electricity crisis in South Africa highlights the significant role that renewable energy can play in terms of power supplementation. In addition, given that renewables can often be deployed in a decentralised manner close to consumers, they offer the opportunity for improving grid strength and supply quality, while reducing expensive transmission and distribution losses.

- » *Pollution reduction:* The releases of by-products through the burning of fossil fuels for electricity generation have a particularly hazardous impact on human health and contribute to ecosystem degradation.
- » *Climate friendly development:* The uptake of renewable energy offers the opportunity to address energy needs in an environmentally responsible manner and thereby allows South Africa to contribute towards mitigating climate change through the reduction of greenhouse gas (GHG) emissions. South Africa is estimated to be responsible for ~1% of global GHG emissions and is currently ranked 9<sup>th</sup> worldwide in terms of per capita CO<sub>2</sub> emissions.
- » *Employment creation:* The sale, development, installation, maintenance, and management of renewable energy facilities have significant potential for job creation in South Africa.
- » *Acceptability to society:* Renewable energy offers a number of tangible benefits to society including reduced pollution concerns, improved human and ecosystem health and climate friendly development.
- » *Support to a new industry sector* - the development of renewable energy offers the opportunity to establish a new industry within the South African economy.

Within a policy framework, the development of renewable energy in South Africa is supported by the White Paper on Renewable Energy (November 2003), which has set a target of 10 000 GWh renewable energy contributions to final energy consumption by 2013. The target is to be achieved primarily through the development of solar, biomass, solar and small-scale hydro.

The 'do nothing' alternative will not assist the South African government in addressing climate change, in reaching the set targets for renewable energy, nor will it assist in supplying the increasing electricity demand within the country. In addition the Northern Cape power supply will be deprived of an opportunity to benefit from the additional generated power being evacuated directly into the Provinces' grids. **The 'do nothing alternative is, therefore, not a preferred alternative.**

## SECTION E. RECOMMENDATION OF PRACTITIONER

Is the information contained in this report and the documentation attached hereto sufficient to make a decision in respect of the activity applied for (in the view of the environmental assessment practitioner)?

YES ✓

If "NO", indicate the aspects that should be assessed further as part of a Scoping and EIA process before a decision can be made (list the aspects that require further assessment).

If "YES", please list any recommended conditions, including mitigation measures that should be considered for inclusion in any authorisation that may be granted by the competent authority in respect of the application.

There are no insurmountable environmental or social constraints that prevent the establishment of the proposed Gillmer Solar Energy Facility. However, sensitive areas / features (see **Figure 3**) were identified on the site and categorised to have high environmental sensitivity are as follow:

- » Remaining natural vegetation on low rocky ridges and out crops; and
- » Drainage areas i.e. water depressions and the Noupoort Spruit.
- » Two heritage sites albeit of low significance.

The proposed PV panels and infrastructure have been positioned to avoid the above sensitive areas (and are illustrated in **Figure 3**). The infrastructure is proposed on mainly area of medium-low ecological sensitivity, which is acceptable in terms of avoidance of sensitive environmental features and therefore avoidance of impacts.

The construction of the proposed Gillmer solar energy facility should be implemented according to the EMP to adequately mitigate and manage potential impacts associated with construction activities. The construction activities and relevant rehabilitation of disturbed areas should be monitored against the approved EMP, the Environmental Authorisation and all other relevant environmental legislation. Relevant conditions to be adhered to include:

### **Design, Construction, and Decommissioning Phases:**

- » All relevant practical and reasonable mitigation measures detailed within this report and the specialist reports contained within Appendix D must be implemented.
- » The draft Environmental Management Programme (EMP) as contained within Appendix G of this report should form part of the contract with the Contractors appointed to construct and maintain the proposed solar energy facility, and will be used to ensure compliance with environmental specifications and management measures. The implementation of this EMP for all life cycle phases of the proposed



project is considered to be key in achieving the appropriate environmental management standards as detailed for this project.

- » During construction, unnecessary disturbance to habitats should be strictly controlled and the footprint of the impact should be kept to a minimum.
- » Perennial grasses which occur naturally in the area should be used to stabilise the site after it has been cleared. A mix of fast growing annual and perennial grass species could be used, which could include species such as *Cynodon dactylon* and *Cenchrus ciliaris*, which are readily available and easily established.
- » Disturbed areas should be rehabilitated as soon as possible once construction is complete in an area.
- » An on-going monitoring programme should be established to detect and quantify any alien species.
- » Identify areas of high erosion risk (drainage lines, existing problem areas). Only special works to be undertaken in these areas to be authorised by ECO and Engineer's representative (ER).
- » Access roads to be carefully planned and constructed to minimise the impacted area and prevent unnecessary degradation of soil. Special attention to be given to roads that cross steep slopes (to prevent unnecessary cutting and filling operations).
- » Erosion control measures- run-off control and attenuation on slopes (sand bags, logs), silt fences, stormwater channels and catch-pits, shade nets, soil binding, geofabrics, hydroseeding or mulching over cleared areas.
- » Contractors must be informed before construction starts on the possible types of heritage sites and cultural material they may encounter and the procedures to follow when they find sites. A professional archaeologist must be appointed during construction to monitor various activities including vegetation clearing and excavation activities to monitor and identify possible archaeological material remains and features that may occur below the surface. If concentrations of archaeological heritage material and human remains are uncovered, all work must cease immediately and be reported to SAHRA so that systematic and professional investigation/ excavation can be undertaken. It is also recommended that a palaeontologist should be appointed do a site visit to determine whether fossils are exposed in the area earmarked for development, prior to construction. This survey would of course be limited to a surface inspection only. In the event of fossils being uncovered during the construction phase, the ECO should photograph and record the position of fossiliferous material.
- » An application for all other permits (e.g. those with respect to protected tree species or protected plant species) must be obtained from the relevant authority prior to the commencement of construction activities.
- » All declared aliens must be identified and managed in accordance with the Conservation of Agricultural Resources Act, 1983 (Act No. 43 of 1983), the implementation of a monitoring programme in this regard is recommended.
- » Before development can continue the regions need to be checked for the presence of bird nesting sites, particularly those of ground nesting species.

- » Utilise visual screening and landscaping on adjacent landowner homesteads in order to mitigate the visual impact upon adjacent landowners. Limit construction, maintenance, and inspection activities to dry periods.
- » Develop emergency maintenance operational plan to deal with any event of contamination, pollution, or spillages.
- » If large areas are cleared for the storage of equipment, these could be rehabilitated using arid site rehabilitation techniques such as planting cover crops reseeding with local grasses and shrubs.
- » Compile and implement a detailed waste management plan.
- » Compile and implement a traffic management plan.
- » Compile and implement a storm water management plan.

**Operation Phase:**

The mitigation and management measures previously listed in this Basic Assessment Report should be implemented in order to minimise potential environmental impacts. The following mitigation measures should also be implemented.

- » Maintenance of erosion control measures (i.e. berms).
- » Ensure bird-friendly tower designs are implemented to minimise the risk of electrocutions. Fit overhead power lines with appropriate flappers to increase the visibility thereof to avifauna. Notes of electrocution and collision events must be sent to a qualified Ornithologist for the recommendation of further mitigation measures if necessary.
- » Install bird diverters on the power line.
- » Development and implementation of a storm water management plan.
- » On-going maintenance of the facility to minimise the potential for visual impacts.
- » On-going monitoring of the site to detect and restrict the spread of alien plant species.
- » Training, skills development and the use of local labour.

Is an EMPr attached?

YES ✓

The EMPr must be attached as Appendix G.

The details of the EAP who compiled the BAR and the expertise of the EAP to perform the Basic Assessment process must be included as Appendix H.

If any specialist reports were used during the compilation of this BAR, please attach the declaration of interest for each specialist in Appendix I.

Any other information relevant to this application and not previously included must be attached in Appendix J.

KAREN JODAS  
NAME OF EAP

\_\_\_\_\_  
SIGNATURE OF EAP

\_\_\_\_\_  
DATE




Figure 3: Gillmer Sensitivity map

## **SECTION F: APPENDICES**

The following appendixes must be attached:

Appendix A: Maps

Appendix B: Photographs

Appendix C: Facility illustration(s)

Appendix D: Specialist reports (including terms of reference)

Appendix E: Public Participation

Appendix F: Impact Assessment

Appendix G: Environmental Management Programme (EMPr)

Appendix H: Details of EAP and expertise

Appendix I: Specialist's declaration of interest

Appendix J: Additional Information

» *J1: List of Co-Ordinates for Power Line*