

# H4 - DWELLING HOUSE

## GENERAL NOTES:

- ALL WORK TO BE IN ACCORDANCE WITH THE NATIONAL BUILDING REGULATIONS. NOTES IN RESPECT OF S.A. STANDARD CODE OF PRACTICE - THE APPLICATION OF THE NATIONAL BUILDING REGULATIONS, SANS 10400.
- ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR/SUBCONTRACTOR PRIOR TO CONSTRUCTION.
- ALL DIMENSIONS AND LEVELS ARE TO BE TAKEN IN PREFERENCE TO SCALING OFF. ANY DISCREPANCIES ARE TO BE REPORTED TO THE OFFICE OF THE ARCHITECT IMMEDIATELY.
- DATUM LEVEL TO BE ESTABLISHED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION.
- ALL RETAINING WALLS, PILES, FOOTINGS, SLABS, BEAMS, COLUMNS AND AGRICULTURAL DRAINS TO ENGINEER'S DETAILS.
- DPC TO ALL HORIZONTAL & VERTICAL OPENINGS & ROOF
- FOUNDATIONS TO BE MINIMUM 300mm BELOW NGL
- SUPPLY ADEQUATE FLASHING TO ALL PARAPET WALLS.

- DPC TO BE MIN 150mm ABOVE NGL
- ALL SUSPENDED REINFORCED CONCRETE SLABS BY ENGINEER.
- WALLS TO COMPLY WITH SANS 10400 - K :**
- EXTERNAL WALLS - IMPERIAL BRICK, PLASTER AND PAINT FINISH.
- RETAINING WALLS - TO ENGINEER'S DETAIL - TO BE DRAINED WITH AGRICULTURAL DRAIN CONNECTED TO STORMWATER MANAGEMENT SYSTEM.
- BRICKFORCE IN EVERY COURSE FOR MIN 5 COURSES ABOVE INTOLS.
- CONTINUOUS DPC AND ANT GUARD AT SLAB LEVEL AND AT WINDOW CILLS AS REQUIRED BY THE LOCAL AUTHORITY AND IN ACCORDANCE WITH NBR AND WINDOW SYSTEMS.
- GALVANISED WIRE TIES OR EQUAL TO BE BUILT INTO ALL EXTERNAL WALLS AT 800 CENTRES HORIZONTALLY AND EVERY 6TH COURSE VERTICALLY.

## STAIRWAYS TO COMPLY WITH SANS 10400 - M :

- STAIRS TO COMPLY FULLY WITH SANS 10400

## DRAINAGE TO COMPLY WITH SANS 10400 - P :

## STORMWATER TO COMPLY WITH SANS 10400 - R :

- RAINWATER GOODS:- R.C. BALCONY SLABS TO BE FITTED WITH FULLBORE DRAINAGE FITTINGS AND CONNECTED TO 100mmØ RWDP'S

## OCCUPANCY CLASS: H4 - DWELLING HOUSE

### STRUCTURE TO COMPLY WITH PART H, J, K, L or N OF SANS 10400:-

- ALL STRUCTURAL WORK TO ENGINEER'S DETAIL TO COMPLY SANS 10400
- COLUMNS:- ALL STRUCTURAL COLUMNS BY ENGINEER

### PUBLIC SAFETY TO COMPLY WITH SANS 10400 - D:-

- BALUSTRADING:- BALUSTRADING ALL TO DETAIL. MIN 1000 HIGH TO COMPLY WITH SANS 10400 - B, SANS 10400 - T, SANS 10400 - K & SANS 10400.


### SITE OPERATIONS TO COMPLY WITH SANS 10400 - F :

### FOUNDATIONS TO COMPLY WITH SANS 10400 - H :


- REINFORCED CONCRETE FOUNDATIONS TO STRUCTURAL ENGINEER'S DETAIL.

### FLOORS TO COMPLY WITH SANS 10400 - J :

- FINISH AS PER SPECIFICATIONS ON CEMENT SCREED ON 100mm CONCRETE SURFACE BED
- CONCRETE SURFACE BED WITH BRC MESH ON 250 MICRON GUNPLAS GREEN UNDERLAY ON WELL COMPACTED AND POISONED SOIL. SOIL POISONING BY SPECIALIST TO LOCAL AUTHORITY'S REQUIREMENTS.
- DAMP PROOF MEMBRANE TO BE WELL LAPPED TO BRICK WALL DPC



## WEST ELEVATION (FROM MUSGRAVE ROAD)




## GROUND FLOOR PLAN

SCALE 1:100



NB : The below braai area structure is existing and was built before this LA submission was made. These drawings merely indicate what has been built and engine architecture indemnifies itself from any loss, damage or liability in this regard.




## EXISTING BRAAI AREA SOUTH ELEVATION

SCALE 1:100

## EXISTING BRAAI AREA EAST ELEVATION


SCALE 1:100

<b>AREAS</b>	<b>PARKING</b>
<b>SITE AREA :</b> 1078m <sup>2</sup>	<b>EXISTING :</b> 2
<b>FAR :</b> NONE ADDED	<b>PROPOSED :</b> 2
<b>COVERAGE :</b>	<b>TOTAL :</b> 4
<b>EXISTING :</b> ± 330m <sup>2</sup>	
<b>PROPOSED :</b> 1.6m <sup>2</sup>	
<b>TOTAL :</b> ± 331.6m <sup>2</sup>	



## SECTION AA

SCALE 1:100



## SITE PLAN

SCALE 1:500

MUNICIPAL STAMPS

NORTH

B. Petit 470714 5041 089.  
 ID NO:

NEIGHBOUR (WHOM GIVES CONSENT)  
**CEDRIC PETIT**  
 ADDRESS 626 MUSGRAVE ROAD ON 1 OF LOT 3026 P.O. NO 626  
 TEL/CELL NO. 082.454.24.21

ARCHITECT  
**CAMERON FINNIE** PR. ARCH 24750893  
  
 ID NO: 5312050139082

OWNER  
**STEPHANIE BENNETT**  
**618 MUSGRAVE ROAD**  
 18/007  
 ALTERATIONS TO EXISTING BOUNDARY WALL AND PEDESTRIAN ENTRANCE FOR STEPHANIE BENNETT 618 MUSGRAVE ROAD ON PORTION 1 OF LOT 3027

**SUBMISSION + PLANS, ELEVATIONS + SECTION**

STAGE	SERIES	TYPE	REV	DATE	CPA
M	GA	100	01	JULY   2021	CF

**ENGINE architecture**  
 t : +27 78 803 8322  
 e : design@enginearchitecture.com  
 a : 124 Burnside 124 Gordon road, Morningdale Durban KZN 4061 South Africa