

# HERITAGE IMPACT ASSESSMENT

(REQUIRED UNDER SECTION 38(8) OF THE NHRA (No. 25 OF 1999))

For the proposed township establishment on the Remainder of Portion 3 of the Farm  
Naboomspruit 348 KR, in Limpopo Province

**Type of development:**

Township Development

**Client:**

Leago Environmental Solutions

**Applicant:**

Modimolle-Mookgophong Local Municipality

**Report prepared by:**



**Beyond Heritage**

Private Bag X 1049

Suite 34

Modimolle

0510

Tel: 082 373 8491

Fax: 086 691 6461

E-Mail: [jaco@heritageconsultants.co.za](mailto:jaco@heritageconsultants.co.za)

Report Author:

Mr. J. van der Walt

Project Reference:

Project number 2280

Report date:

May 2022

Revised June 2022

## APPROVAL PAGE

<b>Project Name</b>	Naboomspruit Township Development
<b>Report Title</b>	Heritage Impact Assessment for the proposed Naboomspruit Township Development Limpopo Province
<b>Authority Reference Number</b>	TBC
<b>Report Status</b>	Final Report
<b>Applicant Name</b>	Modimolle-Mookgophong Local Municipality

<b>Responsibility</b>	<b>Name</b>	<b>Qualifications and Certifications</b>	<b>Date</b>
<b>Project Manager</b>	Jaco van der Walt - Archaeologist	MA Archaeology ASAPA #159 APHP #114	May 2022

**DOCUMENT PROGRESS****Distribution List**

Date	Report Reference Number	Document Distribution	Number of Copies
26 May 2022	2280	Leago Environmental Solutions	Electronic Copy

**Amendments on Document**

Date	Report Reference Number	Description of Amendment
7 June 2022	2280	Technical revision

**INDEMNITY AND CONDITIONS RELATING TO THIS REPORT**

The findings, results, observations, conclusions and recommendations given in this report are based on the author's best scientific and professional knowledge as well as available information. The report is based on survey and assessment techniques which are limited by time and budgetary constraints relevant to the type and level of investigation undertaken. Beyond Heritage reserves the right to modify aspects of the report including the recommendations if and when new information becomes available from ongoing research or further work in this field or pertaining to this investigation.

Although Beyond Heritage exercises due care and diligence in rendering services and preparing documents Beyond Heritage accepts no liability, and the client, by receiving this document, indemnifies Beyond Heritage against all actions, claims, demands, losses, liabilities, costs, damages and expenses arising from or in connection with services rendered, directly or indirectly by Beyond Heritage and by the use of the information contained in this document.

This report must not be altered or added to without the prior written consent of the author. This also refers to electronic copies of this report which are supplied for the purposes of inclusion as part of other reports, including main reports. Similarly, any recommendations, statements or conclusions drawn from or based on this report must make reference to this report. If these form part of a main report relating to this investigation or report, this report must be included in its entirety as an appendix or separate section to the main report.

**COPYRIGHT**

Copyright on all documents, drawings and records, whether manually or electronically produced, which form part of the submission and any subsequent report or project document, shall vest in Beyond Heritage.

The client, on acceptance of any submission by Beyond Heritage and on condition that the client pays to Beyond Heritage the full price for the work as agreed, shall be entitled to use for its own benefit:

- The results of the project;
- The technology described in any report; and
- Recommendations delivered to the client.

Should the applicant wish to utilise any part of, or the entire report, for a project other than the subject project, permission must be obtained from Beyond Heritage to do so. This will ensure validation of the suitability and relevance of this report on an alternative project.

## REPORT OUTLINE

Appendix 6 of the GNR 326 EIA Regulations published on 7 April 2017 provides the requirements for specialist reports undertaken as part of the environmental authorisation process. In line with this, Table 1 provides an overview of Appendix 6 together with information on how these requirements have been met.

**Table 1. Specialist Report Requirements.**

Requirement from Appendix 6 of GN 326 EIA Regulation 2017	Chapter
(a) Details of - (i) the specialist who prepared the report; and (ii) the expertise of that specialist to compile a specialist report including a curriculum vitae	Section a
(b) Declaration that the specialist is independent in a form as may be specified by the competent authority	<i>Declaration of Independence</i>
(c) Indication of the scope of, and the purpose for which, the report was prepared	Section 1
(cA) an indication of the quality and age of base data used for the specialist report	Section 3.4.
(cB) a description of existing impacts on the site, cumulative impacts of the proposed development and levels of acceptable change;	9
(d) Duration, Date and season of the site investigation and the relevance of the season to the outcome of the assessment	Section 3.4
(e) Description of the methodology adopted in preparing the report or carrying out the specialised process inclusive of equipment and modelling used	Section 3
(f) details of an assessment of the specific identified sensitivity of the site related to the proposed activity or activities and its associated structures and infrastructure, inclusive of site plan identifying site alternatives;	Section 8 and 9
(g) Identification of any areas to be avoided, including buffers	Section 8 and 9
(h) Map superimposing the activity including the associated structures and infrastructure on the environmental sensitivities of the site including areas to be avoided, including buffers	Section 8
(I) Description of any assumptions made and any uncertainties or gaps in knowledge	Section 3.7
(j) a description of the findings and potential implications of such findings on the impact of the proposed activity including identified alternatives on the environment or activities;	Section 1.3
(k) Mitigation measures for inclusion in the EMPr	Section 10.1
(l) Conditions for inclusion in the environmental authorisation	Section 10. 1.
(m) Monitoring requirements for inclusion in the EMPr or environmental authorisation	Section 10. 5.
(n) Reasoned opinion - (i) as to whether the proposed activity, activities or portions thereof should be authorised; (iA) regarding the acceptability of the proposed activity or activities; and (ii) if the opinion is that the proposed activity, activities or portions thereof should be authorised, any avoidance, management and mitigation measures that should be included in the EMPr, and where applicable, the closure plan	Section 10.3
(o) Description of any consultation process that was undertaken during the course of preparing the specialist report	Section 5
(p) A summary and copies of any comments received during any consultation process and where applicable all responses thereto; and	Refer to BAR report
(q) Any other information requested by the competent authority	N.A

**Executive Summary**

Leago Environmental Solutions was appointed by Real Development Planning Company on behalf of the Modimolle-Mookgophong Local Municipality to undertake an Environmental Impact Assessment (EIA) for the proposed development of a township on the Remainder of Portion 3 of the Farm Naboomspruit 348 KR, in Limpopo Province. Beyond Heritage was appointed to conduct a Heritage Impact Assessment (HIA) for the project and the study area was assessed on desktop level and by a non-intrusive pedestrian field survey. Key findings of the assessment include:

- The proposed development site currently has a closed dumping site and two community centres being Mookgophong Social Development and the Phomolong Early Childhood Development the rest of the property is fallow and overgrown with pioneer trees and vegetation;
- Examination of historical topographic maps and aerial images showed no structures or stone walled settlements in the study area and the impact footprint is considered to be of low heritage potential. This was confirmed during the site visit and no heritage finds of significance were recorded during the survey;
- The palaeontological sensitivity of the study area is insignificant, and no further studies are required for this aspect.

The impact on heritage resources is low and the project can commence provided that the recommendations in this report are adhered to, based on the South African Heritage Resource Authority (SAHRA) 's approval.

**Recommendations:**

- Implementation of a Chance Find Procedure for the project.
- Monitoring of the development footprint by the ECO.

**Declaration of Independence**

<b>Specialist Name</b>	Jaco van der Walt
<b>Declaration of Independence</b>	<p>I declare, as a specialist appointed in terms of the National Environmental Management Act (Act No 108 of 1998) and the associated 2014 Environmental Impact Assessment (EIA) Regulations, that I:</p> <ul style="list-style-type: none"> <li>• I act as the independent specialist in this application;</li> <li>• I will perform the work relating to the application in an objective manner, even if this results in views and findings that are not favourable to the applicant;</li> <li>• I declare that there are no circumstances that may compromise my objectivity in performing such work;</li> <li>• I have expertise in conducting the specialist report relevant to this application, including knowledge of the Act, Regulations and any guidelines that have relevance to the proposed activity;</li> <li>• I will comply with the Act, Regulations and all other applicable legislation;</li> <li>• I have no, and will not engage in, conflicting interests in the undertaking of the activity;</li> <li>• I undertake to disclose to the applicant and the competent authority all material information in my possession that reasonably has or may have the potential of influencing - any decision to be taken with respect to the application by the competent authority; and - the objectivity of any report, plan or document to be prepared by myself for submission to the competent authority;</li> <li>• All the particulars furnished by me in this form are true and correct; and</li> <li>• I realise that a false declaration is an offence in terms of regulation 48 and is punishable in terms of section 24F of the Act.</li> </ul>
<b>Signature</b>	
<b>Date</b>	19/05/2022

**a) Expertise of the specialist**

Jaco van der Walt has been practising as a CRM archaeologist for 15 years. He obtained an MA degree in Archaeology from the University of the Witwatersrand focussing on the Iron Age in 2012 and is a PhD candidate at the University of Johannesburg focussing on Stone Age Archaeology with specific interest in the Middle Stone Age (MSA) and Later Stone Age (LSA). Jaco is an accredited member of ASAPA (#159) and have conducted more than 500 impact assessments in Limpopo, Mpumalanga, North West, Free State, Gauteng, KZN as well as he Northern and Eastern Cape Provinces in South Africa.

Jaco has worked on various international projects in Zimbabwe, Botswana, Mozambique, Lesotho, DRC Zambia, Guinea, Afghanistan and Tanzania. Through this, he has a sound understanding of the IFC Performance Standard requirements, with specific reference to Performance Standard 8 – Cultural Heritage.

**TABLE OF CONTENTS**

<b>REPORT OUTLINE</b> .....	<b>4</b>
<b>EXECUTIVE SUMMARY</b> .....	<b>5</b>
<b>DECLARATION OF INDEPENDENCE</b> .....	<b>6</b>
A) EXPERTISE OF THE SPECIALIST.....	6
<b>ABBREVIATIONS</b> .....	<b>10</b>
<b>GLOSSARY</b> .....	<b>10</b>
<b>1 INTRODUCTION AND TERMS OF REFERENCE:</b> .....	<b>11</b>
1.1 TERMS OF REFERENCE.....	11
1.2 PROJECT DESCRIPTION .....	12
1.3 ALTERNATIVES .....	12
<b>2 LEGISLATIVE REQUIREMENTS</b> .....	<b>16</b>
<b>3 METHODOLOGY</b> .....	<b>17</b>
3.1 LITERATURE REVIEW.....	17
3.2 GENEALOGICAL SOCIETY AND GOOGLE EARTH MONUMENTS.....	17
3.3 PUBLIC CONSULTATION AND STAKEHOLDER ENGAGEMENT:.....	17
3.4 SITE INVESTIGATION.....	18
3.5 SITE SIGNIFICANCE AND FIELD RATING.....	20
3.6 IMPACT ASSESSMENT METHODOLOGY.....	21
3.7 LIMITATIONS AND CONSTRAINTS OF THE STUDY .....	22
<b>4 DESCRIPTION OF SOCIO-ECONOMIC ENVIRONMENT</b> .....	<b>22</b>
<b>5 RESULTS OF PUBLIC CONSULTATION AND STAKEHOLDER ENGAGEMENT:</b> .....	<b>22</b>
<b>6 LITERATURE / BACKGROUND STUDY:</b> .....	<b>23</b>
6.1 LITERATURE REVIEW (SAHRIS) .....	23
6.2 ARCHAEOLOGICAL BACKGROUND.....	23
<b>7 DESCRIPTION OF THE PHYSICAL ENVIRONMENT</b> .....	<b>26</b>
<b>8 FINDINGS OF THE SURVEY</b> .....	<b>27</b>
8.1 HERITAGE RESOURCES.....	27
8.2 CULTURAL LANDSCAPE.....	27
8.3 PALEONTOLOGICAL HERITAGE .....	29
<b>9 POTENTIAL IMPACT</b> .....	<b>30</b>
<b>10 CONCLUSION AND RECOMMENDATIONS</b> .....	<b>31</b>

10.1	RECOMMENDATIONS FOR CONDITION OF AUTHORISATION.....	31
10.2	CHANCE FIND PROCEDURES .....	31
10.3	REASONED OPINION .....	31
10.4	POTENTIAL RISK .....	32
10.5	MONITORING REQUIREMENTS .....	33
10.6	MANAGEMENT MEASURES FOR INCLUSION IN THE EMPR .....	34
10.7	KNOWLEDGE GAPS .....	35
<b>11</b>	<b>REFERENCES.....</b>	<b>36</b>

## LIST OF FIGURES

FIGURE 1.1.	REGIONAL SETTING OF THE PROJECT (1: 250 000 TOPOGRAPHICAL MAP).....	13
FIGURE 1.2.	LOCAL SETTING OF THE PROJECT (1: 50 000 TOPOGRAPHICAL MAP).....	14
FIGURE 1.3.	AERIAL IMAGE SHOWING DEVELOPMENTS IN THE STUDY AREA.....	15
FIGURE 3.1.	TRACKLOG OF THE SURVEY PATH IN GREEN.....	19
FIGURE 6.1:	MOVEMENT OF BANTU SPEAKING FARMERS (HUFFMAN 2007).....	24
FIGURE 7.1.	ENTRANCE TO EXISTING DEVELOPMENTS IN THE AREA (MOOKGOPHONG SOCIAL DEVELOPMENT).....	26
FIGURE 7.2.	EXISTING DEVELOPMENTS IN THE AREA (PHOMOLONG EARLY CHILDHOOD DEVELOPMENT CENTRE).....	26
FIGURE 7.3.	OLD LAYDOWN AREA MARKED BY PIPES.....	26
FIGURE 7.4.	DENSE VEGETATION COVER LIMITED ACCESSIBILITY.....	26
FIGURE 8.1.	1965 TOPOGRAPHIC MAP OF THE STUDY AREA INDICATING NO DEVELOPMENTS OLDER THAN 60 YEARS IN THE STUDY AREA. STRUCTURES, TRAIN STATION AND A CEMETERY ARE INDICATED IN THE WIDER AREA.....	27
FIGURE 8.2.	2003 GOOGLE EARTH IMAGE SHOWING CLEARED AREAS IN THE NORTHERN SECTION OF THE PROJECT AREA.....	28
FIGURE 8.3.	2012 GOOGLE EARTH IMAGE SHOWING CLEARED AREAS IN THE NORTH AND SOUTH OF THE PROJECT AREA.....	28
FIGURE 8.4.	PALEONTOLOGICAL SENSITIVITY OF THE APPROXIMATE STUDY AREA (YELLOW POLYGON) AS INDICATED ON THE SAHRA PALAEONTOLOGICAL SENSITIVITY MAP.....	29

**LIST OF TABLES**

TABLE 1. SPECIALIST REPORT REQUIREMENTS.....	4
TABLE 2. PROJECT DESCRIPTION.....	12
TABLE 3. INFRASTRUCTURE AND PROJECT ACTIVITIES .....	12
TABLE 4. SITE INVESTIGATION DETAILS .....	18
TABLE 5. HERITAGE SIGNIFICANCE AND FIELD RATINGS.....	21
TABLE 7. IMPACT ASSESSMENT OF THE PROPOSED PROJECT.....	30
TABLE 8. MONITORING REQUIREMENTS FOR THE PROJECT.....	33
TABLE 9. HERITAGE MANAGEMENT PLAN FOR EMPR IMPLEMENTATION .....	34

**ABBREVIATIONS**

ASAPA: Association of South African Professional Archaeologists
BGG Burial Ground and Graves
BIA: Basic Impact Assessment
CFPs: Chance Find Procedures
CMP: Conservation Management Plan
CRR: Comments and Response Report
CRM: Cultural Resource Management
DEA: Department of Environmental Affairs
DFFE: Department of Forestry Fisheries and the Environment
EA: Environmental Authorisation
EAP: Environmental Assessment Practitioner
ECO: Environmental Control Officer
EIA: Environmental Impact Assessment*
EIA: Early Iron Age*
EIA Practitioner: Environmental Impact Assessment Practitioner
EMPr: Environmental Management Programme
ESA: Early Stone Age
ESIA: Environmental and Social Impact Assessment
GIS Geographical Information System
GPS: Global Positioning System
GRP Grave Relocation Plan
HIA: Heritage Impact Assessment
LIA: Late Iron Age
LSA: Late Stone Age
MEC: Member of the Executive Council
MIA: Middle Iron Age
MPRDA: Mineral and Petroleum Resources Development Act, 2002 (Act No. 28 of 2002)
MSA: Middle Stone Age
NEMA National Environmental Management Act, 1998 (Act No. 107 of 1998)
NHRA National Heritage Resources Act, 1999 (Act No. 25 of 1999)
NID Notification of Intent to Develop
NoK Next-of-Kin
PRHA: Provincial Heritage Resource Agency
SADC: Southern African Development Community
SAHRA: South African Heritage Resources Agency

*\*Although EIA refers to both Environmental Impact Assessment and the Early Iron Age both are internationally accepted abbreviations and must be read and interpreted in the context it is used.*

**GLOSSARY**

Archaeological site (remains of human activity over 100 years old)

Early Stone Age (~ 2.6 million to 250 000 years ago)

Middle Stone Age (~ 250 000 to 40-25 000 years ago)

Later Stone Age (~ 40-25 000, to recently, 100 years ago)

The Iron Age (~ AD 400 to 1840)

Historic (~ AD 1840 to 1950)

Historic building (over 60 years old)

## 1 Introduction and Terms of Reference:

Beyond Heritage was appointed to conduct a Heritage Impact Assessment (HIA) for the proposed development of a township on the Remainder of Portion 3 of the Farm Naboomspruit 348 KR, in Limpopo Province (Figure 1.1 to 1.3). The report forms part of the Basic Assessment Report (BAR) and Environmental Management Programme Report (EMPr) for the development.

The aim of the study is to survey the proposed development footprint to identify cultural heritage sites, document, and assess their importance within local, provincial, and national context. It serves to assess the impact of the proposed project on non-renewable heritage resources, and to submit appropriate recommendations with regard to the responsible cultural resources management measures that might be required to assist the developer in managing the discovered heritage resources in a responsible manner. It is also conducted to protect, preserve, and develop such resources within the framework provided by the National Heritage Resources Act of 1999 (Act No 25 of 1999). The report outlines the approach and methodology utilized before and during the survey, which includes Phase 1, review of relevant literature; Phase 2, the physical surveying of the area on foot and by vehicle; Phase 3, reporting the outcome of the study.

During the survey, no sites of significance were recorded. General site conditions and features on sites were recorded by means of photographs, GPS locations and site descriptions. Possible impacts were identified and mitigation measures are proposed in the following report. SAHRA as a commenting authority under section 38(8) of the National Heritage Resources Act, 1999 (Act No. 25 of 1999) require all environmental documents, compiled in support of an Environmental Authorisation application as defined by NEMA EIA Regulations section 40 (1) and (2), to be submitted to SAHRA for commenting. Upon submission to SAHRA the project will be automatically given a case number as reference. As such the EIA report and its appendices must be submitted to the case as well as the EMPr, once it's completed by the Environmental Assessment Practitioner (EAP).

### 1.1 Terms of Reference

#### Field study

Conduct a field study to: (a) locate, identify, record, photograph and describe sites of archaeological, historical or cultural interest; b) record GPS points of sites/areas identified as significant areas; c) determine the levels of significance of the various types of heritage resources affected by the proposed development.

#### Reporting

Report on the identification of anticipated and cumulative impacts the operational units of the proposed project activity may have on the identified heritage resources for all 3 phases of the project; i.e., construction, operation and decommissioning phases. Consider alternatives, should any significant sites be impacted adversely by the proposed project. Ensure that all studies and results comply with the relevant legislation, SAHRA minimum standards and the code of ethics and guidelines of ASAPA.

To assist the developer in managing the discovered heritage resources in a responsible manner, and to protect, preserve, and develop them within the framework provided by the National Heritage Resources Act of 1999 (Act No 25 of 1999).

## 1.2 Project Description

Project components and the location of the proposed township development are outlined under Table 2 and 3.

**Table 2. Project Description**

<b>Farm and Magisterial District</b>	Remainder of Portion 3 of the Farm Naboomspruit 348 KR, Waterberg District municipality.
<b>Central co-ordinate of the development</b>	28° 43'01.59"E; 24°31' 25.52"S.
<b>Topographic Map Number</b>	2428 DA

**Table 3. Infrastructure and project activities**

<b>Type of development</b>	Township Development
<b>Size of development</b>	The site is approximately 9.5 hectares in extent.
<b>Project Components</b>	<p>The proposed development entails 91 stands / sites for:</p> <ul style="list-style-type: none"> <li>• 85 Residential 1 (dwelling house)</li> <li>• Institutional (orphanage and early childhood development centre)</li> <li>• 1 Business 1 (shops and other business related uses)</li> <li>• 1 Place of Public Worship</li> <li>• 1 Municipal (municipal commonage)</li> <li>• 1 Government (social services offices)</li> </ul>

## 1.3 Alternatives

No alternatives were provided for assessment. The extent of the area assessed allows for siting of the development within this alternative to minimize impacts to heritage resources.






Figure 1.1. Regional setting of the project (1: 250 000 topographical map).



**Legend**

Study Area



REFERENCE	
Coordinate System: GCS Hartebeesthoek 1994	
CLIENT	
LEAGOENVIRO	
TITLE	
Township establishment on the Remainder of Portion 3 of the Farm Naboomspruit 348 KR	
PROJECT No. 2270	REV 1
SCALE 1:11,090	A3
GIS	JVDW 5/18/2022

Figure 1.2. Local setting of the project (1: 50 000 topographical map).




Figure 1.3. Aerial image showing developments in the study area.

## 2 Legislative Requirements

The HIA, as a specialist sub-section of the EIA, is required under the following legislation:

- National Heritage Resources Act (NHRA), Act No. 25 of 1999
- National Environmental Management Act (NEMA), Act No. 107 of 1998 - Section 23(2)(b)
- Mineral and Petroleum Resources Development Act (MPRDA), Act No. 28 of 2002 - Section 39(3)(b)(iii)

A Phase 1 HIA is a pre-requisite for development in South Africa as prescribed by SAHRA and stipulated by legislation. The overall purpose of heritage specialist input is to:

- Identify any heritage resources, which may be affected;
- Assess the nature and degree of significance of such resources;
- Establish heritage informants/constraints to guide the development process through establishing thresholds of impact significance;
- Assess the negative and positive impact of the development on these resources; and
- Make recommendations for the appropriate heritage management of these impacts.

The HIA should be submitted, as part of the impact assessment report or EMPr, to the PHRA if established in the province or to SAHRA. SAHRA will ultimately be responsible for the evaluation of Phase 1 HIA reports upon which review comments will be issued. 'Best practice' requires Phase 1 HIA reports and additional development information, as per the impact assessment report and/or EMPr, to be submitted in duplicate to SAHRA after completion of the study. SAHRA accepts Phase 1 HIA reports authored by professional archaeologists, accredited with ASAPA or with a proven ability to do archaeological work.

Minimum accreditation requirements include an Honours degree in archaeology or related discipline and 3 years post-university CRM experience (field supervisor level). Minimum standards for reports, site documentation and descriptions are set by ASAPA in collaboration with SAHRA. ASAPA is based in South Africa, representing professional archaeology in the SADC region. ASAPA is primarily involved in the overseeing of ethical practice and standards regarding the archaeological profession. Membership is based on proposal and secondment by other professional members.

Phase 1 HIA's are primarily concerned with the location and identification of heritage sites situated within a proposed development area. Identified sites should be assessed according to their significance. Relevant conservation or Phase 2 mitigation recommendations should be made. Recommendations are subject to evaluation by SAHRA.

Conservation or Phase 2 mitigation recommendations, as approved by SAHRA, are to be used as guidelines in the developer's decision-making process.

Phase 2 archaeological projects are primarily based on salvage/mitigation excavations preceding development destruction or impact on a site. Phase 2 excavations can only be conducted with a permit, issued by SAHRA to the appointed archaeologist. Permit conditions are prescribed by SAHRA and includes (as minimum requirements) reporting back strategies to SAHRA and deposition of excavated material at an accredited repository.

In the event of a site conservation option being preferred by the developer, a site management plan, prepared by a professional archaeologist and approved by SAHRA, will suffice as minimum requirement.

After mitigation of a site, a destruction permit must be applied for with SAHRA by the applicant before development may proceed.

Human remains older than 60 years are protected by the National Heritage Resources Act, with reference to Section 36. Graves older than 60 years, but younger than 100 years fall under Section 36 of Act 25 of 1999 (National Heritage Resources Act), as well as the Human Tissues Act (Act 65 of 1983) and are the jurisdiction of SAHRA. The procedure for Consultation Regarding Burial Grounds and Graves (Section 36[5]) of Act 25 of 1999 is applicable to graves older than 60 years that are situated outside a formal cemetery administrated by a local authority. Graves in this age category, located inside a formal cemetery administrated by a local authority, require the same authorisation as set out for graves younger than 60 years, in addition to SAHRA authorisation. If the grave is not situated inside a formal cemetery, but is to be relocated to one, permission from the local authority is required and all regulations, laws and by-laws, set by the cemetery authority, must be adhered to.

Human remains that are less than 60 years old are protected under Section 2(1) of the Removal of Graves and Dead Bodies Ordinance (Ordinance No. 7 of 1925), as well as the Human Tissues Act (Act 65 of 1983) and are the jurisdiction of the National Department of Health and the relevant Provincial Department of Health and must be submitted for final approval to the office of the relevant Provincial Premier. This function is usually delegated to the Provincial MEC for Local Government and Planning; or in some cases, the MEC for Housing and Welfare. Authorisation for exhumation and reinternment must also be obtained from the relevant local or regional council where the grave is situated, as well as the relevant local or regional council to where the grave is being relocated. All local and regional provisions, laws and by-laws must also be adhered to. To handle and transport human remains, the institution conducting the relocation should be authorised under Section 24 of Act 65 of 1983 (Human Tissues Act).

### 3 METHODOLOGY

#### 3.1 Literature Review

A brief survey of available literature was conducted to extract data and information on the area in question to provide general heritage context into which the development would be set. This literature search included published material, unpublished commercial reports and online material, including reports sourced from the South African Heritage Resources Information System (SAHRIS).

#### 3.2 Genealogical Society and Google Earth Monuments

Google Earth and 1:50 000 maps of the area were utilised to identify possible places where sites of heritage significance might be located; these locations were marked and visited during the fieldwork phase. The database of the Genealogical Society was consulted to collect data on any known graves in the area.

#### 3.3 Public Consultation and Stakeholder Engagement:

Stakeholder engagement is a key component of any EA process, it involves stakeholders interested in, or affected by the proposed development. Stakeholders are provided with an opportunity to raise issues of concern (for the purposes of this report only heritage related issues will be included). The aim of the public consultation process was to capture and address any issues raised by community members and other stakeholders during key stakeholder and public meetings.

### 3.4 Site Investigation

The aim of the site visit was to:

- a) survey the proposed project area to locate, identify, record, photograph and describe sites of archaeological, historical or cultural interest;
- b) record GPS points of sites/areas identified as significant areas;
- c) determine the levels of significance of the various types of heritage resources recorded in the project area.

**Table 4. Site Investigation Details**

	Site Investigation
Date	10 May 2022
Season	Autumn– Accessibility within the proposed project area was compromised due to waterlogged areas as well impenetrable vegetation cover. The general area was however sufficiently covered to understand the heritage character of the area (Figure 3.1).




Figure 3.1. Tracklog of the survey path in green.

### 3.5 Site Significance and Field Rating

Section 3 of the NHRA distinguishes nine criteria for places and objects to qualify as ‘part of the national estate’ if they have cultural significance or other special value. These criteria are:

- Its importance in/to the community, or pattern of South Africa’s history;
- Its possession of uncommon, rare or endangered aspects of South Africa’s natural or cultural heritage;
- Its potential to yield information that will contribute to an understanding of South Africa’s natural or cultural heritage;
- Its importance in demonstrating the principal characteristics of a particular class of South Africa’s natural or cultural places or objects;
- Its importance in exhibiting particular aesthetic characteristics valued by a community or cultural group;
- Its importance in demonstrating a high degree of creative or technical achievement at a particular period;
- Its strong or special association with a particular community or cultural group for social, cultural or spiritual reasons;
- Its strong or special association with the life or work of a person, group or organisation of importance in the history of South Africa;
- Sites of significance relating to the history of slavery in South Africa.

The presence and distribution of heritage resources define a ‘heritage landscape’. In this landscape, every site is relevant. In addition, because heritage resources are non-renewable, heritage surveys need to investigate an entire project area, or a representative sample, depending on the nature of the project. In the case of the proposed project the local extent of its impact necessitates a representative sample and only the footprint of the areas demarcated for development were surveyed. In all initial investigations, however, the specialists are responsible only for the identification of resources visible on the surface. This section describes the evaluation criteria used for determining the significance of archaeological and heritage sites. The following criteria were used to establish site significance with cognisance of Section 3 of the NHRA:

- The unique nature of a site;
- The integrity of the archaeological/cultural heritage deposits;
- The wider historic, archaeological and geographic context of the site;
- The location of the site in relation to other similar sites or features;
- The depth of the archaeological deposit (when it can be determined/is known);
- The preservation condition of the sites; and
- Potential to answer present research questions.

In addition to this criteria field ratings prescribed by SAHRA (2006), and acknowledged by ASAPA for the SADC region, were used for the purpose of this report. The recommendations for each site should be read in conjunction with section 10 of this report.

**Table 5. Heritage significance and field ratings**

<b>FIELD RATING</b>	<b>GRADE</b>	<b>SIGNIFICANCE</b>	<b>RECOMMENDED MITIGATION</b>
National Significance (NS)	Grade 1	-	Conservation; national site nomination
Provincial Significance (PS)	Grade 2	-	Conservation; provincial site nomination
Local Significance (LS)	Grade 3A	High significance	Conservation; mitigation not advised
Local Significance (LS)	Grade 3B	High significance	Mitigation (part of site should be retained)
Generally Protected A (GP. A)	-	High/medium significance	Mitigation before destruction
Generally Protected B (GP. B)	-	Medium significance	Recording before destruction
Generally Protected C (GP.C)	-	Low significance	Destruction

### 3.6 Impact Assessment Methodology

The criteria below are used to establish the impact rating on sites:

- The **nature**, which shall include a description of what causes the effect, what will be affected and how it will be affected.
- The **extent**, wherein it will be indicated whether the impact will be local (limited to the immediate area or site of development) or regional, and a value between 1 and 5 will be assigned as appropriate (with 1 being low and 5 being high):
- The **duration**, wherein it will be indicated whether:
  - \* the lifetime of the impact will be of a very short duration (0-1 years), assigned a score of 1;
  - \* the lifetime of the impact will be of a short duration (2-5 years), assigned a score of 2;
  - \* medium-term (5-15 years), assigned a score of 3;
  - \* long term (> 15 years), assigned a score of 4; or
  - \* permanent, assigned a score of 5;
- The **magnitude**, quantified on a scale from 0-10 where; 0 is small and will have no effect on the environment, 2 is minor and will not result in an impact on processes, 4 is low and will cause a slight impact on processes, 6 is moderate and will result in processes continuing but in a modified way, 8 is high (processes are altered to the extent that they temporarily cease), and 10 is very high and results in complete destruction of patterns and permanent cessation of processes.
- The **probability of occurrence**, which shall describe the likelihood of the impact actually occurring. Probability will be estimated on a scale of 1-5 where; 1 is very improbable (probably will not happen), 2 is improbable (some possibility, but low likelihood), 3 is probable (distinct possibility), 4 is highly probable (most likely) and 5 is definite (impact will occur regardless of any prevention measures).
- The **significance**, which shall be determined through a synthesis of the characteristics described above and can be assessed as low, medium or high; and
- the **status**, which will be described as either positive, negative or neutral.
- the degree to which the impact can be reversed.
- the degree to which the impact may cause irreplaceable loss of resources.
- the *degree* to which the impact can be mitigated.

The **significance** is calculated by combining the criteria in the following formula:

$$S=(E+D+M) P$$

S = Significance weighting

E = Extent

D = Duration

M = Magnitude

P = Probability

The **significance weightings** for each potential impact are as follows:

- < 30 points: Low (i.e., where this impact would not have a direct influence on the decision to develop in the area),
- 30-60 points: Medium (i.e., where the impact could influence the decision to develop in the area unless it is effectively mitigated),
- 60 points: High (i.e., where the impact must have an influence on the decision process to develop in the area).

### 3.7 Limitations and Constraints of the study

The authors acknowledge that the brief literature review is not exhaustive on the literature of the area. Due to the nature of heritage resources and pedestrian surveys, the possibility exists that some features or artefacts may not have been discovered/recorded and the possible occurrence of graves and other cultural material cannot be excluded. This report only deals with the footprint area of the proposed development and consisted of non-intrusive surface surveys. This study did not assess the impact on medicinal plants and intangible heritage as it is assumed that these components would have been highlighted through the public consultation process if relevant. It is possible that new information could come to light in future, which might change the results of this Impact Assessment.

## 4 Description of Socio-Economic Environment

StatsSA indicates that according to Census 2011, of the 35 640 people in Mookgophong 85,6% are black African, 13,2% are white, with the other population groups making up the remaining 1,2%. Most of those aged 20 years and older (37,7%) have some secondary education, 23,2% have completed matric, 19,8% have some primary education and 7,3% have some form of higher education. Of the mentioned age group, 12,0% have no form of schooling. Of the 15 791 economically active (employed or unemployed but looking for work) people in the municipality, 23,5% are unemployed. 29,2% of the 8 654 economically active youth (15–35 years) in the area are unemployed. Agricultural activities include cattle, poultry, game, maize, wheat, sunflower, grapes, citrus and vegetables.

## 5 Results of Public Consultation and Stakeholder Engagement:

### 5.1.1 Stakeholder Identification

Adjacent landowners and the public at large will be informed of the proposed activity as part of the BA process by the EAP. Site notices and advertisements notifying interested and affected parties will be placed at strategic points and in local newspapers as part of the process. No heritage concerns have been raised thus far.

## 6 Literature / Background Study:

### 6.1 Literature Review (SAHRIS)

Several Cultural Resource Management studies were conducted in the Mookgopong area. Pistorius (2001) recorded no sites of significance; Kusel (2007) recorded a late Iron Age site, two engraving sites, an initiation site and numerous graves. Roodt (2000 & 2005) recorded Middle Stone Age flakes as well as undecorated pottery associated with the Iron Age.

The archaeological database at Wits has 19 sites on record for the 2428 DA 1: 50 000 map. These sites consist of Early and Middle Stone Age sites close to Mokopane and Late Iron Age sites close to Modimolle. None of these sites are located close to the project site.

#### 6.1.1 Google Earth and The Genealogical Society of South Africa (Graves and burial sites)

Google Earth and 1:50 000 maps of the area were utilised to identify possible places where archaeological and historical sites might be located. The database of the Genealogical Society of South Africa indicated no known grave sites within the study area

### 6.2 Archaeological Background

South Africa has one of the longest archaeological sequences in the world because humanity evolved in the area stretching from the Cape to Ethiopia. Most of this sequence covers the times when our ancestors used stone tools. It is worthwhile, thus, to review the archaeological record for southern Africa and to place in context the known occurrences. The archaeology of the area can be divided into the Stone Age, Iron Age and Historical timeframe. These can be divided as follows:

#### 6.2.1 Stone Age

The Stone Age is divided in the Early; Middle and Late Stone Age. It refers to the earliest people of South Africa who mainly relied on stone for their tools.

**Earlier Stone Age:** The period from  $\pm 2.5$  million yrs. -  $\pm 250\,000$  yrs. ago. Acheulean stone tools are dominant. No Acheulean sites are on record near the study area, but isolated finds may be possible, however, isolated finds have little value. Therefore, the project is unlikely to disturb a site of significance.

**Middle Stone Age:** The Middle Stone Age includes various lithic industries in SA dating from  $\pm 250\,000$  yrs. – 25 000 yrs. before present. This period is first associated with archaic *Homo sapiens* and later *Homo sapiens sapiens*. Material culture includes stone tools with prepared platforms and stone tools attached to handles.

**Later Stone Age:** The period from  $\pm 25\,000$ -yrs before present to the period of contact with either Iron Age farmers or European colonists. This period is associated with *Homo sapiens sapiens*. Material culture from this period includes: microlithic stone tools; ostrich eggshell beads and rock art. Sites located in the open are usually poorly preserved and therefore have less value than sites in caves or rock shelters.

A Single ESA site is on record near the project area at the Wits archaeological database, and isolated finds are possible. However, isolated finds have little value. Therefore, the project is unlikely to disturb a significant site. Important LSA deposits have been excavated in Oliboompoort Cave (Mason, 1962) and other sites in the Waterberg to the north (Van der Ryst, 1998). Sites in the open are usually poorly preserved and therefore have less value than sites in caves or rock shelters.

### 6.2.2 Iron Age (general)

The Iron Age as a whole represents the spread of Bantu speaking people and includes both the pre-Historic and Historic periods. It can be divided into three distinct periods:

- The Early Iron Age: Most of the first millennium AD.
- The Middle Iron Age: 10th to 13th centuries AD
- The Late Iron Age: 14th century to colonial period.

The Iron Age is characterised by the ability of these early people to manipulate and work Iron ore into implements that assisted them in creating a favourable environment to make a better living.




Figure 6.1: Movement of Bantu speaking farmers (Huffman 2007)

According to the most recent archaeological cultural distribution sequences by Huffman (2007), the study area falls within the distribution area of various cultural groupings originating out of both the Urewe Tradition (eastern stream of migration) and the Kalundu Tradition (western stream of migration). The facies that may be present are:

- Urewe Tradition: Moloko Branch – Icon facies AD 1300 - 1500 (Late Iron Age)
- Madikwe facies AD 1500-1700 (Late Iron Age)
- Blackburn Branch- Uitkomst facies AD 1650-1820 (Late Iron Age)
- Rooiberg facies AD 1650-1750 (Late Iron Age)
- Kwale branch- Mzonjani facies AD 450 – 750 (Early Iron Age)
- Kalunda Tradition: Benfica sub-branch – Bambata facies AD 150-650 (Early Iron Age)
- Happy Rest sub-branch – Diamant facies AD 750-1000 (Early Iron Age)
- Eiland facies AD 1000-1300 (Middle Iron Age)

### **6.2.3 Historical Background**

Mookgopong was initially a rest stop between Pretoria and Polokwane and in 1910 Tin was discovered in the area where Mookgopong is located today and subsequently taverns and stores were established to cater for the miners that streamed into the district. These activities led to the establishment of the town formerly known as Naboomspruit (Pistorius 2001).

## 7 Description of the Physical Environment

The project area is situated on the southern edge of town of Mookghopong in the Limpopo Province. The site is bordered on the north east by 1<sup>st</sup> street on the south by 3<sup>rd</sup> Avenue and on the east by a unnamed road. The project area currently has a closed dumping site and two community centres being Mookgophong Social Development and the Phomolong Early Childhood Development while the rest of the property is fallow and used for illegal dumping and previous activities that could have been a laydown area, marked by water pipes etc. The surrounding environment is mainly dominated by existing township and industrial centre of the town. The project area is overgrown with pioneer species like sicklebush (*Dichrostachys*). Waterlogged areas and the impenetrable vegetation cover severely limited heritage visibility and access in the area.



Figure 7.1. Entrance to existing developments in the area (Mookgophong Social Development) .



Figure 7.2. Existing developments in the area (Phomolong Early Childhood Development Centre).



Figure 7.3. Old laydown area marked by pipes.



Figure 7.4. Dense vegetation cover limited accessibility.

## 8 Findings of the Survey

### 8.1 Heritage Resources

The study area was assessed by a non-intrusive pedestrian survey. The project area currently has a closed dumping site and two community centres being Mookgophong Social Development and the Phomolong Early Childhood Development while the rest of the property is fallow and used for illegal dumping. Most of the site has been altered by previous clearing and levelling activities (Figure 8.2 & 8.3) and no structures, graves or heritage finds of significance was recorded during the survey.

### 8.2 Cultural Landscape

The study area is in a rural setting with no developments older than 60 years within the impact area (Figure 8.1) and is currently largely undeveloped apart from two community centres being Mookgophong Social Development and the Phomolong Early Childhood Development.




Figure 8.1. 1965 Topographic map of the study area indicating no developments older than 60 years in the study area. Structures, train station and a cemetery are indicated in the wider area.



Figure 8.2. 2003 Google Earth image showing cleared areas in the northern section of the project area.



Figure 8.3. 2012 Google Earth image showing cleared areas in the north and south of the project area.

### 8.3 Paleontological Heritage

According to the SAHRA Paleontological map the study area is of insignificant sensitivity, and it is recommended that this project be exempt from any further palaeontological impact assessment.



Colour	Sensitivity	Required Action
RED	VERY HIGH	Field assessment and protocol for finds is required
ORANGE/YELLOW	HIGH	Desktop study is required and based on the outcome of the desktop study, a field assessment is likely
GREEN	MODERATE	Desktop study is required
BLUE	LOW	No palaeontological studies are required however a protocol for finds is required
GREY	INSIGNIFICANT/ZERO	No palaeontological studies are required
WHITE/CLEAR	UNKNOWN	These areas will require a minimum of a desktop study. As more information comes to light, SAHRA will continue to populate the map

Figure 8.4. Paleontological sensitivity of the approximate study area (yellow polygon) as indicated on the SAHRA Palaeontological sensitivity map.

## 9 Potential Impact

No heritage sites of significance occur within the impact area and no adverse impact to heritage resources is expected. Any additional effects to subsurface heritage resources can be successfully mitigated by implementing a Chance Find Procedure. Mitigation measures as recommended in this report should be implemented during all phases of the project. Impacts of the project on heritage resources is expected to be low during all phases of the development (Table 7).

### 9.1.1 Pre-Construction phase

It is assumed that the pre-construction phase involves the removal of topsoil and vegetation as well as the establishment of infrastructure. These activities can have a negative and irreversible impact on heritage features if any occur. Impacts include destruction or partial destruction of non-renewable heritage resources.

### 9.1.2 Construction Phase

During this phase, the impacts and effects are similar in nature but more extensive than the pre-construction phase. Potential impacts include destruction or partial destruction of non-renewable heritage resources.

### 9.1.3 Operation Phase

No impacts are expected during the operation phase.

### 9.1.4 Impact Assessment for the Project

**Table 6. Impact assessment of the proposed project.**

<b>Nature:</b> During the construction phase activities resulting in disturbance of surfaces and/or sub-surfaces may destroy, damage, alter, or remove from its original position archaeological and paleontological material or objects.		
	<b>Without mitigation</b>	<b>With mitigation (Preservation/ excavation of site)</b>
<b>Extent</b>	Local (2)	Local (2)
<b>Duration</b>	Permanent (5)	Permanent (5)
<b>Magnitude</b>	Minor (2)	Minor (2)
<b>Probability</b>	Improbable (2)	Improbable (2)
<b>Significance</b>	<b>18 (Low)</b>	<b>18 (Low)</b>
<b>Status (positive or negative)</b>	Negative	Negative
<b>Reversibility</b>	Not reversible	Not reversible
<b>Irreplaceable loss of resources?</b>	Yes	Yes
<b>Can impacts be mitigated?</b>	NA	NA
<b>Mitigation:</b>		
<ul style="list-style-type: none"> <li>• Implementation of a Chance Find Procedure for the project;</li> <li>• Monitoring of the development footprint by the ECO</li> </ul>		
<b>Cumulative impacts:</b>		
The proposed project will have a low cumulative impact as no known heritage resources will be adversely affected.		
<b>Residual Impacts:</b>		
Although surface sites can be avoided or mitigated, there is a chance that completely buried sites would still be impacted on, but this cannot be quantified.		

## 10 Conclusion and recommendations

The area has been altered and impacted on by surrounding road development, clearing and levelling of the study area in the past. Examination of historical topographic maps and aerial images showed no structures or stone walled settlements in the study area and the impact footprint is considered to be of low heritage potential. This was confirmed during the site visit and no heritage finds of significance was recorded during the survey. According to the SAHRA Paleontological sensitivity map the study area is of insignificant paleontological significance and no further studies are required for this aspect.

No adverse impact on heritage resources is expected by the project and it is recommended that the project can commence on the condition that the following recommendations (Section 10) are implemented as part of the EMP and based on approval from SAHRA.

### 10.1 Recommendations for condition of authorisation

The following recommendations for Environmental Authorisation apply and the project may only proceed based on approval from SAHRA:

#### Recommendations:

- Implementation of a Chance Find Procedure for the project (as outlined in Section 10.2).
- Monitoring of the development footprint by the ECO.

### 10.2 Chance Find Procedures

#### 10.2.1 Heritage Resources

The possibility of the occurrence of subsurface finds cannot be excluded. Therefore, if during construction any possible finds such as stone tool scatters, artefacts or bone and fossil remains are made, the operations must be stopped, and a qualified archaeologist must be contacted for an assessment of the find and therefore chance find procedures should be put in place as part of the EMP. A short summary of chance find procedures is discussed below and monitoring guidelines for this procedure are provided in Section 10.5.

This procedure applies to the developer's permanent employees, its subsidiaries, contractors and subcontractors, and service providers. The aim of this procedure is to establish monitoring and reporting procedures to ensure compliance with this policy and its associated procedures. Construction crews must be properly inducted to ensure they are fully aware of the procedures regarding chance finds as discussed below.

- If during the pre-construction phase, construction, operations or closure phases of this project, any person employed by the developer, one of its subsidiaries, contractors and subcontractors, or service provider, finds any artefact of cultural significance or heritage site, this person must cease work at the site of the find and report this find to their immediate supervisor, and through their supervisor to the senior on-site manager.
- It is the responsibility of the senior on-site Manager to make an initial assessment of the extent of the find and confirm the extent of the work stoppage in that area.
- The senior on-site Manager will inform the ECO of the chance find and its immediate impact on operations. The ECO will then contact a professional archaeologist for an assessment of the finds who will notify the SAHRA.

### 10.3 Reasoned Opinion

The overall impact of the project is considered to be low and residual impacts can be managed to an acceptable level through implementation of the recommendations made in this report. The socio-economic

benefits also outweigh the possible impacts of the development if the correct mitigation measures are implemented for the project.

#### **10.4 Potential risk**

Potential risks to the proposed project are the occurrence of intangible features and unrecorded cultural resources (of which graves are the highest risk). This can cause delays during construction, as well as additional costs involved in mitigation and possible layout changes.

**10.5 Monitoring Requirements**

Day to day monitoring can be conducted by the Environmental Control Officers (ECO). The ECO or other responsible persons should be trained along the following lines:

- *Induction training:* Responsible staff identified by the developer should attend a short course on heritage management and identification of heritage resources.
- *Site monitoring and watching brief:* As most heritage resources occur below surface, all earth-moving activities need to be routinely monitored in case of accidental discoveries. The greatest potential impacts are from pre-construction and construction activities. The ECO should monitor all such activities daily. If any heritage resources are found, the chance finds procedure must be followed as outlined above.

**Table 7. Monitoring requirements for the project**

Heritage Monitoring					
Aspect	Area	Responsible for monitoring and measuring	Frequency	Proactive or reactive measurement	Method
Cultural Heritage Resources	Entire project area	ECO	Weekly (Pre construction and construction phase)	Proactively	<ul style="list-style-type: none"> <li>• If risks are manifested (accidental discovery of heritage resources) the chance find procedure should be implemented:                             <ol style="list-style-type: none"> <li>1. Cease all works immediately;</li> <li>2. Report incident to the Sustainability Manager;</li> <li>3. Contact an archaeologist/ palaeontologist to inspect the site;</li> <li>4. Report incident to the competent authority; and</li> <li>5. Employ reasonable mitigation measures in accordance with the requirements of the relevant authorities.</li> </ol> </li> <li>• Only recommence operations once impacts have been mitigated.</li> </ul>

**10.6 Management Measures for inclusion in the EMPr**

**Table 8. Heritage Management Plan for EMPr implementation**

Area	Mitigation measures	Phase	Timeframe	Responsible party for implementation	Target	Performance indicators (Monitoring tool)
General project area	Implement chance find procedures in case possible heritage finds are uncovered	Construction	Throughout the project	Applicant EAP	Ensure compliance with relevant legislation and recommendations from SAHRA under Section 35, 36 and 38 of NHRA	ECO Checklist/Report
General project area	Regular Monitoring by the ECO	Construction	Throughout the project	Applicant EAP	Ensure compliance with relevant legislation and recommendations from SAHRA under Section 35, 36 and 38 of NHRA	ECO Checklist/Report

### **10.7 Knowledge Gaps**

Due to the altered character of the study area, the often-ephemeral nature of heritage resources and accessibility constraints the possibility of discovery of heritage resources during the construction phase cannot be excluded. This limitation is successfully mitigated with the implementation of a chance find procedure and monitoring of the study area by the ECO.

## 11 References

- Berg, J.S. (Ed)., Geskiedenisatlas van Suid-Afrika. Die vier noordelike provinsies. Edited by J. S. Bergh. 1999. Pretoria: J. L. van Schaik Uitgewers.
- Bulpin, T.V., 1989: Lost Trails of the Transvaal. Books of Africa (Pty) Ltd, Johannesburg.
- Deacon, H.J. & Deacon, J. 1999. Human Beginnings in South Africa: Uncovering the Secrets of the Stone Age. Cape Town: David Phillips Publishers.
- De Vaal, J.B. Ou Handelsvoetpaaie deur die Laeveld in U. De V. Pienaar, 1990: Neem uit die Verlede. Nasionale Parkeraad van Suid-Afrika, Pretoria.
- De Vaal, J.B. Coenraad de Buys – renegaat en baanbreker van Soutpansberg in U. De V. Pienaar, 1990: Neem uit die Verlede. Nasionale Parkeraad van Suid-Afrika, Pretoria.
- Huffman, T.N. 1982. Archaeology and ethnohistory of the African Iron Age. Annual Review of Anthropology 11: 133-50.
- Huffman, T.N. 2007. Handbook to the Iron Age: The Archaeology of Pre-Colonial Farming Societies in Southern Africa. University of KwaZulu-Natal Press, Scottsville.
- Kuman, K., 1998. The earliest South African Industries. In: *Lower Palaeolithic Settlement of the Old World*. Eds by M.D. Petraglia and R. Korisetter, pp 151-186. Routledge Press, London.
- Kusel, U. 2007. Cultural Heritage Resources Impact Assessment Of The Farms Groothoek 220 Kr, Nyhoffsbul 231 Kr And Zwartkop 219 Kr Sterkrivier Naboomspruit Limpopo
- Lewis-Williams, J.D., 1981. *Believing and Seeing: Symbolic Meanings in southern San Rock Paintings*. Academic Press, London.
- Mason, J.R. 1962. *The Prehistory of the Transvaal*. Johannesburg: Witwatersrand University Press.
- Mitchell, P. 2002. The Archaeology of Southern Africa. Cambridge: Cambridge University Press.
- Mucina, L. & Rutherford, M.C. 2006. The vegetation map of South Africa, Lesotho and Swaziland. SANBI, Pretoria.
- National Heritage Resources Act NHRA of 1999 (Act 25 of 1999)
- Pistorius, J.C.C. 2001. A Phase 1 Archaeological Survey for the proposed new 132 Kv Transmission line between the Boekenhoutfontein substation and the Naboomspruit substation in the Northern Province of South Africa.
- Roodt, F. 2000. Archaeological Impact Assessment Naboomspruit waste disposal site, Vlakfontein, Northern Province.
- Roodt, F. 2005. Phase 1 Heritage Impact Assessment Township establishment Naboomspruit Ext 4, Mookgopong Portions 37 – 43 of the Farm Vlakfontein 522 KR.
- Ross, R. 2002. A concise history of South Africa. Cambridge: Cambridge University Press.
- SAHRA Report Mapping Project Version 1.0, 2009
- Van der Ryst, M.M., 1998. *The Waterburg Plateau in the Northern Province, Republic of South Africa, in the Later Stone Age*. BAR International Series 715, Oxford.
- Van der Ryst, M.M., 2006. *Seeking Shelter: Later Stone Age Hunters, Gatherers and Fishers of Oliboompoort in the western Waterberg south of the Limpopo*. Unpublished doctoral thesis, University of the Witwatersrand, Johannesburg