

**R1011 - Roodeplaat Wind Farm
Estimated Water Demand for Construction**



	Length (m)	Layerworks (mm)	Width (m)	Earthworks Volume (m ³)
A) Roads Earthworks				
Good Prov & internal roads	20 424	150	8	24 509
Poor Prov & internal roads	4 549	300	8	10 918
New Internal Roads	23 985	450	6	64 760
Road layerwork volume =				100 186 m ³

Water = approx 10% / volume
based on 2200kg/m³ =

220 l / m³

Total water for roads =

22 041 kl

Construction period =

12 months

Water demand =

1 837 kl / month

@ 22 d / month

83 kl / day

15kl Water tanker trucks per day =

5.6 trucks / day

B) Platforms Earthworks

length =	75	65	m
width =	35		m
layerworks =	900		mm
number of platforms =	46		WTGs
Platform layerwork volume =	101 430		m ³

Water - approx 10% / volume
based on say 2200kg/m³ =
(will differ with insitu OMC etc.)

220 l / m³

Total water for platforms =

22 315 kl

Construction period =

16 months

Water demand =

1 395 kl / month

@ 22 d / month

63 kl / day

15kl Water tanker trucks per day =

4.2 trucks / day

C) Foundation Earthworks

diameter =	20 m
layerworks =	300 mm
number of platforms =	46 WTGs
Platform layerwork volume =	4 335 m ³

Water - approx 10% / volume
based on say 2200kg/m³ =
(will differ with insitu OMC etc.)

220 l / m³

Total water for foundations =

954 kl

Construction period =

16 months

Water demand =

60 kl / month

@ 22 d / month

2.7 kl / day

15kl Water tanker trucks per day =

0.2 trucks / day

Total Estimated Water Demand

Total Water demand (A+B+C) =	45 309 kl	
Total Water consumption =	150 kl / day	[Estimated storage required]
Total Water Abstraction Rate =	2.60 l/s	(based at 16h pump per day)
15kl Water tanker trucks per day (average) =	10.0 trucks / day	[Peak Demand]

R1011 - Roodeplaat Wind Farm



Estimated Water Demand for Construction

Concrete requirements :

Construction Period	16	months
Foundations (number off)	46	WTGs
Concrete / foundation	550	m ³
Concrete total m³	25 300	m³
concrete m ³ / month	1581	m ³ / month
litre water / m ³ concrete	200	liter

Total Estimated Water Demand

Total Water demand =	5060	kl
Total Water consumption =	316	kl / month
@ 22 d / month	14.4	kl / day [Estimated storage required]
Total Water Abstraction Rate =	0.25	l/s (based at 16h pump p/d)
15kl Water tanker trucks per day (average) =	1.0	trucks / day

R1011 - Roodeplaat Wind Farm



Estimated Water Demand for Staff Accommodation

Water Consumption requirements :

	Peak Period	Off-Peak Period	
	16	8	months
Workers living on site during construction	200	50	
Water demand for "On-site" staff	120	120	litre pppd
Total	24.0	6.0	kl / day
Workers traveling to site during construction	100	30	
Water demand for "Off-site" staff	40	40	litre pppd
	4.0	1.2	kl / day

Total Estimated Water Demand

Total Water demand =	14 579	kl	
Total Water consumption =	808	kl / month (peak)	
Total Water consumption =	26.9	kl / day (peak)	[Estimated storage required]
Total Water Abstraction Rate =	0.47	l/s (based at 16h pump p/d)	