

Dear Mr Mfanekiso

Below is a listing of all the work that will take place on Robben Island as per the proposals, submitted to Council and to Manco. It is important to emphasize that the proposed installations and video stations will be permanent. All additions for exhibition purposes will be designed to be removable. Below are the specifications for restoration as per the brief given to prospective contractors.

Murray's Harbour wall 1

Careful removal of billboards on wall
Filling of Holes after billboard removal
Sealing of plaster on Wall

Blue stone Cladding and Installation:

To recreate a section of the original wall. Approx. 16 Square metres
Construct an installation of the bluestone with tools displayed

Repair of Jetty Floor

Remove damaged section and Re-plaster.

Harbour Buildings

Repainting of painted Walls,
Sanding and varnishing of wooden Window frames and doors.
Replacement of Lintels,
sanding and painting Fascia boards,
Make good

Wall 2 (Bluestone clad Wall leading from Harbour Masters Office to Dankie Hek 1)

Careful removal of all the billboards on the wall
Removal and (neatening) of electrical cables, poles and lights
Restore pointing where needed
Repair holes in the wall with suitable aggregate or bluestone
Repair bluestone lintel above plaque
Replace missing slabs on wall top

Visitors Centre

Restore metal window pane,
Careful removal of posters and wooden box display
Refitting of box display on adjacent wall.
Repair and paint
Make Good

Dankie Hek 1

Seal metal window bars
Repair and paint interior

Linda Penicela 17/10/11 10:28 AM

Comment: Requires permit pictures of the position, specifications of construction

Unknown Author 17/10/13 8:39 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:28): "..."
See Attached images for location and artists impression.
The location is to the left of the Harbour masters office. On the adjacent plaster wall.
Wall Dimensions:
15m X 4 m X 400mm
Cladding Dimensions : 16m²
Construction:
The stone used will be existing
Blue stone found discarded adjacent to the harbour in the vicinity of the boardwalk... [1]

Linda Penicela 17/10/11 10:31 AM

Comment: Specifications, square metres of the wall, number of wooden frames
Specification of paints for walls and facias

Unknown Author 17/10/13 8:56 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:31): "..."
Wall Area: 620 m²
Quantities of Windows & Doors:
23 Wood Windows & frames to be sand... [2]

Linda Penicela 17/10/11 10:35 AM

Comment: Length of the wall and height, current pictures
Estimate the areas where pointing is to be done, current pictures
Materials to be used

Unknown Author 17/10/13 10:03 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:35): "..."
Wall Dimensions: 150m X 2.7m
See Attached Document for images.
The areas for pointing can only be asce... [3]

Linda Penicela 17/10/11 10:38 AM

Comment: How may window panes, current pictures
Paint specifications
How many box display to be refitted, pictures

Unknown Author 17/10/13 10:40 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:38): "..."
16 window panes
See attached images
Paint Specs.: Etch primer & Plascon en... [4]

Linda Penicela 17/10/11 10:40 AM

Comment: Paint specifications
Area in square metres to be painted supply current pictures

Unknown Author 17/10/13 10:42 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:40): "..."
See attached images
Interior Wall Paint: Plascon enamel.
Dimensions of painted area: 15m² ... [5]

Make Good

Pathway to MSP

Level existing pathway

Refinish Pathway

slope pathway to curb height (Wheelchair access)

MSP Exterior

Prep and restore Dankie Hek 2

Prep and restore stairs and surrounds

Prep and varnish window frames

Fill and repaint window sills

Armory

Make good

Study room

Make good

Registration Room

Make good

Guard Room (Admin Office)

Make good

Censorship Office

Make good

Watch Gallery

Make good

Spine Corridor floor

Seal with gloss sealant (simulate wax polish)

Restore enamel black strips on sides

Spine Corridor Door (leading to hospital yard)

Repair and refit door

Prep and repaint

Spine Corridor Door (leading to B Block yard)

Make good

B Block Yard

Remove museum boards

Make good

Linda Penicela 17/10/11 10:42 AM

Comment: Paints specification and total area in square metres to be painted
Heritage Consultant to ensure public participation in regards to paint color as per SAHRA 's previous advice
Number of window sills
Number of window frames, type of varnish
Current pictures of all spaces to be painted

Unknown Author 17/10/13 10:44 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:42): "..."

Paint Specs:

Door: Plascon enamel
Steps: Plascon enamel
Fascia Boards: Plascon Acrylic
Window sills: Plascon Acrylic
Frames: Marine grade varnish

Quantities

Sills: 11
Frames: 11
Door: 2
Step area: 26m²
Door area :12m²

Linda Penicela 17/10/11 10:56 AM

Comment: Paint specification and total area to be painted
Current Pictures

Unknown Author 17/10/13 10:51 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:56): "..."

Floor Sealant: Epoxy floor coating for concrete floors
Paint Specs: Plascon enamel
See attached pictures
Dimensions of floor: 32.5m X 1.8m

Linda Penicela 17/10/11 10:57 AM

Comment: Paint specification
Total area to be painted
Current pictures

Unknown Author 17/10/13 10:54 AM

Comment: Reply to Linda Penicela (10/11/2017, 10:57): "..."

Door Paint: Plascon enamel
Door Dimensions: 1.8m X 2.1m

Rust to be removed by sanding and grinding.
Door bullet hinge to be re-welded, an anti-Rust primer (NS4)is to applied prior to application of topcoats.

A Section

Seal flaking paint, make good

B Section

Make good

C Section

Seal flaking paint, make good

Refit yard door and repair intel

Sand and repaint yard window grates

D section

Exterior door and rail: repair rusted galvanizing
make good communal cell

Furthermore, we asked RIM to authorize the following activities that will be undertaken by the different service providers. The tasks are itemized by space. (this list duplicates and specifies further, the activities spelt out above,)

Space	Tasks
NMG	<ol style="list-style-type: none"> 1. Removal of all pictures, posters and objects currently hanging at NMG 2. Installation 'Special Hanging of Ahmed Khathrada's Quotation' 3. Installation of 'Special Hanging of UNESCO statement 4. Removal of Projectors and Video Wall from NMG orientation room 5. Installation of AV system Orientation room 6. Installation of Video in Orientation room 7. Installation of Video in the departure lounge 8. Installation of the timeline 9. Installation video monitors along the departure queue

Linda Penicela 17/10/11 10:58 AM
Comment: Paint specification
 Number of window grates and square metres
 Current pictures

Unknown Author 17/10/13 12:54 PM
Comment: Reply to Linda Penicela (10/11/2017, 10:58): "..."
 Grates to be removed and sandblasted to remove rust, Grates to be primed with anti rust NS4 red oxide and finished in Plascon enamel topcoats.
 Total quantity of window grates: 18
 Front Grates: 26.1 m²
 Back Grates: 11.6m²
 See attached images.

Linda Penicela 17/10/11 11:00 AM
Comment: Current Pictures and specification of rust repair paint

Unknown Author 17/10/13 2:01 PM
Comment: Reply to Linda Penicela (10/11/2017, 11:00): "..."
 See Attached images.
 The ramp rail, will be sanded down,The rust removed and rail primed with NS4 anti rust primer and finished with cold galvanising paint. (95 Zinc Spray)
 The door and bars will be sanded down,The rust removed and prepared with NS4 anti rust primer and finished with Plascon enamel topcoats.

	<p>10. Installation of drapes in the departure lounge</p> <p>11. Installation of sound system for the departure lounge</p>
Ferries	<p>1. Installation of branding paraphernalia for the Ferries</p> <p>2. Installation of sound system and soundscape on the Ferries</p>
Murray's Harbour Wall	<p>1 Removal of the Blue Posters from the walls</p> <p>2. Treatment and restoration of the walls, Harbour building</p> <p>3. Treatment of the Harbour floor to prevent injury</p> <p>4. Removal and (neatening) of electrical cables, poles and lights</p> <p>5. Cementing and fixing of facades.</p> <p>6. Fixing of broken plaster/concrete and replacement of slabs where necessary</p> <p>7. Painting of Exterior of Harbour building</p> <p>8. Creation of art installation with blue stone dedicated to the "Bouspan"</p> <p>9. Sandblasting (embossing) of words 'set he captives free in 11 languages plus Herero and Ovambo.</p> <p>10. Duplication of the 'Bandieten' rolls rendered on glass – with the original pictures of the POQO prisoners in the background. [*the creative execution is still in early stages and different options are being researched.]</p>
The 1st Gate	<p>1. Painting and restoration of the guard's offices</p> <p>2. Installation of the exhibition Dankie Hek' in the guard office</p>

- Linda Penicela 17/10/11 11:02 AM**
Comment: Length and height of the wall
Current pictures of the wall
Methodology of treatment and restoration
- Unknown Author 17/10/19 11:04 AM**
Comment: Reply to Linda Penicela (10/11/2017, 11:02): "..."
See above Harbour Buildings related info.
Wood windows, doors & frames to be sanded and revarnished with marine grade varnish.
Fascia boards to be sanded down , primed and repainted with a washable acrylic.
Flaking paint will be scrapped from the walls,cracks filled with exterior filler , primed with plaster primer and finished with washable acrylic topcoats.
- Linda Penicela 17/10/11 11:04 AM**
Comment: Specify materials to be used,
Provide current pictures
Area to be affected in square metres
- Linda Penicela 17/10/11 11:06 AM**
Comment: Specify paints
Specify the areas in square metres
Current pictures
- Unknown Author 17/10/19 11:20 AM**
Comment: Reply to Linda Penicela (10/11/2017, 11:06): "..."
See above Murrays Harbour Buildings response
- Linda Penicela 17/10/11 11:07 AM**
Comment: Specify the art installation and material
Size of the installation
Artistic sample
- Unknown Author 17/10/19 11:21 AM**
Comment: Reply to Linda Penicela (10/11/2017, 11:07): "..."
See Drawings in image document and ... [6]
- Linda Penicela 17/10/11 11:09 AM**
Comment: Specify the art installation and material
Size of the installation ... [7]
- Unknown Author 17/10/19 11:30 AM**
Comment: Reply to Linda Penicela (10/11/2017, 11:09): "..."
See image document for artistic sample... [8]
- Linda Penicela 17/10/11 11:10 AM**
Comment: 1)Specify the art installation and material
2)Size of the installation ... [9]
- Linda Penicela 17/10/11 11:12 AM**
Comment: 1) Paint specification and area to be painted
2) Current pictures ... [10]
- Unknown Author 17/10/19 11:38 AM**
Comment: Reply to Linda Penicela (10/11/2017, 11:12): "..."
See Above Dankie Hek1

<p>The Visitor Center</p>	<ol style="list-style-type: none"> 1. Painting and restoration of the building (including the three cells at the back) 2. Removal of existing exhibitions 3. Fixing and neatening of wires/cables 4. Installation of audiovisual System 5. Installation of Journey of Sorrow exhibition 6. Preparation of warder's room 7. Installation of 'sculpture' of the original visitor center experience [two rows of fences with a passage and corrugated iron] by Lionel Davis 8. Landscape of the front of the Visitor Centre with the Installation of 'seating areas' dedicated to memory of visitors who came to Robben Island
<p>Front of MSP</p>	<p>Landscape of the the Front of the MSP with a renewed path.</p>
<p>Open Air Exhibition</p>	<ol style="list-style-type: none"> 1. Installation of 'open air' exhibition at the Leper Graveyard [including the excavation of the Children's Leper Bath]
<p>MSP</p>	<ol style="list-style-type: none"> 1. Painting and restoration of select spaces in the MSP 2. Installation of exhibition [installations] at the Main Prison Gate, the Amoury, Reception Office, Corridor, Censor, Cat Walk, Section B Courtyard,

Linda Penicela 17/10/11 11:14 AM
Comment: 1) Paint specification and area to be painted
2) Current pictures

Unknown Author 17/10/19 11:50 AM
Comment: Reply to Linda Penicela (10/11/2017, 11:14): "..."
Visitor room Waiting Room:
Remove posters & remove cabinet from current wall and refit cabinet on adjacent wall.
Scrape and fill walls, Prime filled areas and apply topcoats
in quareented enamel finish
Cells:
Scrape and fill walls, Prime filled areas and apply topcoats
in quareented enamel finish
Sand down metal doors and bars, apply rust proof primer and finish in a quareanteed white enanamel Velvaglo

Linda Penicela 17/10/11 11:15 AM
Comment: Heritage specialist required to advise and monitor excavation

	<p>Section B, Section A and Section C including courtyard and</p> <p>2. Communal Cells Section B Courtyard</p> <p>3. Installation of AV system [projectors, monitors and soundscapes.</p>
<p>Labelling and text panels</p> <p>*This step will be ongoing as spaces and exhibitions become ready.</p>	<p>1. To remove all 'outdated' labels and signage</p> <p>2. Install new labels and text panels</p>