




Appendix A: Site Plans












Appendix B: Site Photographs





1. Panoramic view from the site direction North



2. Panoramic view from the site direction North East



3. Panoramic view from the site direction East



4. Panoramic view from the site direction South East



5. Panoramic view from the site direction South



6. Panoramic view from the site direction South West



7. Panoramic view from the site direction West



8. Panoramic view from the site direction North West



9. View on basestation position direction North



10. View on base station position direction East



11. View on base station position direction South East




12. General view on site establishment area





#### PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT





1267 Pretorius Street Block B, Hadefields Complex Hatfield, 0083

Tel. +27 (12) 342 2900 Fax: +27 (12) 342 9208

Postnet Suite 146 Private Bag X15 Menlo Park

SITE NAME:

#### **HIGHFLATS**

BASE STATION NUMBER:

REV	DATE	BY	DESCRIPTION
А	16/11/2011	HV	FIRST ISSUE

OWNER: VAN DER LINDE GERHARDUS PHILLIPPUS JOHANNES

STRICTLY COMPANY CONFIDENTIAL

PROPERTY DESCRIPTION:

PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT

#### COORDINATES:

LAT: 26° 28' 11.69" S LONG: 30°31' 13.74" E

PROJECT:

NEW 9x9m TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

#### ADDRESS:

OFF THE R33 TOWARDS LOTHAIR MSUKALIGWA GERT SIBANDE MPUMALANGA

#### **INFRASTRUCTURE** PLANNING SERVICES



Tel. +27 (12) 804 1504/6 Fax: +27 (12) 804 7072 admin@infraplan.co.za

P.O. Box 32017 Totiusdal 0134

RFQ NO.:

152068

PROJECT NUMBER:

120167

DRAWINGS MUST NOT BE SCALED. ONLY FIGURED DIMENSIONS TO BE USED. DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCEMENT OF WORK.  $\label{eq:commencement}$ 

ALL WORK TO BE PERFORMED ACCORDING TO MTN BTS SITE INFRASTRUCTURE SPECIFICATION RI/01/1001 ISSUE 1 REVISION 0 NOVEMBER 2007


DRAWN: HANS V.D. WALT DATE: 16/11/2011 REF. NO: 812/T9511

> SITE DETAIL: ALTERNATIVE 1 SHEET 7 OF 11

**GRAVEL ROAD** 



#### PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT





1267 Pretorius Street Block B, Hadefields Complex Hatfield, 0083

Tel. +27 (12) 342 2900 Fax: +27 (12) 342 9208

Postnet Suite 146 Private Bag X15 Menlo Park

SITE NAME:

#### **HIGHFLATS**

BASE STATION NUMBER:

т	⁻∩	ᆮ	4	4

REV	DATE	BY	DESCRIPTION
А	16/11/2011	HV	FIRST ISSUE

OWNER: VAN DER LINDE GERHARDUS PHILLIPPUS JOHANNES

#### STRICTLY COMPANY CONFIDENTIAL

#### PROPERTY DESCRIPTION:

PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT

#### COORDINATES:

LAT: 26° 28' 11.69" S LONG: 30°31' 13.74" E

#### PROJECT:

NEW 9x9m TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

#### ADDRESS:

OFF THE R33 TOWARDS LOTHAIR MSUKALIGWA GERT SIBANDE MPUMALANGA

### **INFRASTRUCTURE** PLANNING SERVICES



414 Rustic Road

Tel. +27 (12) 804 1504/6 Fax: +27 (12) 804 7072 admin@infraplan.co.za

P.O. Box 32017 Totiusdal 0134

RFQ NO.:

152068

PROJECT NUMBER:

120167

DRAWINGS MUST NOT BE SCALED. ONLY FIGURED DIMENSIONS TO BE USED. DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCEMENT OF WORK.  $\label{eq:commencement}$ 

ALL WORK TO BE PERFORMED ACCORDING TO MTN BTS SITE INFRASTRUCTURE SPECIFICATION RI/01/1001

ISSUE 1 REVISION 0 NOVEMBER 2007 DRAWN: HANS V.D. WALT DATE: 16/11/2011

> SITE DETAIL: ALTERNATIVE 2 SHEET 8 OF 11

REF. NO: 812/T9511

**GRAVEL ROAD** 

R AZIMUTH ANTENNA	LIFICLIT								
	HEIGHT - M BOTTOM (m)	ECH. ELEC.	FEEDER SIZE	FEEDER LENGTH (m)					
0° K 80010123			7/8"	± 56					
120° K 80010123	3 51		7/8"	± 56					/ <mark> </mark>
240° K 80010123	3 51		7/8"	± 56			4007 Paul		\
							Block B, I Hatfield, 0	0083	Tel Fax
							SITE NA	AME: HIC	G١
							BASE S	TATION NUMBER:	
							REV	DATE BY	T
							$\vdash$	16/11/2011 HV	
							NOTES:		_
							1	: VAN DER LINDE GERHA	IAF
2635	21000							STRICTLY CO	
AVIATIONLIGHTS  3x KATHREIN 80010123  DIRECTIONAL ANTENNAE	0.6m MICROWAVE DISH TELECOMMUNICATIONS DIRECTIONAL ANTENNAE	TELECOMMUNICATIONS DIRECTIONAL ANTENNAE	OLIS	NEER'S DESIGN AND SPECIFICATIONS (PAINTED RED & WHITE)			 COORD LAT: 2 LONG  PROJECT  ADDRES OFF T MSUK GERT MPUM	NEW 9x9m TELECO WITH A LATTICE	

MTN A	ANTENN	NAE KEY						
	AZIMUTH	ANTENNA	HEIGHT - BOTTOM (m)	MECH.	ELEC. FEEDE TILT SIZE			
1	0°	K 80010123	57	1161	7/8"			
2	120°	K 80010123	57		7/8"	± 62		NIN
3	240°	K 80010123	57		7/8"	± 62		
								1267 Pretorius Street Block B, Hadefields Complex Hatfield, 0083  SITE NAME:  HIGHFLATS  BASE STATION NUMBER:  T9511  REV DATE BY DESCRIPTION  A 16/11/2011 HV FIRST ISSUE  NOTES: OWNER: VAN DER LINDE GERHARDUS PHILLIPPUS JOHANNES
	60000	-5635					70000	
Æ	\$2	4E	HSIQ SNO	AE AE	S H	Ω Q Q		
	AVIATION LIGHT	3x KATHREIN 80010123 DIRECTIONAL ANTENNAE	0.6m MICROWAVE DISH	DIRECTIONAL ANTENN	TELECOMMUNICATIONS DIRECTIONAL ANTENNAE	60m 3-LEGGED LATTICE MAST TO ENGINEER'S DESIGN AND SPECIFICATIONS (PAINTED RED & WHITE)	2.4m HIGH STEEL PALISADE FENCE WITH FLATWRAP RAZOR ON TOP (GALVANISED)  TELECOMMUNICATION EQUIPMENT CONTAINER  MTN 2.1x.1.6m MINI-D EQUIPMENT CONTAINER TO ENGINEER'S DESIGN AND SPECIFICATIONS (WHITE)	INFRASTRUCTURE PLANNING SERVICES  414 Rustic Road Silvertondale 0184  RFQ NO.: 152068  RPQ VECT NUMBERS
						ENGINEER	TE EQUE  MTN 2.1x1.6fr  CONTAINER TO F	PROJECT NUMBER: 120167  DRAWINGS MUST NOT BE SCALED. ONLY FIGURED DIMENSIONS TO BE USED. DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCEMENT OF WORK.  ALL WORK TO BE PERFORMED ACCORDING TO MTN BTS SITE INFRASTRUCTURE SPECIFICATION RI/01/1001 ISSUE 1 REVISION 0 NOVEMBER 2007  DRAWN: HANS V.D. WALT DATE: 16/11/2011  SCALE: 1:100 REF. NO: 812/T9511  SOUTH ELEVATION: ALTERNATIVE 2 SHEET 10 OF 11



TYPICAL 3 LEGGED LATTICE MAST (PAINTED RED AND WHITE)



1267 Pretorius Street Block B, Hadefields Complex Hatfield, 0083

Tel. +27 (12) 342 2900 Fax: +27 (12) 342 9208

Postnet Suite 146 Private Bag X15 Menlo Park

SITE NAME:

#### **HIGHFLATS**

BASE STATION NUMBER:

#### T9511

REV	DATE	BY	DESCRIPTION		
Α	16/11/2011	HV	FIRST ISSUE		

OWNER: VAN DER LINDE GERHARDUS PHILLIPPUS JOHANNES

#### STRICTLY COMPANY CONFIDENTIAL

PROPERTY DESCRIPTION:

PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT

#### COORDINATES:

LAT: 26° 28' 11.69" S LONG: 30°31' 13.74" E

#### PROJECT:

NEW 9x9m TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

#### ADDRESS:

OFF THE R33 TOWARDS LOTHAIR MSUKALIGWA GERT SIBANDE MPUMALANGA

## **INFRASTRUCTURE** PLANNING SERVICES



414 Rustic Road

Tel. +27 (12) 804 1504/6 Fax: +27 (12) 804 7072 admin@infraplan.co.za

P.O. Box 32017 Totiusdal 0134

RFQ NO.: 152068

PROJECT NUMBER:

120167

DRAWINGS MUST NOT BE SCALED. ONLY FIGURED DIMENSIONS TO BE USED. DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCEMENT OF WORK.

ALL WORK TO BE PERFORMED ACCORDING TO MTN BTS SITE INFRASTRUCTURE SPECIFICATION RI/01/1001 ISSUE 1 REVISION 0 NOVEMBER 2007

DRAWN: HANS V.D. WALT SCALE: NTS

DATE: 16/11/2011 REF. NO: 812/T9511

FACILITY ILLUSTRATION

SHEET 11 OF 11

Appendix D: Specialist Reports - Not Applicable

Appendix E: Comments and responses report

#### **Interested & Affected Parties Register / Comments and Responses Report**

 Site number:
 T9511

 Site Name:
 Highflats

 EIA reference no.:
 17/2/3/GS-89

			Interested and Affected		Comments and Responses Report			
No.	Date	Name	Address	Contact detail	Reacted to:	Record of initial I&AP registration	Issues raised / Comments received	EAP Response
1	17/05/2012	The Municipal Manager	PO Box 48 Frmelo 2350	Mr T Dlamini, Environmental Management Section, Fax: 017 801 3851	NA	Auto I&AP	No comments received	Sent Draft BAR
2	17/05/2012	The Ward Councillor	1 37	Clr SL Jele, Ward 15, Fax 017 801 3851	NA	Auto I&AP	No comments received	Sent Draft BAR
3	17/05/2012	The District Municipality	ICAPT Sinange District Milinicinality	Mr A Ngcobo, Environmental Management Section, 017 811 1207	NA	Auto I&AP	No comments received	Sent Draft BAR
4	17/05/2012	SAHRA	Town, 8000; PO Box 4637, Cape	Mr P Hine/Mrs Colette Scheermeyer, Tel: 0214624502, Fax: 0214624509, Email: phine@sahra.org.za	NA	Auto I&AP	No comments received	Sent Draft BAR
5	17/05/2012	SACAA	Private Bag x73, Halfway House 1685	Tel: (011) 545 1000 Fax: (011) 545 1451	NA	Auto I&AP	Approved with day & night markings	Paint mast red & white and install red navigation lights on top
6	03/10/2011	GPJ van der Linde	IP() Boy 141 Lothair 23/0	Mr GPJ van der Linde, 017 845 1074, Mobile 082 865 4082	Lease Negotiations	Land Owner	Signed Lease	Sent Draft BAR
7	25/05/2012	Lion Match Forestry (Pty) Ltd	1 032 Ulliuelli Ruau. Dulbali 4001.	Karen van Wyk, Company Secretarial Dept. Tel: (031) 308 1711 Fax: (031) 312 9681	Public Notice	17/05/2012	No objection, concerns regarding warning lights on tower. Thanks for additional info. Sent Postal Address for copy of BAB	Acknowledge receipt, Registered as I&AP, Sent additional info, Sent Draft BAR



Registration No. 2007/011484/07

892 Umgeni Road, Durban 4001, KwaZulu-Natal, South Africa, P O Box 918, Durban, 4000 Telephones National (031) 308 1711 International + 27 31 308 1711 Fax (031) 312 9681

25 May 2012

Attention: WA Van't Foort Torbiouse Solutions CC P.O. Box 32017 Totiusdal 0134

Email: admin@torbiousesolutions.co.za

Dear Sir/ Madam

RE: INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT PORTION 3 OF THE FARM HIGHFLATS 252 IT

We acknowledge receipt of your letter dated 17 May 2012, regarding the above.

We have no objection to your proposed establishment of a MTN (Pty) Ltd telecommunication base station on the property neighbouring ours (Remaining Extent of Portion 3 of the Farm Highflats 252 IT).

We are concerned, however, about the aerial bombers (fire-fighting aircraft) we are required to use from time to time, it being a forestry area, and request that adequate warning lights are installed on the tower to minimise risk to these low-flying aircraft.

Please confirm receipt of the above request – we would appreciate a response regarding our concern.

Yours faithfully,

RM BAKER Group Secretary

For Lion Match Forestry (Pty) Ltd

Owner of Portion 2 & 7 of the farm Clifton 143 IT

21 June 2012

Lion Match Forestry (Pty) Ltd Group Secretary P O Box 918 Durban 4000



Reg. No. 2001/080535/23 PO Box 32017, Totiusdal, 0134

> 414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504 / 6 Fax: (012) 804 7072 e-mail: admin@torbiousesolutions.co.za

Fax: 031 - 312 9681

Email: KarenvW@lionmatch.co.za

DEAR SIR/MADAM

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT OF PORTION 3 OF THE FARM HIGHFLATS 252 IT.

Thank you for your letter of concern. You have been registered as an Interested & Affected Party. We herewith wish to acknowledge receipt of your correspondence dated the 25<sup>th</sup> of May 2012, the contents of which has been noted.

An application for approval of the mast was submitted by the client to the South African Civil Aviation Authority (SACAA). The SACAA prescribe day and night markings for all masts from 45m and higher. This means the mast will be painted red & white (prescribed day markings), and red navigation lights (prescribed night markings) will be installed on the mast.

Please note that you will receive a copy of the Basic Assessment Report for your perusal and comments.

Kindly confirm the postal addres to which you want the Report to be send.

Yours faithfully

WA VAN'T FOORT For: Torbiouse Solutions CC

#### Wilbert Van't Foort

From:

Karen van Wyk [KarenvW@lionmatch.co.za]

Sent: To: 21 June 2012 04:31 PM Wilbert Van't Foort

Cc:

Desire Strydom [MTN - Sandton]; Baker, Robert

Subject:

RE: 120621 T9511 Highflats - Telecommunication mast

Dear Mr Van't Foort

Thank you for your email and the attached letter addressing our concerns.

You may post the report to:

PO Box 918 Durban 4000

(please mark it for my attention)

Regards,

Karen van Wyk Company Secretarial Dept.



Tel: +27 31 308 1711 Direct Tel: +27 31 308 1746 Fax: +27 31 312 9681 Direct Fax: 086 545 0474 www.lionmatch.co.za

The Lion Match Company (Pty) Ltd
Reg. No. 1998/008912/07
Chairman NMI Abdoola
Deputy Chairman AH Trikamjee
Group Managing Director C de Jager
Directors A Heeralal, SA Moosa, SM Moosa, AGS Osman
Group Secretary RM Baker

From: Wilbert Van't Foort [mailto:wilbert@infraplan.co.za]

Sent: 21 June 2012 03:31 PM

To: Karen van Wyk

Cc: Desire Strydom [ MTN - Sandton ]

Subject: 120621 T9511 Highflats - Telecommunication mast

Dear Madam,

## RE: ESTABLISHMENT OF MTN TELECOMMUNICATION BASE STATION ON PORTION 3, REMAINING EXTENT OF THE FARM HIGHFLATS 252 IT

Please find attached our reply letter to your enquiry regarding the above mentioned development.

Kind Regards,

Wilbert van't Foort Environmental Assessment Fax: 086 690 0468



# Torblouse Solutions CC 414 Rustic Road, Silvertondale, 0184 PO Box 32017, Totiusdal, 0134 e-mail admin@torbiousesolutions.co.za

Reg. No. 2001/0080535/23 Tel (012) 804 1504/6 Fax (012) 804 7072

#### Disclaimer

The information contained in this communication from the sender is confidential. It is intended solely for use by the recipient and others authorized to receive it. If you are not the recipient, you are hereby notified that any disclosure, copying, distribution or taking action in relation of the contents of this information is strictly prohibited and may be unlawful.

This email has been scanned for viruses and malware, and automatically archived by Mimecast SA (Pty) Ltd, an innovator in Software as a Service (SaaS) for business. Mimecast Unified Email Management (UEM) offers email continuity, security, archiving and compliance with all current legislation. To find out more, contact Mimecast.

Appendix F: EMPR



## **Environmental Management Plan (EMP)**

(Compiled and Submitted in terms of the National Environmental Management Act (Act 107 of 1998))

## MobileTelephone Networks (Pty) Ltd

Project Reference Number:

17/2/3GS-89

Portion 3 (Remaining Extent) of the farm Highflats 252 IT

T9511

11 September 2012

## **DOCUMENT APPRAISAL**

Reference No.		Responsible Person	Signature	Date
Stage of Document	Final			
Document Compilation				
Document Review				
Document Authorisation	on			

**Department Reference Number: 17/2/3GS-89** 

### **CONTENTS PAGE**

1.1.1	1	INTRODUCTION		1-1
1.1.1		1.1 BACKGROUND AND BRIEF PROJECT DESCRIPTION		1-1
2 ADMINISTRATION AND REGULATION OF ENVIRONMENTAL OBLIGATIONS         2.1           2.1         ENVIRONMENTAL SITE AGENT         2.1           2.2         ENVIRONMENTAL AWARENESS TRAINING FOR SITE PERSONNEL         2.1           2.3         ON SITE COMMUNICATION PROCEDURE         2.2           2.3.1         Environmental Awareness Training for Site Personnel         2.2           2.3.2         ESA Diary Entries         Error! Bookmark not defined           2.3.3         Method Statements         Error! Bookmark not defined           2.3.4         Record Keeping         2.2           2.3.5         Photographs         2.2           2.3.5         Photographs         2.2           2.3.5         Photographs         2.2           2.3.6         Environmental Completion Statement         2.2           2.4         BASIC RULES OF CONDUCT         2.2           2.5         INTERNAL REVIEW AND AUDITING         2.3           3.1         SITE DEMARCATION         3.1           3.2         CONSTRUCTION FACILITIES         3.1           3.2         CONSTRUCTION FACILITIES         3.1           3.2.1         Construction Camp         3.1           3.2.2         Toilet Facilities         3.2      <				1-1
2.1         ENVIRONMENTAL SITE AGENT         2-1           2.2         ENVIRONMENTAL AWARENESS TRAINING FOR SITE PERSONNEL         2-1           2.3         ON SITE COMMUNICATION PROCEDURE         2-2           2.3.1         Environmental Awareness Training for Site Personnel         2-2           2.3.2         ESA Diary Entries         Error! Bookmark not defined.           2.3.3         Method Statements         Error! Bookmark not defined.           2.3.5         Photographs         2-2           2.4         BASIC RULES OF CONDUCT         2-2           2.5         INTERNAL REVIEW AND AUDITING         3-3           3.1         STIE DEMARCATION         3-1           3.2         CONSTRUCTION FACILITIES         3-1           3.2         Toilet Facilities         3-1           3.2.1         Construction Acceptable Security of Securi		1.1.2 Contents of the EMP		1-1
2.2         ENVIRONMENTAL AWARENESS TRAINING FOR SITE PERSONNEL         2.1           2.3         ON SITE COMMUNICATION PROCEDURE         2.2           2.3.1         Environmental Awareness Training for Site Personnel         2.2           2.3.2         ESA Diary Entries         Error! Bookmark not defined.           2.3.3         Method Statements         2.2           2.3.5         Photographs         2.2           2.3.6         Environmental Completion Statement         2.2           2.4         BASIC RULES of CONDUCT         2.2           2.5         INTERNAL REVIEW AND AUDITING         2.3           3.1         STE DEMARCATION         3.1           3.2         CONSTRUCTION FACILITIES         3.1           3.2.1         CONSTRUCTION FACILITIES         3.1           3.2.2         Toilet Facilities         3.2           3.2.1         CONSTRUCTION FACILITIES         3.2           3.2.1         Vostruction Camp         3.1           3.2.2         Toilet Facilities         3.2           3.3.1         Vegetation Clearing         3.2           3.3.2         Vegetation Clearing         3.2           3.3.3         Trenching         3.3           3.4.1         Handl	2	ADMINISTRATION AND REGULATION OF ENVIRONMENTA	AL OBLIGATIONS	2-1
2.2         ENVIRONMENTAL AWARENESS TRAINING FOR SITE PERSONNEL         2.1           2.3         ON SITE COMMUNICATION PROCEDURE         2.2           2.3.1         Environmental Awareness Training for Site Personnel         2.2           2.3.2         ESA Diary Entries         Error! Bookmark not defined.           2.3.3         Method Statements         2.2           2.3.5         Photographs         2.2           2.3.6         Environmental Completion Statement         2.2           2.4         BASIC RULES of CONDUCT         2.2           2.5         INTERNAL REVIEW AND AUDITING         2.3           3.1         STE DEMARCATION         3.1           3.2         CONSTRUCTION FACILITIES         3.1           3.2.1         CONSTRUCTION FACILITIES         3.1           3.2.2         Toilet Facilities         3.2           3.2.1         CONSTRUCTION FACILITIES         3.2           3.2.1         Vostruction Camp         3.1           3.2.2         Toilet Facilities         3.2           3.3.1         Vegetation Clearing         3.2           3.3.2         Vegetation Clearing         3.2           3.3.3         Trenching         3.3           3.4.1         Handl		2.1 Environmental Site Agent		2-1
2.3   ON SITE COMMUNICATION PROCEDURE   2.3.1   Environmental Awareness Training for Site Personnel   2.3.2   ESA Diary Entries   Error! Bookmark not defined.   2.3.3   Method Statements   Error! Bookmark not defined.   2.3.4   Record Keeping   2.2   2.3.5   Photographs   2.2   2.3.6   Environmental Completion Statement   2.2   2.3.6   Environmental Completion Statement   2.2   2.3.6   Environmental Completion Statement   2.2   2.3.6   Environmental Review and Audurting   2.3   2.3   ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE   3.1   SITE DEMARCATION   3.1   3.2   CONSTRUCTION FACILITIES   3.1   3.2.1   Construction Camp   3.2.2   Toilet Facilities   3.1   3.2.3   Water Provision   3.2   3.2.4   General Aesthetics   3.2   3.2.4   General Aesthetics   3.2   3.3.1   Vegetation Clearing   3.3.3   SITE CLEARING   3.2   3.3.2   Site Access   3.2   3.3.3   Trenching   3.3   3.3   Trenching   3.3   3.3   3.4   MATERIALS HANDLING AND STORAGE   3.3.4   Handling   3.3   3.4.2   Storage of Construction Materials   3.3   3.5   Refuelling   3.3   3.5   Refuell				2-1
2.3.2   ESA Diary Entries   Error!   Bookmark not defined   2.3.3   Method Statements   Error!   Bookmark not defined   2.3.4   Record Keeping   2.2   2.3.5   Photographs   2.2   2.3.5   Environmental Completion Statement   2.2   2.4   BASIC RULES OF CONDUCT   2.5   INTERNAL REVIEW AND AUDITING   2.3   2.3   ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE   3.1   SITE DEMARCATION   3.1   3.2.1   Construction Facilities   3.1   3.2.1   Construction Camp   3.1   3.2.2   Toilet Facilities   3.3.3   SITE CLEARING   3.2.3   Water Provision   3.2.3   Water Provision   3.2.4   General Aesthetics   3.2.3   General Aesthetics   3.2.3   Site Access   3.2.3   Site Access   3.2.3   3.3.3   Trenching   3.3.3   Trenching   3.3.3   Site Access   3.2.3   3.3.4   Handling   3.3   3.4.1   Handling   3.3   3.4.1   Handling   3.3   3.4.1   Handling   3.3   3.4.1   Handling   3.3   3.5.1   Refuelling   3.3   3.5.2   Maintenance   3.4   3.5   3.5.2   Maintenance   3.4   3.5   3.5   Refuelling   3.3   3.5.1   Refuelling   3.3   3.5.2   Maintenance   3.4   3.5   3		2.3 ON SITE COMMUNICATION PROCEDURE		2-2
2.3.2   ESA Diary Entries		2.3.1 Environmental Awareness Training for Site Personnel		2-2
2.3.3   Method Statements			Error! Bookmark not d	lefined.
2.3.5       Photographs       2-2         2.3.6       Environmental Completion Statement       2-2         2.4       BASIC RULES OF CONDUCT       2-2         2.5       INTERNAL REVIEW AND AUDITING       2-3 <b>3 ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE</b> 3.1       SITE DEMARCATION       3-1         3.2       CONSTRUCTION FACILITIES       3-1         3.2.1       Construction Camp       3-1         3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3.1       Vegetation Clearing       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT <td< td=""><td></td><td></td><td>Error! Bookmark not d</td><td>lefined.</td></td<>			Error! Bookmark not d	lefined.
2.3.6   Environmental Completion Statement   2-2		2.3.4 Record Keeping		2-2
2.4       BASIC RULES OF CONDUCT       2-2         2.5       INTERNAL REVIEW AND AUDITING       2-3         3       ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE       3-1         3.1       SITE DEMARCATION       3-1         3.2       CONSTRUCTION FACILITIES       3-1         3.2.1       Construction Camp       3-1         3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4 </td <td></td> <td>2.3.5 Photographs</td> <td></td> <td>2-2</td>		2.3.5 Photographs		2-2
2.5         INTERNAL REVIEW AND AUDITING         2-3           3         ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE         3-1           3.1         SITE DEMARCATION         3-1           3.2         CONSTRUCTION FACILITIES         3-1           3.2.1         CONSTRUCTION FACILITIES         3-1           3.2.2         Toilet Facilities         3-1           3.2.3         Water Provision         3-2           3.2.4         General Aesthetics         3-2           3.3         SITE CLEARING         3-2           3.3.1         Vegetation Clearing         3-2           3.3.2         Site Access         3-2           3.3.3         Trenching         3-3           3.4         MATERIALS HANDLING AND STORAGE         3-3           3.4.1         Handling         3-3           3.4.2         Storage of Construction Materials         3-3           3.4.3         Storage of Equipment         3-3           3.5.1         Refuelling         3-3           3.5.2         Maintenance         3-4           3.5.1         Refuelling         3-3           3.5.2         Maintenance         3-4           3.6         ACCIDENTAL LEAKS AND SP		2.3.6 Environmental Completion Statement		2-2
3		2.4 BASIC RULES OF CONDUCT		2-2
3.1       SITE DEMARCATION       3-1         3.2       CONSTRUCTION FACILITIES       3-1         3.2.1       Construction Camp       3-1         3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Flora       3-6		2.5 Internal Review and Auditing		2-3
3.2       CONSTRUCTION FACILITIES       3-1         3.2.1       Construction Camp       3-1         3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Flora       3-6         3.10.2       Protection of Flora	3	ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHA	ASE	3-1
3.2.1       Construction Camp       3-1         3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       STIE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.10.       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.2       Protection of Flora       3-6 <t< td=""><td></td><td>3.1 SITE DEMARCATION</td><td></td><td>3-1</td></t<>		3.1 SITE DEMARCATION		3-1
3.2.2       Toilet Facilities       3-1         3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Flora       3-6         3.10.2       Protection of Flora       3-6		3.2 CONSTRUCTION FACILITIES		3-1
3.2.3       Water Provision       3-2         3.2.4       General Aesthetics       3-2         3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5.1       Refuelling AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Flora       3-6         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Heritage AND Cultural Features       3-6         3.12       DUST CO		3.2.1 Construction Camp		3-1
3.2.4 General Aesthetics       3-2         3.3 SITE CLEARING       3-2         3.3.1 Vegetation Clearing       3-2         3.3.2 Site Access       3-2         3.3.3 Trenching       3-3         3.4 MATERIALS HANDLING AND STORAGE       3-3         3.4.1 Handling       3-3         3.4.2 Storage of Construction Materials       3-3         3.4.3 Storage of Equipment       3-3         3.5.1 Refuelling AND MAINTENANCE       3-3         3.5.2 Maintenance       3-4         3.6 ACCIDENTAL LEAKS AND SPILLS       3-4         3.7 WASTE MANAGEMENT       3-4         3.7.1 Solid Waste       3-4         3.8 EROSION CONTROL       3-5         3.10 PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1 PROTECTION OF NATURAL FEATURES       3-6         3.10.2 Protection of Flora       3-6         3.10.3 Protection of Flora       3-6         3.11 PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12 DUST CONTROL       3-6         3.13 NOISE CONTROL       3-7         3.14 CEMENT       3-7		3.2.2 Toilet Facilities		3-1
3.3       SITE CLEARING       3-2         3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-7         3.13       NOISE CONTROL<				3-2
3.3.1       Vegetation Clearing       3-2         3.3.2       Site Access       3-2         3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Flora       3-6         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Heritage and Cultural Features       3-6         3.12       Dust Control       3-6         3.13       Noise Control       3-7         3.14       Cement       3-7				3-2
3.3.2       Site Access         3.3.3       Trenching         3.4       MATERIALS HANDLING AND STORAGE         3.4.1       Handling         3.4.2       Storage of Construction Materials         3.4.3       Storage of Equipment         3.5.1       Refuelling AND MAINTENANCE         3.5.1       Refuelling         3.5.2       Maintenance         3.6       ACCIDENTAL LEAKS AND SPILLS         3.7       WASTE MANAGEMENT         3.7.1       Solid Waste         3.8       EROSION CONTROL         3.9       FIRE CONTROL         3.10.       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA         3.10.1       Protection of Natural Features         3.10.2       Protection of Flora         3.10.3       Protection of Fauna         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES         3.12       DUST CONTROL         3.13       NOISE CONTROL         3.14       CEMENT				3-2
3.3.3       Trenching       3-3         3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7       3.7       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10.1       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-7         3.14       CEMENT       3-7		e e		3-2
3.4       MATERIALS HANDLING AND STORAGE       3-3         3.4.1       Handling       3-3         3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Flora       3-6         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-7         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				3-2
3.4.1 Handling       3-3         3.4.2 Storage of Construction Materials       3-3         3.4.3 Storage of Equipment       3-3         3.5 REFUELLING AND MAINTENANCE       3-3         3.5.1 Refuelling       3-3         3.5.2 Maintenance       3-4         3.6 ACCIDENTAL LEAKS AND SPILLS       3-4         3.7 WASTE MANAGEMENT       3-4         3.8 EROSION CONTROL       3-5         3.9 FIRE CONTROL       3-5         3.10 PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1 Protection of Natural Features       3-5         3.10.2 Protection of Flora       3-6         3.10.3 Protection of Fauna       3-6         3.11 PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12 DUST CONTROL       3-6         3.13 NOISE CONTROL       3-7         3.14 CEMENT       3-7				3-3
3.4.2       Storage of Construction Materials       3-3         3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.4.3       Storage of Equipment       3-3         3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7		· · · · · · · · · · · · · · · · · · ·		
3.5       REFUELLING AND MAINTENANCE       3-3         3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7		· · · · · · · · · · · · · · · · · · ·		
3.5.1       Refuelling       3-3         3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7		E 1 1		
3.5.2       Maintenance       3-4         3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.6       ACCIDENTAL LEAKS AND SPILLS       3-4         3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.7       WASTE MANAGEMENT       3-4         3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.7.1       Solid Waste       3-4         3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.8       EROSION CONTROL       3-5         3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.9       FIRE CONTROL       3-5         3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.10       PROTECTION OF NATURAL FEATURES, FLORA AND FAUNA       3-5         3.10.1       Protection of Natural Features       3-5         3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.10.1 Protection of Natural Features       3-5         3.10.2 Protection of Flora       3-6         3.10.3 Protection of Fauna       3-6         3.11 PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12 DUST CONTROL       3-6         3.13 NOISE CONTROL       3-7         3.14 CEMENT       3-7				
3.10.2       Protection of Flora       3-6         3.10.3       Protection of Fauna       3-6         3.11       PROTECTION OF HERITAGE AND CULTURAL FEATURES       3-6         3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.10.3 Protection of Fauna 3.63 3.11 PROTECTION OF HERITAGE AND CULTURAL FEATURES 3.12 DUST CONTROL 3.13 NOISE CONTROL 3.14 CEMENT 3.60 3.70 3.71 3.71				
<ul> <li>3.11 PROTECTION OF HERITAGE AND CULTURAL FEATURES</li> <li>3.12 DUST CONTROL</li> <li>3.13 NOISE CONTROL</li> <li>3.14 CEMENT</li> <li>3-6</li> <li>3-7</li> <li>3-7</li> <li>3-7</li> </ul>				
3.12       DUST CONTROL       3-6         3.13       NOISE CONTROL       3-7         3.14       CEMENT       3-7				
3.13 NOISE CONTROL 3-7 3.14 CEMENT 3-7				
3.14 CEMENT 3-7				3-7
				3-7
				3-7

3.16		MPLAINTS REGISTER	3-7			
3.17	SITE	REHABILITATION AND LANDSCAPING	3-8			
4 E	NVIRC	ONMENTAL SPECIFICATIONS: OPERATIONAL PHASE	4-1			
4.	1.1	Maintenance	4-1			
5 E	NVIRC	ONMENTAL SPECIFICATIONS: DECOMMISSIONING PHASE	5-1			
5.	1.1	Procedure	5-1			
6 E	EMERGENCY RESPONSE PLAN					
6.1	TVP	ICAL REMEDIAL WORK OPTIONS	6.1			

#### **EXECUTIVE SUMMARY**

The proponent, MTN (Pty) Ltd, intends the **ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION MAST** ON PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT.

The **Mpumalanga Department of Economic Development, Environment & Tourism** requested that an Environmental Management Plan (EMP) be prepared for the proposed project, which addresses all phases of the proposed project, for submission to them [for approval]. The scope of environmental management described in this EMP pertains to the project as a whole and aims to integrate environmental planning, design, construction and operational activities on the site.

The EMP has as its basis the recommendations listed in the Basic Assessment Report. It is important to note that the project and the implementation of environmental specifications is an ongoing process that is dynamic in nature. This EMP forms part of the contractual obligation between the Contractor and the proponent, MTN (Pty) Ltd.

#### 1 INTRODUCTION

#### 1.1 Background and Brief Project Description

The proposed project involves the **ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION MAST ON PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT.** 

**Torbiouse Solutions CC** was appointed to compile the Environmental Management Plan in respect of the proposed project.

#### 1.1.1 Aims of the EMP

The purpose of the EMP is to set environmental targets for the Contractor and reasonable standards against which the Contractor's performance in this regard can be measured during construction. This document will form the basis for the environmental specifications that the Constructor is obliged to comply with during construction of the proposed project. This document will thus form a binding agreement between the Contractor and MTN (Pty) Ltd.

The EMP addresses issues in order to ensure that all environmental aspects are carefully considered and monitored and adverse impacts managed. It is important to note that the development and implementation of environmental specifications is ongoing and the EMP is typically dynamic in nature.

#### 1.1.2 Contents of the EMP

The EMP consists of the following sections:

**Chapter 1: Introduction:** This section includes the project background, aims of this EMP and describes the contents of this EMP.

Chapter 2: Administration and regulation of environmental obligations: This section identifies the proposed mechanisms for monitoring compliance with the EMP and reporting thereof.

Chapter 3: Environmental Specifications: Construction Phase: This section includes environmental specifications relating to the construction phase of the project.

**Chapter 4: Environmental Specifications: Operational Phase:** This section includes environmental specifications relating to the operational phase of the project.

Chapter 5: Environmental Specifications: Decommissioning Phase: This section includes environmental specifications relating to the decommissioning of the site.

Chapter 6: Emergency Response Plan: This section provides a summary of responses to emergency situations

#### 2 ADMINISTRATION AND REGULATION OF ENVIRONMENTAL OBLIGATIONS

#### 2.1 Environmental Site Agent

The Environmental Site Agent (ESA) is the person, appointed by the Contractor on behalf of the Applicant or the Environmental Consultant appointed on behalf of the Applicant, involved with the project and all projects within the operational region of the Contractor and who is responsible for the implementation of the environmental management plan. This person is therefore responsible for the environmental issues involved with the construction phase of the project. The ESA will be required to oversee a number of sites at any given time and is required to manage his/her time effectively to ensure that he/she fulfils his/her environmental obligations in respect of all sites.

The ESA must be a person with adequate environmental knowledge to understand and implement this management plan. It is required that the ESA reports to the Applicant (MTN (Pty) Ltd) irrespective of who appointed the ESA. The ESA has the authority to stop works if in his/her opinion there is a serious threat to or impact on the environment, caused directly from the construction operations. This authority is to be limited to emergency situations where consultation with the HOD Implementation and/or Property Supervisor and/or National Property Manager is not immediately available. In all such work stoppage situations, the ESA is to inform the HOD Implementation and/or Property Supervisor and/or National Property Manager of the reasons for the stoppage as soon as possible thereafter.

Upon failure by the Contractor and/or his employees to show adequate consideration to the environmental aspects of this EMP, the ESA may recommend the suspension of works pending an investigation by the HOD Implementation and/or Property Supervisor and/or National Property Manager.

#### 2.2 Environmental Awareness Training for Site Personnel

All Contractor teams involved in work on the project are to be briefed on their obligations towards environmental controls and methodologies in terms of this EMP prior to the commencement of work. The briefing will take the form of an on site talk, when an RFQ (Request for Quotation) site survey is set up, and shall be demonstrated by the ESA. The education / awareness programme should be aimed at all levels of employees within the Contractor team. (See "Do's and Don'ts" summary sheet).

### 2.3 On Site Communication Procedure

### 2.3.1 Environmental Awareness Training for Site Personnel

The Site Instruction book entries will be used for the recording of general site instructions as they relate to the work taking place on site. It will also be used for the issuing of stop work orders for the purposes of immediately halting any particular activities of the Contractor in lieu of the environmental risk that they may pose.

### 2.3.2 Record Keeping

All records relating to the implementation of this EMP must be kept on site; on the MTN Operating System and archived at an adequate archive facility where it is safe and can be retrieved easily. These records should be kept for two years and should at any time be available for scrutiny by any relevant authorities.

### 2.3.3 Photographs

It is recommended that photographs are taken on the site prior to, during and immediately after construction as a visual reference. These photographs should be stored with other records related to this EMP and on the MTN Operating System. If captured in digital format, hard copies must be kept with all other records relevant to the implementation of this EMP. In particular, the Contractor and ESA are responsible for taking photographs of the environmental aspects of environmentally sensitive areas for use in rehabilitation processes.

### 2.3.4 Environmental Audit Report

An Environmental Audit Report is a report completed by the ESA and signed off by the HOD Implementation and/or the Property Supervisor and/or National Property Manager, and then sent to the relevant authorities, by the ESA, stating the completion of the project and compliance with the EMP and conditions.

### 2.4 Basic Rules of Conduct

The following list represents the basic "Do's and Dont's" towards environmental awareness, which all participants in this project must consider whilst carrying out their tasks and duties. These are not exhaustive and serve as a quick reference aid. NOTE: **All new site personnel must attend an** 

**environmental awareness presentation.** Please inform your foreman or manager if you have not attended such a presentation alternatively contact the ESA.

### DO:

- ✓ Use the toilet facilities provided report dirty or full facilities;
- ✓ Clear your work areas of litter and building rubbish at the end of each day use the waste bins provided and ensure that litter will not blow away;
- ✓ Report all fuel or oil spills immediately and stop the spill continuing;
- ✓ Dispose of cigarettes and matches carefully. (Littering is an offence);
- ✓ Confine work and storage of equipment to the immediate work area and within the site boundary;
- ✓ Where possible use a drip tray under vehicles and machinery and empty drip trays after rain and throw away where instructed;
- ✓ Use all safety equipment and comply with all safety procedures;
- ✓ Ensure a working fire extinguisher is immediately at hand if any "HOT WORK" is undertaken e.g. welding, grinding, gas cutting etc;
- ✓ Try to avoid producing dust wet dry ground and soil;

### DONT:

- \* Make any fires;
- ★ Enter any fenced off or marked area;
- \* Allow cement or cement bags to blow around;
- \* Allow waste, litter, oils or foreign materials into the stormwater channels;
- ⋆ Litter or leave food laying around;
- \* Make loud noises around the site. Report or repair noisy vehicles
- \* Damage or cut down any trees or plants without permission.

### 2.5 Internal Review and Auditing

The Contractor and ESA shall establish an internal review procedure to monitor the progress and implementation of the EMP during the construction phase. All audits will be signed off by the HOD Implementation and/or Property Supervisor and/or National Property Manager.

Where necessary, and upon the recommendation of the ESA and/or the Contractor, procedures that require modification will be changed to improve the efficiency of the EMP. All modifications to the EMP shall be approved by the Department before; if possible, any changes or adjustments to the EMP are implemented. Any material changes or adjustments to the EMP shall be registered accordingly on MTN's operating system.. Adjustment and update of the original EMP document is not required when these *ad hoc* changes are made.

At the conclusion of the project an environmental audit report shall be compiled\_by the ESA, and signed off by HOD Implementation and/or Property Supervisor and/or National Property Manager and submitted to the Department by the ESA. This report shall be compiled by the ESA, in collaboration with the Contractor and/or the Environmental Consultant and/or the Applicant.. It shall, as a minimum, outline the implementation of the EMP during the construction phase, and highlight any problems and issues that arose during the construction period to report, on a formal basis, the lessons learnt from this project.

### 3 ENVIRONMENTAL SPECIFICATIONS: CONSTRUCTION PHASE

### 3.1 Site Demarcation

The "site" refers to the total area where the contract will take place and any other area reasonably required by the Contractor to undertake the construction activities in order to fulfil the contract. Areas where construction is prohibited are referred to as 'no-go' areas. 'No-go' areas identified on site include all areas outside of the footprint of the base station as well as environmentally sensitive sites. The environmental sensitivity of the area should be ascertained and then the position and orientation of the BTS site as per the approved drawings should be pegged out. 'No-go' areas should be demarcated to prevent environmental degradation thereto. This responsibility rests with the ESA and/or the Contractor.

The Contractor shall be responsible for any clean-up and/or rehabilitation of all areas impacted outside the site and within the 'no-go' areas.

### 3.2 Construction Facilities

### 3.2.1 Construction Camp

Construction crews may not stay on site overnight unless special permission has been obtained from the landowner. In the event that the landowner has given such permission, the position of the construction camp shall be agreed by the ESA and Contractor.

### 3.2.2 Toilet Facilities

The Contractor shall provide suitable sanitary arrangements (chemical toilets), which shall be located within the construction camp and/or in the construction footprint (where applicable) of the BTS. The siting of toilets shall be done in consultation with the ESA to ensure ease of access. Where required, toilet/s shall be secured to prevent them blowing over.

The Contractor shall be responsible for ensuring that all ablution facilities are maintained in a clean and sanitary condition to the satisfaction of the ESA. The Contractor shall provide toilet paper. The Contractor shall appoint a suitable sub-contractor to empty toilets on a regular basis. The sub-contractor and Contractor shall ensure that there is no spillage when the chemical toilets are cleaned and that the contents are properly removed from site.

The Contractor shall be responsible for enforcing the use of these facilities. Performing ablutions outside of established toilet facilities is strictly prohibited.

### 3.2.3 Water Provision

The Contractor shall be responsible for ensuring that there is access to clean drinking water for all employees on site. The use of water in rivers, dams, ponds etc. as drinking water is strictly forbidden.

### 3.2.4 General Aesthetics

All construction areas must be kept neat and tidy at all times. Different materials and equipment must be kept in designated areas and storing/stockpiling shall be kept orderly.

### 3.3 Site Clearing

### 3.3.1 Vegetation Clearing

Before clearing of vegetation, the Contractor shall ensure that all litter and non-organic material is removed from the area to be cleaned. All vegetation that may not be removed must be clearly identified and demarcated. Where the surrounding flora is required to be protected from traffic, the entire construction area should be fenced off with a temporary 1.8m fence. The fence should be removed upon completion of construction. This responsibility rests with the Contractor and the ESA. The use of herbicides is prohibited.

### 3.3.2 Site Access

All access to and from the BTS shall be on demarcated roads (where possible). The route for permanent access to the site shall be determined prior to construction, and shall be pegged out accordingly. Photographs shall be taken indicating the route detail. Rehabilitation of secondary roads must be conducted by the Contractor. No machinery may disturb any vegetation along side any road.

### 3.3.3 Trenching

All trenching must completed in such a manner as to limit damage to the surrounding environment. If required in the authorisation, trenching is to be done by hand.

### 3.4 Materials Handling and Storage

### 3.4.1 Handling

The Contractor shall ensure that all suppliers and their delivery drivers are aware of procedures and restrictions in terms of this EMP. The Contractor (and suppliers) shall ensure that all materials are appropriately secured to ensure safe passage between destinations. Loads shall have appropriate cover to prevent spillage from the vehicle during transit. The Contractor shall be responsible for any clean-up resulting from the failure by his employees or suppliers to properly secure transported materials. The Contractor shall ensure that delivery drivers are supervised during offloading.

### 3.4.2 Storage of Construction Materials

The Contractor shall ensure that areas for storage of construction materials are determined in consultation with the ESA and adequately demarcated. All construction materials including but not limited to building material shall be stored on such demarcated areas.

### 3.4.3 Storage of Equipment

Drip trays shall be provided for stationary plant (such as compressors, pumps, generators etc.) and for "parked" plant (e.g. mechanised equipment).

### 3.5 Refuelling and Maintenance

### 3.5.1 Refuelling

Where reasonably practicable, plant and vehicles shall be refuelled using suitable equipment (e.g funnels) and the necessary drip trays.

### 3.5.2 Maintenance

All vehicles and equipment shall be kept in good working order and serviced regularly. Leaking equipment shall be removed from the site. All maintenance of equipment and vehicles shall be performed off site. No washing of plant and equipment shall be undertaken on site.

### 3.6 Accidental Leaks and Spills

The Contractor shall ensure that his employees are aware of the procedure to be followed for dealing with spills and leaks. Any accidental leak or spill of fuel, oil or any other hazardous substance must be reported immediately to the ESA to ensure that the best remediation method is quickly implemented.

In the event of a hydro-carbon spill, the source of the spillage shall be isolated and the spillage contained. The area shall be cordoned off and secured. The Contractor shall ensure that there is always a supply of absorbent material readily available to absorb / breakdown spills.

The Contractor shall be liable to arrange for professional service providers to clear the area affected by the spill, if required.

### 3.7 Waste Management

### 3.7.1 Solid Waste

Solid waste includes all construction waste (cement bags, tags, wrapping materials, cans, wire, nails, etc.) and surplus food, food packaging, organic waste etc. The Contractor shall be responsible for the establishment of a solid waste control and removal system that is acceptable to the ESA in order to prevent the spread of waste in, and beyond, the construction area. An integrated waste management approach shall be used, based on the principles of waste minimisation, reduction, reuse and recycling of materials. Containers for glass, paper, metals and plastics shall be provided, if sufficient solid waste is generated. The construction camp area (if applicable) is particularly suited for this purpose.

The Contractor shall provide vermin and weatherproof bins (with lids) of sufficient number and capacity to store solid waste produced on a daily basis. The lids shall be kept firmly on the bins at all times. Bins shall be located in areas where there is a concentration of labour and shall be easily

accessible. Bins shall be emptied regularly as required, preferably every second day. The general cleanliness of the site shall form part of the ESA inspections.

All solid waste may be temporarily stored on site in a demarcated area, which meets the satisfaction of the ESA. All solid waste shall be disposed of off site at a licensed landfill site. The stockpiling of construction rubble, cut vegetation or other material shall only be permitted in areas approved by the ESA. No waste material or litter shall be burnt or buried on site.

### **Erosion Control**

The Contractor shall, as an ongoing exercise, provide erosion control to the satisfaction of the ESA. During construction, the Contractor shall protect areas susceptible to erosion by installing necessary temporary and permanent draining works as soon as possible.

Any runnels or erosion channels developed during the construction period shall be backfilled and compacted, and the areas restored to an acceptable condition (as determined by the ESA). Stabilisation of cleared areas to prevent and control erosion shall be actively managed.

During construction, the Contractor shall implement measures to prevent the migration of materials (fines) from the construction site into river courses, drainage lines, stormwater and sewerage systems.

### 3.8 Fire Control

No fires shall be allowed on site. At least one 12.5kg type ABC (all purpose) fire extinguisher shall be kept on the construction site.

### 3.9 Protection of Natural Features, Flora and Fauna

### 3.9.1 Protection of Natural Features

The Contractor shall not deface, paint, damage or mark any natural features outside the site for any purpose unless agree beforehand with the ESA. The Contractor shall not permit his employees to make use of any natural water sources situated on or near the site for purposes of swimming, personal washing and/or the washing of machinery or clothes.

### 3.9.2 Protection of Flora

The removal, damage or disturbance of flora, fauna or avifauna is forbidden. The clearing of vegetation within the construction area shall be undertaken in accordance with that specified in section 3.3.1.

The Contractor shall be familiar with any Ordinances, Acts, By-laws and/or regulations pertaining to the protection of natural features, flora and fauna on site. Where applicable, the Contractor shall apply for the necessary permits prior to removing any plants listed in the relevant schedules promulgated in terms of the legislation.

### 3.9.3 Protection of Fauna

The Contractor shall ensure that no hunting, trapping, shooting, poisoning or other disturbance of any fauna takes place. The feeding of wild animals is prohibited. No domestic pets or livestock are permitted on site.

### 3.10 Protection of Heritage and Cultural Features

The Contractor shall not, without a permit issued by the relevant heritage resources authority, destroy, damage, excavate, alter, deface or otherwise disturb archaeological finds. Archaeological finds can take the form of buried walls, old bottles, porcelain fragments, earthenware fragments, accumulations of bone and ash dumps.

If any archaeological or paleontological artefacts and/or human burials or remains are uncovered during construction, work in the vicinity of the find shall cease. The Contractor shall immediately notify the HOD Implementation and/or Property Supervisor and/or National Property Manager, who shall contact the South African Heritage Resources Agency (SAHRA). The Contractor will be required to abide by the specifications as set out by SAHRA or the heritage specialist appointed to investigate the find or burial.

### 3.11 Dust Control

The Contractor shall ensure that the generation of dust is minimised and shall implement a dust control programme to maintain a safe working environment, minimise nuisance and protect damage to natural vegetation.

The Contractor shall ensure that all exposed soil and material stockpiles are adequately protected against the wind. Where possible, dust suppression shall take place by way of spraying.

### 3.12 Noise Control

The Contractor shall be familiar with and adhere to, any local by-laws and regulations regarding the generation of noise and hours of operation. Working hours shall be confined to the hours between [insert time as per EA/ROD] and [insert time as per EA/ROD]. The Contractor shall be held responsible for any complaints received from the department and/or public with respect to any contravention of agreed noise conditions.

### 3.13 Cement

Cement and concrete mixing directly on the ground shall not be allowed. Where possible, ready mix concrete shall be utilised in all site construction. Mixing of cement, if applicable, shall take place on impermeable surfaces to the satisfaction of the ESA.

Unused cement bags shall be stored out of the rain where they will not be affected by run-off. Used (empty) cement bags shall be collected and stored in weatherproof containers to prevent wind blown cement dust and water contamination. Used cement bags shall not be used for any other purpose and shall be disposed of on a regular basis via the solid waste management system.

All excess concrete shall be removed from site on completion of concrete works and disposed of at a licensed landfill site. Washing of the excess concrete or washing of concrete pump trucks into the ground is prohibited.

### 3.14 Mast Colour

The mast shall be painted red & white in accordance with that stated in ROD/EA and in accordance with Civil Aviation Authority requirements.

### 3.15 Complaints Register

The ESA shall have accessible on the construction site a complaints register in terms of which all complaints received from interested and affected parties shall be recorded. The Complaints register shall be kept on site for the duration of construction activities and all complaints received shall be reported to the ESA.

### 3.16 Site Rehabilitation and Landscaping

On completion of the project, the Contractor shall ensure that all structures, equipment, materials, waste, rubble, notice boards and temporary fences used during the construction operation are removed with minimum damage to the surrounding area. The Contractor shall clean and clear the site to the satisfaction of the ESA.

In the case of accidental spills of oils, the affected soils shall be dug out and removed from the site for disposal at a licensed hazardous waste site and replaced with fresh topsoil.

Rehabilitation shall especially focus on all scarred and open areas, in order to reduce visual impacts as a result of the construction phase. Stored topsoil, if applicable, shall be used for rehabilitation purposes.

### 4 ENVIRONMENTAL SPECIFICATIONS: OPERATIONAL PHASE

The following responsibilities will be met to prevent negative environmental impacts:

- Providing a budget for maintenance;
- Maintaining all approved infrastructure in good working order to effectively fulfill its intended purpose and to prevent negative environmental impacts;
- Not construct any additional buildings, infrastructure etc. contrary to the approved Environmental Authorization, without performing an environmental impact assessment to evaluate alternatives and environmental impacts;
- To immediately remedy any factors that contribute to negative environmental impacts;
- [Where the ROD requires this insert this clause] To do an annual environmental audit and to have the results in writing available at the administration offices of MTN.

### 4.1.1 Maintenance

Procedure to be followed to ensure the high standards of appearance and quality are maintained on the BTS sites to ensure that environmental issues are adequately addressed and that BTS sites are effectively maintained.

- All BTS sites must be maintained and cleaned as per the schedule set by the Field Maintenance Supervisor responsible;
- 2. The items that must be checked will be as per the list below and as reflected in detail in the Site Maintenance Report and Statement of Work reference documentation;
  - a. Fence and Gate: Secure and rust treat as necessary;
  - b. Signage: Check all signs as per the BTS Site Infrastructure Specification;
  - c. Terrain:
    - i. Clean and de-weed inside and outside the BTS site and clean a 1m perimeter area around the fence. In areas susceptible to soil erosion, cut weed perimeter in such a way as to protect soil from erosion;
    - ii. De-weed invasive vegetation in the surrounding area of the BTS site;
    - iii. Check for any rubble that could have accumulated from previous maintenance work or during the BTS site build and remove and dump and a registered waste disposal site.
  - d. Equipment Room: De-rust, wash walls and floor and dust interior;

- e. BTS Cabinet: Replace filter
- f. Container: Replace blown fluorescent lights (discard used lights in safe manner to ensure no mercury exposure), clean roof and cut away branches hanging over the site;
- g. Air Conditioner: Wash, dry and seal;
- h. Mast Navigation Lights: Replace blown globes
- i. Mast: Check foundation, bolts, bolt torque, cable tray, cage and contact specialist to remove nests;
- j. Road: Check condition i.e. check for signs of soil erosion, potholes and general sturdiness;
- k. Power Source: Check condition i.e. still safe and insulated;
- I. Maintenance Waste: All waste generated from the maintenance work must be removed from the area and disposed of at an approved landfill.
- 3. Invasive vegetation can easily be recognized as it is found in the immediate vicinity surrounding the site, but does not grow in the natural environment in the surrounding area. Normally the seeds of invasive vegetation are brought in an area with sand used during BTS site construction. Every effort must be made to remove invasive vegetation before it produces seeds.
- 4. In non environmentally sensitive areas, MTN approved weed killers may be used, under controlled conditions, to minimize weed growth. Soil erosion must be considered and prevented prior to using any weed killers.
- 5. Problems or non-compliance, such as poor road maintenance or erosion, mast paint peeling and poor mast condition, must be reported immediately. The necessary corrective action must be implemented to rectify the situation.

### 5 ENVIRONMENTAL SPECIFICATIONS: DECOMMISSIONING PHASE

The objective to provide guidelines is to prevent structures being left to deteriorate. Therefore it is imperative that non-functional structures are removed as soon as possible and the area is rehabilitated. If non-functional structures are no longer required, it must be maintained as if it is in use to prevent the environmental degradation of the area.

The Applicant will be responsible for the following:

- Removal of the construction building rubble to a suitable licensed disposal facility;
- Ensuring that suitable arrangements are made to protect the environment against long term negative impacts;
- Minimize negative visual impacts;
- Maintain the storm water channels in a working condition;
- Clean up contaminants of the environment;
- Prevent erosion through regular monitoring and rehabilitation of degraded areas.

### 5.1.1 Procedure

Procedure to be followed when decommissioning a BTS site.

- A Work Authorisation must be issued by the Planning and Optimisation Division instructing
  the Implementation Division to decommission a particular site. In most cases, there will be a
  replacement BTS site issued at the same time. This may involve more than one BTS site to
  achieve the same coverage, largely depending on the site location and the Planning
  Engineer;
- 2. The BTS site will only be decommissioned once the replacement site has been activated (this is preferred, but not always possible), otherwise the replacement site must have at least been approved by the Property division and an instruction to proceed with the replacement BTS site build has been given to the Implementation Division;
- 3. When the site is decommissioned, the following areas should be considered as detailed further below:
  - a. Slab and concrete work;
  - b. Tower;
  - c. Antennas:
  - d. Feeder System;
  - e. Fencing and Guardrails;

- f. Container;
- g. Site Rehabilitation;
- h. Dumping
- i. Power connection to be disconnected

### **Slab and Concrete Work**

- 4. All the concrete, cement and reinforcing on site must be removed and disposed of in a Registered dump by the Contractor. All land must be filled with landfill and compacted as necessary. (refer to owners requirements). If the landlord agrees, the concrete, cement and reinforcing can remain as is.
- 5. All stone or site fill must be removed and disposed of in an approved landfill by the Contractor.

### **Tower**

- 6. The tower must be dismantled in a controlled manner and transported to the original tower manufacturer for inspection. The tower must be inspected for conformance to the current MTN specification. If the tower meets MTN's current tower specifications it must be packed for redistribution to another BTS site.
- 7. If the tower does not meet MTN's current tower specification it must be sent to the central warehouse or a location specified by the warehouse. The tower will then be retained until it can be removed (depreciated) from the asset register and sold as scrap metal.
- 8. All accessories associated with the tower such as booms, antenna poles, cat ladders, cables etc must be inspected and returned to the central warehouse for inspection, packaging and redistribution to another BTS site.
- All antennas shall be returned to the warehouse for testing to ensure that they still meet the
  manufacturers specification. The central warehouse will identify whether they are on MTN's
  accepted antenna list. If so, they will be placed back in stock and redistributed to another
  BTS site.
- 10. If the antenna is not on MTN's current accepted antenna list, it will be sent to the central warehouse until it is removed from the asset register (depreciated) and scrapped.
- 11. Antenna brackets will be returned to the central warehouse for inspection and redistribution.

### **Feeder System**

- 12. Connectors will be cut off the feeder cable, the open ends will be weather sealed, rolled and sent to the central warehouse for inspection, evaluation and redistribution.
- 13. The warehouse will dispose of unusable feeder cable according to the approved disposal procedure.

- 14. All feeder brackets and clamps must be packed and sent to the central warehouse for distribution.
- 15. Earthing materials must be returned to the central warehouse for redistribution or disposal. Waterproofing should be disposed of by the Contractor in an approved landfill.

### **Fencing and Guardrails**

- 16. All fencing must me removed in a controlled manner for reuse. Concrete must be removed and dumped in an approved landfill by the Contractor.
- 17. Gates and access ways must be returned to the central warehouse for inspection and redistributed to another BTS site.
- 18. All electric fencing must be removed and returned to the central warehouse for inspection and redistribution.

### Container

- 19. The container must be stripped of all equipment, returned to the manufacturer for inspection and refurbished if necessary. The container is then redistributed to another BTS site, preferably in the same region.
- 20. All other equipment must be sent to the Central Warehouse for evaluation and redistribution, if applicable.
- 21. All the equipment above must go through acceptance testing as per the acceptance procedure relating to that specific piece of equipment.

### Site Rehabilitation

22. The BTS site, access roads and any trenches must be rehabilitated, conforming to ISO standards and to a level accepted by both the ESA and the landlord and must meet legal obligations that may be imposed or apply to that particular BTS site.

### **Dumping**

- 23. No Contractor or Sub-contractor will dispose of any (dump) material or product without the approval from the responsible ESA.
- 24. All materials or products must be disposed of in the correct manner, in approved dumping site by the Contractor or Sub-Contractor. MTN must ensure that this procedure is followed for all sites decommissioned.

### Records

Records of such decommissioning shall be kept electronically on the MTN Operating System.

### **6 EMERGENCY RESPONSE PLAN**

The objective of this section is to provide a brief summary of options available to the ESA. The details of the design will reside with the designers, but cognizance should be taken of the design philosophy and key aspects given in the guidelines to problem solving given below.

### 6.1 Typical remedial work options

The following table is provided to assist the Contractor and ESA with problem solving:

Observation or Event	Action by ESA	Action by Contractor
Spillage of diesel or	Report to ESA and continue	Action will be required asap by following the
hydrocarbons on soil	observations.	next steps:
	Also check:	> Dig down into the soil to see how far down
	That the source causing the	the pollution has penetrated;
	spillage is decommissioned,	> If penetration is less than 300mm:
	and that the affected area is	a. Turn the soil over to expose it to the air:
	isolated to prevent spreading	b. Apply Mono Ammonium Phosphate
	of the hazardous substance	(MAP) at a rate of 58gr/m <sup>2</sup> to the dug up soil
		c. Water enough to keep the soil moist
		> If penetration is greater than 300mm:
		a. Remove the affected soil and spread in
		a layer not more than 300mm thick;
		b. Apply MAP at a rate of 50gr/m <sup>2</sup>
		c. Water enough to keep the soil moist
		> Repeat the above steps every 6 weeks or
		until the soil is clean
General Surface	Report to ESA and continue	Action will be required asap:
Erosion	observations.	> Implement erosion protection works at
	Also check:	identified problem areas;
	> In respect of erosion of roads	> Implement remedial works to be done at
	that all vehicular movement	affected areas in order to restore the area
	is restricted to the existing	to its previous or better status.
	access routes to prevent	
	criss-crossing of tracks	
	through undisturbed areas.	

This EMP has been assessed/reviewed and agreed with:

HOD – Implementation	SUPERVISOR - Property
Name:	Name:
Region:	Region:
Date:	Date:
Environmental Consultant (ESA)	HOD - Maintenance
Name:	Name:
Company:	Region:
Date:	Date:

### Appendix G1: Public Participation and Other Information

G1(a) - Public Participation - Proof of Site Notice

G1(b) - Public Participation - Proof of Written Notices to I&AP

G1(c) - South African Civil Aviation Authority Information


G1(d) - Public Participation - Proof of Newspaper Advertisement

G1(e) - Register of Interested and Affected Parties

G1(a) - Proof of Site Notice




Site Notice 1 affixed to temporary stand next to tree and wooden house



Site Notice 1 affixed to temporary stand next to tree and wooden house



Site Notice 1 affixed to temporary stand next to tree and wooden house



Site Notice 2 affixed to temporary stand next to old building



Site Notice 2 affixed to temporary stand next to old building



Site Notice 2 affixed to temporary stand next to old building



Site Notice 3 affixed to temporary stand next to Country Trax Board



Site Notice 3 affixed to temporary stand next to Country Trax Board



Site Notice 3 affixed to temporary stand next to Country Trax Board

G1(b) - Proof of Written Notices

17 May 2012

Owner of Portion 4 of the farm Highflats 252 IT Owner of the farm Usutu Opstal 251 IT Mr. J.P Cilliers P.O Box 423 LOTHAIR 2370



Reg. No. 2001/080535/23 PO Box 32017, Totiusdal, 0134 414 Rustic Road Silvertondale, 0164 Pretorla

Tel: (012) 804 1504 / 6 Fax: (012) 804 7072 e-mall: admin@torbiousesolutions.co.za

Via Registered Mail

### **DEAR SIR/MADAM**

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT PORTION 3 OF THE FARM HIGHFLATS 252 IT.

We are acting on behalf of MTN (Pty) Ltd in order to apply to the Mpumalanga Department of Economic Development, Environment and Tourism to establish a telecommunication base station on Remaining Extent of Portion 3 of the Farm Highflats 252 IT.

### Attached hereto find:

- 1. Public Participation notice
- 2. Site Development plan

be ELEWIR

3. Facility Illustration

Should you have any further queries, please do not hesitate to contact us.

Yours faithfully

PP

**WA VAN'T FOORT** 

For: Torbiouse Solutions CC

### PUBLIC PARTICIPATION PROCESS

17/2/3 GS - 89 REFERENCE NUMBER:

Establishment of an enclosed telecommunication base station with a 54m mast for MTN (Pty) Ltd: T9511 Highflats Regulation 546 activity 3:

Remaining Extent Portion 3 of the farm Highflats 252 IT Location:

Co-ordinates (WGS84 format) of the alternatives on the above property.

Longitude: 30° 31' 13.74" E (Lattice type mast painted red and white) Latitude: 26° 28' 11.69" S Alternative 1:

the National Environmental Management Act 1998 (Act No. 107 of 1998) as Notice is hereby given of a public participation process in terms of the Environmental impact Assessment Regulations 2010 (R543) as amended promulgated in terms of amended ("NEMA").

Basic assessment procedures will be applied in accordance with regulation 543 and an application is to be submitted to the Mpumalanga Department of Economic Development, Environment and Tourism.

The applicant furthermore intends to apply to the Mpumalanga Department of Economic Development, Environment and Tourism for exemption in terms of regulation 50(1) of the Environmental Impact Assessment Regulations 2010 (R543) to assess alternatives with regard to the planned activity.

Applicant: MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

### Environmental Assessment Practitioner (EAP):

Torbiouse Solutions CC.

P.O. Box 32017, Totiusdal, 0134

Attention: WA van't Foort

Telephone: (012) 804 1504/6; Facsimile: (012) 804 7072

E-mail: admin@torbiousesolutions.co.za

Further information regarding the proposed activity can be obtained from the EAP.

Any interested and affected party may, in writing, make representations on the proposed activity or request to be registered as an interested and affected party, by physical & postal addresses (including facsimile & e-mail where possible) and contact number(s) and quoting the activity reference number, to the EAP within 30 submitting the written representations or registration request, including their name, calendar days from the publication of this notice.

(date in full) Notice publication date:

# UHLELO LOKUHLANGANYELA KOMPHAKATHI

17/2/3 GS - 89 NOMBOLO YEREFERENSI:

Umyalelo womthetho 546 umsebenzi 3: Isakhiwo esiyisizinda sezokuxhumana ngocingo esivalekile se-MTN (Pty) Ltd ene-mast engama-54m kanye nendawo (nezindawo) yokubeka impahla: T9511 Highflats

Indawo: Remaining Extent Portion 3 of the farm Highflats 252 IT

Ezinye izindawo zezizinda ezihlukile ezifana nalesi esingenhla (WGS84 sokwakheka):

Ubude: 30° 31' 13.74"E Induku ye-lattice ependwe ngokubomvu nokumhlophe Ububanzi: 26° 28' 11.69"S Esihlukile 1:

Vemithetho Yokuhlola Umthelela Wamandla Kwezenhlalo (i-Environmental Impact njengoba ichibiyelwe yamenyezelwa Igalokhu kunikezwa isaziso sengubo yokubamba ighaza komphakathi ngokuhambisana Ezenhlalo Kuzwelonke (i-National Environmental Management Act) ka-1998 (Umthetho weNombolo-107 ka-1998) Assessment Regulations) ka-2010 (R543) ngokuhambisana Nomthetho Wokuphatha njengoba uchibiyelwe (i-"NEMA").

yomthetho 543 bese kufakwa isicelo eMnyangweni Wezolimo, Ukunakekelwa kanye WaseMpumalanga. Umenzi wesicelo uhlose futhi ukwenza isicelo kuMnyango Wezolimo waseMpumalanga, Ukulondolozwa Kwamagugu Nezemvelo akhululwe ngokwemibandela yomthetho 50(1) weMithetho Yokuhlolwa zinqubo eziyisisekelo zokuhlola zizosetshenziswa ngokuvumelana nemiyalelo Kokuthinteka Kwemvelo ka-2010 (R543) ukuze ahlole ezinye izindlela zokuqhubeka nomsebenzi ohleliwe. neZemvelo

Umuntu ofaka isicelo:

MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

isisebenzi Esihiola Ezemvelo (Environmental Assessment Practitioner (EAP)): Forbiouse Solutions CC., P.O. Box 32017, Totiusdal, 0134

kuqondiswe ku- W A van't Foort


Jcingo: (012) 804 1504/6, Ifeksi: (012) 804 7072,


-e-meyili: admin@torbiousesolutions.co.za

Nanoma ubani omunye othandayo nothintekayo, ngokubhala, makenze isitatimende Olunye ulwazi maqondana nalo msebenzi ohlongozwayo lungatholakala ku-EAP.

ngomsebenzi ohlongozwayo noma isicelo sokubhaliswa njengomuntu onothando noma othintekayo, ngokuthi alethe isitatimende esibhaliwe noma isicelo sokubhalisa, namagama abo, ikheli lendawo neleposi (kufakwe ifeksi ne-e-meyili uma kunokwenzeka) kanye nezinombolo zokubathinta futhi basho nenombolo yereferensi yomsebenzi, ku-EAP ezinsukwini zekhalenda ezingama-30 kusukela ekushicilelweni kwalesi saziso.

Jsuku lokushicilelwa kweSaziso:







CHARER VAN DER LINDE GERHARFING PHILLIPPUB EDHANDES

9TRICTLY COMPANY CONFIDENTIAL PROPERTY DESCRIPTION POPTION 1 (REMAINING EXTENT) OF THE FARM MIGHELATS 252 IT

COORDINATES LAT 26\*28\*1168\*S LONG 30\*31\*1374\*E

NEW PARM TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MIN (PTV) LTD PROJECT

ADDRESS
OF THE RAS TOWARDS LOTHAIR
MSUKALIDMA
CERT STRANDE
MPUMALANGA

INFRASTRUCTURE PLANNING SERVICES

P.O. Box 12017 Tologram

ORAMANS BADEN NOT HE ROLLED ONE V FOLKED ORBITALISMS TO BE VERY STORMED ORBITALISMS TO BE VISIONED OR USE OF COLOUR CITYLISMS TO BE VISIONED OR USE OF COLOUR CITYLISMS TO BE VISIONED OR VISIONED OR

FACILITY ILLUSTRATION SHEET 11 OF 11

17 May 2012

Owner of Portion 2 & 7 of the farm Clifton 143 IT Lion Match Forestry (Pty) Ltd P.O Box 918 DURBAN 4000



Reg. No. 2001/080535/23 PO Box 32017, Totiusdal, 0134 414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504 / 6 Fax: (012) 804 7072 e-mail: admln@torblousesolutions.co.za

Via Registered Mail

### **DEAR SIR/MADAM**

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT PORTION 3 OF THE FARM HIGHFLATS 252 IT.

We are acting on behalf of MTN (Pty) Ltd in order to apply to the Mpumalanga Department of Economic Development, Environment and Tourism to establish a telecommunication base station on Remaining Extent of Portion 3 of the Farm Highflats 252 IT.

### Attached hereto find:

1. Public Participation notice

evereuse -

- 2. Site Development plan
- 3. Facility Illustration

Should you have any further queries, please do not hesitate to contact us.

Yours faithfully

P.P

**WA VAN'T FOORT** 

For: Torbiouse Solutions CC

Members: GA Anholts; KW Anholts

## PUBLIC PARTICIPATION PROCESS

REFERENCE NUMBER:

17/2/3 GS - 89

Establishment of an enclosed telecommunication base station with a 54m mast for MTN (Pty) Ltd: T9511 Highflats Regulation 546 activity 3:

Remaining Extent Portion 3 of the farm Highflats 252 IT Location:

Co-ordinates (WGS84 format) of the alternatives on the above property.

Longitude: 30° 31' 13.74" E (Lattice type mast painted red and white) Latitude: 26° 28' 11.69" S Alternative 1:

Notice is hereby given of a public participation process in terms of the Environmental Impact Assessment Regulations 2010 (R543) as amended promulgated in terms of the National Environmental Management Act 1998 (Act No. 107 of 1998) as amended ("NEMA").

an application is to be submitted to the Mpumalanga Department of Economic Basic assessment procedures will be applied in accordance with regulation 543 and Development, Environment and Tourism. The applicant furthermore intends to apply to the Mpumalanga Department of Economic Development, Environment and Tourism for exemption in terms of regulation 50(1) of the Environmental Impact Assessment Regulations 2010 (R543) to assess alternatives with regard to the planned activity.

Applicant: MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

Environmental Assessment Practitioner (EAP):

Torbiouse Solutions CC.

P.O. Box 32017, Totiusdal, 0134

Telephone: (012) 804 1504/6; Facsimile: (012) 804 7072 Attention: W A van't Foort

E-mail: admin@torbiousesolutions.co.za

Further information regarding the proposed activity can be obtained from the EAP.

Any interested and affected party may, in writing, make representations on the proposed activity or request to be registered as an interested and affected party, by submitting the written representations or registration request, including their name, physical & postal addresses (including facsimile & e-mail where possible) and contact number(s) and quoting the activity reference number, to the EAP within 30 calendar days from the publication of this notice.

(date in full) Notice publication date:

# UHLELO LOKUHLANGANYELA KOMPHAKATHI

17/2/3 GS - 89 NOMBOLO YEREFERENSI:

Umvalelo womthetho 546 umsebenzi 3: Isakhiwo esiyisizinda sezokuxhumana ngocingo esivalekile se-MTN (Pty) Ltd ene-mast engama-54m kanye nendawo (nezindawo) yokubeka impahla: T9511 Highflats

ndawo: Remaining Extent Portion 3 of the farm Highflats 252 IT

Ezinye izindawo zezizinda ezihlukile ezifana nalesi esingenhla (WGS84 sokwakheka);

Ubude: 30° 31' 13.74"E Induku ye-lattice ependwe ngokubomvu nokumhlophe Ububanzi: 26° 28' 11.69"S Esihlukile 1:

Nemithetho Yokuhlola Umthelela Wamandla Kwezenhlalo (i-Environmental Impact njengoba ichibiyelwe yamenyezelwa Ezenhíalo Kuzwelonke (i-National Agalokhu kunikezwa isaziso senqubo yokubamba iqhaza komphakathi ngokuhambisana Environmental Management Act) ka-1998 (Umthetho weNombolo-107 ka-1998) ngokuhambisana Nomthetho Wokuphatha Assessment Regulations) ka-2010 (R543) njengoba uchibiyelwe (i-"NEMA").

yomihetho 543 bese kufakwa isicelo eMnyangweni Wezolimo, Ukunakekelwa kanye neZemvelo WaseMpumalanga. Umenzi wesicelo uhlose futhi ukwenza isicelo akhululwe ngokwemibandela yomthetho 50(1) weMithetho Yokuhlolwa киМпуапдо Wezolimo waseMpumalanga, Ukulondolozwa Kwamagugu Nezemvelo Kokuthinteka Kwemvelo ka-2010 (R543) ukuze ahlole ezinye izindlela zokuqhubeka nemiyalelo eziyisisekelo zokuhlola zizosetshenziswa ngokuvumelana nomsebenzi ohleliwe. oqnbuiz Jkuze

Umuntu ofaka Isicelo:

MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

isisebenzi Esihiola Ezemvelo (Environmental Assessment Practitioner (EAP)); Forbiouse Solutions CC., P.O. Box 32017, Totiusdal, 0134

kuqondiswe ku- W A van't Foort


Jcingo: (012) 804 1504/6, Ifeksi: (012) 804 7072,


-e-meyili: admin@torbiousesolutions.co.za

ngomsebenzi ohlongozwayo noma isicelo sokubhaliswa njengomuntu onothando noma Nanoma ubani omunye othandayo nothintekayo, ngokubhala, makenze isitatimende namagama abo, ikheli lendawo neleposi (kufakwe ifeksi ne-e-meyili uma kunokwenzeka) kanye nezinombolo zokubathinta futhi basho nenombolo yereferensi yomsebenzi, ku-Olunye ulwazi maqondana nalo msebenzi ohlongozwayo lungatholakala ku-EAP, othintekayo, ngokuthi alethe isitatimende esibhaliwe noma

Jsuku lokushicilelwa kweSaziso:

EAP ezinsukwini zekhalenda ezingama-30 kusukela ekushicilelweni kwalesi saziso.





TYPICAL 3 LEGGED LATTICE MAST (PAINTED RED AND WHITE)



120 Protorus Greek (14 a)P (1) This immediate Carper (14 a)P (1) This immediate Carper (14 a)P (1) This immediate Carper (14 a)P (14 a

HIGHFLATS

BASE STATION NUMBER

DESCRIPTION HV FIRSTISSUE T9511 à 18/11/2011 REV DATE MOTES

CHREST VAN DER UNDE GERNARDUS PHELIPPEIS JOHANNES

STRICTLY COMPANY CONFIDENTIAL PROPERTY DESCRIPTION PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHELATS 252 IT

COORDINATES LAT 26"28" 11.69" S LONG 30" 31" 13.74" E

NEW 9x9m TÉLÉCOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

AODŘÉSS DF THE RJJ TOWARDS LOTHAIR MSURALIOMA GERT SIRANDE MPUMALANGA

INFRASTRUCTURE PLANNING SERVICES

414 Ruste Road Giverandale 0184

742 +27 (12) 804 15048 6at +27 (12) 804 7072 edmingerimples on pr

7 O Bus 32017 7 Shandal 0134

152068 PROJECT NUMBER 120187

ORANGES MAIN NOT BE SCALED ONLY ROLLING CONFINGUAGE TO BE ORANGED WITH SEASON OF THE S

FACILITY ILLUSTRATION SHEET 11 OF 11

17 May 2012



Owner Remaining Extent of Portion 1 of the farm Highflats 252 IT
Owner of Portion 8 of the farm Highflats 252 IT
Highflats Boerdery (Pty) Ltd
P.O Box 210
ERMELO
2350

Reg. No. 2001/080535/23 PO Box 32017, Totiusdal, 0134 414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504 / 6 Fax: (012) 804 7072 e-mail: admin@torblousesolutlons.co.za

Via Registered Mail

### **DEAR SIR/MADAM**

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT PORTION 3 OF THE FARM HIGHFLATS 252 IT.

We are acting on behalf of MTN (Pty) Ltd in order to apply to the Mpumalanga Department of Economic Development, Environment and Tourism to establish a telecommunication base station on Remaining Extent of Portion 3 of the Farm Highflats 252 IT.

### Attached hereto find:

- 1. Public Participation notice
- 2. Site Development plan

evereuse,

3. Facility Illustration

Should you have any further queries, please do not hesitate to contact us.

Yours faithfully

WA VAN'T FOORT

For: Torbiouse Solutions CC

Members: GA Anholts; KW Anholts

## PUBLIC PARTICIPATION PROCESS

REFERENCE NUMBER:

17/2/3 GS - 89

Establishment of an enclosed telecommunication base station with a 54m mast for MTN (Pty) Ltd: T9511 Highflats Regulation 546 activity 3;

Remaining Extent Portion 3 of the farm Highflats 252 IT Location:

Co-ordinates (WGS84 format) of the alternatives on the above property.

Longitude: 30° 31' 13.74" E (Lattice type mast painted red and white) Latitude: 26° 28' 11.69" S Alternative 1:

the National Environmental Management Act 1998 (Act No. 107 of 1998) as Notice is hereby given of a public participation process in terms of the Environmental impact Assessment Regulations 2010 (R543) as amended promulgated in terms of amended ("NEMA").

Basic assessment procedures will be applied in accordance with regulation 543 and an application is to be submitted to the Mpumalanga Department of Economic Development, Environment and Tourism. The applicant furthermore intends to apply to the Mpumalanga Department of Economic Development, Environment and Tourism for exemption in terms of regulation 50(1) of the Environmental Impact Assessment Regulations 2010 (R543) to assess alternatives with regard to the planned activity.

### Applicant:

MTN (Pty) Ltd, P.O. Box 4559, Northaliff, 2115.

### Environmental Assessment Practitioner (EAP):

Torbiouse Solutions CC.

P.O. Box 32017, Totiusdal, 0134

Attention: W A van't Foort

Telephone: (012) 804 1504/6; Facsimile: (012) 804 7072

E-mail: admin@torbiousesolutions.co.za

Further information regarding the proposed activity can be obtained from the EAP.

Any interested and affected party may, in writing, make representations on the proposed activity or request to be registered as an interested and affected party, by physical & postal addresses (including facsimile & e-mail where possible) and contact number(s) and quoting the activity reference number, to the EAP within 30 submitting the written representations or registration request, including their name, calendar days from the publication of this notice.

(date in full) Notice publication date:

# UHLELO LOKUHLANGANYELA KOMPHAKATHI

17/2/3 GS - 89 NOMBOLO YEREFERENSI: Umyalelo womthetho 546 umsebenzi 3: Isakhiwo esiyisizinda sezokuxhumana ngocingo esivalekile se-MTN (Pty) Ltd ene-mast engama-54m kanye nendawo (nezindawo) yokubeka impahla: T9511 Highflats

ndawo: Remaining Extent Portion 3 of the farm Highflats 252 IT

(WGS84 Ezinye izindawo zezizinda ezihlukile ezifana nalesi esingenhla sokwakheka);

Ubude: 30° 31' 13.74"E Induku ye-lattice ependwe ngokubomvu nokumhlophe Ububanzi: 26° 28' 11.69"S Esihlukile 1:

Vemithetho Yokuhlola Umthelela Wamandla Kwezenhlalo (i-Environmental Impact njengoba ichibiyelwe yamenyezelwa Igalokhu kunlkezwa isaziso senqubo yokubamba iqhaza komphakathi ngokuhambisana Ezenhlalo Kuzwelonke (i-National Environmental Management Act) ka-1998 (Umthetho weNombolo-107 ka-1998) Assessment Regulations) ka-2010 (R543) ngokuhambisana Nomthetho Wokuphatha njengoba uchibiyelwe (i-"NEMA").

/omthetho 543 bese kufakwa isicelo eMnyangweni Wezolimo, Ukunakekelwa kanye WaseMpumalanga. Umenzi wesicelo uhlose futhi ukwenza isicelo akhululwe ngokwemibandela yomthetho 50(1) weMithetho Yokuhlolwa zinqubo eziyisisekelo zokuhlola zizosetshenziswa ngokuvumelana nemiyalelo kuMnyango Wezolimo waseMpumalanga, Ukulondolozwa Kwamagugu Nezemvelo Kokuthinteka Kwemvelo ka-2010 (R543) ukuze ahlole ezinye izindlela zokuqhubeka nomsebenzi ohleliwe. neZemvelo

Umuntu ofaka Isicelo:

MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

isisebenzi Esihiola Ezemvelo (Environmental Assessment Practitioner (EAP)); orbiouse Solutions CC., P.O. Box 32017, Totiusdal, 0134


kuqondiswe ku- W A van't Foort


Ucingo: (012) 804 1504/6, Ifeksi: (012) 804 7072,

-e-meyili: admin@torbiousesolutions.co.za

Nanoma ubani omunye othandayo nothintekayo, <u>ngokubhala,</u> makenze isitatimende ngomsebenzi ohlongozwayo noma isicelo sokubhaliswa njengomuntu onothando noma патадата abo, ikheli lendawo neleposi (kufakwe ifeksi ne-e-meyili uma kunokwenzeka) kanye nezinombolo zokubathinta futhi basho nenombolo yereferensi yomsebenzi, ku-EAP ezinsukwini zekhalenda ezingama-30 kusukela ekushicilelweni kwalesi saziso. othintekayo, ngokuthi alethe isitatimende esibhaliwe noma isicelo sokubhalisa, Olunye ulwazi maqondana nalo msebenzi ohlongozwayo lungatholakala ku-EAP.

Usuku lokushicilelwa kweSaziso:





TYPICAL 3 LEGGED LATTICE MAST (PAINTED RED AND WHITE)



190 Presenta deres State & Verillande Cempler Hannel Otto

HIGHFLATS T9511

DESCRIPTION FIRST ISSUE ř 2 16/11/2011 REV DATE A 16/11/2011

CAMER VANDER LINDE GERNANDUS PALLIPPUS (CHANNES NOTES

9TRUTLY COMPANY CONFIDENTIAL PROPERTY DESCRIPTION PORTION OF REMAINING EXTENT) OF THE FARM HIGHEATS 232.11

COORDINATES LAT 28: 26: 11 69" S LONG 30: 31: 3374" E

PROJECT

NEW BYSH TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

ADDRESS
DF THE RA3 TOWARDS LOTHANR
MSUKALIGWA
GET SIBANDE
MPUMALANGA

INFRASTRUCTURE PLANNING SERVICES

742 - 27 (52) 804 15048 Far + 27 (12) 804 7072 Memografishm on 23

P.O. Box 52017 Tollyadai 0134

414 Ruth Ruth Fa Shwitzman Fa 2144 2160 NO 152088 PROJECT NUMBER 120187

CRAMMOND MARTHOT SER GEALED CHALF PROMETO DESCRIPTIONS TO SER USE OTHER PROMETOR COMBUNET MARTHOT MARTHOT MARTHOT SER OTHER PROMETOR SECONDATIONS ASSOCIATED TO SER SECONDATIONS ASSOCIATED TO SERVICE SECONDATIONS ASSOCIATED TO SERVICE SECONDATIONS ASSOCIATED TO SERVICE SECONDATIONS ASSOCIATED TO SE REF NO 612/T051

Our Reference: T9511 / 17/2/3 GS-89 Your Reference:

17 May 2012

The Municipal Manager Msukaligwa Local Municipality P O Box 48 Ermelo 2350

Attention:

Mr T Dlamini

017 - 801 3851

**Environmental Management Section** 



Reg. No. 2001/080535/23

PO Box 32017, Totlusdal, 0134

414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504/ 6

Fax: (012) 804 7072

e-mail: admin@torblousesolutions.co.za

Facsimile:

E-mail:

Dear Sir / Madam,

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT OF PORTION 3 OF THE FARM HIGHFLATS 252 IT.

In terms of the Act and related regulations and guidelines Local Authorities are identified as key interested and affected parties (I&AP).

We request you to evaluate the attached information on the proposed project and provide us with your written comments and/or inputs, if any, by faxing or e-mailing such within 30 days from the date of this notification. It will be assumed that you do not have any comments on the Environmental Application of the proposed project on the expiry of the 30 day response period.

Should you have any further queries please do not hesitate to contact us.

Kind Regards,

WA VAN'T FOORT

For: Torbiouse Solutions co

17/05/2012 12:16 A02E041005518 Serial No.

Destination	Start Time	Time	Prints	Result	Note	
0178013851	05-17 12:12		012/012	0K		

Note

Timer TX, POL: Polling. ORG: Original Size Setting, FME: Frame Erase TX,
Mixed Original TX, CALL: Manual TX, CSAC: CSAC: FMD: Forward, PC: PC-Fax,
Pouble-Sided Binding Direction, SP: SPECIAL Original, FCODE: F-code, RTX: Re-TX,
Relay: MBR: Confidential, BUL: Bulletin, SIP: SIP Fax, IPADR: IP Address Fax.

Result OK: Communication OK, S-OK: Stop Communication, PW-OFF: Power Switch OFF, TEL: RX from TEL, NG: Other Error, Cont: Continue, No Ans: No Answer, Refuse: Receipt Refused, Busy: Busy, M-Full: Memory Full, LOVR: Receiving length Over, POVER: Receiving page Over, FIL: File Error, DC:Decode Error, MDN:NDN Response Error, DSN:DSN Response Error.

Our Reference: T9511 / 17/2/3 GS-89

Your Reference:

17 May 2012

The Municipal Manager Msukaligwa Local Municipality P O Box 48

Attention:

Mr T Diamini Environmental Management Section

TORBIOUSE SOLUTIONS

Reg. No. 2001/080535/23

PO Box 32017, Totlusdal, 0134

414 Rustic Road Silvertondale, 0124 Pretoria

Facelmile: E-mail:

017 - 801 3851

Tel: (012) 804 1504/ 6
Fax: (012) 804 7072
e-mail: admin@torbiousesolutions.co.za

Dear Sir / Madam,

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LYD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT OF PORTION 3 OF THE FARM HIGHFLATS 252 IT.


In terms of the Act and related regulations and guidelines Local Authorities are identified as key interested and affected parties (I&AP).


We request you to evaluate the attached information on the proposed project and provide us with your written comments and/or inputs, if any, by faxing or e-mailing such within 30 days from the date of this notification. It will be assumed that you do not have any comments on the Environmental Application of the proposed project on the expiry of the 30 day response period.


Should you have any further queries please do not healtate to contact us.


Kind Regards.


10 Bilist WA VAN'T FOORT





















			1	N NI	1347 Photomatics and the second secon		PROPERTY GEGRETION PROPERTY DESCRETION PORTION 3 OF EMANING EXTERT) COORDINATES LET 26 25 11 87 3 LENG 36 27 31 13 74 E  FRO.ECT NEW PORT TOTAL CHAIR WITH A LATTICE MAST FOR MIN (PTY) LED  INFRAST ROLLOW  INFRAST ROLLOM  A LATTICE MAST FOR TOTAL CHAIR MINMALANGA  INFRAST ROLLOM  15,000  PROJECT NUMBER  ALL WARE 10 PROPER OF TOTAL CHAIR MAL WARE 10 PROPERTY DESCRIPTION  RELET 1000  REF NO 122175  RELET 1000  REF NO 122175  SCALE 1 100  REF NO 122175  SCALE 1 100  SCALE 1 100  SCALE 1 100  SHEET 9 OF 11
						2400	S AM HIGH STEEL  (MITTER STATE OF MALLE EN STEEL  MITTER STATE OF MALLE STEEL  MITTER STATE OF MALLE STEEL  (MITTER STATE STAT
	FEEDER LENGTH (m)	± 56	# 56	1.56			SAM 3-LEGGED LATTICE MAST TO  ENGINEERS DESIGN AND SPECIFICATIONS (PAINTED RED & WHITE)
	FEEDER	77B**	778"	7/6			
	FLEC						DIGECTIONAL ANTENNAE  TELECOMMUNICATIONS
	- MECH						DIRECTIONAL ANTENNAE
	HEIGHT - BOTTOM (m)	21	51	51		00015	D DUM MILDEROWAVE DISH
EKEY	ANTENNA	X 80010123	K 80010123	K 80010123			22 25 25 25 25 25 25 25 25 25 25 25 25 2
TENNA	AZIMUTH A	.0	120* K	240" K		96969- 000vg-	2x KATHREIN 90010123 DIRECTIONAL ANTENNAE
MTN ANTENNAE KEY	SECTOR AZ	-	2	6		Journ	ETHON LIGHTANA

						USED DURENSIONS TO BE CERTIFICOUS NITE BEFORE COMMENCERENT ALL WANT CHE PERFORMED ACCORDED TO THE BITE BEFUEL I TOWNER HAND TO THE
					S Am HIOH STREEL PALESCENE FEAUE WITH FLATIVINGS (GALVANUSED)  TELECOLABILINGCATIONS (OALVANUSED)  WAND SPECUFICATIONS (WHITE)  WHO SPECUFICATIONS (WHITE)  WHO SPECUFICATIONS (WHITE)	MIN
	FEEDER	± 62	* 62	1 02	(PANITED RED & WHITE)  WORN SHEGGED LATTICE MAST TO  WANTED RED & WHITE)	
	FEEDER	7/6	718"	7/10		
	FLEC				DIMECTIONAL ANTENNAE TELECOMMUNICATIONS TELECOMMUNICATIONS	į
	MECH TILT				DIRECTIONAL ANTENNAE	
	нЕКЗНТ - ВОТТОМ (m)	57	22	22	TELECOMMUNICATIONS  0 6m MICROWAVE DISH	
MTN ANTENNAE KEY	ANTENNA	K 80010123	K 60010123	K 60010123	DIRECTIONAL ANTENNAE  PANISTINA MATERIA BOOTOTO STATEMENT ANTENNAE  PANISTINA LANGUAGE  PANISTINA LANGUAGE	
ANTEN	AZIMUTH	.0	120*	240.	00000 ETHOLI MOITANA	
MTN	SECTOR	-	171	rs.	LIGHTNING SPIKE —	



TYPICAL 3 LEGGED LATTICE MAST (PAINTE)



SITE NAME

TM, 427/12/340 2000

Prints Eath 148 Prints Eng X13 Mark Park

HIGHFLATS BASE STATION NUMBER

T9511

DESCRIPTION FIRST ISSUE ₹ ¥ 16/11/2011 DATE REV

OWNER VANDER LINCE GERMANDIS PHILIPPIB JOHANNES

NOTEB

GTRICTLY COMPANY CONFIDENTIAL
PROPERTY DESCRIPTION
POSTION 3 (REMAINING EXTENT)
OF THE FARM HIGHELATS 232 IT

GOORDINATES LAT 26" 28" 11 89" 8 LONG 30" 31" 13 74" E

ROJECT

NEW 9x9m TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MTN (PTY) LTD

ADDRESS
OF THE R33 TOWARDS LOTHAR
ASUKALIGAWA
GERT SRANDE
MFURALANSA

INFRASTRUCTURE PLANNING SERVICES

ALL PLES NO.

Tel. +27 (12) 404 19040 For +27 (12) 404 7072

P.O. Des 32017 Telegraphics 0134

152068 PROJECT NUMBER 120167

DRAWNES AUST NOT BE SCALED ONLY FIGURED DIVENSIONS TO BE URBED CHARITE DETENDENCY COMMENCEMENT ALL WORK TO BE PREVIOUSED ACCOUNTS AT MINISTER BY ALL WORK TO BE PREVIOUSED ACCOUNTS. WHICH STITE BY BE WERE ACCOUNTS AND ACCOUNTS AND ACCOUNTS AND ACCOUNTS AND ACCOUNTS AND ACCOUNTS.

DATE 1811/2011
SCALE MTS REF NO 812/19511

Our Reference: T9511 / 17/2/3 GS-89

Your Reference:

17 May 2012

The Ward Councillor Msukaligwa Local Municiaplity P O Box 48 Ermelo 2350

Attention:

Clr S L Jele

Councillor: Ward 15

Facsimile:

017 - 801 3851

E-mail:



Reg. No. 2001/080535/23

PO Box 32017, Totiusdal, 0134

414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504/ 6

Fax: (012) 804 7072

e-mail: admin@torbiousesolutions.co.za

Dear Sir / Madam,

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B) : II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT OF PORTION 3 OF THE **FARM HIGHFLATS 252 IT.** 

In terms of the Act and related regulations and guidelines ward councillors are identified as key interested and affected parties (I&AP).

We request you to evaluate the attached information on the proposed project and provide us with your written comments and/or inputs, if any, by faxing or e-mailing such within 30 days from the date of this notification. It will be assumed that you do not have any comments on the Environmental Application of the proposed project on the expiry of the 30 day response period.

Please forward the attached documentation to the relevant Resident Association or provide us with their contact details.

Should you have any further queries please do not hesitate to contact us.

Kind Regards,

**WA VAN'T FOORT** 

For: Torbiouse Solutions cc

17/05/2012 12:12

Serial No. A02E041005518 TC: 908947

Destination	Start Time	Time	Prints	Result	Note
0178013851	05-17 12:08	00:04:00	012/012	0K	

Note

TX, POL: Polling, ORG: Original Size Setting, FME: Frame Erase TX, Original TX, CALL: Manual TX, CSRC: CSRC, FWD: Forward, PC: PC-Fax, P-Bided Binding Direction, SP: Special Original, FCODE: F-Code, RTX: Re-TX, MBX: Confidential, BUL: Bulletin, SIP: SIP Fax, IPADR: IP Address Fax, rnet Fax

Result OK: Communication OK, S-OK: Stop Communication, PW-OFF: Power Switch OFF, TEL: RX from TEL, NG: Other Error, Cont: Continue, No Ans: No Answer, Refuse: Receipt Refused, Busy: Busy, M-Full: Memory Full, LOVR: Receiving length Over, POVER: Receiving page Over, FIL: File Error, DC: Decode Error, MDN: MDN Response Error, DSN: DSN Response Error.

Our Reference: T9511 / 17/2/3 GS-89

Your Reference:

17 May 2012

The Ward Councillor Msukaligwa Local Municiaplity P O Box 48 Ermelo 2350

Attention:

Cir S L Jele Councillor: Ward 15

Facelmile: E-mail:

017 - 801 3851



Reg. No. 2001/080535/23

O Box 32017, Totlusdel, 0134

414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 504 1504/ 6 Fax: (012) **504 7**072 e-mail: admin@torblousesolutions.co.za

Deer Sir / Madam.

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT OF PORTION 3 OF THE FARM HIGHFLATS 252 IT,

n terms of the Act and related regulations and guidelines ward councillors are identified as key storested and affected parties (I&AP).

We request you to evaluate the attached information on the proposed project and provide us with your written comments and/or inputs, if any, by faxing or e-mailing such within 30 days from the date of this notification. It will be assumed that you do not have any comments on the Environmental Application of the proposed project on the expiry of the 30 day response period.


Please forward the attached documentation to the relevant Resident Association or provide us with their contact details.


Should you have any further queries please do not hesitate to contact us.


Kind Regards.


po Baling


WA VAN'T FOORT
For: Torblouse Solutions co





















				1267 Probebs Street Tal. 427 (12) NA STOD Probes Edge 1/8 Fall & Heinfall Complex Far. 427 (12) NA STOG Probes Edge 7/8 Fall MANGE SITE NAME	HIGHFLATS BASE BTATION NUMBER T9511	REV DATE BY DESCRIPTION A 10/11/2011 HV FIRST ISSUE	NOTES	OWNER VAN DER LINGS GERANGOLS PRELIFFIES SOUWERS		PROPERTY COMPANY CONFIDENTIAL PROPERTY COMPANY CONFIDENTIAL PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHELATS 252 IT COORDINATES LLIT 24"26" 11 59"5 LLIT 24"26" 11 59"6  ANDRESS OF THE RAST FOR MITH CHYLLID ADDRESS OF THE RAST FOR MITH CHYLLID ADDRESS OF THE RAST FOR MITH CHYLLID ADDRESS OF THE RAST FOR EXAME METHALANCIAN METHALANCIANCIAN METHALANCIANCIANCIAN METHALANCIANCIANCIANCIANCIANCIANCIANCIANCIANCI
								4 6400 1	<b>-</b> -	S An HIGH STEEL  PALLANDER ON TOPE  (CALVANISED)  TELECOMMUNICATION  MTN 2 Lx1 & MININ-D ECUIPMENT  PALLANDE FROM  MAIN PROPERION  (CALVANISED)  (CALVANISED
	FEEDER FEEDER 9.ZE LENGTH (m)		772" ± 5:0							SAM SHEGGED LATTICE MAST TO ENGINEER'S DESIGN AND SPECIFICATIONS (PAINTED NED & WHITE)
	MECH ELEC.									DIMECLIONAL ANTENNAE TELECOMMUNICATIONS DIRECTIONAL ANTENNAE
4E KEY	ANTENNA BOTTOM(m)	4	K 80010123 51					C	D0018-	DIRECTIONAL ANTENNAE  DIRECTIONAL ANTENNAE  TELECOMMUNICATIONS  DIRECTIONAL ANTENNAE
MTN ANTENNAE KEY	SECTOR AZMUTH	120.	3 240						₹ 969- 30076-	3× KATHREIN 80010123

				TA TA	STRICTLY COMPANY CONFIDENTIAL  PROPERTY DESCRIPTION  A 10/11/2011 NY FIRST ISSUE  PROPERTY DESCRIPTION  OF THE FARM HIGHFLATS 752 IT  COORDINATES  OWNER VAN IEST LIKE GERMANING EXTENT  OF THE FARM HIGHFLATS 752 IT  COORDINATES  OWNER AND THE COMMUNICATION BASES AND  WITH ALATTICE MAST FOR MITH PRIVILED  COORDINATES  LUNG 387 317 37 7F E  LUNG 387 317 37 7F E  LUNG 387 317 30 7F E  LUNG 387 317 31 7F E  LUNG 387 317 30 7F E  LUNG 387 317 31 7F E  LUNG 387 31 31 7F E  LUNG 3	SHEET 10 OF 11
					AND SPECIFICHONION ON THE MAIN STREET  CONTINIER TO ENGINEER'S DESIGNATION OF THE ENGINEER'S DES	
	FEEDER LENGTH (m)	* * * *	1 62	204	ENGINEERED DESIGN AND SPECIFICATIONS	
	FEEDER	2/2	7/10-	776	OT TZAM SUTTAL GBODSJ-E noo	
	FLEC			-	DIRECTIONAL ANTENIAGE	
	MECH TLT					
	BOTTOM (m)	29	23	6	DIRECTIONAL AUTENIAN  TELECOMMUNICATIONS  THE COMMUNICATIONS  THE	
1.	$\neg$	X 80010123	K 80010523	CZ:01009 V	0002.9	
ENNAE	AZDMUTH AN	$\top$	1	Kau N S	DIRECTIONAL ANTENNAE  3x MATHREIN 60010123  CHEGOTIONAL ANTENNAE	
MTN ANTENNAE KEY	SECTOR AZD	+	+	2	тетиним зерке ———————————————————————————————————	







1277 Presenta Street Back B. Hendricks Campian Tea 427 (13/345-908 Hendry COTS

HIGHFLATS

BASE STATION NUMBER

T9511

DESCRIPTION FIRST ISBUE REV DATE BY A 16/11/2011 HV

OWNER VANCER LINEE GERMANDUS PHILIPPIES JOHANNES

NOTES

STRICTLY COMPANY CONFIDENTIAL
PROPERTY DEGREPTION
PORTION 3 (REMAINING EXTENT)
OF THE FARM HIGHFLATS 252 IT

COORDINATES LAT 26" 28" 11 69" 3 LONG 30" 31" 13 74" E

NEW BYSH TELECOMMUNICATION BASESATION WITH A LATTICE MAST FOR MIN (PTY) LTD PROJECT

ADDRESS
OF THE R3 TOWARDS LOTHAIR
MSUKALIGWA
GERT SIBANDE
MPUAALANGA

INFRASTRUCTURE PLANNING SERVICES

AN PLE REL

T-4 - 27 (12) 424 15049 Far + 27 (12) 804 7072

P.O. P. SZBITY TAKEN OLSM

152068 PROJECT NUMBER 120167

DANIMINED INJETHOT RESIDENCE DAY FROUND DIRECHIONS TO RE-LIEDD DANIMINES ON RESIDENCE DO HATTE REFORE COMMENCERENT ALL WORK TO REFORMED ACCORDING TO MAN THE REF PREPARATION OF REFORMED ACCORDING TO MAN THE REF REALE I REVIEW ON ROW MAN TO THE THE PROPARE AND THE PROPARE TO THE PROPARE AND THE PROPARE

REF NO 812/19511 DRAWN HANS V D WALT DATE 16/11/2011
SCALE NIS REF NO 812/1951

REGISTERED LETTER TOSII GEREGISTREERDE BRIEF (with an insurance option/met 'r. versekeringsopsie)	Postage paid R c  Service fee / Diensgeld R c  Insurance / Versekering R c
Full tracking and tracing/Volledige volg en spoor	Total / Totaal Rc
Addressed to/Geadresseer aan High Flots Boendery (Pey) und P.O. Box 210	Versekerde waarde van inhoud R
Ermelo 2350 Postcode Poskinde The value of the contents of this letter is as indicated and compensation is not payable for a letter	Toll-free number Tolvry nommer 0800 111 502
documentary proof Optional insurance up to R2 000 00 is available and applies to domestic registered letters only:  Die manne van met fillhout van hierite oner is abos sergedul en vergoeding sal nie betaat word vir in hierit voor heheud envirange auth ein vergoeding is behank tot R100 00. Geen vergoeding is somet hilly will have bevorg betaande in the vergoeding is behank tot R100 00. Geen vergoeding is somet hilly will have bevorg betaande in the vergoeding is somet hilly confirmed betaat word vergoeding is	Affix Track and Trace REGISTERED LETTER Ith a domestic insurance option) D /48 008 722 2/A Paraal van aaneem- beample Datumstempel
REGISTERED LETTER T951 GEREGISTREERDE BRIEF (with an insurance option/met 'n versekeringsopsie)	Postage paid R c  Service fee / Diensgeld R c  Insurance / Versekering R c  Total / Total R c
Full tracking and tracing/Volledige volg en spoor	
Addressed to/Geadresseer aan Lion Match Forestry (R-y) Utd P.O Box 918	Insured value of contents  Versekerde waarde van inhoud R
Ourban 4000 Postode	Tolvry nommer 0800 111 502
The value of the contents of this letter is as indicated and compensation is not payable for a letter received unconditionally. Compensation is limited to R100.00. No compensation is payable without documentary proof. Optional insurance up to R2 000.00 is available and applies to domestic registered retiters only.  The wagnor with this content in the content of th	Affix Track and Trace REGISTERED LETTER h a domestic insurance option) coal 9860 117 502 www sape, co 72 D 748 008 719 ZA STOMER COPY 301028R  Paraaf van aaneem- beample  Registered Letter a domestic insurance option) anneem- beample
REGISTERED LETTER T9511 GEREGISTREERDE BRIEF (with an insurance option/met 'n versekeringsopsie)	Postage paid Rc  Service fee / Diensgeld Rc  Insurance / Versekering Rc
Full tracking and fracing/Volledige volg en spoor	Total / Totaal Rc
	nsured value of contents  Versekerde waarde van inhoud R
P.O Box 423	Enquiries/Navrae Initial of accepting accepting officer
Lothair 2370 Pustcode	Tolvry nommer 0800 111 502
(with	AGENT Transit and
Intelligence of the coordinate of the co	748 008 696 ZA  OMER COPY 3010zer Paraaf van aaneem beampte Datumstempel

REGISTERED LETTER GEREGISTREERDE BRIEF (with an insurance option net in versekeringsopsie)	Postage paid R
Full tracking and tracing/Voiledige velg en spoor Addressed to/Geadressed nam	Insured value of contents  Versekerde waarde van inhoud Rc
PO Box 4637 Cape Town 8 MO Postorda	Enquiries/Navrae Toll-free number Tolvry nommer 0800 111 502
The value of the contents of this letter is as indicated and compensation is not payable for a letter received unconditionally. Compensation is limited to R100.00. No compensation is payable without documentary proof. Optional insurance up to R2.000.00 is available and applies to domestic registered letters only.  Die waarde van me in oud van hieritie time! is coor sangedui en vergoeding set me betaal word vir 'n brief wit sooder optionally coloring wind die. Cestimet with second coloring with the coording is access represented by behalf with the coordinate with the coloring with the coordinate with the coloring with	REGISTERED LETTER (with a gomestic insurance option) ShareCall 0560 111 502 www.sapc.co.22  RD 748 008 682 ZA  CUSTOMER COPY 301028R aaneembeampte  Datt/mstempel

17 May 2012

South African Heritage Resources Agency P O Box 4637 Cape Town 8000



Reg. No. 2001/080535/23 PO Box 32017, Totiusdal, 0134 414 Rustic Road Slivertondale, 0184 Pretoria

Tel: (012) 804 1504 / 6 Fax: (012) 804 7072 e-mail: admln@torblousesolutions.co.za

### **DEAR SIR/MADAM**

INTENTION TO SUBMIT AN APPLICATION IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 AS AMENDED ("NEMA") TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 (A) & (B): II (EE) IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION BASE STATION ON REMAINING EXTENT PORTION 3 OF THE FARM HIGHFLATS 252 IT.

We are acting on behalf of MTN (Pty) Ltd in order to apply to the Mpumalanga Department of Economic Development, Environment and Tourism to establish a telecommunication base station on Remaining Extent of Portion 3 of the Farm Highflats 252 IT.

### Attached hereto find:

- 1. Public Participation notice
- 2. Site Development plan
- 3. Facility Illustration

Should you have any further queries, please do not hesitate to contact us.

Yours faithfully

WA VAN'T FOORT
For: Torbiouse Solutions CC

# PUBLIC PARTICIPATION PROCESS

17/2/3 GS - 89 REFERENCE NUMBER:

an enclosed ਰੱ Regulation 546 activity 3 (a) & (b) : ii (ee) : Establishment telecommunication base station with a 54m mast for MTN (Pty) Ltd: Highflats

Remaining Extent Portlon 3 of the farm Highflats 252 IT Location:

20-ordinates (WGS84 format) of the alternatives on the above property.

Longitude: 30° 31' 13.74" E (Lattice type mast painted red and white) Latitude: 26° 28' 11.69" S Alternative 1:

the National Environmental Management Act 1998 (Act No. 107 of 1998) as Notice is hereby given of a public participation process in terms of the Environmental mpact Assessment Regulations 2010 (R543) as amended promulgated in terms of amended ("NEMA").

Basic assessment procedures will be applied in accordance with regulation 543 and an application is to be submitted to the Mpumalanga Department of Economic Development, Environment and Tourism. The applicant furthermore intends to apply to the Mpumalanga Department of Economic Development, Environment and Tourism for exemption in terms of regulation 50(1) of the Environmental Impact Assessment Regulations 2010 (R543) to assess alternatives with regard to the planned activity.

### Applicant:

MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

# Environmental Assessment Practitioner (EAP):

Torbiouse Solutions CC.

P.O. Box 32017, Totiusdal, 0134

Attention: W A van't Foort

Felephone: (012) 804 1504/6; Facsimile: (012) 804 7072

E-mail: admin@torbiousesolutions.co.za

Further information regarding the proposed activity can be obtained from the EAP.

Any interested and affected party may, in writing, make representations on the physical & postal addresses (including facsimile & e-mail where possible) and proposed activity or request to be registered as an interested and affected party, by contact number(s) and quoting the activity reference number, to the EAP within 30 submitting the written representations or registration request, including their name, calendar days from the publication of this notice.

Notice publication date:

17 May 2012

# UHLELO LOKUHLANGANYELA KOMPHAKATHI

NOMBOLO YEREFERENSI: 17/2/3 GS - 89

Isakhiwo esiyisizinda sezokuxhumana ngocingo esivalekile se-MTN (Pty) Ltd ene-mast engama-54m kanye Umyalelo womthetho 546 umsebenzi 3 (a) & (b) : ii (ee) : nendawo (nezindawo) yokubeka impahla: T9511 Highflats

Indawo: Remaining Extent Portion 3 of the farm Highflats 252 IT

izindawo zezizinda ezihlukile ezifana nalesi esingenhla (WGS84 isimo sokwakheka); Ezinye

Ubude: 30° 31' 13.74"E Induku ye-lattice ependwe ngokubomvu nokumhlophe Ububanzi: 26° 28' 11.69"S Esihlukile 1:

njengoba ichibiyelwe yamenyezelwa Vgalokhu kunikezwa isaziso senqubo yokubamba iqhaza komphakathi ngokuhambisana Nemithetho Yokuhlola Umthelela Wamandla Kwezenhlalo (i-Environmental Impact ngokuhambisana Nomthetho Wokuphatha Ezenhlalo Kuzwelonke (i-National Environmental Management Act) ka-1998 (Umthetho weNombolo-107 ka-1998) Assessment Regulations) ka-2010 (R543) njengoba uchibiyelwe (i-"NEMA").

ukuze akhululwe ngokwemibandela yomthetho 50(1) weMithetho Yokuhlolwa Kokuthinteka Kwemvelo ka-2010 (R543) ukuze ahlole ezinye izindlela zokuqhubeka ezlyisisekelo zokuhlola zizosetshenziswa ngokuvumelana nemiyalelo yomthetho 543 bese kufakwa isicelo eMnyangweni Wezolimo, Ukunakekelwa kanye neZemvelo WaseMpumalanga. Umenzi wesicelo uhlose futhi ukwenza isicelo kuMnyango Wezolimo waseMpumalanga, Ukulondolozwa Kwamagugu Nezemvelo nomsebenzi ohleliwe. zingubo

## Umuntu ofaka isicelo:

MTN (Pty) Ltd, P.O. Box 4559, Northcliff, 2115.

slsebenzl Esihlola Ezemvelo (Environmental Assessment Practitioner (EAP)): orbiouse Solutions CC., P.O. Box 32017, Totiusdal, 0134


kuqondiswe ku- W A van't Foort


Ucingo: (012) 804 1504/6, Ifeksi: (012) 804 7072, e-meyili: admin@torbiousesolutions.co.za

Nanoma ubani omunye othandayo nothintekayo, ngokubhala, makenze isitatimende ngomsebenzi ohlongozwayo noma isicelo sokubhaliswa njengomuntu onothando noma kanye nezinombolo zokubathinta futhi basho nenombolo yereferensi yomsebenzi, kuothintekayo, ngokuthi alethe isitatimende esibhaliwe noma isicelo sokubhalisa, namagama abo, ikheli lendawo neleposi (kufakwe ifeksi ne-e-meyili uma kunokwenzeka) EAP ezinsukwini zekhalenda ezingama-30 kusukela ekushicilelweni kwalesi saziso. Olunye ulwazi maqondana nalo msebenzi ohlongozwayo lungatholakala ku-EAP.

Usuku lokushicilelwa kweSaziso:

17 May 2012





TYPICAL 3 LEGGED LATTICE MAST (PAINTED RED AND WHITE)



1387 Frederica Broad Tel. +27 (13) 342 2500 Fee: +27 (15) 342 2500 Fee: +27 (15) 342 2200

DESCRIPTION HIGHELATS
BAGE STATION NUMBER 18/11/2011 HV FIRBT 19SUE B REV DATE

OWER VANDER CARAMILIA PALLIFILI LINAARG

STRICTLY COMPANY CONFIDENTIAL PROPERTY DESCRIPTION PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT

COORDINATES LAT 28' 28' 11.69' B LONG 39' 31' 13.74' E

NEW BYTH TELECOMMUNICATION BASEBATION WITH A LATTICE MART FOR MTN (PTY) LTD

ADDRESS
OF THE R33 TOWARDS LOTHAIN
MUNICIONAL GAR
GERT STRANDE
MPUMALANGA

INFRASTRUCTURE PLANNING FFVICES

Tel. -27 (17) 804 (1044) Fax -27 (17) 804 7072

P.O. Ben 32017 Telegraph 0134

RFG NO 1520AD PROJECT NUMBER 120107

DRAWNARD MAIN NOT DE STALED, CHR. V PRUMED CHROSENSE TO DE UNDER COMPENSOR OF MATERIAL C

### G1(c) - SACAA Approval

### SOUTH AFRICAN



Physical Address: Ikhaya Lokundiza Treur Close Waterfall Park

Bekker Street

Midrand

Postal Address: Private Bag X1 Halfway House

1685

Telephone Number: +27 11 545 1232

E-ma l'Address: obstactes@caa.co.za

o45 1232 obstacle

Fax Number: +27 11 545 1451 Website Address: www.caa.co.za

CR

### OBSTACLE FOR APPROVAL CAA Obstacle ID: CAA\_2012\_8\_001 **APPLICANT** Contact Person: Asha Govender **OWNER** Company Name: Mobile Telephone Networks (Pty) Lt CompanyName: Mobile Telephone Networks (Ply) Ltd Phone Number: (011) 912-3000 ContactPerson: Asha Govender Cell Number: (083) 212-4863 PhoneNumber: (011) 912-3000 Email address: Govend\_A@min.co.za CellNumber: (083) 212-4863 VATNumber: 4630140434 Email: Govend\_A@mln.co.za Address: MTN Innovation Center, 216 14th A City: Roodepoort State: Gauteng ZipCode: 2195 **DETAILS OF PROPOSED STRUCTURE** Type of Structure Constructtion Start Dat Tower Site ID Number: T9511 Construction End Date: Site Name: Highflats Lat\_degree: 26 Lat\_minute: 28 Lat\_seconds: 11.69 Long\_degree: 30 Long\_minute: 31 13.74 Long\_seconds: 1641 Coordinate Data Source Handheld GPS (non surv Site Elevation\_m: Structure Height\_m: 54 Coordinate Other Sub Structure Heigh\_m: 0 Height to top of Structure\_m: 1695 Elevation Data Source Handheld GPS (non surv GuyWireJib\_m: Elevation Other: Datum: Application Date 01/08/2012 Type of Application: Replacement Shared New Received Date: 31/08/2012 Notes: Conditions: None Attached Documents: This application replaces approval ID: CAA\_2012\_1\_124Co-Dayl larkings ☐ SurveyReport ordinales changed NightMarkings [ SketchDiagram DayNightMarkings 🖾 ☐ GISCoverage OtherSpecial Other Approved Not Approved AGG AFRICAN CIVII. MUNTION AUTHORITY Koos Pretorius Act.Manager: A.O.G. Date

G1(d) - Proof of Newspaper Advertisement

E-mail CV to: hr@mbf.co.za

## O Bayport

URGENTLY NEEDED

## Legals

blic & Legal

mental Assessment ner (EAP): se Solutions CC. r. W Avan't Foort x 32017. II, 0134 ne: 012-804-7072,

CAL

OBS

0910 Public / Legal Notices

ERENCE NUMBER:
3 GS - 99
3 GS - 99
3 GS - 99
3 GS - 80
3 Id (ac) Establishment of closed telecommunication station with a 54m mast TN (Pty)\_Ltd:
7 Country Trax
10 cn. Portion 2 of the farm zocht 383 IT
zocht 383 IT
zocht 383 IT
zocht 383 IT
dinates (WGS84 format)
alternatives on the above PARTICIPATION

NOTICE PARTICIPATION

ERENCE NUMBER:
3 GS - 89
3 Idation 548 activity 3 (a) &
(ee): Establishment of an
used telecommunication
station with a 54m mast
TN (Pty) Ltd:
1 Highflats
tion: Remaining Extent of
To, 3 of the farm Highflats
T.

tive 1: e: 26° 58° 10.16" S ide: 30° 11° 20.90" E type mast painted red

ative 1: de: 26° 28` 11.69" S tude: 30° 31` 13.74" E e type mast painted red hite nates (WGS84 format) ternatives on the above

orbiouse Solutions CC.
Itternion: W A van't Foort
O. Box 32017,
Vilusdal, 0134
Hephone: 012-804-1504/6;
Icsimile: 012-804-7072,
mail: admin
orbiousesolutions.co.za
ther information regarding
proposed activity can be
ained from the EAP,
interested and affected
y may, in writing, make
esentativity or request to
gistered as an interested
iffected party, by
itting the written
seriations or registration
st, including their name,
al & postal addresses
ling facsimile & e-mail
possible) and contact
r(s) and quoting the
reference number, to the
thin 30 calendar days
yublication of this

CLASSIFIEDS

Fax 013-753-2422 Tel 013-754-1600 

## \*VACANCIES

valid Code 14/EC driver's licence, with a min of 3 years' driving experience on this lic A valid Dangerous Goods Driver's P Interlink/superlink experience The abili

te: Applicants must include hentic references and fication with their applications

licence/PRDP

rry@sigroup.co.za or devi@sigroup.co.za or contact Henry at 079 476 2944/
0861 744 768.

STAFF INITIATIVES

Kindly send all applications to fax: 086 517 2484 or e-mail:

Code 14/EC (DGP) Drivers
Urgently Required

ic (Grade 12) • A

## ESPE INNING PROPERTY

WITH STUNNING VIEW
WED 30 MAY 2012 at 11:00 at

off to a flying start Get your career

SA Express is calling on all students who are looking to kick-start their careers, working for one of the fastest growing Regional Airline in Africa. Established on 24 April 1994, SA Express plays a significant role in the country's hospitality, travel and tourism industry and is a vital contributor to the country's socio-economic development.

owing business areas:

If you have traceable references and the relevant experience your CV to fanies@workforce.co.za or fax to 086 231 9381

Riggers

Diesel Mechanics/Fitters with a sound knowledge of Hydraulics
30 Ton Mobile Crane Operators (Code 14 (EC) Essential)

Grader Operator

Underground Trackless Operators for LHD, Drill Rig and Dump Truck

enue Management tomer Service and Marketing mical Services

workforce

evenue Managemen zing will offer a opportunity for rters to develop plement plans that the additional revenu araner will be provid g focused on indust ics and airline mics. In addition, a will be assigned to dividual.

arner will be expect alop forecasts and

WILDLIFE ECONOMY PROJECT

**KRUGER NATIONAL PARK SOUTH** 

TEMP PROJECT ADMINISTRATOR

INVASIVE SPECIES CONTROL UNIT

ARKETING

ARKETING

tole: Caring for our

ustomers is an important

lement for the airline,

way to distinguish the

irline from its competito

with the ever increasing

NICAL
RENTICESHIP
RENTICESHIP
RENTICESHIP
RENTICESHIP Indergo prescribed raining at an raining at an training facility go prescribed at Training at SA s Technical division Theoretical trainin

plete and pass Trade at an accredited centr cation requirements: It have Grade 12 or N3 Maths and Science Higher grade and ower grade).

INANCE

XPERIENTIAL LEARNERS

ole: To provide individuals

e environment in able to put theory

OPERATIONS CONTROL
CENTER LEANERSHIP
FLIGHT OPERATIONS.
Purpose of the experientiearning programme:
the program will provide
individuals holding

bout the programme he duration of the cogramme is Eight (8) cogramme is Eight (8) rooths. The successful andidates will gain exposure in the AMC. Reparture control system, tamp operations; Dispatch tamp operations control ystems and processes in arrivation Airline Industry, siducation requirements: sade 12 and aviation.

of certificates and ID document, to the Human Re a 0001 or fax: (012) 426-5588 or e-mail: jobapplic l date: 24 May 2012

tion up to 1 November 2012, ren-


ed CV, covering letter and certified tesources Department, PO Box 787,

osing date, please assume that your

bscribes and is committed to the principles of employment equity and equal appointments will be made in terms of SANParks' Employment Equity policy. SANParks reserves the right not to make an appointment.

Appointment to this position would be done in accordance with SA Express' Employment Equity larget and policy, Preference would be given to candidates who are Previously Disadvantaged Individuals as defined. Corresponder will only be entered into with short-listed candidates.





G2: Motivation for Exemption of assessing alternatives

Our Reference:

Your Reference:

T9511 Highflats

17/2/3GS-89

11 September 2012

Mpumalanga Department of Economic Development, **Environment and Tourism** The Deputy Director **Environmental Impact Management** Gert Sibande District Office 13 de Jager Street Ermelo 2350

Attention:

Mr Bheki Mndawe

Fax No:

072 814 5409

E-mail:

bemndawe@mpg.gov.za

Dear Sir,



Reg. No. 2001/080535/23

PO Box 32017, Totiusdal, 0134

414 Rustic Road Silvertondale, 0184 Pretoria

Tel: (012) 804 1504/6

Fax: (012) 804 7072

e-mail: admin@torbiousesolutions.co.za

MOTIVATION FOR EXEMPTION FROM ASSESSING ALTERNATIVES IN TERMS OF THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT 1998 ("NEMA") AS AMENDED TO THE COMPETENT AUTHORITY FOR LISTED ACTIVITY 3 IN REGULATION 546: ESTABLISHMENT OF A MTN (PTY) LTD TELECOMMUNICATION MAST ON PORTION 3 (REMAINING EXTENT) OF THE FARM HIGHFLATS 252 IT.

In terms of Regulation 50 of the EIA Regulations, August 2010, as contemplated in subregulation 22 (2)(h), we hereby apply for exemption from assessing alternatives in this application.

### Motivation:

### (a) The property on which or location where it is proposed to undertake the activity:

The Portion 3 (Remaining Extent) of the farm Highflats 252 IT, where the establishment is proposed was identified by the radio planners of MTN as the best position to place the mast to reach the transmission coverage on the MTN network. The site is on a farm with disturbed grassland. Environmental impact at this site and on this property will be limited to the visual aspect, as well as the grass that need to be removed from the 81m<sup>2</sup> footprint area. The development is planned open grassland where no large trees or any endangered plants will need to be removed. The neighbouring properties were not regarded as feasible site alternatives due to more limitations on the network coverage, as well as possible increased impact on the site footprint area where more indigenous vegetation would have to be removed. The environmental impact on the footprint area would most probably be of much higher significance if the site was moved to another locality within a certain radius from the proposed site.

### (b) The type of activity to be undertaken:

There are no type alternatives available or feasible to replace the establishment of telecommunication masts.

### (c) The design or layout of the activity:

The proposed design of the activity is a 54m high lattice telecommunication mast. The 54m height is required to reach the transmission network coverage on the MTN network. The lattice type mast is the only design alternative that provides the required equipment capacity and wind-load capacity. A monopole type mast is not considered a feasible option for this specific development because of more restrictions with regard to the equipment and wind-load capacity. Further disadvantage of a monopole type mast is increased visibility due to the more solid type structure against the sky background. The SACAA (South African Civil Aviation Authority) requires day and night markings for all masts above 45m of height, meaning the mast has to be painted red and white with red lights on top for maximum visibility to aircraft to prevent aircraft accidents. Therefore, the only feasible design alternative that is considered as Alternative 2 in the Basic Assessment Report, is a 60m high lattice mast painted red & white. No other design or colour alternatives are considered to be feasible due to the red and white colour requirement of the SACAA.

### (d) The technology to be used in the activity:

MTN Kathrein directional antennae (x3) and 600mm Microwave dish to be placed at top of mast. Telecommunications directional antennae (x6) to be placed underneath the dish antennae by possible future share parties. MTN mini-D equipment container (with extension) to be placed on ground level under the mast. Telecommunication equipment container to be placed next to MTN container under mast. 2 New MTN standard concrete manholes for future fibre optic link with 110mm underground nextube sleeve for fibre optic cable from the manhole to the equipment container. The proposed technology used for this mast will have minimum impact on the environment and there is no alternative technology available to reach the required network coverage.

### (e) The operational aspects of the activity:

- Increased electricity consumption on the existing supply grid: The infrastructure is designed to operate on
  economical electricity consumption. A generator will be installed as a backup electricity supply in the event of
  a power failure. There are no feasible alternatives available to replace electrical power supply.
- Noise generation by air conditioning units and by backup generator if electricity supply fails: The air conditioning units and backup generator operate at very low and well accepted noise levels. There are no feasible alternatives to replace the air conditioning units or the backup generator.
- Non-ionising electromagnetic fields on allocated frequency: The electromagnetic fields are well below the
  accepted level to prevent any damage to living organisms (within International Commission on Non-ionising
  Radiation Protection, ICNIRP, and World Health Organisation, WHO, guidelines) and are restricted within the
  allocated frequency. There are no feasible alternatives to obtain the required network coverage within the
  allocated frequency.
- Increase in potential air traffic obstacles: Lower mast options are not feasible alternatives to reach the
  required network coverage as this would require multiple mast applications to reach the same network
  coverage with increased environmental impact on the footprint area of several masts as well as increased
  visual impact on each separate mast development.
- Visual impact of the 54m (Alt1) or 60m (Alt2) lattice mast painted red & white on short, medium and long distance observation: Other design, height or colour alternatives are not feasible as prescribed above.

We trust that the above motivation is sufficient to consider and approve this application for exemption from assessing several site alternatives.

Kind Regards,

Wilbert van't Foort

For: Torbiouse Solutions cc