



# MYEZO ENVIRONMENTAL MANAGEMENT SERVICES

*Environmental Stewardship*

**GIJIMA – ARBOR RAILWAY SIDING – BASIC ASSESSMENT REPORT**

**ARBOR RAILWAY SIDING BASIC ASSESSMENT REPORT FOR PROPOSED OPERATIONS  
OF A RAIL SIDING TO STORE, HANDLE AND RAIL COAL, MPUMALANGA PROVINCE**

**Document Name: GAB – R – Updated BAR**

**Volume 3 of 3 – Specialist Reports**

**Date: 30 January 2020**

**Rev 3.0**

**DARDLEA Ref: 1/3/1/16/1N-213**

**Myezo Ref No: GAB 2018/11**

## List of Annexures

- **Volume 1 of 3 – BAR**
- **Volume 2 of 3 – EMPr**
- **Volume 3 of 3 – Specialist Reports**

- **Volume 1 of 3 – BAR**

Annexure 1.3-1: The copy of the commitment from Eskom in relation to the envisaged monthly tonnage.

Annexure 1.4-1: An application for the expansion of the lease area to Transnet Freight Rail (TFR) has been submitted by Gijima and a recent communique in relation to the progress of the application

Annexure 1.5-1: Water Use Licence (WUL) on the 8 December 2015 (Licence No. 04/B20F/G/4009)

Annexure 2.1-1: EAP CV

Annexure 2.1-2: Company Profile

Annexure 5.8-1: EMPr Environmental Authorisation

Annexure 6.1-1: Minutes of Meeting convened with Adi Environmental

Annexure 6.1-2: Comments to the BID and Scoping Report

Annexure 11.1-1: IAP Register

Annexure 11.1-2: Outcomes of meetings

Annexure 11.2-1: Site Notices (English, isiZulu, Setswana Translation)

Annexure 11.3-1: Background Information Document

Annexure 11.5-1: Proof of newspaper advert

Annexure 11.5-2: Proof of site notice

Annexure 11.5-3: Reply Slip (English)

Annexure 11.5-4: Site Notice distribution

Annexure 11.5-5: Notification email to IAPs

Annexure 11.5-6: Notification letter to authorities

Annexure 11.5-7: IAP Site Notice Distribution

Annexure 11.5-8: Comments received (email etc)

- **Volume 2 of 3 – EMPr**

Annexure 1.1-1: EAP CV

Annexure 1.1-2: Company profile

Annexure 1.1-3: Copy of commitment from ESKOM

Annexure 1.1-4: Communique in relation to the lease agreement for Southern Side

Annexure 1.1-5: EMPr Environmental authorisation

Annexure 1.1-6: Water Use Licence

◦ **Volume 3 of 3 – Specialist Reports**

Annexure 16.2-1: Water Management Plan for the proposed increase in scope activities

Annexure 16.2-2: Integrated Water and Waste Management Plan (IWWMP)

Annexure 16.2-3: Rehabilitation Strategy Implementation Programme

Annexure 16.2-4: Soil Chemistry Report

Annexure 16.2.5: Heritage Specialist Report

Annexure 16.2.6: Biodiversity Management Plan

Annexure 16.2-7: Stockpile Coal Handling Capacity Report

**Annexure 16.2-1: Water Management Plan for the proposed increase in scope activities**

---

Report produced by P.E.C.

---

Compiled by

**I. van der Linde**  
Pr.Eng

ECSA Registration no: 980531  
E-mail: sakkievd@telkomsa.net  
Mobile: +2773 692 9602

P.O. Box 2966  
Ermelo  
2350

---

On

**The water management plan for the proposed extension of the existing siding on the southern side of Arbor Station**



---

For the client


**Gijima Supply Chain Management Services (Pty) Ltd**

**Reg. No.: 2001/015676/07**

---

Signoff

Engineer: I. van der Linde



Date: 2018/09/08

Client: \_\_\_\_\_

\_\_\_\_\_

Date: \_\_\_\_\_

---

Date: September 2018

## Table of contents

<b>Item</b>		<b>Page</b>
1]	Introduction	3
2]	Site location	4
3]	Phasing in of infrastructure	4
	3.1] Layout for phase 1	5
	3.2] Layout for phase 2	6
	3.3] Water management strategy	7
	3.4] Soil sealing arrangements	7
4]	Metrological data	11
5]	Water runoff calculations	11
	5.1] Storm water catchment area	11
	5.2] Dirty water catchment area for phase 1	12
	5.3] Dirty water catchment area for phase 2	12
	5.4] Runoff calculations	13
	5.5] Water balance	13
6]	Water management infrastructure	14
	4.1] Storm water channel	14
	4.2] Dirty water drains	15
	4.3] Culvert pipes	15
	4.4] Silt trap	15
	4.5] PCD	16
	4.6] Pump	16
7]	Conclusion	16
 <b>Annexures:</b>		
	Annexure A Channel Sizes	17
 <b>Drawings:</b>		
	General layout	19
	General layout – Phase 1	20
	General layout – Phase 2	21
	Catchment Areas	22
	Infrastructure – PCD & Silt trap	23
	Infrastructure – Drainage	24
	Infrastructure – Sealing arrangements	25

## 1] Introduction:

Gijima Supply Chain Management Services (Pty) Ltd (Gijima for short) is currently operating a coal loading facility on the northern side of Arbor Station. This facility is not very conducive for the staging and loading of trains and it was decided to also develop the southern side of the station as a loading facility in order to increase the overall loading capacity of the siding. However, due to the shortage of funds it was also decided that this development will be phased in on a piecemeal basis and the income generated from this facility will fund the capital requirement for the development.

It is the intention to utilize the two lines next to the existing platform (indicated as red and yellow lines on the drawings) as the future loading lines. All the other infrastructure required to comply with the various regulations will eventually be placed within the existing Transnet boundary as shown in yellow shading on Figure 1.



Figure 1: Proposed site for the future expansion of the existing facility

## 2] Site location:

Arbor Station is located in the Mpumalanga Province right next to the R555 highway between the towns of Delmas and Ogies. It is surrounded by the towns of Delmas, Kendal and Balmoral. The GPS coordinates of the station building at Arbor are 26° 02' 25.95" S and 28° 52' 59.60" E.



**Figure 2: The location of Arbor Siding**

The area in question is situated to the south of Arbor station as indicated on Figure 1 and is approximately 6.4ha in size.

## 3] Phasing in of the infrastructure:

It is the intention to initially use the infrastructure “as is” with the minimum construction possible to modify the site in order to stockpile the coal and load it on to the trains. For the sake of the ease of reference this stage will be called “Phase 1”. The infrastructure which will be constructed in phase 1 will be in line with the future infrastructure requirement for phase 2.

Phase 2 will represent the completed works to stockpile 17 000 tons of coal and a throughput of 72 000 tons per month. The water management calculations will be done for this scenario.



### 3.1] Layout for phase 1:

The terrain will only be cleared and leveled and some minor earthworks will be required to enable the front end loaders to get to the rail track structure to load the tractors. Figure 3 gives the proposed startup layout for phase 1.

A storm water drain and berm wall will also be installed on the TFR boundary line to divert the runoff storm water away from the siding in order to separate the clean and dirty water systems.



Figure 3: Layout for Phase 1



Cross-section of the siding for phase 1

Figure 4: Cross section for phase 1

### 3.2] Layout for phase 2:

Line 6 will be moved to the TFR boundary which will then encapsulate the dirty area between line 5 and line 6. In order to manage and contain the polluted runoff the following items are added to the basic layout design: See Figure 5

- Redirecting the contaminated water flow
- Adding a silt trap
- Adding a Pollution Control Dam (PCD)



Figure 5: Layout for Phase 2





Figure 6: Cross section for phase 2



### The silt trap:


Sealing the silt trap is similar to the PCD except that the floor or ramp will be covered with a 200mm thick concrete slab.



**Figure 8: Sealing arrangements for the silt trap**

### The stockpile areas:

Spray a 1mm thick bitumen layer on top of the prepared surface area for the stockpiles and cover it with a 150mm low permeable material (such as a clayey discard layer). As soon as water is added (which will be daily) the very fine particles will settle at the bottom of the layer to form a very effective natural seal. This seal will “grow” over time as the vehicle wheels pulverize the surface particles and the seal will become even more effective.




**Figure 9: Sealing arrangement for the stockpiles**

**The dirty water channels:**

**Subsurface drains:**

Unfortunately the dirty water catchment drains have to run through the centre line of the stockpile areas for this specific kind of loading area layout. For maintenance and safety reasons it would be better to install subsurface drains to collect and discharge the dirty water in this case.


The subsurface drains will effectively be 500mm x 500mm in size. The drains will be lined with a 1.5mm HDPE liner and the water will permeate to the drainpipe by means of a thick geo-fabric and a coarse sand fill at the top as shown in Figure 10. The slope of all the subsurface drains will be 1:1000.



**Figure 10: Layout for the subsurface drains**

**Surface drains:**


Open drains will be lined with a 1.5mm HDPE liner and weighed down at the bottom by means of either sand bags, hand stone or even coarse gravel.




**Figure 11: Sealing of the open drains**

**Underfloor drainage:**

According to the “Class C” specification for landfills subsurface drains have to be installed below the floor of the PCD for monitoring purposes. Due to the relatively small size of the PCD a single ring drain at the floor edges will suffice. Although the final ground levels for phase 2 are yet unknown it will be assumed that the outlet of the ring drain will daylight inside the storm water channel. These drains are indicated on Figure 5 by the red lines.



**Figure 12: Layout of the underfloor drains**



**Figure 13: Layout of the drains and pipes**

#### 4] **Metrological data:**

The following metrological data were used to calculate the expected runoff volumes for the relevant areas and infrastructure:

- Rainstorm with a 1:50 year return period
- 2 hour storm duration
- Precipitation of 650mm per year
- Evaporation =  $1.5 \times \text{Area} \times \text{temperature} / 20$  in  $\text{m}^3$  per year
- Average temperature is  $18^\circ\text{C}$
- Runoff factor of 0.2 for the storm water due the agricultural nature for most of the catchment area
- Runoff factor of 0.4 for the dirty water runoff on the siding

#### 5] **Water runoff calculations:**

##### 5.1] **Storm water catchment area:**

The size of the catchment area according to Google Earth is about 49.6ha – see the blue shaded area on Figure 14.



**Figure 14: Storm water catchment area**

### 5.2] Dirty water catchment area for phase 1:

The size of the polluted area will be about 3.8ha – see purple shaded area on Figure 15.



Figure 15: Polluted area for phase 1

### 5.3] Dirty water catchment area for phase 2:

The size of the polluted area will be about 5.0ha – see purple shaded area on Figure 16.



Figure 16: Polluted area for phase 2



## 5.4] Runoff calculations:

Table 1 gives the expected runoff figures for a 1:50 year rainstorm for the three different areas in question.

STORMWATER CALCULATIONS				
Arbor Siding				
INPUT DATA MACRO SYSTEM		(1 in 50yr Storm)		
Mean Annual Rainfall R	(mm/yr)	650		
Frequency F	(yr)	50		
Time lapse T	(minutes)	120		
Catchment Area A Total	(Ha)	50		
Area		Intensity(mm/hr)	Discharge Q (m <sup>3</sup> /s)	Volume V (m <sup>3</sup> )
Storm water	(Ha)	53.2	1.5	10,556
Runoff factor	%			
Dirty water phase 1	(Ha)	53.2	0.2	1,575
Runoff factor	%			
Dirty water phase 2	(Ha)	53.2	0.3	2,128
Runoff factor	%			
Total Runoff (m <sup>3</sup> /s)				14,259

Table 1: Estimated 1:50 year water runoff figures

The following equation can be used to calculate the annual expected runoff volumes for each area:

$$\text{Volume} = \text{Area} \times \text{annual precipitation} \times \text{runoff factor}$$

For phase 1:

$$\text{Dirty water volume} = 37\,000 \times 0.65 \times 0.4 \approx 9\,600\text{m}^3$$

For phase 2:

$$\text{Dirty water volume} = 50\,000 \times 0.65 \times 0.4 \approx 13\,000\text{m}^3$$

## 5.5] Water balance:

Estimated evaporation:

Assume that the water surface area in the PCD is 2 000m<sup>2</sup> and the evaporation calculation is also only valid for phase 2 then:

$$\Rightarrow \text{Water evaporation} \approx 1.5 \times \text{Area} \times \text{Ave Temp}/20 = 1.5 \times 2\,000 \times 18/20 \approx 2\,700\text{m}^3/\text{year}.$$

## Water balance:

As stated in item 3.3 the annual water need for recycling will be  $27\,000\text{m}^3$ .

Water balance = inflow – outflow =  $13\,000 - 2\,700 - 27\,000 = -16\,700\text{m}^3/\text{year}$  or a deficit of 55 700 liters per day ( $\approx 4 \times$  Water bowsers per day).

The implications of having a negative water balance are:

- An additional water source will have to be identified. One option will be to divert some of the storm water runoff into the dam as well.
- The capacity of the PCD must therefore only cater for the 1:50 year rainstorm which will, according to Table 1, be in the order of  $2\,200\text{m}^3$ .


## 6] Water management infrastructure:

Currently the existing natural slope along the length of the siding is in the order of 1:45 and this figure will be used for the calculation of the size of the storm water drain.

However, the surface level of the siding for phase 2 will have to follow the level of the existing railway line which is sloping down towards the west at an angle of 1:100. This slope will be used to determine the sizes of the dirty water channels.

### 6.1] Storm water channel:

The channel falls about 16m over a distance of 930m. According to the “channel size calculator” (Annexure A) for the expected water flow rate of  $1.5\text{m}^3/\text{s}$  the required minimum size of the trench will be as shown in Figure 17.



**Cross section of the storm water ditch and the berm wall**

**Figure 17: Storm water drain and the berm wall**

It is estimated that the ditch will flow at the 90% level with a 1:50 year rainstorm and the flow speed can reach up to 2.3m/s. Therefore some scouring of the sidewalls of the channel can be expected at the bends and it is suggested that the bends should be lined with hand stone.

## 6.2] Dirty water drains:

Most of the dirty water drains will be subsurface drains and the rate of filtration will determine the flow rate inside the drain. Refer to Figure 10 for the drain layout.

Only the drain between the loading area and the silt trap will be an open drain which will be lined with a HDPE membrane as discussed under item 3.4. It will have the following minimum dimensions: Refer to Annexure A for the calculations.




Figure 18: Layout for the dirty water drains

The channel will be 50% full at the design flow of  $0.3\text{m}^3/\text{s}$  and the water speed will be 1.9m/s.

## 6.3] Culvert pipes:

Most of the existing pipe culverts on site were built with  $\text{Ø} 600\text{mm}$  concrete pipes and the same size will be used to construct the new culvert. According to Annexure A this pipe will flow at 60% depth for a discharge rate of  $0.3\text{m}^3/\text{s}$  and at a speed of 1.9m/s.

Due to the fact that it will be a private road inside the siding, it will not be necessary to install concrete headwalls and simple stone pitching around the pipe inlet and outlet will suffice.

## 6.4] Silt trap:

The silt trap as described under item 3.4 will have a capacity of about  $150\text{m}^3$  which will give a retention time of about 10 minutes at the peak flow of  $0.3\text{m}^3/\text{s}$ . This will remove most of the sediment but the suspended solids within the water body will spill over into the PCD.

## 6.5] PCD:

The site topography is of such a nature that it will be difficult to get water into the dam by gravity and still have enough height difference available to daylight the underfloor drainage system. Therefore it is foreseen that a relatively big but shallow dam will have to be constructed.

A dam capacity of  $2\,200\text{m}^3$  converts to a dam size of  $80\text{m} \times 30\text{m}$  measured from centre of wall to centre of wall and a total depth of  $2.3\text{m}$  (water depth= $1.5\text{m}$ ).

All the water inlet and outlet structures to be concrete lined.




Figure 19: Layout of the PCD

Also refer to Figure 12 for the underfloor drainage layout.

## 6.6] Mobile Pump:

A mobile pump with a gooseneck outlet must be supplied to extract water from the PCD to fill the water bowsers.

## 7] Conclusion:

This is a simple and straight forward railway siding design in terms of the water management issues but it might become technically challenging to migrate from phase 1 to phase 2 without closing the siding for some period of time.

# Annexure A

## Channel Sizes

L. van der Linde  
Pr.Eng  
ECSA Registration no: 989531  
E-mail: Sakkievd@telkomza.net  
Mobile: 075-692 9602

Reference: PEC/ARB  
Date: 2018-09-07

**ERWAY ENGINEERING CONSULTING**

**Arbor Siding: Storm water channel @ 1:60 slope** **Q (required) = 1.5 m³/s**

CHANNEL FLOW			Manning Values								
Bottom Width (m)	1.000		Metal, Plastic	0.011							
Manning N	0.025		Concrete	0.015							
Side Slope	1:1.000		Corrugated Material	0.022							
Channel Length (m)	5.0	Earth Channel	0.025								
Height Difference (m)	0.5	Channel - Weedy	0.03								
<p>DATA: B2 = 2.000, P = 2.414, Area = 0.750, R = 0.311, S = 0.017, V (m/s) = 1.60, Q (m³/s) = 1.50</p> <p>Equations: <math>V = 1.49 R^{2/3} S^{1/2}</math>, <math>Q = VA</math></p>											
Capacity for Partial Flow											
Base	dh	Depth	d/Depth	Slope	B2	p	Area	R	V	Q	% Q
0.500	0.1	0.500	0.05	1.000	1.000	1.141	0.357	0.045	0.87	0.04	1.56%
0.600	0.2	0.500	0.1	1.000	1.200	1.283	0.110	0.086	1.02	0.11	5.21%
0.700	0.3	0.500	0.15	1.000	1.300	1.424	0.173	0.121	1.28	0.22	12.27%
0.800	0.4	0.500	0.2	1.000	1.400	1.566	0.240	0.153	1.50	0.36	19.98%
0.900	0.5	0.500	0.25	1.000	1.500	1.707	0.313	0.183	1.69	0.53	29.28%
1.000	0.6	0.500	0.3	1.000	1.600	1.849	0.390	0.211	1.86	0.72	40.17%
1.030	0.7	0.500	0.35	1.000	1.700	1.990	0.473	0.237	2.01	0.95	52.66%
1.050	0.8	0.500	0.4	1.000	1.800	2.131	0.560	0.263	2.15	1.20	66.77%
1.070	0.9	0.500	0.45	1.000	1.900	2.273	0.653	0.287	2.28	1.49	82.54%
1.080	1.0	0.500	0.5	1.000	2.000	2.414	0.750	0.311	2.41	1.80	100.00%

**Arbor Siding: Dirty water channel @ 1:100 slope** **Q (required) = 0.3 m³/s**

CHANNEL FLOW			Manning Values								
Bottom Width (m)	0.500		Metal, Plastic	0.011							
Manning N	0.025		Concrete	0.015							
Side Slope	1:1.000		Corrugated Material	0.022							
Channel Length (m)	5.0	Earth Channel	0.025								
Height Difference (m)	0.5	Channel - Weedy	0.03								
<p>DATA: B2 = 1.500, P = 1.914, Area = 0.505, R = 0.261, S = 0.010, V (m/s) = 1.20, Q (m³/s) = 0.30</p> <p>Equations: <math>V = 1.49 R^{2/3} S^{1/2}</math>, <math>Q = VA</math></p>											
Capacity for Partial Flow											
Base	dh	Depth	d/Depth	Slope	B2	p	Area	R	V	Q	% Q
0.500	0.1	0.500	0.05	1.000	0.600	0.641	0.028	0.042	0.82	0.02	1.65%
0.550	0.2	0.500	0.1	1.000	0.700	0.783	0.039	0.077	1.20	0.07	5.30%
0.600	0.3	0.500	0.15	1.000	0.800	0.924	0.096	0.105	1.49	0.15	10.65%
0.650	0.4	0.500	0.2	1.000	0.900	1.066	0.140	0.131	1.72	0.24	17.70%
0.700	0.5	0.500	0.25	1.000	1.000	1.207	0.188	0.158	1.91	0.36	26.51%
0.750	0.6	0.500	0.3	1.000	1.100	1.349	0.240	0.176	2.11	0.51	37.16%
0.800	0.7	0.500	0.35	1.000	1.200	1.490	0.298	0.200	2.28	0.69	39.74%
0.850	0.8	0.500	0.4	1.000	1.300	1.631	0.360	0.221	2.43	0.88	64.34%
0.900	0.9	0.500	0.45	1.000	1.400	1.772	0.428	0.241	2.58	1.10	81.06%
0.950	1.0	0.500	0.5	1.000	1.500	1.914	0.500	0.261	2.72	1.36	100.00%

**Arbor Siding: Culvert @ 1:100 slope** **Q (required) = 0.3 m³/s**

CHANNEL FLOW			Manning Values								
Bottom Width (m)	0.100		Metal, Plastic	0.011							
Manning N	0.025		Concrete	0.015							
Side Slope	1:0.600		Corrugated Material	0.022							
Channel Length (m)	5.0	Earth Channel	0.025								
Height Difference (m)	0.55	Channel - Weedy	0.03								
<p>DATA: B2 = 0.550, P = 0.550, Area = 0.305, R = 0.183, S = 0.010, V (m/s) = 0.98, Q (m³/s) = 0.30</p> <p>Equations: <math>V = 1.49 R^{2/3} S^{1/2}</math>, <math>Q = VA</math></p>											
Capacity for Partial Flow											
Base	dh	Depth	d/Depth	Slope	B2	p	Area	R	V	Q	% Q
0.550	0.1	0.550	0.055	0.000	0.550	0.663	0.039	0.042	0.85	0.03	3.97%
0.550	0.2	0.550	0.11	0.000	0.650	0.770	0.061	0.079	1.22	0.07	11.37%
0.550	0.3	0.550	0.165	0.000	0.650	0.880	0.091	0.103	1.45	0.13	26.44%
0.550	0.4	0.550	0.22	0.000	0.650	0.990	0.121	0.122	1.64	0.28	35.52%
0.550	0.5	0.550	0.275	0.000	0.650	1.100	0.151	0.130	1.77	0.27	41.27%
0.550	0.6	0.550	0.33	0.000	0.650	1.210	0.182	0.150	1.88	0.34	52.48%
0.550	0.7	0.550	0.385	0.000	0.650	1.320	0.212	0.160	1.97	0.42	64.03%
0.550	0.8	0.550	0.44	0.000	0.650	1.430	0.242	0.169	2.04	0.49	75.84%
0.550	0.9	0.550	0.495	0.000	0.650	1.540	0.272	0.177	2.10	0.57	87.84%
0.550	1.0	0.550	0.55	0.000	0.650	1.650	0.302	0.183	2.15	0.65	100.00%

# Drawings


<p><b>Notes</b></p> <p>RELEVANT STANDARDS</p> <ol style="list-style-type: none"> <li>1. SABS 1200 A &amp; AA - GENERAL</li> <li>2. SABS 1200 AD - DAMS</li> <li>3. SABS 1200 E &amp; DA - EARTHWORKS</li> <li>4. SABS 10405 - GEOMEMBRANES</li> </ol>	<p><b>Data</b></p> <p>References:</p> <ul style="list-style-type: none"> <li>- Google Earth</li> </ul>	<p>Gijima Supply Chain Management Services (Pty) Ltd Reg. No.: 2000/015676/07 Arbor Sidling Portion 1 of farm Van der Linde Delmas</p> <p>Approved: Name: _____ Signature: _____ Date: _____</p>		
<p><b>Site Location</b></p>	<p><b>Site Position</b></p>	<p><b>Client</b></p> <p>Gijima Supply Chain Management Services (Pty) Ltd Arbor Sidling Water Management System Arbor Sidling 26°00'19.78" S 28°52'51.23" E</p>	<p><b>Approved:</b> <i>HL-6</i></p> <p><b>Title:</b> General layout - Arbor Sidling</p> <p><b>Scale:</b> Not to scale</p> <p><b>Plan No:</b> ARB/18/03/Sheet 1 of 7</p> <p><b>Drawn:</b> WL</p> <p><b>Date:</b> 08/09/2018</p>	<p><b>Erway Engineering Consulting</b></p> <p>Erway der Linde trading as PEC PO Box 2866 Ermelo, 2850 ECSA Reg. No: 980531 Mobile: 073 692 9602</p>







<p><b>Notes</b></p> <p>RELEVANT STANDARDS</p> <ol style="list-style-type: none"> <li>1 SABS 1200 A &amp; AA - GENERAL</li> <li>2 SABS 1200 AD - DAMS</li> <li>3 SABS 1200 D &amp; DA - EARTHWORKS</li> <li>4 SABS 10409 - GEOMEMBRANES</li> </ol>	<p><b>Data</b></p> <p>References:</p> <ul style="list-style-type: none"> <li>- Google Earth</li> </ul> <p>Catchment Areas:</p> <ul style="list-style-type: none"> <li>- Storm water = 49.6ha</li> <li>- D/W Phase 1 = 3.7ha</li> <li>- D/W Phase 2 = 5.0ha</li> </ul>	<p>Gijima Supply Chain Management Services (Pty) Ltd          Reg. No.: 2803/015676/07          Arbor Sliding          Portion 1 of Farm Vandykspuit          Delmas</p> <p>Approved: _____          Name: _____          Signature: _____          Date: _____</p>		
<p><b>Storm water catchment area</b></p>	<p><b>Dirty water catchment area for Phase 2</b></p>	<p><b>Dirty water catchment area for Phase 1</b></p>	<p><b>Dirty water catchment area for Phase 2</b></p>	
<p><b>Client:</b>          Gijima Supply Chain Management Services (Pty) Ltd</p>	<p><b>Description:</b>          Arbor Sliding Master Management System</p>	<p><b>Location:</b>          Arbor Sliding</p>	<p><b>GPS Coordinates:</b>          28°02'49.78" S 28°52'51.23" E</p>	<p><b>Approved:</b> Ivan der Linde          Pr. Eng. <i>Ivan der Linde</i>          Date: 08/09/2018</p>
	<p>Ivan der Linde trading as PEC          PO Box 2966          Ermelo, 2950          ECSA Reg. No: 980531          Mobile: 078 692 9602</p>	<p><b>Title:</b> Catchment Areas  <b>Scale:</b> Not to scale  <b>Plan No:</b> ARB/18/03/sheet 4 of 7  <b>Drawn:</b> WL  <b>Date:</b> 08/09/2018</p>	<p><b>Approved:</b> Ivan der Linde          Pr. Eng. <i>Ivan der Linde</i>          Date: 08/09/2018</p>	



**Notes**

RELEVANT STANDARDS

1. SABS 2200 A & AA - GENERAL
2. SABS 1000 AD - DAMS
3. SABS 1200 D & DA - EARTHWORKS
4. SABS 10409 - BEDMEMBRANES

**Data**

**Volumetric:**

- 1. 150 year rain storm
- 2. PCD = 2 200m<sup>3</sup>
- 3. Silt trap = 450m<sup>3</sup>
- 4. Storm water = 1.5m<sup>3</sup>/s
- 5. Dirty water = 0.3m<sup>3</sup>/s

**Calculation Areas:**

- Storm water = 49.6ha
- D/W Phase 2 = 5.0ha

**GIJIMA**

For: Gijima Supply Chain Management (Pty) Ltd

Services: Pp0113

Reg. No.: 2002/015676/07

Arb: Siding

Portion 1 of Farm Vandykspuit

Delmas

Approved: \_\_\_\_\_

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Title	infrastructure - PCD & Silt Trap
Scale	As per sheet
Plan No.	4P/18/01/Sheet 5 of 7
Drawn	JUL
Date	08/09/2018

Approved: *[Signature]*

Project: \_\_\_\_\_

Date: 25/05/2018

Client	Gijima Supply Chain Management
Description	Services (Pp0113)
Location	Arb: Siding/Water Management System
GPS Coordinates	34°02'26.78" S, 08°33'51.25" E


Member Underwriting as PIC

PCB No: 2966

Ernie M. 0350

SCSA Reg. No: 930331

McBiller: 072 9975901



**NOTES**

**RELEVANT STANDARDS**

- SABS 1200 A & AA - GENERAL
- SABS 1200 AD - DAMS
- SABS 1200 D & DA - EARTHWORKS
- SABS 1040B - GEOMEMBRANES

**Defa**

**Volumes:**

- 1.50 year rain storm
- PCD = 2 200m<sup>3</sup>
- Silt trap = 150m<sup>3</sup>
- Storm water = 1.5m<sup>3</sup>/s
- Dirty water = 0.5m<sup>3</sup>/s

**Catchment Areas:**

- Storm water = 49.6ha
- D/W Phase 2 = 3.6ha

**Drain Lengths:**

- Storm water berms = 860m
- Storm water chert = 75m
- D/W open drain = 260m
- D/W Centre drains = 400m
- Solid pipes = 100m

**GILJIMA**

Giljima Supply Chain Management Services (Pty) Ltd  
Reg. No. 2007/015676/07  
Arbor Ridge  
Porton Letlam Vandykswat  
Delmas

Approved: \_\_\_\_\_  
Name: \_\_\_\_\_  
Signature: \_\_\_\_\_  
Date: \_\_\_\_\_


Client:	Infrastructure - Drainage
Description:	RCS to Stals
Location:	ARB/18/07/Sheet 6 of 7
Site Coordinates:	36°02'49.78" S 26°13'51.25" E

Approved:	1 van der Linde
Scale:	As to Stals
Plan No:	ARB/18/07/Sheet 6 of 7
Client:	RCS
Date:	06/09/2018

**PERWAY ENGINEERING CONSULTING**

1 van der Linde cradingas PIC  
PO Box 2965  
Ficksburg, 7830  
RCS Ref. No. 930591  
Mobile: 073 892 5622

Client:	Giljima Supply Chain Management Services (Pty) Ltd
Description:	Arbor Ridge Water Management System
Location:	Arbor Ridge
Site Coordinates:	36°02'49.78" S 26°13'51.25" E



**NOTES**

**RELEVANT STANDARDS**

- SABS 1200 A & A.1 - GENERAL
- SABS 1200 D - DAMS
- SABS 1200 D & DA - BENT FORMS
- SABS 10409 - GEOMEMBRANE

**Data**

**Volumes:**

- 1:50 year return storm
- PCD = 2 200m<sup>3</sup>
- Silt trap = 150m<sup>3</sup>
- Storm water = 1,5m<sup>3</sup>/s
- Dirty water = 0,9m<sup>3</sup>/s

**Catchment Areas:**

- Storm water = 49,6ha
- Dirty Phase 2 = 3,0ha

**Drain Lengths:**

- Storm water-term = 860m
- Storm water open = 75m
- D/W open drain = 200m
- D/W Centre drains = 400m
- Solid pipes = 100m

**GIJIMA**

Government of Limpopo Region, Water Supply, Air Quality & Environmental Management Services (Pty) Ltd

Reg No.: 2001/015575/07

Arbor Siding

Portion 1 of Farm Mendak 3026

Dielmas

Approved: \_\_\_\_\_

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Title:	Infrastructure - Sealing Arrangements
Scale:	Not to scale
Plan No:	ARB/18/01/Sheet 7 of 7
Drawn:	IVL
Date:	08/09/2018

Approved:	i van der Linde
Pr Eng:	<i>[Signature]</i>
Date:	08/09/2018

Client:	Gijima Supply Chain Management Services (Pty) Ltd
Description:	Arbor Siding Water Managem. System
Location:	A7/Bor Station
GPS Coordinates:	26°02'19.78" S 28°52'51.28" E

Client:	Erway Engineering Consulting
Address:	PO Box 2966 Ermelo, 2950
ECSA Reg. No.:	980531
Mobile:	073 692 9602

**Annexure 16.2-2: Integrated Water and Waste Management Plan (IWWMP)**

January 22, 2018

	<p>Letsoalo Water And Environmental Services cc P.O. Box 19016 Pretoria West 0117 Reg: 2010/005979/23 Tax ref Number: 9170/262/18/3 Vat Number: 4380258477</p> <p>Tel : (012) 321 0073 Cell : 082 821 6621 Fax : 0866 134 794 e-mail : <a href="mailto:ishmael@lwes.co.za">ishmael@lwes.co.za</a> Website : <a href="http://www.lwes.co.za">www.lwes.co.za</a></p>
---	--

Date: 22 January 2018

Gijima Supply Chain Management (Pty) Ltd  
PO Box 71486  
Bryanston East  
2021.  
South Africa

Attention: Mr Ramphele and Mr Cronje

**TITLE: UPDATE – INTEGRATED WATER AND WASTEWATER MANAGEMENT PLAN FOR SUPPLY CHAIN MANAGEMENT (PTY) LTD, IN LINE WITH WATER USE LICENCE NUMBER 04/B20F/G/4009**

Good day

The Integrated Water and Wastewater Management Plan (IWWMP) for Gijima Supply Chain Management (Pty) Ltd, Arbor Siding, in accordance to the conditions of Water Use Licence Number **04/B20F/G/4009**, dated 18 December 2015, bears reference.

Please see attached the Draft report for your attention and approval.

Please do not hesitate to contact me should you have any queries.

Best regards,

Ishmael Phalane,



Engineering Technologist – Civil Engineering (ECSA: 201480763)

January 22, 2018



LETSOLO WATER AND ENGINEERING SERVICES CC

## [INTERGRATED WATER AND WASTEWATER MANAGEMENT PLAN]

## [Arbor Siding]

Reference: LWES 416

22 January 2018

Prepared By:	Prepared for:
<p>Ishmael Phalane B-TECH; Civil Engineering (ECSA – Reg No: 201480763)</p> <p>Letsolo Water and Environmental Services cc 76 Phudufufu Street Atteridgeville Ext 25 Kalafong Heights 0008</p> <p>Tel: (012) 321 0073 Cell : 082 821 6621 Fax : 0866 134 794 e-mail : <a href="mailto:jshmael@lwes.co.za">jshmael@lwes.co.za</a> Website : <a href="http://www.lwes.co.za">www.lwes.co.za</a></p>	<p>Mr Peet Cronje, and Mr Vellie Ramphele</p> <p>Gijima Supply Chain Management (Pty) Ltd PO Box 71486 Bryanston East 2021. South Africa</p> <p>Tel: +27 (0) 11 658 0349 Fax: +27 (0) 11 658 1332 <a href="http://www.gijimasupplychains.co.za">www.gijimasupplychains.co.za</a></p>



---

January 22, 2018

## EXECUTIVE SUMMARY

Letsolo Water and Environmental Services cc, hereafter referred to as Letsolo, was appointed to update the Integrated Water and Wastewater Management Plan for Gijima Supply Chain Management Services (Gijima) for Arbor Siding.

Gijima is located on Portion 1 of the Farm Van Dykspuit 214 IR, approximately 5 km West of Kendal power station. The Siding falls within the Victor Khanye Local Municipality in the magisterial District of eMalahleni, Mpumalanga Province.

Gijima Supply Chain Management Services (Pty) Ltd is undertaking a coal loading operations, which includes haulage of coal from various mines, stockpile and load to railway wagons for transportation to the markets. The coal stock piling footprint of the activity covers approximately 9000 square meters.

No coal extraction/ mining activities as well as disposal of coal takes place on site.

Gijima was issued with Water Use Licence (Licence Number **04/B20F/G/4009**) on 18 December 2015.

The water uses applicable to the WUL and this Integrated Water and Waste Management Plan (IWWMP) are listed below.

- 21(a): Taking water from a water resource; and
- 21(g): Disposing of waste which may detrimentally impact on a water resource.

As part of the approved Water Use License (WUL), the Siding must update the IWWMP annually. The first update of the IWWMP after the issuance of the Water Use Licence was in 2016. This report is the second update of the IWWMP. This update takes into account the stresses in the Water Management Area (WMA) due to mining and related activities, commercial agricultural activities and other waste discharge and disposal activities. The IWWMP is therefore a living document that will be revised and updated throughout the life of the operations to accommodate additional information and improved technology. The annual update ensures that water and wastewater management is continually optimised and adapted to the changing needs of the water management area.

January 22, 2018

## Table of Contents

1	INTRODUCTION .....	1
1.1	ACTIVITY BACKGROUND .....	1
1.2	REGIONAL SETTING AND LOCATION OF ACTIVITY .....	2
1.3	PROPERTY DESCRIPTION .....	4
1.4	PURPOSE OF IWWMP .....	4
2	Conceptualization of activity.....	4
2.1	DESCRIPTION OF ACTIVITY .....	4
2.2	EXTENT OF ACTIVITY .....	5
2.3	ACTIVITY LIFE DESCRIPTION .....	5
2.4	ACTIVITY INFRASTRUCTURE DESCRIPTION.....	5
2.5	KEY WATER USES AND WASTE STREAMS .....	5
2.5.1	<i>Water Uses</i> .....	5
2.5.2	<i>Sewage facilities and waste management</i> .....	5
2.5.3	<i>Waste Streams</i> .....	6
2.6	ORGANIZATIONAL STRUCTURE OF ACTIVITY.....	6
2.7	EDUCATION AND TRAINING .....	4
2.8	INTERNAL AND EXTERNAL COMMUNICATION.....	4
2.9	BUSINESS AND CORPORATE POLICIES .....	4
3	Regulatory water and waste management framework.....	4
3.1	SUMMARY OF ALL WATER USES .....	4
3.2	EXISTING LAWFUL WATER USES.....	5
3.3	WASTE MANAGEMENT ACTIVITY (NEMWA) .....	5
3.4	WASTE RELATED AUTHORIZATIONS .....	5
4	Present Environmental Situation.....	5
4.1	CLIMATE.....	5
4.2	REGIONAL CLIMATE RAINFALL .....	6
4.3	EVAPORATION .....	7
4.4	SURFACE WATER .....	4
4.5	WATER MANAGEMENT AREA (WMA 2).....	4
4.6	QUATERNARY CATCHMENT (B20F).....	4
4.7	SURFACE WATER HYDROLOGY .....	4
4.7.1	<i>Olifants River</i> .....	4
4.7.2	<i>Wilge River</i> .....	5
4.8	SURFACE WATER QUALITY .....	5
4.8.1	<i>Sampling Method</i> .....	5
4.8.2	<i>Location of monitoring points</i> .....	5
4.8.3	<i>Surfacewater Quality Interpretation</i> .....	6
4.9	GROUNDWATER QUALITY.....	6
4.9.1	<i>Location of Groundwater monitoring points</i> .....	7
4.9.2	<i>Groundwater Quality Interpretation</i> .....	7
4.10	MEAN ANNUAL RUNOFF (MAR) .....	4
4.11	RESOURCES CLASS AND RIVER HEALTH RECEIVING WATER QUALITY OBJECTIVES AND RESERVE.....	4
4.12	SURFACE WATER USER SURVEY.....	4
4.13	SENSITIVE AREAS SURVEY .....	4
4.14	GROUNDWATER .....	5
4.15	SOCIO- ECONOMIC ENVIRONMENT .....	5
5	Analysis and characterization of the water use activity.....	5

January 22, 2018

5.1	WATER AND WASTE MANAGEMENT .....	5
5.2	WATER SUPPLY .....	5
5.3	STORM WATER .....	6
5.4	WASTE MANAGEMENT .....	6
	<i>Gijima have a colour coded system using separate bins for different waste types and thus separating waste at source. To avoid the need for licensing of the storage of waste, collection occurs at intervals of less than 90 days.</i> .....	6
5.4.1	<i>Hazardous Waste</i> .....	6
5.4.2	<i>Domestic Waste</i> .....	6
5.5	WASTE RECOVERY AND REDUCTION.....	6
5.6	WATER BALANCE .....	6
5.7	MONITORING AND CONTROL.....	7
5.7.1	<i>Surface water monitoring</i> .....	7
5.7.2	<i>Groundwater monitoring</i> .....	7
5.8	RISK ASSESSMENT / BEST PRACTICE ASSESSMENT .....	7
5.8.1	<i>Surface Water Risk rating criteria</i> .....	7
6	Water and Waste Management .....	12
6.1	WATER AND WASTE MANAGEMENT PHILOSOPHY (PROCESS WATER, STORMWATER, AND WASTE).....	12
6.1.1	<i>Process Water</i> .....	12
6.1.2	<i>Stormwater</i> .....	11
6.1.3	<i>Waste</i> .....	11
6.1.4	<i>Groundwater</i> .....	11
6.2	IWWMP ACTION PLAN .....	11
6.3	CONTROL AND MONITORING .....	14
6.3.1	<i>Monitoring of change in baseline (environment) information (Surface water and Groundwater)</i> .....	14
6.4	AUDIT AND REPORT ON PERFORMANCE MEASURES .....	14
6.5	AUDIT AND REPORT ON RELEVANCE OF IWWMP ACTION PLAN .....	14
7	REHABILITATION MANAGEMENT PLAN .....	14
7.1	REHABILITATION OBJECTIVES .....	14
8	Conclusion.....	15
8.1	REGULATORY STATUS OF ACTIVITY .....	15
8.2	STATEMENT OF WATER USES REQUIRING AUTHORISATION, DISPENSING WITH LICENSING REQUIREMENT AND POSSIBLE EXEMPTION FROM REGULATION.....	15
9	References .....	15

## List of Figures

FIGURE 1-1: SITE LOCATION MAP .....	3
FIGURE 2-1: GIJIMA'S WORKFORCE COMPOSITION .....	4
FIGURE 4-1: MAP AND MAE (MM).....	4
FIGURE 4-2: ANNUAL AVERAGE CONCENTRATIONS FOR ALL SURFACE WATER MONITORING POINTS	6
FIGURE 4-3: ANNUAL AVERAGE CONCENTRATION FOR ALL GROUNDWATER MONITORING POINTS ....	7
FIGURE 4-4: WATER QUALITY MONITORING POINTS .....	4
FIGURE 5-1: ARBOR SIDING WATER BALANCE SKETCH .....	7

---

January 22, 2018

## List of Tables

TABLE 1-1: PROPERTY INFORMATION.....	4
TABLE 3-1: SUMMARY OF WATER USES .....	5
TABLE 4-1: MAXIMUM, MINIMUM AND MEAN MONTHLY TEMPERATURE .....	6
TABLE 4-2: MAP AND MAE (MM) .....	4
TABLE 4-3: SURFACEWATER MONITORING POINTS.....	5
TABLE 4-4: GROUNDWATER MONITORING POINTS .....	7
TABLE 4-5: MEAN ANNUAL RUNOFF .....	4
TABLE 5-1: SCALING RISK .....	8
TABLE 5-2: SOIL EROSION.....	11
TABLE 5-3: WATER QUALITY DETERIORATION.....	10
TABLE 5-4: HYDROLOGICAL YIELD .....	12

---

January 22, 2018

## Glossary of Terminology

**Catchment** - The area from which any rainfall will drain into the watercourse or watercourses or part of the water course, through surface flow to a common point or common points

**Constitution** – Refers to the Constitution of the Republic of South Africa, 1996 (Act No. 108 of 1996).

**Environment** – The external circumstances, conditions and objects that affect the existence and development of an individual, organism or group; these circumstances include biophysical, social, economic, historical, cultural and political aspects. Environment means the surroundings within which humans exist and that are made up of-

- (i) the land, water and atmosphere of the earth;
- (ii) micro-organisms, plant and animal life;
- (iii) any part or combination of (i) and (ii) and the interrelationships among and between them; and
- (iv) the physical, chemical, aesthetic and cultural properties and conditions of the foregoing that influence human health and well-being.

**Environmental Impact Assessment** - An Environmental Impact Assessment (EIA) refers to the process of identifying, predicting and assessing the potential positive and negative social, economic and biophysical impacts of any proposed project, plan, programme or policy which requires authorisation of permission by law and which may significantly affect the environment. The EIA includes an evaluation of alternatives. As well as recommendations for appropriate mitigation measures for minimizing or avoiding negative impacts, measures enhancing the positive aspects of the proposal and environmental management and monitoring measures.

**Existing Lawful use** - An existing lawful use means a water use which has taken place at any time during a period of two years immediately before the date of commencement of the National Water Act 1998, (Act 36 of 1998) or which has been declared an existing lawful water use under section 33 and which was authorized by or under any law which was in force immediately before the date of commencement of the National Water Act.

**General Standards** - These are quality standards for waste water or effluent arising in any area other than an area in which the Special standards area applicable. These standards were published in Government Gazette No. 9225, on 18 May 1984, Regulation No. 991, in terms of the Water Act (Act 54 of 1956).

**Groundwater Recharge** - The inflow of water into a groundwater reservoir from the surface, e.g. infiltration of precipitation and its movement to the water table.

**Hydrogeological** –The study of distribution and movement of groundwater.

**Hydrological** – The study of movement, distribution and quality of surface water and groundwater.

**Public Participation Process** – A process of involving the public in order to identify issues and concerns, and obtain feedback on options and impacts associated with a proposed project, programme or

---

January 22, 2018

---

development. Public Participation Process in terms of NEMA refers to: a process in which potential interested and affected parties are given an opportunity to comment on, or raise issues relevant to specific matters.

**Red Data Book (South African)** – An inventory of rare, endangered, threatened or vulnerable species of South African plants and animals.

**Reserve** means the quantity and quality of water required -

(a) to satisfy basic human needs by securing a basic water supply, as prescribed under the Water Services Act, 1997 (Act No. 108 of 1997), for people who are now or who will, in the reasonably near future, be -

(i) relying upon;

(ii) taking water from; or

(iii) being supplied from, the relevant water resource; and

(b) to protect aquatic ecosystems in order to secure ecologically sustainable development and use of the relevant water resource.

**Special Standards** - These are quality standards for waste water or effluent arising in the catchment area draining water to any river specified in Schedule 1, or a tributary thereof at any place between the source thereof and the point mentioned in the Schedule. These standards were published in Government Gazette No. 9225, on 18 May 1984, Regulation No. 991, in terms of the Water Act (Act 54 Of 1956).

**The Act** - The National Water Act, (NWA) (Act 36 of 1998)

**The Department** - Means the Department of Water and Sanitation

**Tributaries** - A stream or river which flows directly into a larger river or stream.

**Mine risk** - Mines are classified into three risk categories namely, categories A, B and C according to the perceived severity of the potential impacts on the water resources due to mining activity.

**Watercourse** means -

(a) a river or spring;

(b) a natural channel in which water flows regularly or intermittently;

(c) a wetland, lake or dam into which, or from which, water flows; and

(d) any collection of water which the Minister may, by notice in the Gazette, declare to be a watercourse, and a reference to a watercourse includes, where relevant, its bed and banks.

**Water quality** means the physical, chemical, toxicological, biological (including microbiological) and aesthetic properties of water that determine sustained (1) healthy functioning of aquatic ecosystems and (2) fitness for use (e.g. domestic, recreational, agricultural, and industrial). Water quality is therefore

---

January 22, 2018

reflected in (a) concentrations or loads of substances (either dissolved or suspended) or micro-organisms, (b) physico-chemical attributes (e.g. temperature) and (c) certain biological responses to those concentrations, loads or physico-chemical attributes.

**Water Resource** - A water resource includes any watercourse, surface water, estuary or aquifer. Watercourses include rivers, springs, and natural perennial and non-perennial channels. Wetlands, lakes, dams, or any collection identified as such by the Minister in the Government Gazette.

**Water use license** - An authorisation from the Department to a designated water user to use water. The authorisation will provide details on the time-frames and conditions for the designated water use

## Abbreviations

BPG	- Best Practice Guideline
DWS	- Department of Water and Sanitation
EC	- Electrical Conductivity
EIA	- Environmental Impact Assessment
EIS	- Ecological Importance and Sensitivity
ELWU	- Existing Lawful Water Use
GDP	- Gross Domestic Product
HDSA	- Historically Disadvantaged South Africans
ISP	- Internal Strategic Perspective
IWULA	- Integrated Water Use License Application
m <sup>3</sup>	- Cubic Metres
MAR	- Mean Annual Runoff
mbgl	- Metres Below Ground Level
mg/l	- Milligrams Per Litre
MPRDA	- Mining and Petroleum Resources Development Act (Act 28 of 2002)
NEMA	- National Environmental Management Act 1998 (Act 107 of 1998)
NWRS	- National Water Resources Strategy

---

January 22, 2018

NWA	– National Water Act 1998 (Act 36 of 1998)
PES	- Present Ecological State
SS	– Suspended Solids
SWMP	- Storm Water Management Plan
TDS	– Total Dissolved Solids
WMA	– Water Management Area
WULA	– Water Use Licence Application



---

January 22, 2018

## 1 INTRODUCTION

Letsolo Water and Environmental Services cc, hereafter referred to as Letsolo, was appointed to update the Integrated Water and Wastewater Management Plan (IWWMP) for Gijima Supply Chain and Management Services (Gijima). It is a legal requirement to have an annual update of the IWWMP for Arbor Siding.

The Department of Water and Sanitation (DWS) published General Notice Number 267, Regulations regarding the procedural requirements for Water Use Licences (WUL) and Appeals, dated 24 March 2017. This regulation, together with the Best Practice Guidelines, also published by the DWS, was used for the compilation of this report in order to comply with the approved structure of the IWWMP.

It is emphasized that the IWWMP is site specific. The elements noted below are covered in this report:

- Quantitative impact assessment and prediction of future impacts
  - Pollution sources and receiving environment – refer to BPG G.4 on Impact Prediction
- Water supply
  - Water resource conservation and/or reuse and reclamation - see BPG H.3
  - Storm water management - see BPG G.1
  - Process water management - see BPG A.3
  - Pollution Control Dams - see BPG A.4
- Ground water management
  - Waste management (domestic waste and industrial residues)
  - Water and salt balances - see BPG G.2
  - Monitoring and auditing systems - see BPG G.3

Gijima was issued with Water Use Licence (Licence Number **04/B20F/G/4009**, File Number **27/2/2/B620/12/9**) on 18 December 2015.

The water uses applicable to the WUL and this Integrated Water and Waste Management Plan (IWWMP) are listed below.

- 21(a): Taking water from a water resource; and
- 21(g): Disposing of waste which may detrimentally impact on a water resource.

### 1.1 Activity Background

A siding, in rail terminology, is a low-speed track section distinct from a running line or through route such as a main line or branch line or spur. It may connect through track or to other sidings at either end. Sidings often have lighter rails, meant for lower speed or less heavy traffic, and few, if any, signals. Sidings connected at both ends to a running line are commonly known as loops.

Throughout history, coal has been used as an energy resource, primarily burned for the production of electricity and/or heat, and is also used for industrial purposes, such as refining metals. A fossil fuel,

---

January 22, 2018

coal forms when dead plant matter is converted into peat, which in turn is converted into lignite, then sub-bituminous coal, after that bituminous coal, and lastly anthracite.

Coal is the largest source of energy for the generation of electricity worldwide.

The objectives of the project includes the moving of high volume commodities from road to rail, supply local and export clients, create jobs and enhance entrepreneur potential in the area. It is to benefit the local economy through salaries paid to employees and tax revenues paid to Government.

The Arbor siding operation is expected to contribute positively towards development of opportunities within Victor Khanye Local Municipality. The local economy will be boosted through provision/creation of employment opportunities for the local community. These opportunities will have a positive effect on the broader value chain extending to suppliers of goods and services from nearby towns.

The operation will contribute positively on livelihoods leading to an increase in the standards of living while causing a reduction in poverty. The coal beneficiation industry has a positive impact of regional and local economic setup. The local economy will benefit through salaries paid to employees and tax revenues paid to Government.

### **1.2 Regional setting and location of activity**

The location of the project site falls within Victor Khanye Local Municipality on the farm Van Dyksput 214, located in the magisterial District of eMalahleni, Mpumalanga Province. Arbor siding is approximately 5 km West of Kendal power station along R555 as Shown in the Figure1-1 below.

Emalahleni falls within the Nkangala District Municipality (NDM). NDM consists of 160 towns and villages and shares the western side of its borders with the economic hub of South Africa, Gauteng. NDM has the following local municipalities under its jurisdiction:

- Victor Khanye LM (previously Delmas LM);
- Emalahleni LM;
- Steve Tshwete LM;
- Emakhazeni LM;
- Thembisile LM; and
- Dr JS Moroka LM.

January 22, 2018




Figure 1-1: Site Location Map

January 22, 2018

### 1.3 Property description

Gijima Supply Chain Management (Pty) Ltd is leasing the property from Transnet Freight Rail. This property falls within Water Management Area 2 (Olifants Water Management Area), in the quaternary catchment B20F. The area drains northerly towards the tributary of the Wilge River and the most reliable rainfall station near the study area is SAWB-0477602.

The property details are summarized in the table (Table 1-1) below:

**Table 1-1: Property Information**

Property detail	Title deed property owner
Portion 1 of the farm Van Dykspuit 214 IR.	Transnet Freight Rail

### 1.4 Purpose of IWWMP

The IWWMP takes into account the stressors in the Water Management Area (WMA) due to mining and related activities, commercial agricultural activities and other waste discharge and disposal activities. The IWWMP is therefore a living document that will be revised and updated throughout the life of the operations to accommodate additional information and improved technology to ensure that water and wastewater management is continually optimised and adapted to the changing needs of the water management area.

The main purpose of the IWWMP is to consolidate all the various site specific programmes (e.g. water, storm water management plans, water reuse and reclamation plans, water conservation and demand management plans and waste minimization and recycling, into a simple implementable management plan. In order to develop an effective IWWMP, Letsolo considered the commercial, environmental, social and operational details at Gijima and developed a plan for existing water use activities. The secondary purpose of this report is to update and clarify the content of the IWWMP to the DWS.

## 2 Conceptualization of activity

### 2.1 Description of activity

The activities at Arbor siding include the offloading, stockpiling and removal of coal. Coal is trucked in from various mines and therefore no mining activities occur on site. There is a culvert crossing, which allows clean runoff from the upstream catchment as well as railway track to freely flow northerly towards the Wilge River System. Existing infrastructures include a Coal stockpile area, Weighbridge and Office structure.

Rail freight economics also indicate that transportation by rail is cheaper than by trucks due to a number of wagons and the amount of coal that can be loaded per wagon.

---

January 22, 2018

## 2.2 Extent of activity

The extent of the siding is limited to Portion 1 of the farm Van Dyksput 214 IR.

## 2.3 Activity life description

A Railway siding does not have a life of operation like mining companies, because there is no extraction and depletion of commodities taking place. However the span depends much on the lease agreement granted by the property owner which can always be renewed.

## 2.4 Activity infrastructure description

The following existing infrastructures are on site:

- Railway line;
- Coal stockpiles;
- Weighbridge;
- Water management facilities; and
- Offices.

## 2.5 Key water uses and waste streams

### 2.5.1 Water Uses

#### 2.5.1.1 Portable Water Supply

Portable water is trucked in by an external source and stored in Jojo Tank.

#### 2.5.1.2 Pollution Control Dam, Clean and Dirty water management

A pollution control dam exists at the most downstream point of the siding. The PCD is designed to contain 1:50 year flood volume as in accordance with GN 704. There is also a freeboard of 0.8 m added to act as a safety barrier, in case there are a few extreme events in a short period of time, to give some extra leeway. The PCD is designed in a square shape, for ease of conceptualization, with walls of less than 5 m to comply with the NWA. The PCD is designed to hold 47 000 m<sup>3</sup>, however it is usually empty due to the low stormwater volumes from the dirty water catchment.

A culvert crossing, allows clean runoff from the upstream catchment as well as railway track to freely flow northerly towards the Wilge River System. A dirty water channel also exists to capture contaminated water in to the PCD.

#### 2.5.2 Sewage facilities and waste management

Toilet facilities have been constructed at the Gijima site as per mining regulation requirements. The toilet facilities are linked to a septic tank sewage system. A service contract with a supplier has been negotiated to ensure that the sewage system is properly operated to achieve the requirements as determined by DWS.

---

January 22, 2018

### **2.5.3 Waste Streams**

Waste is categorized as either general or hazardous. Within these two categories, waste is categorized according to its source, namely domestic, commercial and industrial. General waste is sub-divided into paper, metals, glass, plastic, organic, and inert materials (which include builder's rubble). Due to its composition and characteristics, general waste does not pose a significant threat to public health or the environment, if managed properly.

#### **2.5.3.1 Waste stream characterization**

Waste is characterized as follows:

##### **a) Hazardous Waste**

Hazardous waste is generated primarily through the servicing and maintenance of vehicles and equipment on site. The waste to be managed includes:

- Oils or other material containing hydrocarbons. An external entity is appointed to collect oil for recycling.
- Residual chemicals and chemical containers from cleaning materials and other chemicals used on site.
- Mercury containing waste such as fluorescent tubes.
- Material containing polychlorinated biphenyls (PCB's) such as transformer oils.

##### **b) Industrial Waste**

Industrial waste on site includes various consumables from servicing activities including used tyres and scrap metal (not contaminated by hydrocarbons). The waste includes:

- Scrap metal
- Used tyres

##### **c) Domestic Waste**

Domestic waste is generated on site, primarily in the temporal office associated with the consumption of food or drink on site. Normal office type waste is also generated. Typical general waste includes: General compactable and non-compactable waste being primarily cans, paper, plastic packets, food scraps and packaging materials.

## **2.6 Organizational structure of activity**

Gijima's workforce composition is summarized in Figure 2-1 below:

January 22, 2018




Figure 2-1: Gijima's workforce composition

---

January 22, 2018

## 2.7 Education and Training

Gijima recognizes the importance of its employees in the achievement of its business objectives and that skills development is the foundation for developing competent and productive employees who are able to participate in meeting the business objectives. The following objectives have been identified to support the skills development drive:

- Assess employees' skills and qualities as and when required;
  - Provide training that is accessible to all employees;
  - Invest in training interventions and assessments that will promote productivity and employability as dictated by economic conditions and within Gijima's financial ability;
  - Establish a mentorship programme designed to address the operation's developmental needs, whilst facilitating the transferral of skills, knowledge and competence to employees;
  - Re-skill employees if feasible and economically viable when contemplating retrenchments;
- and
- Utilise the Work Place Skills Plan as a vehicle to align skills development with both business growth strategies and employment equity plans.

The purpose of the Skills Development Plan is to provide Gijima with the required mechanisms and opportunities for identifying and developing the skills needed by the Siding and thereby ensuring that employees achieve their full growth potential. In addition, the Skills Development Plan will provide employees with the opportunity to further their capacity within the industry as well as equipping them with alternative skills. Gijima and the Core Contractor will each develop Skills Development Plans for their businesses as a whole. In agreement with the contractor, skills development plans will be in line with the principles of Human Resource Development Programme. There is a commitment to skills development that has an impact beyond the organization and provides a basis for sustained employability through portable skills and development that is linked to the National Qualifications Framework (NQF).

## 2.8 Internal and external communication

Internal and external communication processes within Gijima are defined. Environmental information, aspects, impact control measures, requirements, performance and other environmental matters are communicated to employees, contractors, I&AP's, authorities, business partners and other relevant organizations.

## 2.9 Business and corporate policies

Arbor established a management system for environment, health, safety and community (HSEC) in a format consistent with ISO14001 and ISO18001 but will not necessarily seek certification of the management system.

## 3 Regulatory water and waste management framework

### 3.1 Summary of all water uses

As mentioned, Gijima was issued with a Water Use Licence (Licence Number 04/B20F/G/4009, File Number 27/2/2/B620/12/9), by the Department of Water and Sanitation on the 18 December 2015.



January 22, 2018

The table below (Table 3-1), indicates the authorized water uses within the siding falling in Portion 1 of Van Dyksput farm 214 IR.

**Table 3-1: Summary of water uses**

Development	Water use	Capacity/ volume	Property information
Dust suppression with water emanating from the PCD	Section 21 (g)	14 432 m <sup>3</sup> /annum	Portion 1 of Van Dyksput Farm 214 IR
Pollution Control Dam	Section 21 (g)	14 4432 m <sup>3</sup> /annum	Portion 1 of Van Dyksput Farm 214 IR
Control Stockpiles	Section 21 (g)	5 000 000 m <sup>3</sup>	Portion 1 of Van Dyksput Farm 214 IR

### 3.2 Existing lawful water uses

An existing lawful water use (ELWU) is a water use that lawfully took place in the period of two years before the commencement of the NWA. This allows any water use that lawfully took place to continue until such time as it can be converted into a licence.

Prior to the approval of the IWUL, there were no water use activities which were authorized as existing lawful uses. The current water uses are considered as an entitlement due to the approval of the IWUL for Arbor Siding.

### 3.3 Waste Management Activity (NEMWA)

Waste management is regulated under the National Environmental Management Waste Act, 2008 (Act No. 59 of 2008) (NEM: WA), the Waste Classification and Management Regulations, 2013 (published under Government Notice R634 in Government Gazette 36784 of 23 August 2013) (Regulations) require under regulation 4(2), that all waste generated by waste generators, be classified in accordance with SANS 10234 within one-hundred-and-eighty (180) days of generation.

It is however not applicable to the Gijima activities and there were no general authorizations issued to the siding regarding the NEMWA terms.

### 3.4 Waste related authorizations

No waste related authorizations applicable for Arbor Siding, however Gijima has made it a mandate to ensure waste is properly managed on site. Hazardous wastes that cannot be re-used or recycled are disposed of to a permitted hazardous waste facility through a contract with an approved waste management company. Industrial waste is also removed and disposed at a licensed waste disposal site. Domestic waste is removed by a contractor and disposed of at a waste disposal site.

## 4 Present Environmental Situation

### 4.1 Climate

The mean daily maximum temperature exceeds 25 °C between November and March, the hottest months. Average maximum temperatures in the winter months (May-August) range from 18.0°C to 21.3°C. The mean minimum summer temperatures range from 11.7°C (March) to 14.2°C (January) with

January 22, 2018

winter mean minima ranging from  $-1.6^{\circ}\text{C}$  to  $2.9^{\circ}\text{C}$ . An extreme maximum temperature of  $33.8^{\circ}\text{C}$  was recorded at Ogies, on 12 November 1990 and an extreme minimum temperature of  $-8.8^{\circ}\text{C}$  on 9 June 1988; please see Table 4-1 below.

**Table 4-1: Maximum, Minimum and Mean Monthly Temperature**

Month	Mean Daily Temp ( $^{\circ}\text{C}$ )		
	Max	Min	Mean Monthly Temp ( $^{\circ}\text{C}$ )
January	27.0	14.2	20.6
February	26.0	13.6	19.8
March	25.7	11.7	18.7
April	23.3	8.1	15.7
May	21.3	2.9	12.1
June	18.0	- 0.5	8.8
July	18.8	- 1.6	8.6
August	20.9	1.2	11.1
September	23.4	6.0	14.7
October	24.7	10.0	17.4
November	25.0	12.0	18.5
December	26.3	13.8	20.1
Annum	23.4	7.6	15.5

#### 4.2 Regional Climate Rainfall

When the rate of rainfall influx exceeds the absorption capacity of the soil, the excess water flows over the surface as overland flow. Rainfall runoff responds differently to variations in topography, soil and characteristics of precipitation, and indirectly to variations in climate, vegetation and land use. Therefore runoff flow controls the volume, periodicity and chemical characteristics of contributions to receiving streams and lake basins.

Many different rainfall data sources and consequent data sets exist for rainfall representation over S.A. Each data source and data set has its own unique advantages as well as disadvantages. Different hydrological rainfall-runoff simulation and peak flow estimation models exist as well as different methods for estimations which require different rainfall parameters with specific required detail and accuracy. Water Research Commission collects Rainfall, Runoff and Evaporation data. This data is herein referred to as WR2005 data. WR2005 includes most data sets all over the country but is currently limited up to and including the year 2004, starting from 1920. Data sets have a record period of 85 years. Major and extensive research efforts and modelling exercises have been conducted to obtain WR2005 rainfall data.

---

January 22, 2018

The maximum annual rainfall for the available record of 1907-2003 occurred in 1999 and was 1400 mm. The maximum monthly rainfall occurs in November to January. The maximum recorded is 474 mm, which occurred in November 1999.

The nearest most reliable rainfall station is station 0478093\_W (Ogies), and is located 8.5 km southeast of Arbor Siding. The Mean Annual Rainfall for the study area is 739 mm; this has been clearly shown in table 4-2 and figure 4-1 below.

### **4.3 Evaporation**

As in the case of rainfall and runoff it is also necessary to analyse the Mean Annual Evaporation (MAE). Much less evaporation data exists than data for rainfall and runoff. Evaporation is measured at dams and mostly stations that are operated by DWS; these stations provide such data. Again, as in the case with rainfall and runoff, much effort has been placed to incorporate evaporation data into the Pitman model and consequently the WR2005 dataset (WRC, 2008). A previous version of WR2005 is also available with evaporation data; this data set is called the WR90 data set (WRC, 1990). The site MAE is estimated at 1517.8 mm as shown in figure 4-1 below.

Evaporation data for site was obtained using the WR90 manual. The Mean Annual Evaporation (Based on S-pan data) is 1517.8 mm. The high evaporation rates will result in high losses of water from the storage dams and the pollution control dams within the site.

January 22, 2018

Table 4-2: MAP and MAE (mm)

Description	October	November	December	January	February	March	April	May	June	July	August	September	Annual
Average Monthly Rainfall (mm)	77.1	115	125.2	143.8	84.8	96.6	43	15	7.5	2.7	8	20.3	739
Average Monthly Evaporation (mm)	165.8	162.5	176.9	167.1	143.5	133.6	103.3	83.3	65.1	72.4	102.6	141.7	1517.8




Figure 4-1: MAP and MAE (mm)

---

January 22, 2018

#### 4.4 Surface Water

Gijima is situated in quaternary catchments B20F. According to the WRC (1994), this catchment has a Mean Annual Precipitation (MAP) of 657mm/a.

The river systems in relation to the study area are categorized in 4 Tiers as follows:

- Tier 1 : Water Management Area 2 (Olifants River)
- Tier 2 : Upper Olifants
- Tier 3 : Quaternary Catchment (B20F)
- Tier 4 : Site Specific Catchments

These areas are discussed below and later in this document.

#### 4.5 Water Management Area (WMA 2)

The study area falls within Water Management Area 2 (WMA2), Olifants, specifically along the watershed between the quaternary catchments B20F (Wilge River). The Olifants River is the most significant River in WMA2 and one of the main tributaries of the Limpopo River. The Olifants Catchment covers about 54 570 km<sup>2</sup>. The upper reaches of the Olifants River Catchment are characterized mainly by mining, agricultural and nature conservation activities.

The mean annual runoff (MAR) for the WMA4 is 2 042 million m<sup>3</sup>/a.

#### 4.6 Quaternary Catchment (B20F)

A catchment or water shed is derived from the topographical landscape. It is sectioned by a water divide, a high land separating two or more water systems. A quaternary catchment is the land and water surface area that contributes to the discharge at the system outlet. The study area falls within the B20F Catchment. B20F would be interpreted as follows:

- "B" denotes the primary catchment region;
- The number 2 denotes the secondary drainage region of Primary B;
- The number 0 denotes Tertiary sub-drainage region 2; and
- "F" denotes the quaternary region.

The site is located across the boundaries of both the B20F quaternary catchments. The Olifants River basin upstream of the Loskop Dam is a government water-controlled catchment. Future growth in water requirements in the Olifants water management area will mainly be in the power generation, mining, urban and industrial sectors, with the largest impact on the Upper-Olifants sub-area. Of the total of water being transferred into the Olifants WMA, the upper Olifants sub-area constitutes about 22%.

#### 4.7 Surface Water Hydrology

##### 4.7.1 Olifants River

The Olifants River originates near Bethal in the Highveld of Mpumalanga, initially flowing northwards before curving eastwards and reaching Mozambique via the Kruger National Park.

In Mozambique, the Olifants River joins the Limpopo River before discharging into the Indian Ocean. The Olifants WMA falls within portions of Gauteng, Mpumalanga and Limpopo. The main tributaries are the Wilge, Elands and Ga-Selati Rivers on the left bank and the Steelpoort, Blyde, Klaserie and

January 22, 2018

Timbavati Rivers on the right bank (Olifants WMA – Overview of Water Resources Availability and Utilisation, 2003).

The Gijima Siding occurs within the upper parts of the Wilge River, within the greater Olifants River Basin. The Klipspruit River transects the northern part of the site. The Olifants River Basin is divided into five regions, each of which consists of a number of quaternary catchments.

#### 4.7.2 Wilge River

The Wilge River holds high significance for this project. The Wilge River flows in a northerly direction. The Wilge River has its origin about 15 km West North West of Leandra, in the Highveld grasslands. It flows roughly northwards until it is joined by its main tributary, the Bronkhorstspruit, that joins its left bank about 25 km downstream of Bronkhorstspruit town. Then it flows in a north-eastern direction until it joins the Olifants about 12 km upstream from the head of the Loskop Dam reservoir.

### 4.8 Surface Water Quality

One of the conditions of the WUL is that Gijima must provide the Department of Water and Sanitation with a Water Quality Monitoring Program for surface points. Surface water quality is conducted on monthly based at Arbor siding to determine and assess any potential impacts from the activities taking place. Significant data is available to draw conclusions regarding the water quality trends. Annual surface water quality data, for a period starting on March 2016 and ending on February 2017, obtained from the Arbor Siding Water Quality Database, was used to determine the annual average water quality.

#### 4.8.1 Sampling Method

All samples will be collected utilizing sterilized bottles. Before a sample can be collected, a prescribed sampling bottle will be labelled in correspondence with the borehole identity from which sampling will take place. The bottle will then be rinsed at least three times with water to be sampled, before it is filled. Sampling date and time will also be recorded on each sample bottle. Care will be taken to ensure that each sample bottle is correctly identifiable, filled accordingly and does not leak. After samples have been collected, they will be stored in a cooler box at a temperature of 40°C and then transported to the Laboratory within 48 hours of sampling for screening.

#### 4.8.2 Location of monitoring points

The location of monitoring points was strategically selected in order to monitor and assess upstream and downstream water quality. As indicated in Table 4-3 below, three (3) surface water quality monitoring points are located in the water resource. The fourth monitoring point serves a purpose of monitoring the quality of water collected from the siding area into a PCD.

**Table 4-3: Surfacewater Monitoring Points**

ID	LABEL	X (Decimal Degrees)	Y (Decimal Degrees)	Frequency of monitoring
1	SW1	28.92417436	-26.04450349	Monthly
2	SW2	28.88386559	-26.03501712	Monthly

January 22, 2018


3	SW3	28.8735138	-26.02875944	Monthly
4	PCD	28.88166875	-26.03907795	Monthly

**4.8.3 Surfacewater Quality Interpretation**

The water quality water findings were compared to the criterion limits specified by the Water Quality Guidelines (DWA SAWTV).

- The annual average concentration for the Jojo Tank indicates good water quality; no excessive contaminations analysed throughout the year and water quality strictly fall within the standards set for domestic usages.
- The concentration for all surface monitoring points is slightly acidic, neutral and slightly alkaline, ranging from 6 to 8. The South African Water Quality Guideline for Domestic Use shows the targeted water quality range is between 6.0 - 9.0 and 6.5 - 8.4 for Irrigational Use.
- Any form of deterioration analysed in monitoring points SW 2 and SW 3 is not associated with the ongoing activities at Arbor Siding, due to their location.

The Figure below (Figure 4-2) illustrates the comparison of all the average concentration for all the sampled surface water monitoring points.



**Figure 4-2: Annual Average Concentrations for all Surface Water Monitoring Points**

**4.9 Groundwater Quality**

Groundwater quality does not change as rapid as surface water quality. Groundwater contains minerals dissolved from soil particles, sediments, and rocks as the water flows at different directions along aquifers. Some other forms of ground water contaminations come from improper disposal of chemical wastes, leachates from solid waste disposal sites and infiltration of stormwater discharges. Samples

January 22, 2018

were collected from both the Upstream and Downstream Boreholes for analysis of the quality. These boreholes supply portable water to the communities around the Arbor siding.

**4.9.1 Location of Groundwater monitoring points**

Two (2) boreholes were identified from upstream and downstream of the Arbor Siding, the exact location is show in the table (Table 4-4) below.

**Table 4-4: Groundwater monitoring points**


ID	LABEL	X (Decimal Degrees)	Y (Decimal Degrees)	Frequency of monitoring
1	Upstream Borehole	28.8803240	-26.04391319	Quarterly
2	Downstream Borehole	28.87344723	-26.03807939	Quarterly

**4.9.2 Groundwater Quality Interpretation**

The water quality water findings were compared to the criterion limits specified by the Water Quality Guidelines (DWA SAWTV).

- The water quality from both boreholes is very good, there is no contamination related to activities at the Siding.
- All variables analysed to determine the water quality fall within the standards set by the Department of Water Affairs and Forestry (DWAF) South African Water Quality Guidelines.
- The average pH concentration is neutral to slightly alkaline for the two boreholes ranging between 6.2 to 8.2 mg/l, falling within standards set for domestic, agricultural and livestock use.

The Figure below (Figure 4-3) simply illustrates the comparison of all the average concentration for both boreholes. As shown below the Downstream Borehole has an increase in concentration of Total Dissolved Solids recorded as annual average.



**Figure 4-3: Annual Average Concentration for all Groundwater Monitoring Points**



January 22, 2018

The Figure 4-4 below shows the location for both groundwater and surface water monitoring points.




Figure 4-4: Water Quality Monitoring Points

January 22, 2018

#### 4.10 Mean Annual Runoff (MAR)

Runoff is the result of precipitation (rainfall) falling on a catchment and eventually running off from the catchment. The amount of rainfall that runs off is dependent on the catchment characteristics.

Due to the complex nature of rainfall-runoff modelling it is not deemed necessary to set up specific models for small catchments (BPGs). Letsolo Water adopts a holistic approach and methodology whereby WR2005 quaternary catchment runoff data is downscaled to site specific runoff data by making use of area and volume relationships as well as a rainfall reduction factor.

The Mean Annual Runoff (MAR) calculations are highly dependent on the surface area. Runoff figures were analysed statistically in a similar manner as rainfall. The MAR for the study area was sourced from the Water Research Commission database (WR2005). **Table 4-5** provides activity based MAR and the quantified impact on the Effective and Quaternary Catchment Areas.

According to *National Water Resource Strategy* (2004), the mean annual rainfall is in the range of 500mm to 800mm over most of the WMA 2. Most surface runoff originates from higher rainfall southern and mountainous areas and is controlled by several large dams.

**Table 4-5: Mean Annual Runoff**

Effective Catchment Names	Effective Catchment Area (km <sup>2</sup> )	Catchment MAR (mm/annum)	Calculated MAR (m <sup>3</sup> /annum)
B20F Quaternary Catchment	506	33.3	16 845 558
SW 1	25.08	33.3	835 164
SW 2	37.62	33.3	1 252 746
SW 3	41.8	33.3	1 391 940

#### 4.11 Resources Class and River Health Receiving Water Quality Objectives and Reserve

#### 4.12 Surface Water User Survey

Most activities surrounding the siding involve agricultural and mining activities. There are small communities in close proximity.

The main water users around the study area are as follows:

- Semi-urban related water users in the farms and communities;
- Irrigation.

#### 4.13 Sensitive Areas Survey

Sensitive areas may be regarded as water resources identified in the close proximity of the project area with an assumption that the siding would have an impact or may affect the environment. There are no sensitive areas within and around the Arbor Siding.

---

January 22, 2018

#### **4.14 Groundwater**

The rail siding site is located adjacent to open cast coal mining operations, namely the Vlakvarkfontein and Intibane Collieries. These open cast operations have not intersected the local groundwater table. However, there are localized groundwater seepages and these occur at depths in excess of 20m from the ground surface. The presence of dolerite intrusions in this area is however likely to also give rise to groundwater seepage. In addition to the above, seepages from localized perched water tables can be expected.

#### **4.15 Socio- economic environment**

The employment rate of the communities in the project area and immediate surrounds (< 50 households) is 47% with employment predominantly on mines in the area, but also as domestic workers and general labourers further afield. Their dwellings vary between self-built traditional mud houses (two informal settlements) and houses developed by the individual landowners that have subsequently been extended. Subsistence agricultural activities are also associated with these communities with predominant activities being vegetable farming and the rearing of chickens and livestock. Unemployment in the Mpumalanga province is currently 27.7% according to Statistics South Africa in the year 2017.

The agricultural industry is of a relatively high significance to the employment structure in Mpumalanga Province, providing employment to 18% of the population, and is followed by community and social services, which provide employment to approximately fifteen percent (15%) of the economically active population. In 2016, the mining sector provided employment to approximately 22% of the economically active population. Mining employment is anticipated to have risen from this figure in recent years as a result of an increase in mining in the area. In the Municipalities concerned, there is less employment provided by agriculture and additional provided by the mining sector.

Integrated development planning (IDP) promotes inter-governmental co-ordination by facilitating a system of communication and co-ordination between local, provincial and national spheres of government. Local development priorities, identified in the IDP process, constitute the backbone of the local governments' budgets, plans, strategies and implementation activities. Hence, the IDP forms the policy framework on which service delivery, infrastructure development, economic growth, social development, environmental sustainability and poverty alleviation rests.

### **5 Analysis and characterization of the water use activity**

#### **5.1 Water and waste management**

The use of water is managed in accordance with the Best Practice Guidelines listed below:

- Stormwater Management Plan (BPG G1) ;
- Groundwater Management Plan ( BPGs H1 and A5);
- Water reuse and optimization plan (BPG H3).

#### **5.2 Water Supply**

The portable water is trucked in by an external supplier and stored in a Jojo Tank.

---

January 22, 2018

### 5.3 Storm water

Clean storm water is diverted by using berms. A berm of approximately 2 m high by 2-3 m wide is constructed between the clean and dirty water catchment.

Dirty storm water management measures comprise of drainage channels and pollution control dam sized to comply with Regulation 704.

### 5.4 Waste Management

Gijima have a colour coded system using separate bins for different waste types and thus separating waste at source. To avoid the need for licensing of the storage of waste, collection occurs at intervals of less than 90 days.

#### 5.4.1 Hazardous Waste

Hazardous wastes that cannot be re-used or recycled are disposed of to a permitted hazardous waste facility (Holfontein) through a contract with an approved waste management company.

#### 5.4.2 Domestic Waste

Domestic waste is removed by a contractor and disposed of at a waste disposal site.

### 5.5 Waste recovery and Reduction

Correct storage of a particular waste type reduces the risk of environmental impacts and limits the risks of pollution. The current waste collection contract is managed by a waste company. The methodology employed is as follows:

- The waste company is contacted when a container is close to full.
- The waste is collected within 48 hours of notification. The full container is replaced with an empty one.
- The contractor separates the waste and transports it to the appropriate licensed facility for disposal. Domestic waste is separated on site and recyclable materials are removed.

### 5.6 Water Balance

The Water Balance (WB) presented in this was reported by Letsolo (October 2017, Reference LWES 304). It illustrates the cumulative flow of water through the system throughout the year. Two (2) WB components were defined, the Stockpile area and the Pollution Control Dam.

Water Balance findings were summarised as follows:

- The Stockpile area has only rainfall as source of inflow water. It is assumed that some volumes of water will be retained into coal material.
- The PCD is expected to have an approximate 218m<sup>3</sup>/a of rainfall and water will be lost through evaporation and dust suppression.

The figure 5-1 below indicates a sketch of how water is distributed within the Arbor Siding.

January 22, 2018




Figure 5-1: Arbor Siding Water Balance Sketch

## 5.7 Monitoring and control

### 5.7.1 Surface water monitoring

Surface water monitoring is an on-going programme as discussed in paragraph 4.8.1 and table 4-3 above.

### 5.7.2 Groundwater monitoring

Groundwater monitoring is conducted quarterly from both boreholes.

## 5.8 Risk assessment / Best Practice Assessment

Arbor established a management system for environment, health, safety and community (HSEC) in a format consistent with ISO14001 and ISO18001 but will not necessarily seek certification of the management system.

A risk-based assessment was undertaken. This Risk Assessment was conducted in line with the Best Practice Guidelines (**BPG G4: Impact Prediction**)

Please refer to the paragraphs below for the criteria and rating.

### 5.8.1 Surface Water Risk rating criteria

The impacts were rated and ranked based on the system as described below:

January 22, 2018

- **Magnitude:** is a measure of the degree of change in a measurement or analysis (e.g., the area of pasture, or the concentration of a metal in water compared to the water quality guideline value for the metal), and was classified as none/negligible, low, moderate or high. The categorisation of the impact magnitude may be based on a set of criteria (e.g. health risk levels, ecological concepts and/or professional judgment) pertinent to each of the discipline areas and key questions analysed. The specialist study must attempt to quantify the magnitude and outline the rationale used. Appropriate, widely-recognised standards were to be used as a measure of the level of impact.
- **Scale/Geographic extent:** refers to the area that could be affected by the impact and was classified as site, local, regional, national, or international.
- **Duration:** refers to the length of time over which an environmental impact may occur: i.e. transient (less than 1 year), short-term (1 to 5 years), medium term (5 to 15 years), long-term (greater than 15 years with impact ceasing after closure of the project), or permanent.
- **Probability of occurrence:** is a description of the probability of the impact actually occurring as improbable (less than 5% chance), low probability (5% to 40% chance), medium probability (40% to 60% chance), highly probable (most likely, 60% to 90% chance) or definite (impact will definitely occur).
- The Impact significance was rated by the specialist using the scoring/ranking system shown in the impact assessment matrix below:

**Table 5-1: Scaling Risk**

Magnitude		Duration		Scale		Probability	
10	Very high/don't know	5	Permanent	5	International	5	Definite/don't know
8	High	4	Long-term (impact ceases after closure)	4	National	4	High probability
6	Moderate	3	Medium term ( 5-15 years)	3	Regional	3	Medium probability
4	Low	2	Short Term (0-5 years)	2	Local	2	Low probability
2	Minor	1	Transient	1	Site only	1	Improbable
1	None					0	None

**5.8.1.1 Scoring system**

Scoring system for assessment of significance:

SP (significance points) = (magnitude + duration + scale) x probability

Where;

January 22, 2018

- SP>75 has high environmental significance;
- SP 30 to 75 Moderate environmental significance; and
- SP<30 Low environmental significance.

#### 5.8.1.2 Risk Identification and Consequences

The following potential risks were identified and further assessed:

##### *Soil Erosion*

Erosion occurs at the clean water catchment areas due to removal of vegetation for access roads. The potential for erosion is increased as loose soil particles are not protected by vegetation cover.

##### *Water quality deterioration*

Water quality impacts are due to a change in natural conditions and enhancement of pollution from sources. On a regional scale, due to a decrease in runoff, the dilution of other pollution sources is affected. Therefore, a reduction in runoff could result in a more pronounced pollution effect.

##### *Catchment yield and hydrology*

The nearby stream will be affected due to a reduction in runoff. Polluted water that would naturally flow to the stream will be retained in the pollution control dam.

#### 5.8.1.3 Risk Estimation

The following sections contain the information on the risk assessment for surface water impacts.

**Table 5-2: Soil Erosion**

<b>Nature:</b> The side slopes of the stockpile must not be too steep.		
	<b>Without mitigation</b>	<b>With mitigation</b>
<b>Magnitude</b>	Moderate (6)	Low (4)
<b>Duration</b>	Medium term (3)	Transient (1)
<b>Scale</b>	Local (2)	Site (1)
<b>Probability</b>	High (4)	Low (2)
<b>Significance</b>	<b>Moderate (44)</b>	<b>Low (12)</b>
<b>Status (positive or negative)</b>	Negative – The impacts are already visible on site.	
<b>Mitigation:</b> A slope of not more than 1:3 is recommended to avoid the formation of erosion gullies and the transportation of sediments to the downstream areas.		

January 22, 2018

**Table 5-3: Water Quality Deterioration**

<b>Nature:</b> Spills from the pollution control Dams pose a risk to the pollution of surface water resources.		
	<b>Without mitigation</b>	<b>With mitigation</b>
<b>Magnitude</b>	Moderate (6)	Low (4)
<b>Duration</b>	Medium term(3)	Medium (3)
<b>Scale</b>	Regional (3)	Site (1)
<b>Probability</b>	High (4)	Medium (3)
<b>Significance</b>	<b>Moderate (48)</b>	<b>Low (24)</b>
<b>Status (positive or negative)</b>	Negative – Deterioration in Water Quality denies the rights of downstream water users to an environment which is not harmful to their well being.	
<b>Mitigation:</b> Storm Water Management measures must be in place in order to protect the environment..		

**Table 5-4: Hydrological Yield**

<b>Nature:</b> This results in the siding area being declared as a dirty water catchment. Direct rainfall that comes in contact with coal is channelled to the Pollution Control Dam. This volume was allowed to flow to the environment prior to the commencement of this activity. This activity results in a reduction in catchment yield.		
	<b>Without mitigation</b>	<b>With mitigation</b>
<b>Magnitude</b>	Moderate (6)	Moderate (6)
<b>Duration</b>	Medium term (3)	Moderate (3)
<b>Scale</b>	Regional (3)	Site (1)
<b>Probability</b>	High (3)	Low (2)
<b>Significance</b>	<b>Moderate (36)</b>	<b>Low (20)</b>
<b>Status (positive or negative)</b>	Negative – The amount of water made available to downstream users is reduced.	
<b>Mitigation:</b> The dirty water Catchment must be managed as small as possible and all disturbed areas must be rehabilitated in such a way that the topography blends in with the surrounding topography in order to allow for free flow.		

## 6 Water and Waste Management

### 6.1 Water and waste management philosophy (process water, stormwater, and waste)

#### 6.1.1 Process Water

Gijima updates the water balance report annually to create a system that can be used as a management tool to assist the environmental manager to achieve the objectives as outlined in the Integrated Water and Wastewater Management Plan (IWWMP).



---

January 22, 2018

### **6.1.2 Stormwater**

The Arbor Siding manages the stormwater separating clean water from dirty water, using channels and berms as stated in Paragraph 2.5.1.2 above.

### **6.1.3 Waste**

Gijima have a colour coded system using separate bins for different waste types and thus separating waste at source. To avoid the need for licensing of the storage of waste, collection occurs at intervals of less than 90 days. The current waste collection contract is managed by a waste company.

### **6.1.4 Groundwater**

Groundwater quality monitoring is conducted quarterly to assess any potential impact from the activities associated with the Siding.

## **6.2 IWWMP Action Plan**

The following activities are ongoing as part of the IWWMP action plan.

- Monthly monitoring of surface water;
- Quarterly monitoring of borehole;
- Update of Water and Salt Balance;
- Management of the stormwater.

## **6.3 Control and monitoring**

### **6.3.1 Monitoring of change in baseline (environment) information (Surface water and Groundwater)**

The monitoring of both groundwater and surface is on-going in accordance with the Arbor Siding Monitoring Programme. Quarterly reports are submitted to the Department of Water and Sanitation (DWS) as required in the Integrated to Water Use License (IWUL).

### **6.4 Audit and report on performance measures**

The Integrated Water Use License is audited internally by Gijima Officials and by an external auditor to check the compliance level to all conditions mentioned in license.

### **6.5 Audit and report on relevance of IWWMP action plan**

The Integrated Water and Wastewater Management Plan action plan will be updated annually as required.

## **7 REHABILITATION MANAGEMENT PLAN**

An overview of all aspects of rehabilitation that will be considered as part of the project, are discussed below.

### **7.1 Rehabilitation objectives**

The objectives are summarized as follows:

- The newly created topography should contribute to and blend in with the natural surrounding environment to ensure self-sustaining, stable systems with alternative utilisation potential.
- Rehabilitation designs are developed so that the least possible amount of material has to be shifted so as not to affect the structure of topsoil and overburden material to be used.

---

January 22, 2018

- Careful selection of indigenous plant species, adapted to the climatic conditions, will be used to ensure a low cost, low maintenance and speedy recovery of disturbed areas. Where possible, self-seeding will be encouraged from the natural seedbed in the topsoil.
- Soil amelioration will only be undertaken to the extent that would bring disturbed soils into equilibrium with the natural environment and not to reach agricultural levels.
- Available material will be used as a cover layer, even if amelioration is required, to avoid further destruction of land by creating borrow pits.

The area will be divided into rehabilitation units as part of the development of the Final Closure Plan. A detailed rehabilitation plan will be developed for each unit, including a terrain analysis, soil and vegetation survey and designs of earthworks and cross sections through each area. A summary of the volumes of material to be shifted at each unit will be provided. A general plan of the area will be prepared at an appropriate scale and indicating the surface topography to accurate interval spacings.

Gijima Supply Chain has an amount of R50 000 secured for Environmental Rehabilitation.

(See Appendix B below)

## **8 Conclusion**

Integrated Water and Wastewater Management Plans (IWWMP) is a logical process whereby the industry considers all the various factors that have a bearing on water and waste management and integrate them spatially and over the life-cycle of the operation. This document must be amended on an annual basis.

### **8.1 Regulatory status of activity**

Gijima Supply Chain Management (Pty) Ltd holds an Integrated Water Use License (IWUL) which was issued on the 18 December 2015.

### **8.2 Statement of water uses requiring authorisation, dispensing with licensing requirement and possible exemption from regulation**

The Siding is authorised for the following water uses as defined in Section 21 of the National Water Act (Act 36 of 1998):

- 21(a): Taking water from a water resource; and
- 21(g): Disposing of waste which may detrimentally impact on a water resource.

## **9 References**

- a) Department of Water Affairs and Forestry, 2007. Best Practice Guideline;
- b) Republic of South Africa, Department of Water Affairs and Forestry, 2006: Integrated Water Resources Management Plan;
- c) DEA, 2010. Framework for Management of Contaminated Land, Department of Environmental Affairs, May 2010.
- d) DMR, 2005. Guideline Document for the Evaluation of the Quantum of Closure-Related Financial Provision Provided by a Mine, dated January 2005.
- e) Letsolo Water and Environmental Services cc (2017); Arbor Siding Water and Salt Balance Report (Ref: LWES 417).

---

January 22, 2018

APPENDIX A: BBBEE

January 22, 2018

**FURTER CARSTENS & VENNOTE/PARTNERS**

J.C. CARSTENS, B.Comm.(Rek), Hons, STR, G.R.(S.A.)  
 V.YIVIER, B.Comm.(Rek), Hons, B.Compl.(Rek), Hons, G.R.(S.A.)  
 Geokrooleerde Rekenmeesters (S.A.) Chartered Accountants (S.A.)  
 Geregistreerde Ouditeure Registered Auditors  
 Posbus / P.O.Box 997 Krugarsdorp 1740  
 1 ste Vloer / Jorisgebou 1 st Floor / Joris Building  
 k/v Rissik & Joubertstr c/o Rissik & Joubert st  
 TEL: 011-953 - 3873  
 Faks / Fax 011- 660 - 5821  
 fcw@mweb.co.za

**Broad-Based Black Economic Empowerment  
 Verification Certificate**

**GIJIMA SUPPLY CHAIN MANAGEMENT SERVICES (PTY) LTD**

Certificate Number: M01/B-BBEE: QSE09/07/2015/013

Registration Number 2001/015676/07  
 VAT No (if applicable) 4340225368  
 Address/Location Arbor Siding, Portion 1 of Farm Vandykspuit,  
 Delmas, Mpumalanga, South Africa

Verification Standard Applied Codes of good practice of 2007  
 Sector specific Transport Sector Charter Gazetted on 21 August 2009  
 Issue Of The Rating Standard Applied Section 9 of the B-BBEE Act 53 of 2003  
 Scorecard Applied Qualifying Small Enterprise Scorecard (< R 35 million)

Broad Based BEE Status Level **I LEVEL TWO**

ELEMENT	WEIGHTING	POINTS
Ownership	25	25.00
Management Control	25	24.95
Employment Equity	27	22.82
Skills Development	25	N/A
Preferential Procurement	25	25.00
Enterprise Development	25	N/A
Socio Economic Development	25	N/A
<b>TOTAL</b>	<b>102</b>	<b>97.77</b>

BEE Procurement Recognition Level	125%	Evaluation Period	1/05/2014 - 31/05/2015
Black Ownership	55.25%	Version Number	One
Black Women Ownership	5.25%	Enterprise Development Beneficiary	Category B
Value Adding Supplier	No		

Although the abovementioned is the current level of turnover/income and is closely related to the economic indicators, it may be more or less in future. Consequently, this Certificate does not serve as a guarantee that the income reflected will continue at the same levels.

Based on our work performed, we have no reason to believe that the B-BBEE status reflected in this Certificate has not been calculated in all material respects, in accordance with the Codes of Good Practice on Black Economic Empowerment, gazetted on 9 February 2007, and in terms of the Broad-Based Black Economic Empowerment Act 53 of South Africa. Our limited assurance report dated 9 July 2015 is available for inspection at the registered office of Gijima Supply Chain Management Services (Pty) Ltd together with the accompanying detailed B-BBEE Scorecard and should be referred to for an understanding of our limited assurance engagement and the extent of work performed. This Certificate has been determined on the basis of information provided by management. We do not accept or assume responsibility to anyone other than Gijima Supply Chain Management Services (Pty) Ltd, for our work, for this report, or for the conclusion we have reached.

V. Yivier / J.C. Carstens  
 IRBA Registration Number: 901962A  
 B-BBEE Approved Registered Auditor  
 Tel. no. (011) 953-3873 Email: fcw@mweb.co.za

Date of Issue: 09 July 2015  
 Expiry Date: 08 July 2016  
 Period of validity: 12 months



Furter Carstens & Vennote/Partners  
 Verification Analyst: M. Dietzsch Cell: 083 357 0845

January 22, 2018

**FURTER CARSTENS & VENNOTE/PARTNERS**

I.C. CARSTENS, B.Comm.(Rel), Hons, STR, G.R.(S.A.)  
 V.VIVIER, B.Comm.(Rel), Hons, B.Compt.(Rel), Hons, G.R.(S.A.)  
 Geotrooieerde Rekenmeesters (S.A.) Chartered Accountants (S.A.)  
 Geregistreerde Ouditeure Registered Auditors  
 Posbus : P.O.Box 997 Krugersdorp 1740  
 1 ste Vloer / Jorisgebou 1 st Floor / Joris Building  
 W/ Pissik & Joubertstr c/o Rissik & Joubert st  
 TEL: 011-933 - 3873  
 Faks / Fax 011- 650 - 5821  
 fcw@mwweb.co.za

**Broad-Based Black Economic Empowerment  
 Verification Certificate**

**GIJIMA SUPPLY CHAIN MANAGEMENT SERVICES (PTY) LTD**

Certificate Number: M01/B-BBEE: QSE09/07/2015/013

Registration Number 2001/015676/07  
 VAT No (if applicable) 4340223368  
 Address/Location Arbor Siding, Portion 1 of Farm Vandykspuit,  
 Delmas, Mpumalanga, South Africa

Verification Standard Applied Codes of good practice of 2007  
 Sector specific Transport Sector Charter Gazetted on 21 August 2009  
 Issue Of The Rating Standard Applied Section 9 of the B-BBEE Act 53 of 2003  
 Scorecard Applied Qualifying Small Enterprise Scorecard (< R 33 million)

Broad Based BEE Status Level **LEVEL TWO**

ELEMENT	WEIGHTING	POINTS
Ownership	25	25.00
Management Control	25	24.95
Employment Equity	27	22.82
Skills Development	25	N/A
Preferential Procurement	25	25.00
Enterprise Development	25	N/A
Socio Economic Development	25	N/A
<b>TOTAL</b>	<b>102</b>	<b>97.77</b>

BEE Procurement Recognition Level	125%	Evaluation Period	1/06/2014 - 31/05/2015
Black Ownership	35.25%	Version Number	One
Black Women Ownership	5.25%	Enterprise Development Beneficiary	Category B
Value Adding Supplier	No		

*Although the abovementioned is the current level of turnover/income and is closely related to the economic indicators, it may be more or less in future. Consequently, this Certificate does not serve as a guarantee that the income reflected will continue at the same level.*

*Based on our work performed, we have no reason to believe that the B-BBEE status reflected in this Certificate has not been calculated in all material respects, in accordance with the Codes of Good Practice on Black Economic Empowerment, gazette on 9 February 2007, and in terms of the Broad-based Black Economic Empowerment Act 53 of South Africa. Our limited assurance report dated 9 July 2015 is available for inspection at the registered office of Gijima Supply Chain Management Services (Pty) Ltd together with the accompanying detailed B-BBEE Scorecard and should be referred to for an understanding of our limited assurance engagement and the extent of work performed. This Certificate has been determined on the basis of information provided by management. We do not accept or assume responsibility to anyone other than Gijima Supply Chain Management Services (Pty) Ltd, for our work, for this report, or for the conclusion we have reached.*

V. Vivier / I.C. Carstens  
 IRBA Registration Number: 901962A  
 B-BBEE Approved Registered Auditor  
 Tel. no. (011) 933-3873 Email: fcw@mwweb.co.za

Date of Issue: 09 July 2015  
 Expiry Date: 08 July 2016  
 Period of validity: 12 months



Furter Carstens & Vennote/Partners  
 Verification Analyst: M. Dietzsch Cell: 083 357 0845

January 22, 2018

APPENDIX B: PROVISION FOR REHABILITATION



VERITAS CA (SA) Incorporated  
Chartered Accountants (S.A.)  
Registered Accountants & Auditors  
Unit 10 Sunpark | 178 Smit Street | Fairland  
Suite 345 | Private Bag XI | Northcliff | 2115  
Tel: (011) 476 2247 | Fax: (011) 476 2245

To: Myezo Environmental Management Services

Date: 17 November 2016

Dear Sir/ Madam

**GIJIMA SUPPLY CHAIN MANAGEMENT SERVICES (PTY) LTD: PROVISION FOR REHABILITATION**

We hereby confirm that Gijima Supply Chain Management Services (Pty) Ltd has an amount of R50 000 (fifty thousand Rand) secured for environmental rehabilitation when required.

Should you require any additional information, please do not hesitate to contact us.

Yours sincerely

A handwritten signature in black ink, appearing to read 'Jaco Neveling', written over a horizontal line.

Jaco Neveling

Accountant

Veritas CA (SA) Inc

**Annexure 16.2-3: Rehabilitation Strategy Implementation Programme**



# LETSOLO

WATER AND ENVIRONMENTAL SERVICES  
"Engineered Solutions for Environmental Quandary"

Letsolo Water And Environmental Services cc

P.O. Box 19016

Pretoria West

0117

Reg: 2010/005979/23

Tax ref Number: 9170/262/18/3

Vat Number: 4380258477

Tel : (012) 321 0073

Cell : 082 821 6621

e-mail : [ishmael@lwes.co.za](mailto:ishmael@lwes.co.za)

Website : [www.lwes.co.za](http://www.lwes.co.za)

Date 22 January 2018

Gijima Supply Chain Management (Pty) Ltd

PO Box 71486

Bryanston East

2021.

South Africa

Attention: Mr Ramphele and Mr Cronje

**REHABILITATION STRATEGY AND IMPLEMENTATION PROGRAMME (RSIP) FOR GIJIMA SUPPLY CHAIN MANAGEMENT (PTY) LTD, IN LINE WITH WATER USE LICENCE (LICENSE NO: 04/B20F/G/4009)**

The above mentioned project is herein referred to.

Please find enclosed the Rehabilitation Strategy and Implementation Programme (RSIP) for Arbor Siding in line with the requirements of the Water Use Licence Application.

Please do not hesitate to contact us should you have any queries.

Best regards,

Ishmael Phalane,

Engineering Technologist – Civil Engineering (ECSA: 201480763)





# LETSOLO

WATER AND ENVIRONMENTAL SERVICES  
"Engineered Solutions for Environmental Quandary"

## ARBOR SIDING

### REHABILITATION STRATEGY AND IMPLEMENTATION PROGRAMME (RSIP)

Reference: LWES 417

Prepared by:	Prepared for
<p>Ishmael Phalane B-TECH; Civil Engineering (ECSA – Reg No: 201480763)</p> <p>Letsolo Water and Environmental Services cc 76 Phudufufu Street Atteridgeville Ext 25 Kalafong Heights 0008</p> <p>Tel: (012) 321 0073 Cell : 082 821 6621 Fax : 0866 134 794 e-mail : <a href="mailto:ishmael@lwes.co.za">ishmael@lwes.co.za</a> Website : <a href="http://www.lwes.co.za">www.lwes.co.za</a></p>	<p>Mr Peet Cronje, and Mr Velile Ramphele</p> <p>Gijima Supply Chain Management (Pty) Ltd PO Box 71486 Bryanston East 2021.</p> <p>South Africa Tel: +27 (0) 11 658 0349 Fax: +27 (0) 11 658 1332 <a href="http://www.gijimasupplychains.co.za">www.gijimasupplychains.co.za</a></p>

## **EXECUTIVE SUMMARY**

The Department of Water and Sanitation (DWS) issued the Water Use Licence (WUL) for activities at Arbor Siding. As part of the WUL conditions, Gijima Supply Chain Management (Pty) Ltd must compile a Rehabilitation Strategy and Implementation Programme (RSIP) to ensure efficient water use activities.

Gijima Supply Chain Management Services (Pty) Ltd is undertaking a coal loading operations on Portion 1 of the Farm Van Dyksput 214 IR also known as Arbor siding, located approximately 5 km West of Kendal power station. The operations include haulage of coal from various activities, stockpile and load to railway wagons for transportation to the markets. The coal stock piling footprint of the activity covers approximately 9000 square meters.

Letsolo Water and Environmental Services cc was appointed to compile the Rehabilitation Strategy and Implementation Programme (RSIP) for Arbor Siding.

For this Report, the principal act of relevance is the National Water Act, 1998 (Act 36 of 1998) which provides for the protection, usage, development, conservation, management and control of the country's water resources in an integrated manner. The Act provides the legal basis, upon which to develop tools and means to give effect to the protection of water resources.

**CONTENTS**

<b>1. INTRODUCTION</b> .....	<b>1</b>
1.1. LEGAL ASPECTS .....	2
1.1.1. <i>South African Legal Framework</i> .....	2
1.1.2. <i>Water Use Authorisation</i> .....	2
1.2. SITE LOCATION .....	2
1.3. DECLARATION OF INDEPENDENCE: .....	4
1.4. SCOPE OF WORK .....	4
<b>2. METHODOLOGY FOLLOWED FOR THIS REPORT</b> .....	<b>5</b>
2.1. PROJECT DETAILS.....	5
<b>3. REHABILITATION STRATEGY AND IMPLEMENTATION PROGRAM</b> .....	<b>6</b>
3.1. FACILITY DESCRIPTION.....	6
3.1.1. <i>Current and proposed infrastructure</i> .....	6
3.1.1.1. <i>Access roads</i> .....	7
3.1.1.2. <i>Fencing and trenching of the mining area</i> .....	7
3.1.1.3. <i>Stockpile</i> .....	7
3.1.1.4. <i>Temporary services during rehabilitation phase</i> .....	7
3.1.1.5. <i>Demolition of offices, workshops and other facilities</i> .....	7
3.1.1.6. <i>Demolition of the pollution control dam, clean and dirty water management channels</i> .....	7
<b>4. ENVIRONMENTAL DESCRIPTION</b> .....	<b>8</b>
4.1. CLIMATE .....	8
4.1.1. <i>Temperature</i> .....	8
4.1.2. <i>Rainfall</i> .....	9
4.1.3. <i>Evaporation</i> .....	9
4.2. GEOLOGY .....	10
4.3. SURFACE WATER.....	10
4.3.1. <i>Water Management Area (WMA 2)</i> .....	10
4.3.2. <i>Quaternary catchments</i> .....	10
4.3.3. <i>Quaternary Catchment B20F</i> .....	10
4.3.4. <i>Surface Water Monitoring</i> .....	11
4.3.4.1. <i>Variables</i> .....	11
4.3.4.2. <i>Sample storage and transportation</i> .....	12

4.3.4.3. Guidelines.....	12
<b>5. REHABILITATION OBJECTIVES .....</b>	<b>12</b>
5.1. OBJECTIVES OF THE RSIP .....	12
<b>6. REHABILITATION STRATEGY .....</b>	<b>14</b>
6.1. BERMS .....	14
6.1.1. Hard parks, vehicle and machinery bays .....	14
<b>7. REHABILITATION MANAGEMENT PLAN .....</b>	<b>14</b>
<b>8. PLANNING INSTRUMENTS.....</b>	<b>18</b>
8.1. MECHANICAL RESHAPING AND VEGETATION .....	18
8.2. POLLUTION CONTROL DAM.....	18
<b>9. REHABILITATION PROCEDURE .....</b>	<b>19</b>
9.1. SCHEDULE OF QUANTITIES .....	19
9.2. COSTING SPECIFICATIONS.....	19
9.3. PRELIMINARY LIST OF ITEMS FOR CONSIDERATION.....	19
<b>10. CONCLUSION AND RECOMMENDATIONS: .....</b>	<b>24</b>
<b>11. RECOMMENDATIONS .....</b>	<b>24</b>
<b>12. SCHEDULE OF REFERENCE .....</b>	<b>25</b>

**LIST OF TABLES**

TABLE 4-1: MAXIMUM, MINIMUM AND MEAN MONTHLY TEMPERATURE .....	8
TABLE 4-2: MONITORING POINTS LOCATION .....	11
TABLE 7-1:REHABILITATION MANAGEMENT PLAN .....	16
TABLE 9-1: PROVISIONAL LIST CONSIDERATIONS FOR THE REHABILITATION SPECIFICATIONS .....	21
TABLE 9-2: MONITORING SYSTEMS .....	22

**LIST OF FIGURES**

FIGURE 1-1: SITE LOCATION .....	3
---------------------------------	---

## GLOSSARY OF TERMINOLOGY

**Integrated Resource Management:** A way of analyzing the change in demand and operation of water institutions that evaluates a variety of supply-side and demand-side management measures to determine the optimal way of providing water services.

**Demand-side management:** Any measure or initiative that will result in the reduction of the expected water usage or water demand.

**Supply-side management:** Any measure or initiative that will increase the capacity of a water resource or water supply system to supply water.

**Distribution management:** Any function relating to the management, maintenance and operation of any system of structures, pipes, valves, pumps, meters or other associated equipment, including all mains, connection pipes and water installations that are used or intended to be used in connection with the supply of water.

**Unaccounted for water:** The difference between the measured volume of water put into the supply and distribution system and the total volume of water measured to authorized consumers whose fixed property address appears on the official list of water services authorities.

**Water Institutions:** Water institutions include both Water Management Institutions and Water Services Institutions as defined in the National Water Act and the National Water Services Act respectively.

**Water Wastage:** Water lost through leaks or water usage which does not result in any direct benefit to a consumer or user. Inefficient use of water: Water used for a specific purpose over and above the accepted and available best practises and benchmarks or water used for a purpose where very little benefit is derived from it.

**ABBREVIATIONS**

WSA	Water Services Authorities
WSI	Water Services Institutions
WSDP	Water Services Development Plans
UAW	Unaccounted for water
IRP	Integrated Resource Planning
IWRM	Integrated Water Resource Management
CMA	Catchment Management Agency
NWA	National Water Act
NWSA	National Water Services Act

## 1. INTRODUCTION

Letsolo Water and Environmental Services cc was appointed to compile a Rehabilitation Strategy and Implementation Programme (RSIP) for Arbor Siding. The Department of Water and Sanitation (DWS) issued the Water Use Licence (WUL) for activities at Arbor Siding (Licence No: 04/B20F/G/4009). As part of the WUL conditions, Gijima Supply Chains Management (Pty) Ltd must compile the Rehabilitation Strategy and Implementation Programme (RSIP) to ensure efficient water use activities.

By definition, Rehabilitation is the recovery of a disturbed area to the land form and productivity that it enjoyed before the disturbance took place. Therefore this report summarises a strategy that may need to be reviewed on an annual basis to ensure that:

- The rehabilitated site is safe for both humans and animals.
- The site is physically, chemically and biologically stable.
- The remaining impacts are of an acceptable nature without deteriorating over time.
- The closure is achieved in as efficient and cost-effective manner possible and with minimal socio-economic upheaval.

The activities are undertaken within the Victor Khanye Local Municipality, in Mpumalanga Province. The surrounding area can be characterised as Residential, Industrial and Agricultural as follows:

- Residential - Arbor community exist on the southern side of the siding;
- Industrial – There is another mining house which is not associated with Arbor Siding. This siding is located on the northern side of the siding; and
- Agricultural - Farming activities take place on the eastern side of the siding.

The following elements were considered in the preparation of the RSIP:

- Land: The establishment of stable land, profiled to prevent erosion and the migration of clean surface water through rehabilitated land, and capable of achieving the pre-determined post-industrial activity.
- Water: The establishment of a water management system, which will prevent erosion and contamination of fresh water sources. Ensure compliance with the water quality management objectives for the specific catchment area.
- Air: The prevention of the dissemination of any form of air pollution emanating from site by re-vegetating rehabilitated land.
- Cover: The appropriate cover design is usually determined by the nature of the activity. Topsoil cover system is designed to maximise run-off of precipitation, while minimising infiltration and preventing ponding. A stable cover should be established, capable of natural survival.





The RSIP must be able to prevent air and water pollution in accordance with the requirements of the relevant regulations and with good international practice. The intended end use should take into consideration the prior land use and the location with respect to current and potential future socio-economic development.

This report must be amended annually to :

- Protect the environment and public health and safety by using safe and responsible closure practice.
- Establish a self-sustaining solution with a minimum of on-going maintenance.
- Minimise off-site impacts.
- Create safe and stable landforms.
- Return the site to beneficial land use.
- Reduce the needs for long-term monitoring and maintenance.
- Meet all regulatory requirements.

### 1.1. Legal Aspects

#### 1.1.1. South African Legal Framework

For this RSIP, the principal Act of relevance is the National Water Act, 1998 (Act 36 of 1998) (NWA) which provides for the protection, usage, development, conservation, management and control of the country's water resources in an integrated manner. The Act provides the legal basis, upon which to develop tools and means to give effect to the protection of water resources.

#### 1.1.2. Water Use Authorisation

Gijima was issued with Water Use Licence (Licence Number 04/B20F/G/4009) on 18 December 2015. The water uses include a coal stockpile area, a dirty water catchment and two pollution control dams to comply with Section 21 (g) of the National Water Act.

### 1.2. Site location

The location of project falls within Victor Khanye Local Municipality on the farm Van Dyksput 214, located in the magisterial District of Witbank, Mpumalanga Province. Arbor siding is approximately 5 km West of Kendal power station along R555.




Figure 1-1: Site Location

**1.3. Declaration of independence:**

I, Ishmael Phalane, act as the independent specialist. I declare that there are no circumstances that may compromise my objectivity in performing such work. I have expertise in conducting the Water Conservation, Demand and Supply Strategy (WCDSS) and report relevant to the environmental authorisation applications. I confirm that I have knowledge of the relevant environmental Acts, Regulations and Guidelines that have relevance to the proposed activity and my field of expertise and will comply with the requirements therein.

I have no, and will not engage in, conflicting interests in the undertaking of the activity.

I undertake to disclose to the applicant and the competent authority all material information in my possession that reasonably has, or may have, the potential of influencing any decision to be taken with respect to the application by the competent authority; and the objectivity of any report, plan or document to be prepared by myself for submission to the competent authority;

All particulars furnished by me in this report are true and correct. I realise that a false declaration is an offence in terms of regulation 48 of the National Environmental Management Act, 107 of 1998 (NEMA) and is punishable in terms of section 24F of the Act.

**1.4. Scope of Work**

The scope of work allows for compilation of the RSIP in line with the requirements of the National Water Act, 1998 (Act 36 of 1998) as prescribed by the Department of Water Affairs.

The scope of work allows for the following:

- Rehabilitation Objectives
- Rehabilitation Strategy
- Rehabilitation management Plan
- Planning Instruments
- Final Landform
- Rehabilitation procedure

## 2. METHODOLOGY FOLLOWED FOR THIS REPORT

In order to ensure that a practical methodology for the rehabilitation strategy is compiled, the following was undertaken:

- a site visit during which time the conditions of the study area were assessed;
- Compile a report comprising of a systematic procedure to rehabilitate the storm water dam.

### 2.1. Project Details

Gijima is operating as railway siding on Portion 1 of the Farm Van Dyksput 214 IR, also known as Arbor siding, located approximately 5 km West of Kendal power station. The activities at Arbor siding entails the offloading, stockpiling and removal of coal. Coal will be trucked in from a mine and therefore no mining activities are anticipated on site. Suitably scaled topographical maps were used to delineate the relevant catchments, which may be impacted on by the proposed activities. The following GIS information was used:

1:50 000 Topographical maps (2628bb), Raster as well as Vector;

- Contour maps (2 meter height difference); and
- Quaternary catchment boundaries.

The study area falls within Water Management Area 4 (Olifants Water Management Area), in the quaternary catchment B20F. The area drains northerly towards the tributary of the Wilge River and the most reliable rainfall station near the study area is SAWB-0477602.

Gijima is a 55.25% BB-BEE South African based supply chain management company (level 2 BBBEE), with its primary focus on the rail-reliant bulk commodity market. Gijima has established strong relationships and alliances with important role players in the Mining Industry and in particular with Transnet Freight Rail. The core business of Gijima since it was founded in 2004 is the development and management of multi-modal logistic solutions within Southern Africa. The TFR/Eskom current strategy of Road to Rail migration is strongly supported by Gijima, and as such, Gijima will contribute to the success of this strategy, with an efficient, cost effective and safe logistic solution, for the provision of coal loading and material handling services at Arbor siding.

### 3. REHABILITATION STRATEGY AND IMPLEMENTATION PROGRAM

#### 3.1. Facility Description

A siding, in rail terminology, is a low-speed track section distinct from a running line or through route such as a main line or branch line or spur. It may connect to through track or to other sidings at either end. Sidings often have lighter rails, meant for lower speed or less heavy traffic, and few, if any, signals. Sidings connected at both ends to a running line are commonly known as loops.

Throughout history, coal has been used as an energy resource, primarily burned for the production of electricity and/or heat, and is also used for industrial purposes, such as refining metals. A fossil fuel, coal forms when dead plant matter is converted into peat, which in turn is converted into lignite, then sub-bituminous coal, after that bituminous coal, and lastly anthracite.

Coal is the largest source of energy for the generation of electricity worldwide.

The objectives of the project includes the moving of high volume commodities from road to rail, supply local and export clients, create jobs and enhance entrepreneur potential in the area. It is to benefit the local economy through salaries paid to employees and tax revenues paid to Government.

The Arbor siding operation is expected to contribute positively towards development of opportunities within Victor Khanye Local Municipality. The local economy will be boosted through provision/creation of employment opportunities for the local community. These opportunities will have a positive effect on the broader value chain extending to suppliers of goods and services from nearby towns. The operation will employ approximately 5 people excluding the already employed truck drivers and Gijima employees. The operation will contribute positively on livelihoods leading to an increase in the standards of living while causing a reduction in poverty. The coal beneficiation industry has a positive impact of regional and local economic setup. The local economy will benefit through salaries paid to employees and tax revenues paid to Government.

##### 3.1.1. Current and proposed infrastructure

Existing infrastructure is listed below:

- Access road
- Fencing and trenching

- Stockpiling
- Buildings - offices
- Water use, reticulation and supply
- Dirty water management systems.

3.1.1.1. Access roads

Existing access roads is used for access to site.

3.1.1.2. Fencing and trenching

A fence is established around the perimeter of the pollution control dam.

3.1.1.3. Stockpile

Coal is trucked in and stockpiled on site. These stockpiles are removed by means of front end loaders for loading into the train wagon.

3.1.1.4. Temporary services during rehabilitation phase

The following will be provided for temporary services:

- Chemical toilets will be made available on site for ablution. These toilets will be serviced as required, by a contractor.
- A diesel generator will be installed to provide electricity if the need arises.
- Waste skips will be used for waste collection and any domestic waste will be removed from the site to a licenced waste facility by a contractor.
- Water requirements relating to ablutions and drinking water are expected to be minimal and if water cannot be sourced on site it will be brought in by a tanker.

3.1.1.5. Demolition of offices, workshops and other facilities

The contractor yard will be constructed by levelling the area. The contractor yard will accommodate offices, workshops, diesel storage facilities for the appointed contractor.

3.1.1.6. Demolition of the pollution control dam, clean and dirty water management channels

A pollution control dam exists at the most downstream point of the dirty water catchment area.

The catchment area for the siding and associated infrastructure has been minimised through the use of clean water cut off drains and berms. These drains are used to intercept any water entering the dirty water area and diverting it to lower soak away points where the water will re-enter the environment.

#### 4. ENVIRONMENTAL DESCRIPTION

##### 4.1. Climate

##### 4.1.1. Temperature

The mean daily maximum temperature exceeds 25 °C between November and March, the hottest months. Average maximum temperatures in the winter months (May-August) range from 18.0°C to 21.3°C. The mean minimum summer temperatures range from 11.7°C (March) to 14.2°C (January) with winter mean minima ranging from -1.6°C to 2.9°C. An extreme maximum temperature of 33.8°C was recorded at Ogies, on 12 November 1990 and an extreme minimum temperature of -8.8°C on 9 June 1988.

**Table 4-1: Maximum, Minimum and Mean Monthly Temperature**

Month	Mean Daily Temp (°C)		
	Max	Min	Mean Monthly Temp (°C)
January	27.0	14.2	20.6
February	26.0	13.6	19.8
March	25.7	11.7	18.7
April	23.3	8.1	15.7
May	21.3	2.9	12.1
June	18.0	- 0.5	8.8
July	18.8	- 1.6	8.6
August	20.9	1.2	11.1
September	23.4	6.0	14.7
October	24.7	10.0	17.4
November	25.0	12.0	18.5
December	26.3	13.8	20.1
Annum	23.4	7.6	15.5

#### 4.1.2. Rainfall

When the rate of rainfall influx exceeds the absorption capacity of the soil, the excess water flows over the surface as overland flow. Rainfall runoff responds differently to variations in topography, soil and characteristics of precipitation, and indirectly to variations in climate, vegetation and land use. Therefore runoff flow, controls the volume, periodicity and chemical characteristics of contributions to receiving streams and lake basins.

Many different rainfall data sources and consequent data sets exist for rainfall representation over S.A. Each data source and data set has its own unique advantages as well as disadvantages. Different hydrological rainfall-runoff simulation and peak flow estimation models exist as well as different methods for estimations which require different rainfall parameters with specific required detail and accuracy. Water Research Commission collects Rainfall, Runoff and Evaporation data. This data is herein referred to as WR2005 data. WR2005 includes most data sets all over the country but is currently limited up to and including the year 2004, starting from 1920. Data sets have a record period of 85 years. Major and extensive research efforts and modelling exercises have been conducted to obtain WR2005 rainfall data.

Mean Annual Precipitation (MAP) is representative of the average rainfall that occurs over an area during any given year. This rainfall is obtained by taking the total rainfall received over time at a specific point including any extreme periods and/or events and averaging it.

The site MAP is estimated at 739 mm.

#### 4.1.3. Evaporation

As in the case of rainfall and runoff it is also necessary to analyse the Mean Annual Evaporation (MAE). Much less evaporation data exists than data for rainfall and runoff. Evaporation is measured at dams and mostly stations that are operated by DWS; these stations provide such data. Again, as in the case with rainfall and runoff, much effort has been placed to incorporate evaporation data into the Pitman model and consequently the WR2005 dataset (WRC, 2008). A previous version of WR2005 is also available with evaporation data; this data set is called the WR90 data set (WRC, 1990). The site MAE is estimated at 1517.8 mm.

The main areas where evaporation can be found are at open water storage. In this instance, evaporation losses occur at the PCD.



#### 4.2. **Geology**

The site is located on the western side of the Witbank Coalfield and is underlain by soils and rocks of the Vryheid Formation of the Ecca Group and typically comprises siltstones, shales and sandstones. The area also appears to be liberally intruded by dolerite. The Vryheid Formation is, in turn, underlain by dwyka tillite of the Dwyka Formation. The upper portion of the overburden is invariably made up of highly weathered to partially weathered overburden consisting of clayey soils, siltstone and sandstone.

#### 4.3. **Surface Water**

##### 4.3.1. Water Management Area (WMA 2)

The study area falls within the Olifants water Management Area (WMA 2). The WMA 2 lies in the north-eastern part of South Africa (*National Water Resources Strategy, 2016*). The Water Management Area hosts four (4) major rivers, namely the Elands, Wilge, Steelpoort and Olifants; however the Colliery occurs within the upper parts of the Wilge River, within the Olifants River Basin.

##### 4.3.2. Quaternary catchments

A catchment or water shed is derived from the topographical landscape. It is sectioned by a water divide, a high land separating two or more water systems. A quaternary catchment is the land and water surface area that contributes to the discharge at the system outlet.

##### 4.3.3. Quaternary Catchment B20F

Arbor siding falls within B20F. This Catchment hosts the downstream of the Wilger River as a main stream. It has an area of 506km<sup>2</sup> with MAR 33.3mm/a and MAP of 666.79mm.

#### 4.3.4. Surface Water Monitoring

The monitoring points are summarised as follows:

**Table 4-2: Monitoring Points Location**

ID	LABEL	X (Decimal Degrees)	Y (Decimal Degrees)	Frequency of monitoring
1	SW1	28.92417436	-26.04450349	Monthly
2	SW2	28.88386559	-26.03501712	Monthly
3	SW3	28.8735138	-26.02875944	Monthly
4	PCD	28.88166875	-26.03907795	Monthly
5	Jojo Tank	28.88116947	-26.03881167	Monthly
6	U/S Borehole	28.8803240	-26.04391319	Quarterly
7	D/S Borehole	28.87344723	-26.03807939	Quarterly

Please take note of the following monitoring point naming criterion:

- SW - Surface Water
- PCD - Pollution Control Dam
- U/S - Upstream
- D/S - Downstream

##### 4.3.4.1. Variables

Surface water and Groundwater samples were collected and the Lab analysis was conducted for the following variables:

- pH-Value at 25 ° C
- Conductivity at 25° C in mS/m
- Total Dissolved Solids
- Suspended Solids
- Nitrate & Nitrite as N
- Chlorides as Cl
- Total Alkalinity as CaCO<sub>3</sub>
- Fluoride as F
- Sulphate as SO<sub>4</sub>
- Calcium as Ca
- Magnesium as Mg

- Sodium as Na
- Potassium as K
- Iron as Fe
- Manganese as Mn
- Aluminium as Al

#### 4.3.4.2. Sample storage and transportation

After samples were collected, they were stored in a cooler box and then transported to the Laboratory within 24 hours of sampling, for screening.

#### 4.3.4.3. Guidelines

The following guidelines were used for the compilation of the report:

- SANS 241 (2015) Aesthetic
- SANS 241 (2015) Acute
- Health SANS 241 (2015) Chronic Health

## 5. REHABILITATION OBJECTIVES

### 5.1. Objectives of the RSIP

The primary objective of the RSIP is to protect the water resource (including the water quality, water quantity and the aquatic ecosystem) after closure. This is achieved through adherence to the hierarchy of decision-taking, which is based on a precautionary approach and includes the following:

- Pollution prevention and minimisation of impacts.
- Water reuse and reclamation; and
- Discharge or disposal of waste and/or waste water.

To achieve this primary objective, the water management infrastructure must be rehabilitated with the following specific objectives in mind:

- To ensure that water management measures take account of and fit into the broader regional water management context;
- To ensure that water of different quality (i.e. clean and dirty water) is kept separate, and managed separately, as far as possible. This will ensure that the contact

between water of different quality, and the potential for unnecessary water quality deterioration, is minimized;

- To ensure that the water management measures are sustainable (durable) over the long term,

The aim of the rehabilitation strategy is to commit to the conditions within the Environmental Principles which states, but is not limited to the following:

- Clear all infrastructure and re-vegetate the areas to near pre-mining conditions;
- Compaction will be managed to protect the soil structure (i.e. ripping of 500 mm). Fertiliser will be applied at the required rate as determined by soil laboratory analysis;
- Topsoils will be replaced and the affected areas will be rehabilitated using indigenous vegetation common to the area. The rehabilitation of the soils will play a significant role in the rehabilitation of vegetation;
- The rehabilitated areas will be ameliorated and seeded with the recommended seed mix and the planted area will be watered thoroughly and regularly; and
- Monitoring will be undertaken to ensure that the rehabilitated areas are self-sustaining and that weed / alien plants are under control. Monitoring will only cease once this has been confirmed.

The objective is to ensure that any long-term residual water quality impacts are identified and adequately managed in the closure scenario. The practical implications of these water management regulations are as follows:

- In the case of temporary cessation, management team must:
  - Review and update the closure plan, where required,
  - Identify all water management measures that need to be put in place to ensure effective operations and maintenance of the pollution control measures during the temporary cessation period, and
  - Identify and implement the required monitoring programmes.
- In the case of permanent cessation of mining, i.e. closure, management team must:
  - Ensure that the required rehabilitation of pollution control measures is undertaken in accordance with the closure objectives and the closure plan.

## **6. REHABILITATION STRATEGY**

The strategy for Arbor Siding is summarised as follows:

### **6.1. Berms**

Clean and dirty water cutoff berms should be rehabilitated with low permeability material containing no carbonaceous formation.

Water drainage paths should be designed to maximise flow without erosion

Cognisance should be taken of materials erodeability when designing flow path gradients

The berm material could be re-used as the mining window advances. Unlevelled spoil piles should be kept to a minimum. A maximum of three cut widths of unlevelled spoil is recommended to reduce rainfall ingress

Low wall ramps should periodically be backfilled to reduce rainfall ingress.

Rehabilitation growth must be maximised to facilitated erosion control and maximise evapotranspiration.

#### **6.1.1. Hard parks, vehicle and machinery bays**

Topsoil, subsoil and soft weathered overburden should be used for rehabilitation, to provide a good foundation vegetation layer. These materials should be stockpiled for reuse after closure.

Dirty water from these areas will contain oils and greases and need to be channelled into the operational system for collecting oils and greases.

## **7. REHABILITATION MANAGEMENT PLAN**

In order to ensure that a systematic methodology for the rehabilitation, the aspects requiring rehabilitation is compiled into a report and the necessary actions and responsible parties are detailed.

The timeframes mentioned in the table hereafter assumes the following:

- Prior to rehabilitation – will include the site clearing and the removal of all foreign infrastructure (approximately one week);
- During rehabilitation – will include the activities associated with the shaping of the area and the establishment of the pre-construction environment (approximately 1 month); and
- After rehabilitation – will include the activities which will be undertaken to monitor the success of the rehabilitation activities (approximately 6 months).

Table 7-1: Rehabilitation Management Plan

Aspect requiring rehabilitation	Actions Required	Responsible Person	Timeframes
	All rehabilitation activities must be limited to the already disturbed area.	Construction Manager and Environmental Manager	Prior, during and after rehabilitation activities.
General	No further removal of vegetation would be allowed without obtaining the necessary permits from the Department of Water and Sanitation.	Construction Manager and Environmental Manager	Prior, during and after rehabilitation activities.
	Any vehicles on the site should be operated with low tyre pressure (as low as possible) in order to minimise soil compaction.	Construction Manager	During rehabilitation activities.
	Particular attention must be given to any possible contaminants (for example vehicle fuel, cleaning chemicals, any waste products) since the soil is very permeable. All potential contaminants must be stored off site and any spills remediated immediately by removal and correct disposal of the soil contaminated.	Construction Manager and Environmental Manager	Prior, during and after rehabilitation activities.
Topography	All foreign material must be removed and disposed of at a licensed site.	Construction Manager and	Prior to rehabilitation activities.

ARBOR SIDING - RSIP

JANUARY 2018

Aspect requiring rehabilitation	Actions Required	Responsible Person	Timeframes
	<p>All other material (such as the berms ) must be monitored for contamination. Should the samples prove that the material has been contaminated, the material must be remediated and be utilised in the reshaping of the land.</p> <p>The area must be reshaped to ensure that the natural contours of the area are reinstated and the area is free draining. This is of particular importance for the natural run of the flood plain.</p>	<p>Environmental Manager</p> <p>Construction Manager and Environmental Manager</p>	<p>Prior and during rehabilitation activities.</p>
Soils	<p>The soils must be analysed to ensure that the soils have not become contaminated.</p> <p>Should the samples indicate that the soils have been contaminated the contaminated soils must be treated for reuse in the rehabilitation procedures.</p> <p>As part of the reshaping activities the compacted soils must be ripped to a depth of 500 mm.</p>	<p>Construction Manager and Environmental Manager</p> <p>Environmental Manager</p> <p>Environmental Manager</p> <p>Construction Manager and Environmental Manager</p>	<p>During rehabilitation activities.</p> <p>Prior to rehabilitation activities.</p> <p>Prior to rehabilitation activities.</p> <p>During rehabilitation activities.</p>



## 8. PLANNING INSTRUMENTS

### 8.1. Mechanical Reshaping and Vegetation

The concept of reshaping consists of flattening the rehabilitated area from their current slope in a balanced cut to fill earthworks operation. The rationale for reshaping is that erosion is reduced, which results in improved vegetation sustainability. Through engineering, the deposit can be re-shaped to a more natural geometry, which will allow it to blend in to the surrounding topography.

Unfortunately, reshaping requires the movement of large quantities of material, an expense that would not have been necessary had the dam been constructed differently. Large volumes of dust are likely to be generated and the exercise should preferably be carried out during a suitable climatic period in the year such as late summer.

Mechanical re-shaping would be performed in a balanced cut to fill operation using earth-moving equipment.

These methods introduce some bio-diversity and with the reduced erosion and slope angle, it may be possible that other species could colonise this site. It is also more likely that animals could use the site.

Dust and noise will be generated during the reshaping process but the deposit could become a more visually pleasing extension to the adjacent ridge and will be more stable.

### 8.2. Pollution control dam

According to the Best Practices, topsoil removal and stockpiling is required before the erection of any new infrastructure. If this was done before the dam was built then this soil should be used for rehabilitation of the site, if soil was not stockpiled then an alternative source of suitable cover will need to be identified (e.g. removal from a borrow pit or other soil stockpiles).

It is important to use a soil source with properties as close to the original soil as possible in order to prevent other problems developing such as contamination of water resources.

Guidelines for removal of existing infrastructure:

- Any vehicles on the site should be operated with low tyre pressure (as low as possible) in order to minimize soil compaction.
- Particular attention must be given to any possible contaminants (for example vehicle fuel, cleaning chemicals, any waste products) since the soil is very permeable.

- All potential contaminants must be stored off-site and any spills remediated immediately by removal and correct disposal of the contaminated soil.

Guidelines for rehabilitation of the soil at the dam site:

- Replace the removed topsoil to a depth of 300mm if possible. Or to a similar depth of the surrounding soils (the soils of the area are typically shallow). If soil was not stockpiled then a new source will need to be identified as discussed above.
- Best Practice Guidelines recommends testing and fertilization of the replaced soil. This should be undertaken, but with a high degree of caution and to a limited extent. Any fertilizer introduced to these permeable soils on a flood plain will leach into the ground/surface water resources with the first irrigation/rains.
- Composted cattle manure can be used to increase the organic matter content of the soil in order to boost plant growth but again should be used with caution to prevent contamination of the water resources by leaching. A soil test result is required in order to accurately determine application rates.
- As per guidelines in the EMPR, an appropriate seed mixture can be used to re-establish the vegetation.
- Advice from a botanical specialist is recommended to ensure that the correct species are planted.

## 9. REHABILITATION PROCEDURE

### 9.1. Schedule of Quantities

The information contained in the rehabilitation plan must be used to develop a Schedule of Quantities (SOQ) for inclusion in the contractor scope of work. In addition, it will be recommended that the rehabilitation plan / specifications be appended to tender.

### 9.2. Costing Specifications

Based on the details of the rehabilitation plan, Gijima must provide a guideline cost for the implementation of the rehabilitation specifications. The costing must be based on accepted industry rates for various tasks, equipment and materials but will not be a formal quotation and must be viewed as an estimate.

### 9.3. Preliminary list of items for consideration

The following items should be considered during rehabilitation phase:

- Site visit
- Soil

- Substrate samples and analysis
- Pre-mining soil type (EMPR; land capability)
- Texture
- Chemical constituents
- Fertility
- Compaction tests
- Vegetation samples and analysis
- Sampling of vegetation in benchmark
- Obtaining and reviewing existing data
- End land use
  - Type (grazing?)
  - Reintroduction of animals
  - Protection from grazing
- Surveying
  - Existing survey plans
  - Additional survey requirements
  - Final topography
  - Contouring and Shaping
- Chemical amelioration
  - Acidic conditions
  - Fertility
  - Salinity / sodicity
- Physical amelioration
  - Compaction
- Climatic considerations
- Temperature
- Rainfall (esp. high intensity and drought)
- Evaporation
- Erosion
  - Maintenance requirements
  - Maintenance fertiliser requirements
  - Mowing or cutting of vegetation
  - Potential long-term problems
- Treating pollution hot spots

These items are tabulated below:

**Table 9-1:** Provisional List Considerations for the Rehabilitation Specifications

<ul style="list-style-type: none"> <li>• Final topography</li> </ul>	<ul style="list-style-type: none"> <li>• Post-mining topography</li> <li>• Backfilling and contouring</li> <li>• Shaping requirements</li> <li>• Drainage requirements (free-draining)</li> <li>• Convex / concave</li> </ul>
<ul style="list-style-type: none"> <li>• Capping materials</li> </ul>	<ul style="list-style-type: none"> <li>• Sources of material</li> <li>• Volumes</li> <li>• Locality</li> <li>• Availability</li> </ul>
<ul style="list-style-type: none"> <li>• Climatic considerations</li> </ul>	<ul style="list-style-type: none"> <li>• Temperature</li> <li>• Rainfall (esp. high intensity and drought)</li> <li>• Evaporation</li> </ul>
<ul style="list-style-type: none"> <li>• Erosion</li> </ul>	<ul style="list-style-type: none"> <li>• Potential sites</li> <li>• Actual sites</li> <li>• Methods of repair and prevention / control</li> <li>• Runoff control structures</li> </ul>
<ul style="list-style-type: none"> <li>• Plant material</li> </ul>	<ul style="list-style-type: none"> <li>• Seed or sod</li> <li>• Mix ratio</li> <li>• Species type</li> <li>• Application rates</li> <li>• Application method</li> </ul>
<ul style="list-style-type: none"> <li>• Watering</li> </ul>	<ul style="list-style-type: none"> <li>• Frequency</li> <li>• Volume</li> </ul>
<ul style="list-style-type: none"> <li>• Ongoing (follow-up) Monitoring</li> </ul>	<ul style="list-style-type: none"> <li>• Procedure</li> <li>• Frequency</li> <li>• Results and interpretation</li> <li>• Maintenance requirements</li> <li>• Maintenance fertiliser requirements</li> <li>• Mowing or cutting of vegetation</li> <li>• Potential long-term problems</li> </ul>

**Table 9-2: Monitoring Systems**

Monitoring of Environmental Impacts and Management	Recommendations and/or comments
Surface Water	<p>Arbor Siding will initiate and implement an extensive surface-water monitoring programme consisting of strategically placed surface water monitoring points to monitor water quality within the affected streams and the dirty water areas. Water monitoring samples will be taken on a monthly basis. The following constituents i.e. pH, TDS, EC, Alkalinity, Suspended solids, Ca, Na, K, Mg, Cl, SO4, Fe, Mn, and Al will be monitored at the different monitoring points.</p> <p>A water quality report will be compiled on a quarterly basis. This report will show all risk areas and areas showing diversion to the current background water quality. Recommendations will also be included in this water quality report.</p>
Groundwater	<p>To determine if any groundwater quality deterioration is occurring, the following constituents (pH, TDS, EC, Alkalinity, Suspended Solids, Ca, Na, Mg, K, Cl, SO4, Fe, Mn, and Al) will be measured. To determine if any groundwater level lowering is taking place, static groundwater levels will be monitored. Monitoring of both groundwater quality and static water levels will be conducted on a quarterly basis.</p> <p>This will ensure that any decline in the quality and yield of groundwater of legitimate groundwater users in the area is detected in time, while also providing a necessary database for future disputes. If it can be proven that the quality of groundwater available to certain users is being adversely affected to a point where it is no longer suitable for the intended use, Gijima will compensate the affected parties.</p>

<p>Air Quality</p>	<p>During the construction, operational and decommissioning phases the machinery movement, blowing wind and blasting will generate dust. The dust will migrate to the prevailing wind direction. Due to the presence of a number of farm houses to the east and the informal settlements to the west, north west and south west of the mining area it will be necessary to conduct ambient dust monitoring.</p>
<p>Noise &amp; Vibration</p>	<p>Noise will be generated during blasting. A monitoring programme for the purpose of monitoring the noise and vibration levels during blasting and machinery movements will be developed.</p>
<p>Interested and Affected Parties</p>	<p>Any additional or new parties that would like to be included the list will be included in the list.</p> <p>Arbor Siding will apply an open-door policy with all I&amp;AP. This will allow the project to pro-actively react to any perceived complaint from its neighbors thus ensuring that the situation is resolved timeously. A complaints register will also be kept at the offices. All complaints and response to the complaints will be kept in the complaints register.</p>

## 10. CONCLUSION AND RECOMMENDATIONS:

Arbor Siding is still operational. Therefore this report must be updated annually. Other practical implications in terms of Rehabilitation Strategy and Implementation Plan are as follows:

- All water management infrastructures should be designed and managed to facilitate closure. This includes the following considerations:
  - The durability and longevity of water management designs, e.g. provision of erosion protection for long-term control of erosion,
  - The consideration of active versus passive care of the water management infrastructure post-closure, and
  - The consideration of the final land use and final land forms should be incorporated into the design of the water management measures for closure.
- The post-closure water use should be considered in the design process
- The final topography should be planned, as far as possible, to be free-draining.

The physical parameters, and more importantly to the backfill of the open cast pits, the chemical composition of the materials need to be assessed in terms of the potential for the liberation of acid drainage from the site.

In addition, the liability for potential pollution needed to be understood before any long term decision was taken.

## 11. RECOMMENDATIONS

The RSIP emphasise that the current pit does not become abandoned in the future and that the site is either returned to its original state or that the community can make use of the site for other economically viable activities. Where it is not possible to return the site to its original state or to develop it for other purposes, it is essential that:

- The site is made safe for both humans and animals.
- The site is physically, chemically and biologically stable.
- The remaining impacts are of an acceptable nature without deteriorating over time.
- The closure is achieved in as efficient and cost-effective manner possible and with minimal socio-economic upheaval.

**12. SCHEDULE OF REFERENCE**

- Alexander, W.J.R. (2002). The standard design flood. Journal of the South African Institution of Civil Engineering. Volume 44, No 1. SAICE.
- Smithers, J.C. and Schulze, R.E. (2002). Design Rainfall Estimation in South Africa. Water Research Commission. Report no. K5/1060. Pretoria.
- Midgley, D.C. (1972). Design flood determination in South Africa. Hydrological Research Unit Report No 1/72. University of the Witwatersrand. Department of Civil Engineering.



**Annexure 16.2-4: Soil Chemistry Report**

ARBOR SIDING

REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT



# ARBOR SIDING SOIL IMPACT ASSESSMENT

Author: Brenton Mabuza  
M.Sc. Soil Science; (SACNASP – Reg No:  
400215/13)  
Reference Number: LWES 417  
Date: 22 January 2018

Letsolo Water and Environmental Services cc  
P O Box 19016, Pretoria West, 0117  
Reg No: 2010/005979/23  
Tax Ref No: 9170/262/18/3  
VAT No: 4380258477

Tel: 012 373 4986 Cell: 082 821 6621  
Fax: 0866 134 794  
Email: [ishmael@lwes.co.za](mailto:ishmael@lwes.co.za)  
Website: [www.lwes.co.za](http://www.lwes.co.za)

### EXECUTIVE SUMMARY

The monitoring of soil resources at the Arbor Coal Siding was conducted as part of ensuring compliance with the Water Use Licence for the management of a coal siding on the property. The property is situated a little more than 20 km, west of the town Ogies, in the western part of the Mpumalanga Province. Three samples were collected at intervals of approximately 200 m at the train loading zone and a 4<sup>th</sup> sample was collected at the mid-point of the gravel haul route. Analysis results revealed that the samples returned acceptable parameter levels for pH, EC and Na levels. The results showed the samples to have either mildly acid or neutral pH, moderate electrical conductivity and sodium levels. Continuous monitoring of the water quality in pollution control dams and the treatment thereof if necessary will have to be carried out and corrective measures adopted if anomalies are detected in the quality.

**TABLE OF CONTENTS**

1. INTRODUCTION .....3  
2. LEGISLATIVE REQUIREMENTS .....3  
3. STUDY AREA.....4  
4. METHODOLOGY .....6  
    4.1. Sampling Depth .....6  
    4.2. Sampling Tools .....6  
    4.3. Sampling location .....6  
    4.4. Sample Identification .....6  
5. SOIL ANALYSIS RESULTS.....8  
    5.1. pH.....8  
    5.2. Electrical Conductivity.....9  
    5.3. Exchangeable Cations - sodium .....10  
6. RECOMMENDATIONS .....11  
7. CONCLUSION.....11

**LIST OF TABLES**

Table 5-1: Soil Analysis Results .....8  
Table 5-2: Soil pH Ranges (After Fertilizer Handbook, 2007).....9  
Table 5-3: Salt tolerance of common agricultural crops (USDA, 2009),  
expressed as electrical conductivity of the soil saturation extract at the  
threshold when crop yield first reduces below the full yield potential (EC<sub>e</sub>,  
threshold).....10  
Table 5-4: Cation Ratio for Sampled Sites .....11

**LIST OF FIGURES**

Figure 3-1: Location Map of Arbor Coal Siding .....5  
Figure 4-1: Soil Sample Points At Map of Arbor Coal Siding.....7

**APPENDICES**

Appendix A : Soil pH map)  
Appendix B : Electrical Conductivity Map  
Appendix C : Sodium Concentration Map  
Appendix D : Laboratory Results

### REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

#### 1. INTRODUCTION

Letsolo Water and Environmental Services was appointed by Gijima Supply Chain Management Services Pty Ltd to undertake a soils analysis of the coal siding at Arbor, 20 km west of the Ogies town in the central part of the Mpumalanga Province. This was meant to ensure compliance with the issued Water Use Licence for the coal siding. The sampling was carried out in November 2017. The site is comprised of a coal stock pile, block of offices, railway route, weighbridge, pollution control dam and a gravel haul route.

Gijima Supply Chain Management Services (Pty) Ltd is undertaking a coal loading operations on Portion 1 of the Farm Van Dyksput 214 IR also known as Arbor siding, located approximately 5 km West of Kendal power station. The operations include haulage of coal from various mines, stockpile and load to railway wagons for transportation to the markets. The coal stock piling footprint of the activity covers approximately 9000 square meters.

The objectives of the survey are to:

- Provide a soil chemistry map depicting levels of pH, Electrical Conductivity and sodium on site
- Provide a report discussing findings in relation to chemistry of soils at the Arbor siding.

#### 2. LEGISLATIVE REQUIREMENTS

The act of relevance to this study is the National Water Act, 1998 (Act 36 of 1998) which emphasises the need to conduct activities that ensure compliance with the requirements of the Water Use Licence. Gijima was issued with Water Use Licence (Licence Number 04/B20F/G/4009) on 18 December 2015. Soil samples were collected for chemical analysis and a soil chemistry map drawn which should show levels of:

- pH
- Electrical Conductivity
- Sodium.

Over and above the above recommended variables, it was deemed necessary to also include other variables for the chemical assessment in order to make informed recommendations. In order to ensure that when the operation ceases, the environment is left in a condition which favours re-vegetation. Therefore, additional variables are checked in line with plant requirements. These additional variables include:

### REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

- Potassium (K) - Potassium rivals nitrogen as the nutrient absorbed in greatest amounts by plants. Like nitrogen, crops take up a relatively large proportion of plant-available potassium each growing season. The slow release of potassium from native soil minerals and from fixed forms in clays can replenish some of the potassium lost by crop removal and leaching. This ability, however, is limited and variable. Fertilization is often necessary to maintain optimum yields.
- Calcium (Ca) - Calcium is essential for proper functioning of plant cell walls and membranes. Sufficient calcium must also be present in actively growing plant parts, especially in fruits and roots. Properly limed soils with constant and adequate moisture will normally supply sufficient calcium to plants
- Magnesium (Mg) - Magnesium acts together with phosphorus to drive plant metabolism and is part of chlorophyll, a vital substance for photosynthesis. Like calcium, magnesium is ordinarily supplied through liming. If magnesium levels are low and lime is required.

### 3. STUDY AREA

The study area falls within Portion 1 of the farm Van Dykspuit farm located in the Mpumalanga Province. The site is cleared of vegetation, is relatively flat with slopes of that do not exceed 1% and has a rail track cutting through the property with coal stock piles along the length of the rail loading zone as well as a gravel haul route, pollution control dam, weighbridge and administration complex. The town of Ogies is located approximately 20 km to the east of Arbor Siding (Figure 3-1).

# ARBOR SIDING

## REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT



Figure 3-1: Location Map of Arbor Coal Siding

#### 4. METHODOLOGY

##### 4.1. Sampling Depth

It is vital to collect samples from appropriate depths because a core taken deeper or shallower will generate erroneous results.

The soils were sampled at 400 - 500 mm beneath the surface. This sample depth was determined to be just beneath the compacted sacrificial layer which is usually compacted and made to be 300 mm thick.

##### 4.2. Sampling Tools

A hand-held soil auger was used and approximately 1 kg of soil sample collected for chemical analysis. Three soil samples were collected approximately 200 m apart along the stock pile area and one soil sample was collected in the middle of the gravel haul route. These were marked A1-4 (Figure 2).

##### 4.3. Sampling location

At every observation point, a gps point was noted. The soils were analysed at the Aquatico laboratory for the following in accordance to the standard prescribed methods (Non-Affiliated Soil Analysis Work Committee, 1990):

- pH(KCl);
- Cation Exchange Capacity (CEC) and exchangeable cations;
- Phosphorus (Bray 1);
- Electrical Conductivity (EC);
- Acid saturation

##### 4.4. Sample Identification

Along with each soil sample, sampling information sheets were filled out that describe the identity of the sample.



# ARBOR SIDING

## REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT



Figure 4-1: Soil Sample Points At Map of Arbor Coating Siding

5. SOIL ANALYSIS RESULTS

The primary goal of soil testing is to inform efficient and effective resource management. Soil testing is the most accurate way to determine lime and nutrient needs. Soil testing is also useful for identifying contaminated sites.


The results provided in this report reflect the properties of the sample submitted to the Laboratory. As seen in Table 5-1 below, the purpose of report is to provide a brief explanation of each of the values provided on the lab soil test report and how they are used to generate recommendations.

Table 5-1: Soil Analysis Results

Sample Site	A 1	A 2	A 3	A 4	
GPS Coordinate	-26.0394S 28.8818E	-26.0397S 28.8828E	-26.0403S 28.8844E	-26.0396S 28.8833E	Optimum Range
Lab Ref	93575	93576	93577	93578	
Exch Cat cmol(+).kg <sup>-1</sup>					
Ca	15.23	12.14	17.255	11.59	
Mg	1.713	1.450	1.573	3.516	
K	0.0664	0.0485	0.0511	0.0166	
Na	0.06956	0.1	0.1086	0.1086	
S value	17.07	13.7	18.988	53.38	
pH <sub>KCl</sub>	6,74	7,35	6,32	6,09	6.2-7.3
P (Bray 1) (mg/kg)	6	4	4	8	30+
EC (mS.m <sup>-1</sup> )	249	194	241	170	< crop threshold

5.1. pH

Coal is generally associated with sulphide bearing minerals. Coal mining thus exposes the sulphide minerals to the environment which leads to the oxidation of these minerals and the creation of acidic conditions through the following process:



One of the most valuable pieces of information you can get from soil testing is a measure of soil acidity. Soil pH is an indicator of the soil's acidity which is a primary factor controlling nutrient availability, microbial processes, and plant growth.

REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

Soil pH refers to the relationship between H<sup>+</sup> and OH<sup>-</sup> ions. These ions relate to each other in a definite ratio and it is therefore common to ignore one of them. By convention, the H<sup>+</sup> ions are usually considered even in the case of a strong base. Soil pH ranges are commonly described as in Table 5-2:

Table 5-2: Soil pH Ranges (After Fertilizer Handbook, 2007)

Description	Acid			Neutral 7	Alkaline
	Very	-----Slight			Slight ----- Very
pH (KCl)	<4.0	4.5 - 4.9	5.0 - 6.7	6.8 - 7.2	7.3 - 8.0 ----- >8.5

From the analysis results provided, the pH(KCl) range for samples 1 and 2 is neutral. Samples 3 and 4 are mildly acid. These samples returned acceptable pH levels for all four points. A pH map for the Arbor site is shown in Appendix A.

(Please Refer to Appendix A for Soil pH map)

5.2. Electrical Conductivity

The Chamber of Mines specifies that for a soil to be defined as arable, it must have an EC of less than 400 mS/m at 25°C. The samples showed EC figures way below the 400mS/m mark. It should be noted that the 400 mS/m ECe value provided is arbitrary and that EC values should rather be based on the yield levels where various plant crop species first reduce below the full yield potential (threshold levels) (Table 3). Samples 1 and 3 returned EC values generally above threshold levels for salt sensitive crops whereas samples 2 and 4 returned EC levels suited to salt sensitive crops indicating acceptable levels of EC. Various salt tolerance levels for various crops are shown in Table 5-3.

Although these are values associated with cropping in agriculture, they give a perspective of salt loading emanating from various environmental activities in relation to the arbitrary figure of 400 mS/m.

## REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

Table 5-3: Salt tolerance of common agricultural crops (USDA, 2009), expressed as electrical conductivity of the soil saturation extract at the threshold when crop yield first reduces below the full yield potential (EC<sub>e</sub>, threshold).

Crop	EC <sub>e</sub> threshold (mS.m <sup>-1</sup> )
a. Small Vegetables	
Cabbage	100 - 180
Spinach	200 - 320
b. Roots and Tubers	
Potato	170
Sweet Potato	150 - 250
c. Legumes	
Beans	100
Peas	150
d. Forages	
Alfalfa	200
Clover	150

(Please Refer to Appendix B for Electrical Conductivity Map)

### 5.3. Exchangeable Cations - sodium

The amounts of exchangeable cations normally follow the trend Ca>Mg>K>Na. The analysis yielded high levels for Ca, extremely low levels of Mg and low levels of K and Na. The high Ca levels suggest that there could have been lime applied to the area in the past or possibly a high base status of the parent materials prevalent in the area. It should be noted though that despite this base status in the environment, acidity levels are high for samples 2 and 3 and measures need to be put in place to correct the very low soil pH.

The general ratio of cations in soils follows the following general ratio for calcium, magnesium, potassium and sodium:

Ca:	Mg:	K:	Na
65:	25:	8:	2

The cation ratios for the 4 sites sampled is as follows:

REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

Table 5-4: Cation Ratio for Sampled Sites

Site	Ca	Mg	K	Na
Arbor 1	89	10	<1	<1
Arbor 2	88	11	<1	<1
Arbor 3	91	8	<1	<1
Arbor 4	75	23	1	<1

Table 5-4 shows that sodium levels in the soils analysed fall below the threshold levels in relation to the other cations. Magnesium levels for samples 1, 2 and 3 fall way below the required levels in the soil with sample 4 returning Mg levels close to the recognized threshold levels. Calcium levels for all the samples are generally high hinting at possible lime application over the past periods over the life span of the siding.

(Please Refer to Appendix C for Sodium Concentration Map)

6. RECOMMENDATIONS

When soil pH is maintained at the proper level, plant nutrient availability is optimized, solubility of toxic elements is minimized, and beneficial soil organisms are most active.


The pH, EC and Na levels show acceptable levels and therefore no mitigation measures are required.

It is recommended that annual soil sample be conducted in order to monitor the improvements and/or deterioration of soil chemistry.


7. CONCLUSION

The soil sample results returned acceptable acidity levels that are only mildly acid or neutral and therefore do not need liming for pH regulation. The electrical conductivity of all the samples returned results that generally are acceptable with reasonable salt levels for all samples. The sodium levels recorded for all the samples fall below the threshold levels and are acceptable.


APPENDIX A : SOIL PH MAP)



APPENDIX B : ELECTRICAL CONDUCTIVITY MAP



APPENDIX C : SODIUM CONCENTRATION MAP





**ARBOR SIDING**

REPORT: ARBOR SIDING SOIL IMPACT ASSESSMENT

**APPENDIX D : LABORATORY RESULTS**



**Annexure 16.2.5: Heritage Specialist Report**

**Phase 1 Cultural Heritage Impact Assessment:**

**THE PROPOSED UPGRADE AND INCREASE IN THE SCOPE OF ACTIVITIES AT THE EXISTING ARBOR  
RAILWAY SIDING, DELMAS REGION, NKANGALA DISTRICT MUNICIPALITY,  
MPUMALANGA PROVINCE**

**Prepared for:**

Myezo Environmental Management Services: Ms D Kotane

- Address: 645 Jacqueline Drive, Garsfontein, 0181, Pretoria; Tel: 012 998 7642; E-mail: dineo@myezo.co.za

**Prepared by:**

J A van Schalkwyk (D Litt et Phil),

- Heritage Consultant: ASAPA Registration No.: 164 - Principal Investigator: Iron Age, Colonial Period, Industrial Heritage.
- Postal Address: 62 Coetzer Avenue, Monument Park, 0181; Tel: 076 790 6777; E-mail: jvschalkwyk@mweb.co.za

**Report No:** 2019/JvS/019

- Status: Final
- Date: March 2019
- Revision No: -
- Date: -



**Copy Right:**

This report is intended solely for the use of the individual or entity to whom it is addressed or to whom it was meant to be addressed. It is provided solely for the purposes set out in it and may not, in whole or in part, be used for any other purpose or by a third party, without the author's prior written consent.

**Specialist competency:**

Johan A van Schalkwyk, D Litt et Phil, heritage consultant, has been working in the field of heritage management for more than 40 years. Originally based at the National Museum of Cultural History, Pretoria, he has actively done research in the fields of anthropology, archaeology, museology, tourism and impact assessment. This work was done in Limpopo Province, Gauteng, Mpumalanga, North West Province, Eastern Cape Province, Northern Cape Province, Botswana, Zimbabwe, Malawi, Lesotho and Swaziland. Based on this work, he has curated various exhibitions at different museums and has published more than 70 papers, most in scientifically accredited journals. During this period, he has done more than 2000 impact assessments (archaeological, anthropological, historical and social) for various government departments and developers. Projects include environmental management frameworks, roads, pipeline-, and power line developments, dams, mining, water purification works, historical landscapes, refuse dumps and urban developments.



J A van Schalkwyk  
Heritage Consultant  
March 2019



**SPECIALIST DECLARATION**

---

I, J A van Schalkwyk, as the appointed independent specialist, in terms of the 2014 EIA Regulations (as amended), hereby declare that I:

- I act as the independent specialist in this application;
- I perform the work relating to the application in an objective manner, even if this results in views and findings that are not favourable to the applicant;
- regard the information contained in this report as it relates to my specialist input/study to be true and correct, and do not have and will not have any financial interest in the undertaking of the activity, other than remuneration for work performed in terms of the NEMA, the Environmental Impact Assessment Regulations, 2014 (as amended) and any specific environmental management Act;
- I declare that there are no circumstances that may compromise my objectivity in performing such work;
- I have expertise in conducting the specialist report relevant to this application, including knowledge of the Act, Regulations and any guidelines that have relevance to the proposed activity;
- I will comply with the Act, Regulations and all other applicable legislation;
- I have no, and will not engage in, conflicting interests in the undertaking of the activity;
- I have no vested interest in the proposed activity proceeding;
- I undertake to disclose to the applicant and the competent authority all material information in my possession that reasonably has or may have the potential of influencing - any decision to be taken with respect to the application by the competent authority; and the objectivity of any report, plan or document to be prepared by myself for submission to the competent authority;
- I have ensured that information containing all relevant facts in respect of the specialist input/study was distributed or made available to interested and affected parties and the public and that participation by interested and affected parties was facilitated in such a manner that all interested and affected parties were provided with a reasonable opportunity to participate and to provide comments on the specialist input/study;
- I have ensured that the comments of all interested and affected parties on the specialist input/study were considered, recorded and submitted to the competent authority in respect of the application;
- all the particulars furnished by me in this specialist input/study are true and correct; and
- I realise that a false declaration is an offence in terms of regulation 48 and is punishable in terms of section 24F of the Act.

Signature of the specialist



J A van Schalkwyk  
March 2019

## EXECUTIVE SUMMARY

**Phase 1 Cultural Heritage Impact Assessment:  
THE PROPOSED UPGRADE AND INCREASE IN THE SCOPE OF ACTIVITIES AT THE EXISTING ARBOR  
RAILWAY SIDING, DELMAS REGION, NKANGALA DISTRICT MUNICIPALITY,  
MPUMALANGA PROVINCE**

*Gijima Supply Chain Management Services (Pty) Ltd* propose the expansion of their scope of activities so as to meet the demand and maximise its operational capacity at Arbor Railway Siding, Delmas region, Nkangala District Municipality, Mpumalanga Province.

In accordance with Section 38 of the NHRA, an independent heritage consultant was appointed by *Myezo Environmental Management Services (Pty) Ltd* to conduct a cultural heritage assessment to determine if the expansion of the scope of activities at the railway siding would have an impact on any sites, features or objects of cultural heritage significance.

This report describes the methodology used, the limitations encountered, the heritage features that were identified and the recommendations and mitigation measures proposed relevant to this. The HIA consisted of a desktop study (archival sources, database survey, maps and aerial imagery) and a physical survey that included the interviewing of relevant people. It should be noted that the implementation of the mitigation measures is subject to SAHRA/PHRA's approval.

The cultural landscape qualities of the region are made up of a pre-colonial element consisting of very limited Stone Age and Iron Age occupation, as well as a much later colonial (farmer) component, which also gave rise to an industrial (mining) component.

### Identified sites

During the physical survey, the following sites, features or objects of cultural significance were identified:

- 7.3.1: Old station building. According to its style and the material used in its construction, this building probably dates to the 1940s. It is similar in style, layout and material as other stations on the same line, e.g. Dryden and Argent. The structure is fenced off and well protected by an alarm system.

### Impact assessment

Impact analysis of cultural heritage resources under threat of the proposed development, is based on the present understanding of the development:

IDENTIFIED HERITAGE RESOURCES					
Site No.	Site type	NHRA category	Field rating	Impact rating: Before/After mitigation	Proposed mitigation (Refer to definitions in Section 12.3)
Station building					
7.3.1	Built structures	Section 34	High significance Grade 4-A	60	(1) Avoidance/Preserve; (2) Archaeological investigation

### Legal requirements

The legal requirements related to heritage specifically are specified in Section 3 of this report. For this proposed project, the assessment has determined that no sites, features or objects of heritage significance occur in the study area. If heritage features are identified during construction, as stated in

the management recommendation, these finds would have to be assessed by a specialist, after which a decision will be made regarding the application for relevant permits.

Reasoned opinion as to whether the proposed activity should be authorised:

- From a heritage point of view, it is recommended that the proposed development be allowed to continue on acceptance of the conditions proposed below.

Conditions for inclusion in the environmental authorisation:

- The Palaeontological Sensitivity Map (SAHRIS) indicate that the study area has a moderate sensitivity of fossil remains to be found and therefore a palaeontological desktop study of the area is required.
- Should archaeological sites or graves be exposed in other areas during construction work, it must immediately be reported to a heritage practitioner so that an investigation and evaluation of the finds can be made.



J A van Schalkwyk  
Heritage Consultant  
February 2019

**TECHNICAL SUMMARY**

<b>Project description</b>	
Description	Expansion of scope of activities at Arbor Railway Siding
Project name	Arbor Railway Siding Expansion

<b>Applicant</b>
<i>Gijima Supply Chain Management Services (Pty) Ltd</i>

<b>Environmental assessors</b>
<i>Myezo Environmental Management Services</i>
Ms D Kotane

<b>Property details</b>													
Province	Mpumalanga												
Magisterial district	Delmas												
District municipality	Nkangala												
Topo-cadastral map	2628BB												
Farm name	Van Dyksput 214 IR												
Closest town	Delmas												
Coordinates	Centre point (approximate)												
	<table border="1"> <thead> <tr> <th>No</th> <th>Latitude</th> <th>Longitude</th> <th>No</th> <th>Latitude</th> <th>Longitude</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>S 26,04055</td> <td>E 28,88314</td> <td>2</td> <td></td> <td></td> </tr> </tbody> </table>	No	Latitude	Longitude	No	Latitude	Longitude	1	S 26,04055	E 28,88314	2		
No	Latitude	Longitude	No	Latitude	Longitude								
1	S 26,04055	E 28,88314	2										

<b>Development criteria in terms of Section 38(1) of the NHR Act</b>	Yes/No
Construction of road, wall, power line, pipeline, canal or other linear form of development or barrier exceeding 300m in length	No
Construction of bridge or similar structure exceeding 50m in length	No
Development exceeding 5000 sq m	Yes
Development involving three or more existing erven or subdivisions	No
Development involving three or more erven or divisions that have been consolidated within past five years	No
Rezoning of site exceeding 10 000 sq m	No
Any other development category, public open space, squares, parks, recreation grounds	No

<b>Land use</b>	
Previous land use	Railway station
Current land use	Railway station



## TABLE OF CONTENTS

	Page
SPECIALIST DECLARATION .....	II
EXECUTIVE SUMMARY.....	III
TECHNICAL SUMMARY .....	V
GLOSSARY OF TERMS AND ABBREVIATIONS .....	VII
COMPLIANCE WITH THE APPENDIX 6 OF THE 2014 EIA REGULATIONS (AS AMENDED).....	IX
1. INTRODUCTION .....	1
2. LEGISLATIVE FRAMEWORK.....	2
3. HERITAGE RESOURCES.....	3
4. STUDY APPROACH AND METHODOLOGY.....	4
5. PROJECT DESCRIPTION .....	7
6. DESCRIPTION OF THE AFFECTED ENVIRONMENT.....	9
7. SURVEY RESULTS .....	19
8. RESULTS: STATEMENT OF SIGNIFICANCE AND IMPACT RATINGS .....	20
9. MANAGEMENT AND MITIGATION MEASURES.....	20
10. CONCLUSIONS AND RECOMMENDATIONS .....	22
11. REFERENCES .....	24
12. ADDENDUM.....	26
1. Indemnity and terms of use of this report.....	26
2. Assessing the significance of heritage resources and potential impacts.....	27
3. Mitigation measures .....	30
4. Relocation of graves.....	32
5. Inventory of identified cultural heritage sites.....	33
6. Curriculum vitae.....	34

## LIST OF FIGURES

	Page
Figure 1. Location of known heritage sites and features in relation to the study area .....	6
Figure 2. Map indicating the track log of the field survey.....	7
Figure 3. Location of the study area in regional context.....	8
Figure 4. Layout of the proposed development.....	9
Figure 5. Views over the study area .....	10
Figure 6. The Palaeontological sensitivity of the study area (arrowed) .....	11
Figure 7. Section of the 1925 map of South African Railways, indicating Arbor station.....	13
Figure 8. Aerial view of the study area dating to 1945 .....	14
Figure 9. Aerial view of the study area dating to 1953 .....	15
Figure 10. Study area on the 1965 version of the 1:50 000 topographic map.....	15
Figure 11. Type P95A housing for foremen, guards, gangers, pumpers, firemen and shunters (1930s).....	16
Figure 12. Typical station house at Delmas.....	17
Figure 13. Last of the station houses (2004) .....	17
Figure 14. Indicating that the station houses has been demolished (2018) .....	18
Figure 15. Where the houses once stood, with the building rubble pushed to one side (arrowed) .....	18
Figure 16. Location of heritage sites in the study area .....	19

## GLOSSARY OF TERMS AND ABBREVIATIONS

---

### TERMS

**Bioturbation:** The burrowing by small mammals, insects and termites that disturb archaeological deposits.

**Cumulative impacts:** “Cumulative Impact”, in relation to an activity, means the past, current and reasonably foreseeable future impact of an activity, considered together with the impact of activities associated with that activity, that in itself may not be significant, but may become significant when added to existing and reasonably foreseeable impacts eventuating from similar or diverse activities.

**Debitage:** Stone chips discarded during the manufacture of stone tools.

**Factory site:** A specialised archaeological site where a specific set of technological activities has taken place – usually used to describe a place where stone tools were made.

**Historic Period:** Since the arrival of the white settlers - c. AD 1830 - in this part of the country.

**Holocene:** The most recent time period, which commenced c. 10 000 years ago.

**Iron Age** (also referred to as **Early Farming Communities**): Period covering the last 1800 years, when new people brought a new way of life to southern Africa. They established settled villages, cultivated domestic crops such as sorghum, millet and beans, and they herded cattle as well as sheep and goats. As they produced their own iron tools, archaeologists call this the Iron Age.

Early Iron Age	AD 200 - AD 900
Middle Iron Age	AD 900 - AD 1300
Later Iron Age	AD 1300 - AD 1830

**Midden:** The accumulated debris resulting from human occupation of a site.

**Mitigation,** means to anticipate and prevent negative impacts and risks, then to minimise them, rehabilitate or repair impacts to the extent feasible.

**National Estate:** The collective heritage assets of the Nation.

**Pleistocene:** Geological time period of 3 000 000 to 20 000 years ago.

**Stone Age:** The first and longest part of human history is the Stone Age, which began with the appearance of early humans between 3-2 million years ago. Stone Age people were hunters, gatherers and scavengers who did not live in permanently settled communities. Their stone tools preserve well and are found in most places in South Africa and elsewhere.

Early Stone Age	2 500 000 - 150 000 Before Present
Middle Stone Age	150 000 - 30 000 BP
Later Stone Age	30 000 - until c. AD 200

**Tradition:** As used in archaeology, it is a seriated sequence of artefact assemblages, particularly ceramics.

### ACRONYMS and ABBREVIATIONS

ASAPA	Association of Southern African Professional Archaeologists
BCE	Before the Common Era (the year 0)

BP	Before Present (calculated from 1950 when radio-carbon dating was established)
CE	Common Era (the year 0)
ESA	Early Stone Age
EIA	Early Iron Age
HIA	Heritage Impact Assessment
I & AP's	Interested and Affected Parties
LIA	Late Iron Age
LSA	Later Stone Age
MIA	Middle Iron Age
MSA	Middle Stone Age
NASA	National Archives of South Africa
NHRA	National Heritage Resources Act
PHRA	Provincial Heritage Resources Agency
SAHRA	South African Heritage Resources Agency
SAHRIS	South African Heritage Resources Information System

**COMPLIANCE WITH THE APPENDIX 6 OF THE 2014 EIA REGULATIONS (AS AMENDED)**

<b>Requirements of Appendix 6 – GN R982</b>	<b>Addressed in the Specialist Report</b>
1. (1) A specialist report prepared in terms of these Regulations must contain-	
a) details of-	
i. the specialist who prepared the report; and	Front page
ii. the expertise of that specialist to compile a specialist report including a curriculum vitae;	Page i Addendum Section 6
b) a declaration that the specialist is independent in a form as may be specified by the competent authority;	Page ii
c) an indication of the scope of, and the purpose for which, the report was prepared;	Section 1
(cA) an indication of the quality and age of base data used for the specialist report;	Section 4
(cB) a description of existing impacts on the site, cumulative impacts of the proposed development and levels of acceptable change;	Section 7.3
d) the duration, date and season of the site investigation and the relevance of the season to the outcome of the assessment;	Section 4.2.2
e) a description of the methodology adopted in preparing the report or carrying out the specialised process inclusive of equipment and modelling used;	Section 4
f) details of an assessment of the specific identified sensitivity of the site related to the proposed activity or activities and its associated structures and infrastructure, inclusive of a site plan identifying site alternatives;	Addendum Section 5; Figure 16
g) an identification of any areas to be avoided, including buffers;	Section 8
h) a map superimposing the activity including the associated structures and infrastructure on the environmental sensitivities of the site including areas to be avoided, including buffers;	Figure 16 Addendum Section 5
i) a description of any assumptions made and any uncertainties or gaps in knowledge;	Section 2
j) a description of the findings and potential implications of such findings on the impact of the proposed activity or activities;	Section 7
k) any mitigation measures for inclusion in the EMPr;	Section 9 & 10
l) any conditions for inclusion in the environmental authorisation;	Section 10
m) any monitoring requirements for inclusion in the EMPr or environmental authorisation;	Section 9
n) a reasoned opinion-	
i. whether the proposed activity, activities or portions thereof should be authorised;	Section 10
(iA) regarding the acceptability of the proposed activity or activities; and	
ii. if the opinion is that the proposed activity, activities or portions thereof should be authorised, any avoidance, management and mitigation measures that should be included in the EMPr, and where applicable, the closure plan;	Section 8, 9, 10
o) a description of any consultation process that was undertaken during the course of preparing the specialist report;	-
p) a summary and copies of any comments received during any consultation process and where applicable all responses thereto; and	-
q) any other information requested by the competent authority.	-
(2) Where a government notice by the Minister provides for any protocol or minimum information requirement to be applied to a specialist report, the requirements as indicated in such notice will apply.	-

**Phase 1 Cultural Heritage Impact Assessment:  
THE PROPOSED UPGRADE AND INCREASE IN THE SCOPE OF ACTIVITIES AT THE EXISTING ARBOR  
RAILWAY SIDING, DELMAS REGION, NKANGALA DISTRICT MUNICIPALITY,  
MPUMALANGA PROVINCE**

## **1. INTRODUCTION**

### **1.1 Background**

*Gijima Supply Chain Management Services (Pty) Ltd* propose the expansion of their scope of activities so as to meet the demand and maximise its operational capacity at Arbor Railway Siding, Delmas region, Nkangala District Municipality, Mpumalanga Province.

*Myezo Environmental Management Services (Pty) Ltd* was contracted by *Gijima Supply Chain Management Services (Pty) Ltd* as independent environmental consultant to undertake the Basic Assessment process for the proposed expansion of the Arbor Railway Siding.

South Africa's heritage resources, also described as the 'national estate', comprise a wide range of sites, features, objects and beliefs. However, according to Section 27(18) of the National Heritage Resources Act (NHRA), No. 25 of 1999, no person may destroy, damage, deface, excavate, alter, remove from its original position, subdivide or change the planning status of any heritage site without a permit issued by the heritage resources authority responsible for the protection of such site.

In accordance with Section 38 of the NHRA, an independent heritage consultant was appointed by *Myezo Environmental Management Services (Pty) Ltd* to conduct a cultural heritage assessment to determine if the expansion of the scope of activities at the railway siding would have an impact on any sites, features or objects of cultural heritage significance.

This report forms part of the Environmental Impact Assessment (EIA) as required by the EIA Regulations in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998) as amended and is intended for submission to the South African Heritage Resources Agency (SAHRA).

### **1.2 Terms and references**

*The aim of a full HIA investigation is to provide an informed heritage-related opinion about the proposed development by an appropriate heritage specialist. The objectives are to identify heritage resources (involving site inspections, existing heritage data and additional heritage specialists if necessary); assess their significances; assess alternatives in order to promote heritage conservation issues; and to assess the acceptability of the proposed development from a heritage perspective.*

*The result of this investigation is a heritage impact assessment report indicating the presence/absence of heritage resources and how to manage them in the context of the proposed development.*

*Depending on SAHRA's acceptance of this report, the developer will receive permission to proceed with the proposed development, on condition of successful implementation of proposed mitigation measures.*

#### **1.2.1 Scope of work**

The aim of this study is to determine if any sites, features or objects of cultural heritage significance occur within the boundaries of the area where the expansion of the scope of activities at the railway siding is to take place. This included:

- Conducting a desk-top investigation of the area;
- A visit to the proposed development site.

The objectives were to:

- Identify possible archaeological, cultural and historic sites within the proposed development areas;
- Evaluate the potential impacts of construction, operation and maintenance of the proposed development on archaeological, cultural and historical resources;
- Recommend mitigation measures to ameliorate any negative impacts on areas of archaeological, cultural or historical importance.

### 1.2.2 Assumptions and Limitations

The investigation has been influenced by the following factors:

- It is assumed that the description of the proposed project, provided by the client, is accurate.
- The unpredictability of buried archaeological remains.
- No subsurface investigation (i.e. excavations or sampling) were undertaken, since a permit from SAHRA is required for such activities.
- It is assumed that the public consultation process undertaken as part of the Environmental Impact Assessment (EIA) is sufficient and that it does not have to be repeated as part of the heritage impact assessment.

## 2. LEGISLATIVE FRAMEWORK

---

### 2.1 Background

Heritage Impact Assessments are governed by national legislation and standards and International Best Practise. These include:

- South African Legislation
  - National Heritage Resources Act, 1999 (Act No. 25 of 1999) (NHRA);
  - Mineral and Petroleum Resources Development Act, 2002 (Act No. 22 of 2002) (MPRDA);
  - National Environmental Management Act 1998 (Act No. 107 of 1998) (NEMA); and
  - National Water Act, 1998 (Act No. 36 of 1998) (NWA).
- Standards and Regulations
  - South African Heritage Resources Agency (SAHRA) Minimum Standards;
  - Association of Southern African Professional Archaeologists (ASAPA) Constitution and Code of Ethics;
  - Anthropological Association of Southern Africa Constitution and Code of Ethics.
- International Best Practise and Guidelines
  - ICOMOS Standards (Guidance on Heritage Impact Assessments for Cultural World Heritage Properties); and
  - The UNESCO Convention concerning the Protection of the World Cultural and Natural Heritage (1972).

### 2.2 Heritage Impact Assessment Studies

South Africa's unique and non-renewable archaeological and palaeontological heritage sites are 'generally' protected in terms of the National Heritage Resources Act (Act No 25 of 1999, Section 35) and may not be disturbed at all without a permit from the relevant heritage resources authority.

The National Heritage Resources Act (Act No. 25 of 1999, Section 38) provides guidelines for Cultural Resources Management and prospective developments:

*“38 (1) Subject to the provisions of subsections (7), (8) and (9), any person who intends to undertake a development categorised as:*

- (a) the construction of a road, wall, powerline, pipeline, canal or other similar form of linear development or barrier exceeding 300m in length;*
- (b) the construction of a bridge or similar structure exceeding 50m in length;*
- (c) any development or other activity which will change the character of a site:*
  - (i) exceeding 5 000 m<sup>2</sup> in extent; or*
  - (ii) involving three or more existing erven or subdivisions thereof; or*
  - (iii) involving three or more erven or divisions thereof which have been consolidated within the past five years; or*
  - (iv) the costs of which will exceed a sum set in terms of regulations by SAHRA or a provincial heritage resources authority;*
- (d) the re-zoning of a site exceeding 10 000 m<sup>2</sup> in extent; or*
- (e) any other category of development provided for in regulations by SAHRA or a provincial heritage resources authority, must at the very earliest stages of initiating such a development, notify the responsible heritage resources authority and furnish it with details regarding the location, nature and extent of the proposed development.”*

And:

*“38 (3) The responsible heritage resources authority must specify the information to be provided in a report required in terms of subsection (2)(a): Provided that the following must be included:*

- (a) The identification and mapping of all heritage resources in the area affected;*
- (b) an assessment of the significance of such resources in terms of the heritage assessment criteria set out in section 6(2) or prescribed under section 7;*
- (c) an assessment of the impact of the development on such heritage resources;*
- (d) an evaluation of the impact of the development on heritage resources relative to the sustainable social and economic benefits to be derived from the development;*
- (e) the results of consultation with communities affected by the proposed development and other interested parties regarding the impact of the development on heritage resources;*
- (f) if heritage resources will be adversely affected by the proposed development, the consideration of alternatives; and*
- (g) plans for mitigation of any adverse effects during and after the completion of the proposed development.”*

### 3. HERITAGE RESOURCES

---

#### 3.1 The National Estate

The National Heritage Resources Act (No. 25 of 1999) defines the heritage resources of South Africa which are of cultural significance or other special value for the present community and for future generations that must be considered part of the national estate to include:

- places, buildings, structures and equipment of cultural significance;
- places to which oral traditions are attached or which are associated with living heritage;
- historical settlements and townscapes;
- landscapes and natural features of cultural significance;
- geological sites of scientific or cultural importance;
- archaeological and palaeontological sites;
- graves and burial grounds, including-

- ancestral graves;
- royal graves and graves of traditional leaders;
- graves of victims of conflict;
- graves of individuals designated by the Minister by notice in the Gazette;
- historical graves and cemeteries; and
- other human remains which are not covered in terms of the Human Tissue Act, 1983 (Act No. 65 of 1983);
- sites of significance relating to the history of slavery in South Africa;
- movable objects, including-
  - objects recovered from the soil or waters of South Africa, including archaeological and palaeontological objects and material, meteorites and rare geological specimens;
  - objects to which oral traditions are attached or which are associated with living heritage;
  - ethnographic art and objects;
  - military objects;
  - objects of decorative or fine art;
  - objects of scientific or technological interest; and
  - books, records, documents, photographic positives and negatives, graphic, film or video material or sound recordings, excluding those that are public records as defined in section 1(xiv) of the National Archives of South Africa Act, 1996 (Act No. 43 of 1996).

### 3.2 Cultural significance

In the NHRA, Section 2 (vi), it is stated that “cultural significance” means aesthetic, architectural, historical, scientific, social, spiritual, linguistic or technological value or significance. This is determined in relation to a site or feature’s uniqueness, condition of preservation and research potential.

According to Section 3(3) of the NHRA, a place or object is to be considered part of the national estate if it has cultural significance or other special value because of

- its importance in the community, or pattern of South Africa's history;
- its possession of uncommon, rare or endangered aspects of South Africa's natural or cultural heritage;
- its potential to yield information that will contribute to an understanding of South Africa's natural or cultural heritage;
- its importance in demonstrating the principal characteristics of a particular class of South Africa's natural or cultural places or objects;
- its importance in exhibiting particular aesthetic characteristics valued by a community or cultural group;
- its importance in demonstrating a high degree of creative or technical achievement at a particular period;
- its strong or special association with a particular community or cultural group for social, cultural or spiritual reasons;
- its strong or special association with the life or work of a person, group or organisation of importance in the history of South Africa; and
- sites of significance relating to the history of slavery in South Africa.

A matrix (see Section 2 of Addendum) was developed whereby the above criteria were applied for the determination of the significance of each identified site. This allowed some form of control over the application of similar values for similar identified sites.

## 4. STUDY APPROACH AND METHODOLOGY

---



## 4.1 Extent of the Study

This survey and impact assessment covers all facets of cultural heritage located in the study area as presented in Section 5 below and illustrated in Figures 3 & 4.

## 4.2 Methodology

### 4.2.1.1 Survey of the literature

A survey of the relevant literature was conducted with the aim of reviewing the previous research done and determining the potential of the area. In this regard, various anthropological, archaeological and historical sources were consulted – see list of references in Section 11.

- Information on events, sites and features in the larger region were obtained from these sources.

### 4.2.1.2 Survey of heritage impact assessments (HIAs)

A survey of HIAs done for projects in the region by various heritage consultants was conducted with the aim of determining the heritage potential of the area – see list of references in Section 11.

- Information on sites and features in the larger region were obtained from these sources.

### 4.2.1.3 Data bases

The *Heritage Atlas Database*, various SAHRA databases, the *Environmental Potential Atlas*, the *Chief Surveyor General* and the *National Archives of South Africa* were consulted.

- Database surveys produced a number of sites located in the larger region of the proposed development.

### 4.2.1.4 Other sources

Aerial photographs and topocadastral and other maps were also studied – see the list of references below.

- Information of a very general nature were obtained from these sources

The results of the above investigation are presented in Figure 1 below – see list of references in Section 11 – and can be summarised as follows:

- Historic structures, inclusive of buildings and monuments occur sporadically throughout the region;
- Structures and features relating to the development of infrastructure occur sporadically throughout the region.
- Informal cemeteries occur sporadically throughout the region.

*Based on the above assessment, the probability of cultural heritage sites, features and objects occurring in the study area is deemed to be **probable**.*




Figure 1. Location of known heritage sites and features in relation to the study area (Circles spaced at a distance of 0,5km: heritage sites = coded green dots)

#### 4.2.2 Field survey

The field survey was done according to generally accepted archaeological practices, and was aimed at locating all possible sites, objects and structures. The area that had to be investigated was identified by the *Myezo Environmental Management Services (Pty) Ltd* by means of maps and .kml files indicating the development area. This was loaded onto an ASUS digital device and used in Google Earth during the field survey to access the areas.

The site was visited on 28 February 2019 and was investigated by walking transects where the development is to take place – see Fig. 2 below. During the site visit, archaeological visibility was limited in some areas due to the grass cover, as well as the occurrence of building rubble.

During the site visit, Mr Benny Xesha, the site manager, pointed out the site boundaries as well as explaining the proposed development. Local people were interviewed as to the existence of graves in the study area, but they confirmed only one large burial site located well to the south.

#### 4.2.4 Documentation

All sites, objects and structures that are identified are documented according to the general minimum standards accepted by the archaeological profession. Coordinates of individual localities are determined by means of the *Global Positioning System (GPS)* and plotted on a map. This information is

added to the description in order to facilitate the identification of each locality. Map datum used: Hartebeeshoek 94 (WGS84).

The track log and identified sites were recorded by means of a Garmin Oregon 550 handheld GPS device. Photographic recording was done by means of a Canon EOS 550D digital camera.




Figure 2. Map indicating the track log of the field survey.  
(Site = blue polygon; track log = dark green line)

## 5. PROJECT DESCRIPTION

### 5.1 Site location

Arbor Railway Siding is located on Portion 1 of Farm Van Dyksput 214-IR within the Nkangala District Municipality, Mpumalanga Province. It is located approximately 23km northeast of Delmas and 16km west of Ogies (Fig. 3). For more information, see the Technical Summary on p. V above.




Figure 3. Location of the study area in regional context.  
(Study area = blue polygon)

## 5.2 Development proposal

Arbor railway siding is operated by Gijima Supply Chain Management Services (Pty) Ltd (Gijima) which currently has a signed lease agreement from Transnet for the operation of the siding which is used for loading coal onto rail wagons for domestic as well as export supply. The market for this service has been identified as Eskom, as well as neighbouring mines.

Arbor Railway Siding has been servicing Eskom with 3 978 201 tons of coal over the 3 year period (June 2013 - September 2016). Following the expiry of their contract, Eskom renewed the contract and increased the tonnage to 9, 5 000 000 tons over a 4 year period spreading from the 1st October 2016 to 30th September 2020 and this translates to 198 000 tons per month. The Northern side (the functional side at Arbor Railway siding) operation has reached its maximum operational capacity in terms of stockpiling, receiving trucks and loading the trains.

Thus, Gijima propose that the Railway Siding be expanded so as to meet the demand and maximise its operational capacity. The expansion forms part of a broader vision to reduce the number of trucks on the road network established by Transnet and Eskom, the Transnet Freight Rail Strategy (Myezo Background Information Document).




Figure 4. Layout of the proposed development (Map supplied by Myezo)

## 6. DESCRIPTION OF THE AFFECTED ENVIRONMENT

### 6.1 Natural Environment

The study area lies in a transformed environment with a well-established industrial (infrastructure) setting (Fig. 5). The geology of the study area is made up of mudrock, sandstone, conglomerate, volcanic rocks belonging to the Transvaal Supergroup. This changes just to the south to fine- to coarse-grained sandstone, shale, coal seams belonging to the Karoo Supergroup. The original vegetation is classified as Soweto Highveld Grassland, falling in the Mesic Highveld Grassland Bioregion. However, most of this has been transformed due to urbanisation and mining activities. The topography of the region is classified as moderately undulating plains and pans. The Wilge River passes approximately 1km to the west of the study area, flowing from south to north.





Figure 5. Views over the study area

The Palaeontological Sensitivity Map (SAHRIS) indicate that the study area (indicated by the white arrow in Fig. 6) has a moderate sensitivity (green) of fossil remains to be found and therefore a palaeontological desktop study of the area is required:

Colour	Sensitivity	Required Action
RED	VERY HIGH	field assessment and protocol for finds is required
ORANGE/YELLOW	HIGH	desktop study is required and based on the outcome of the desktop study, a field assessment is likely
GREEN	MODERATE	desktop study is required
BLUE	LOW	no palaeontological studies are required however a protocol for finds is required
GREY	INSIGNIFICANT/ZERO	no palaeontological studies are required
WHITE/CLEAR	UNKNOWN	these areas will require a minimum of a desktop study. As more information comes to light, SAHRA will continue to populate the map.




Figure 6. The Palaeontological sensitivity of the study area (arrowed)

## 6.2 Cultural Landscape

*The aim of this section is to present an overview of the history of the larger region in order to eventually determine the significance of heritage sites identified in the study area, within the context of their historic, aesthetic, scientific and social value, rarity and representivity.*

The cultural landscape qualities of the region are made up of a pre-colonial element consisting of very limited Stone Age and Iron Age occupation, as well as a much later colonial (farmer) component, which also gave rise to an industrial (mining) component.

### 6.2.1 Stone Age

Very little habitation of the highveld area took place during Stone Age times. Tools dating to the Early Stone Age period are mostly found in the vicinity of larger watercourses, e.g. the Vaal River, or in sheltered areas such as the Magaliesberg. During Middle Stone Age (MSA) times (c. 150 000 – 30 000 BP), people became more mobile, occupying areas formerly avoided. The MSA is a technological stage characterized by flakes and flake-blades with faceted platforms, produced from prepared cores, as distinct from the core tool-based ESA technology. Open sites were still preferred near watercourses.

Late Stone Age (LSA) people had even more advanced technology than the MSA people and therefore succeeded in occupying even more diverse habitats. Some sites are known to occur in the region. These vary from sealed (i.e. cave) sites, located to the south of the study area (Wadley & Turner 1987), to open sites near the Vaal River. Also, for the first time we get evidence of people's activities derived from material other than stone tools. Ostrich eggshell beads, ground bone arrowheads, small bored stones and wood fragments with incised markings are traditionally linked with the LSA. The LSA people

have also left us with a rich legacy of rock art, which is an expression of their complex social and spiritual beliefs.

### 6.2.2 Iron Age

Iron Age people started to settle in southern Africa c. AD 300, with one of the oldest known sites at Broederstroom south of Hartebeespoort Dam dating to AD 470. Having only had cereals (sorghum, millet) that need summer rainfall, Early Iron Age (EIA) people did not move outside this rainfall zone, and neither did they occupy the central interior highveld area. Because of their specific technology and economy, Iron Age people preferred to settle on the alluvial soils near rivers for agricultural purposes, but also for firewood and water.

The occupation of the larger geographical area (including the study area) did not start much before the 1500s. By the 16th century things changed, with the climate becoming warmer and wetter, creating condition that allowed Late Iron Age (LIA) farmers to occupy areas previously unsuitable, for example the treeless plains of the Free State and the Mpumalanga highveld.

This wet period came to a sudden end sometime between 1800 and 1820 by a major drought lasting 3 to 5 years. The drought must have caused an agricultural collapse on a large, subcontinent scale.

This was also a period of great military tension. Military pressure from Zululand spilled onto the highveld by at least 1821. Various marauding groups of displaced Sotho-Tswana moved across the plateau in the 1820s. Mzilikazi raided the plateau extensively between 1825 and 1837. The Boers trekked into this area in the 1830s. And throughout this time settled communities of Tswana people also attacked each other.

As a result of this troubled period, Sotho-Tswana people concentrated into large towns for defensive purposes. Because of the lack of trees, they built their settlements in stone. These stone-walled villages were almost always located near cultivatable soil and a source of water. Such sites are known to occur near Kriel (e.g. Pelsler et al 2006) and to the south (Taylor 1979).

### 6.2.3 Historic period

White settlers moved into the area during the first half of the 19<sup>th</sup> century. They were largely self-sufficient, basing their survival on cattle/sheep farming and hunting. Pretoria was started in 1850, but Johannesburg only dates to the 1880s, after the discovery of gold.

When coal had to be transported from the coal fields of the Witbank to the Witwatersrand area, a need for a direct railway link with the industries in the Rand area arose. In 1906, a railway line was opened between Apex and Witbank, crossing Witklip to where coal was located on the farm Brakfontein of Mr NC Erasmus. In 1907 the surveyor Ewan Curry, instructed by Frank Campbell Dumat, surveyed the layout for the town on the farm Witklip. The name Delmas refers to a small farm (in southern French dialect: *mas*) of Dumat's grandfather in France.

The Delmas district was proclaimed in 1954 and used to be mainly agricultural. As early as 1909 the Delmas Estate and Colliery Co began mining coal in the district. In addition to good roads, the Johannesburg-Witbank railway line and freeway traverses the district and the Springs-Ermelo line runs along the southern boundary. Cultivated holdings were established at Eloff and Sundra. Apart from coal, silica is also mined in the district.



### 6.3 Site specific review

Although landscapes with cultural significance are not explicitly described in the NHRA, they are protected under the broad definition of the National Estate (Section 3): Section 3(2)(c) and (d) list "historical settlements and townscapes" and "landscapes and natural features of cultural significance" as part of the National Estate.

The examination of historical maps and aerial photographs help us to reconstruct how the cultural landscape has changed over time as it shows how humans have used the land.

The railway line from Apex Junction eastwards towards Witbank via Dryden was completed in 1906 (Praagh 1906). All the known, currently existing stations along this route, is clearly indicated on the 1925 version of the South African Railway Map as is included in the Blue Book for that year (Fig. 7). However, it is not clear which of the stations were completed and when – for example, in June 1910 a portion of portion 1 of the farm Weltevreden 2271R was acquired by the South African Railways for a station (Dryden) on this line. However, it would be a mistake to assume that the type of station buildings and houses, for example, previously (Arbor) and currently still at Delmas were completed at the same time. Clearly the materials used, e.g. yellow face bricks, as well as the layout and fittings (doors, window frames, etc.), indicate a construction date from probably only the late 1930s, but more probably the 1940s.



Figure 7. Section of the 1925 map of South African Railways, indicating Arbor station (South African Railways 1925)

According to Wasserfall (1989:225-226) the first houses for railway workers were wood-and-iron houses. These were portable and could be located where the need was the biggest. In the former Transvaal region, much use was made of the old NZASM (Nederlandsche Zuid-Afrikaansche Spoorweg Maatschappij) houses, but of course was limited to these old lines.

Construction of accommodation for (white) railway workers was very slow to take off, largely as a result of the depression 1906-1907. A total of only 136 new tenements was erected in 1910 – 71 on the Pretoria Division and 65 on the Johannesburg Division. A further 96 tenements were erected in the Orange Free State. All of these were wood-and-iron tenements, sometime accommodating up to five families (Wasserfall 1989:234).

It was only towards the end of 1918 that a bungalow type brick dwelling was adopted. Thereafter, the size of the structures increased as well as number of structures that were built. By 1951, the number of houses owned by the Railways totalled 16 190 country-wide.

From the aerial photographs in Fig. 8 and Fig. 9, respectively dating to 1945 and 1953, it can clearly be seen that the station was already well developed, consisting of a number of houses as well as branch lines.

On both the aerial images and the 1965 version of the 1:50 000 topographic map (Fig. 10), what is referred to as a service railway line can be seen to branch of in a north-eastern direction. A more formal line, making a S-curve towards the south, goes to the old Arbor Coal Mine. However, it is not indicated on the 1965 version of the 1:50 000 topographic map, as probably by that time it has already been demolished.

On the 1965 version of the topographic, what is commonly referred to as farm labourer houses, are indicated to the southwest of the station, outside of the study area.



Figure 8. Aerial view of the study area dating to 1945  
(Photo: 55\_44\_0599)




Figure 9. Aerial view of the study area dating to 1953  
(Photo: 303\_002\_00483)




Figure 10. Study area on the 1965 version of the 1:50 000 topographic map




Figure 11. Type P95A housing for foremen, guards, gangers, pumpers, firemen and shunters (1930s) (From Wasserfall 1989)

Fig. 11 and Fig. 12 serve as examples of the houses that might have been built at Arbor Station and what could have existed at other stations on the same line, e.g. Argent and Dryden. Fig. 12 is one example of a variety of houses that are still standing at Delmas station. Unfortunately, in Delmas the houses have fallen on bad times and it is not easy to get access to them in order to conduct proper background research.



Figure 12. Typical station house at Delmas

From the Google aerial image in Fig. 13 it can be seen that at least one house was still standing at Arbor Station in 2004, whereas the rest seems to have been in ruins. By 2018 (Fig. 14) this last house was also demolished, and the site was cleared by all the building rubble having pushed towards the southern boundary of the station site (Fig. 15).



Figure 13. Last of the station houses (2004)  
(Image: Google Earth)



Figure 14. Indicating that the station houses has been demolished (2018)  
(Image: Google Earth)



Figure 15. Where the houses once stood, with the building rubble pushed to one side (arrowed)

## 7. SURVEY RESULTS

During the physical survey, the following sites, features and objects of cultural significance were identified in the study area (Fig. 16) – see **Section 5 of Addendum** for a specific description of the sites:

### 7.1 Stone Age

- No sites, features or objects of cultural significance dating to the Stone Age were identified in the study area

### 7.2 Iron Age

- No sites, features or objects of cultural significance dating to the Iron Age were identified in the study area.

### 7.3 Historic period

- 7.3.1: Old station building. According to its style and the material used in its construction, this building probably dates to the 1940s. It is similar in style, layout and material as other stations on the same line, e.g. Dryden and Argent. The structure is fenced off and well protected by an alarm system.




Figure 16. Location of heritage sites in the study area

## 8. RESULTS: STATEMENT OF SIGNIFICANCE AND IMPACT RATINGS

### 8.1 Impact assessment

Heritage impacts are categorised as:

- Direct or physical impacts, implying alteration or destruction of heritage features within the project boundaries;
- Indirect impacts, e.g. restriction of access or visual intrusion concerning the broader environment;
- Cumulative impacts that are combinations of the above.

Impact analysis of cultural heritage resources under threat of the proposed development, is based on the present understanding of the development and is summarised in Table 1 below:

**Table 1: Impact assessment**

IDENTIFIED HERITAGE RESOURCE: Railway Station Building					
Nature: Expansion of activities might have a permanent and irreversible impact on this structure.					
			Without mitigation	With mitigation	
Extent			Region	Site	
Duration			Permanent	Permanent	
Intensity			Low	Low	
Probability			Definite	Probable	
Significance			Medium (60)	Low (27)	
Status (positive or negative)			Negative	Neutral	
Reversibility			Non-reversible	Non-reversible	
Irreplaceable loss of resources?			Yes	No	
Can impacts be mitigated			Yes		
Mitigation: Full documentation					
Cumulative impact: Loss of information regarding specific technological development in the region.					
Site No.	Site type	NHRA category	Field rating	Impact rating: Before/After mitigation	Proposed mitigation (Refer to definitions in Section 12.3)
Railway station building					
7.3.1	Built structures	Section 34	High significance Grade 4-A	60	(1) Avoidance/Preserve; (2) Archaeological investigation

## 9. MANAGEMENT AND MITIGATION MEASURES

Heritage sites are fixed features in the environment, occurring within specific spatial confines. Any impact upon them is permanent and non-reversible. Those resources that cannot be avoided and that are directly impacted by the proposed development can be excavated/recorded and a management plan can be developed for future action. Those sites that are not impacted on can be written into the management plan, whence they can be avoided or cared for in the future.

Sources of risk were considered with regards to development activities defined in Section 2(viii) of the NHRA that may be triggered and are summarised in Table 3A and 3B below. These issues formed the basis of the impact assessment described. The potential risks are discussed according to the various phases of the project below.

### 9.1 Objectives



- Protection of archaeological, historical and any other site or land considered being of cultural value within the project boundary against vandalism, destruction and theft.
- The preservation and appropriate management of new discoveries in accordance with the NHRA, should these be discovered during construction activities.

The following shall apply:

- Known sites should be clearly marked in order that they can be avoided during construction activities.
- The contractors and workers should be notified that archaeological sites might be exposed during the construction activities.
- Should any heritage artefacts be exposed during excavation, work on the area where the artefacts were discovered, shall cease immediately and the Environmental Control Officer shall be notified as soon as possible;
- All discoveries shall be reported immediately to a heritage practitioner so that an investigation and evaluation of the finds can be made. Acting upon advice from these specialists, the Environmental Control Officer will advise the necessary actions to be taken;
- Under no circumstances shall any artefacts be removed, destroyed or interfered with by anyone on the site; and
- Contractors and workers shall be advised of the penalties associated with the unlawful removal of cultural, historical, archaeological or palaeontological artefacts, as set out in the National Heritage Resources Act (Act No. 25 of 1999), Section 51. (1).

## 9.2 Control

In order to achieve this, the following should be in place:

- A person or entity, e.g. the Environmental Control Officer, should be tasked to take responsibility for the heritage sites and should be held accountable for any damage.
- Known sites should be located and isolated, e.g. by fencing them off. All construction workers should be informed that these are no-go areas, unless accompanied by the individual or persons representing the Environmental Control Officer as identified above.
- In areas where the vegetation is threatening the heritage sites, e.g. growing trees pushing walls over, it should be removed, but only after permission for the methods proposed has been granted by SAHRA. A heritage official should be part of the team executing these measures.

**Table 2A: Construction Phase: Environmental Management Programme for the project**

<b>Action required</b>	Protection of heritage sites, features and objects		
<b>Potential Impact</b>	The identified risk is damage or changes to resources that are generally protected in terms of Sections 27, 28, 31, 32, 34, 35, 36 and 37 of the NHRA that may occur in the proposed project area.		
<b>Risk if impact is not mitigated</b>	Loss or damage to sites, features or objects of cultural heritage significance		
<b>Activity / issue</b>	<b>Mitigation: Action/control</b>	<b>Responsibility</b>	<b>Timeframe</b>
1. Removal of Vegetation 2. Construction of required infrastructure, e.g. access roads, water pipelines	See discussion in Section 9.1 above	Environmental Control Officer	During construction only
<b>Monitoring</b>	See discussion in Section 9.2 above		

**Table 2B: Operation Phase: Environmental Management Programme for the project**

<b>Action required</b>	Protection of heritage sites, features and objects		
<b>Potential Impact</b>	It is unlikely that the negative impacts identified for pre-mitigation will occur if the recommendations are followed.		
<b>Risk if impact is not mitigated</b>	Loss or damage to sites, features or objects of cultural heritage significance		
<b>Activity / issue</b>	<b>Mitigation: Action/control</b>	<b>Responsibility</b>	<b>Timeframe</b>
1. Removal of Vegetation 2. Construction of required infrastructure, e.g. access roads, water pipelines	See discussion in Section 9.1 above	Environmental Control Officer	During construction only
<b>Monitoring</b>	See discussion in Section 9.2 above		

### 9.3 Mitigation measures

*Mitigation: means to anticipate and prevent negative impacts and risks, then to minimise them, rehabilitate or repair impacts to the extent feasible.*

For the current study, the following mitigation measures are proposed (see **Section 4** of the **Addendum** for a discussion of all mitigation measures):

- Site 7.3.1: Built structure (railway station)
  - (1) Avoidance/Preserve: This is viewed to be the primary form of mitigation and applies where any type of development occurs within a formally protected or significant or sensitive heritage context and is likely to have a high negative impact; or, alternatively
  - (2) Archaeological investigation: This is appropriate where development occurs in a context of heritage significance and where the impact is such that it can be mitigated. Mitigation is to excavate the site by archaeological techniques, document the site (map and photograph) and analyse the recovered material to acceptable standards.

## 10. CONCLUSIONS AND RECOMMENDATIONS

*Gijima Supply Chain Management Services (Pty) Ltd* propose the expansion of their scope of activities so as to meet the demand and maximise its operational capacity at Arbor Railway Siding, Delmas region, Nkangala District Municipality, Mpumalanga Province.

This report describes the methodology used, the limitations encountered, the heritage features that were identified and the recommendations and mitigation measures proposed relevant to this. The HIA consisted of a desktop study (archival sources, database survey, maps and aerial imagery) and a physical survey that included the interviewing of relevant people. It should be noted that the implementation of the mitigation measures is subject to SAHRA/PHRA's approval.

The cultural landscape qualities of the region are made up of a pre-colonial element consisting of very limited Stone Age and Iron Age occupation, as well as a much later colonial (farmer) component, which also gave rise to an industrial (mining) component.

### Identified sites

During the physical survey, the following sites, features or objects of cultural significance were identified:

- 7.3.1: Old station building. According to its style and the material used in its construction, this building probably dates to the 1940s. It is similar in style, layout and material as other stations on the same line, e.g. Dryden and Argent. The structure is fenced off and well protected by an alarm system.

#### Impact assessment

Impact analysis of cultural heritage resources under threat of the proposed development, is based on the present understanding of the development:

IDENTIFIED HERITAGE RESOURCES					
Site No.	Site type	NHRA category	Field rating	Impact rating: Before/After mitigation	Proposed mitigation (Refer to definitions in Section 12.3)
Station building					
7.3.1	Built structures	Section 34	High significance Grade 4-A	60	(1) Avoidance/Preserve; (2) Archaeological investigation

#### Legal requirements

The legal requirements related to heritage specifically are specified in Section 3 of this report. For this proposed project, the assessment has determined that no sites, features or objects of heritage significance occur in the study area. If heritage features are identified during construction, as stated in the management recommendation, these finds would have to be assessed by a specialist, after which a decision will be made regarding the application for relevant permits.

#### Reasoned opinion as to whether the proposed activity should be authorised:

- From a heritage point of view, it is recommended that the proposed development be allowed to continue on acceptance of the conditions proposed below.

#### Conditions for inclusion in the environmental authorisation:

- The Palaeontological Sensitivity Map (SAHRIS) indicate that the study area has a moderate sensitivity of fossil remains to be found and therefore a palaeontological desktop study of the area is required.
- Should archaeological sites or graves be exposed in other areas during construction work, it must immediately be reported to a heritage practitioner so that an investigation and evaluation of the finds can be made.

## 11. REFERENCES

---

### 11.1 Data bases

Chief Surveyor General  
Environmental Potential Atlas, Department of Environmental Affairs and Tourism.  
Heritage Atlas Database, Pretoria  
National Archives of South Africa  
SAHRA Archaeology and Palaeontology Report Mapping Project (2009)  
SAHRIS Database

### 11.2 Literature

- Birkholtz, P. 2008. *Heritage scan in terms of the proposed Argent Siding on a Portion of the Farm Boschpoort 211 IP between Delmas and Kendal Mpumalanga Province*. Pretoria: Unpublished report.
- Birkholtz, P. 2013. *Proposed coal mining activities on a section of Portion 16 of the farm Vlakvarkfontein 213 IR, Viktor Khanye Local Municipality, Mpumalanga Province*. Pretoria: Unpublished report.
- Coetzee, T. 2014. *Phase 1 archaeological impact assessment for Environmental Assurance (Pty) Ltd on the area demarcated for the development of Argent Siding near Delmas, Mpumalanga*. Unpublished report.
- Day, J.R. 1963. *Railways of Southern Africa*. London: Arthur Barker Limited.
- Fourie, W. 2018. *Vlakvarkfontein Coal Mine extension, associated infrastructure and amendments to existing licence conditions*. Pretoria: Unpublished report.
- Hutten, M. 2011. *Heritage Impact Assessment report in terms of a Mining Right Application on the farm Boschpoort 211 IR*. Pretoria: Unpublished report.
- Mason, R.J. 1969. *The Prehistory of the Transvaal*. Johannesburg: Witwatersrand University Press.
- Muncina, L. & Rutherford, M.C. 2006. *The Vegetation Map of South Africa, Lesotho and Swaziland*. Pretoria: SANBI.
- Pelser, A., Van Schalkwyk, J.A., Teichert, F. & Masiteng, I. 2007. The archaeological investigation of an Iron Age site on the farm Rietfontein 101IS, Emalaheni district, Mpumalanga Province. *NCHM Research Journal* 2:1-24.
- Praagh, L.V. (ed.) 1906. *The Transvaal and its mines*. London: Praagh & Lloyd.
- Raper, P.E. 2004. *South African place names*. Johannesburg: Jonathan Ball Publishers.
- Reeks, G.W. 2012. *A History of Silver Mining in the greater Pretoria region, 1885-1999*. MA thesis, University of South Africa.
- South African Railways 1925. *Report of the General Manager of the Railways and Harbours, 1925*. Government Blue Book 1925. Pretoria: Government Printer.
- Taylor, M.O.V. 1979. Wildebeestfontein: a Late Iron Age site in the southeastern Transvaal. In Van der Merwe, N.J. & Huffman, T.N. (eds.) 1979. *Iron Age studies in Southern Africa*. Goodwin Series No. 3. Cape Town: South African Archaeological Society. Pp. 120-132.

Tomose, N. 2011. *Phase 1 Heritage Impact Assessment: Proposed Vlakvarkfontein Colliery Expansion Project*. Pretoria: Unpublished report.

Wadley, L & Turner, G. 1987. Hope Hill shelter: a Later Stone Age site in southern Transvaal. *South African Journal of Science* 83(3):98-105.

Wasserfall, J. 1989. *Early Mine and Railway Houses in South Africa: a two part study of ideology and design in working class houses*. Cambridge. Unpublished PhD - King's College, University of Cambridge.

### **11.3 Maps and aerial photographs**

1: 50 000 Topocadastral maps

Google Earth

Aerial photographs: Chief Surveyor-General

---

## 12. ADDENDUM

---

### 1. Indemnity and terms of use of this report

The findings, results, conclusions and recommendations given in this report are based on the author's best scientific and professional knowledge as well as available information. The report is based on survey and assessment techniques which are limited by time and budgetary constraints relevant to the type and level of investigation undertaken and the author reserve the right to modify aspects of the report including the recommendations if and when new information may become available from ongoing research or further work in this field or pertaining to this investigation.

Although all possible care is taken to identify all sites of cultural importance during the investigation of study areas, it is always possible that hidden or sub-surface sites could be overlooked during the study. The author of this report will not be held liable for such oversights or for costs incurred as a result of such oversights.

Although the author exercises due care and diligence in rendering services and preparing documents, he accepts no liability and the client, by receiving this document, indemnifies the author against all actions, claims, demands, losses, liabilities, costs, damages and expenses arising from or in connection with services rendered, directly or indirectly by the author and by the use of the information contained in this document.

This report must not be altered or added to without the prior written consent of the author. This also refers to electronic copies of this report which are supplied for the purposes of inclusion as part of other reports, including main reports. Similarly, any recommendations, statements or conclusions drawn from or based on this report must make reference to this report. If these form part of a main report relating to this investigation or report, this report must be included in its entirety as an appendix or separate section to the main report.

## 2. Assessing the significance of heritage resources and potential impacts

A system for site grading was established by the NHRA and further developed by the South African Heritage Resources Agency (SAHRA 2007) and has been approved by ASAPA for use in southern Africa and was utilised during this assessment.

### 2.1 Significance of the identified heritage resources

According to the NHRA, Section 2(vi) the **significance** of a heritage sites and artefacts is determined by its aesthetic, architectural, historical, scientific, social, spiritual, linguistic or technical value in relation to the uniqueness, condition of preservation and research potential. It must be kept in mind that the various aspects are not mutually exclusive, and that the evaluation of any site is done with reference to any number of these.

#### Matrix used for assessing the significance of each identified site/feature

1. SITE EVALUATION				
<b>1.1 Historic value</b>				
Is it important in the community, or pattern of history				
Does it have strong or special association with the life or work of a person, group or organisation of importance in history				
Does it have significance relating to the history of slavery				
<b>1.2 Aesthetic value</b>				
It is important in exhibiting particular aesthetic characteristics valued by a community or cultural group				
<b>1.3 Scientific value</b>				
Does it have potential to yield information that will contribute to an understanding of natural or cultural heritage				
Is it important in demonstrating a high degree of creative or technical achievement at a particular period				
<b>1.4 Social value</b>				
Does it have strong or special association with a particular community or cultural group for social, cultural or spiritual reasons				
<b>1.5 Rarity</b>				
Does it possess uncommon, rare or endangered aspects of natural or cultural heritage				
<b>1.6 Representivity</b>				
Is it important in demonstrating the principal characteristics of a particular class of natural or cultural places or objects				
Importance in demonstrating the principal characteristics of a range of landscapes or environments, the attributes of which identify it as being characteristic of its class				
Importance in demonstrating the principal characteristics of human activities (including way of life, philosophy, custom, process, land-use, function, design or technique) in the environment of the nation, province, region or locality.				
<b>2. Sphere of Significance</b>		High	Medium	Low
International				
National				
Provincial				
Regional				
Local				
Specific community				
<b>3. Field Register Rating</b>				
1.	National/Grade 1: High significance - No alteration whatsoever without permit from SAHRA			
2.	Provincial/Grade 2: High significance - No alteration whatsoever without permit from provincial heritage authority.			
3.	Local/Grade 3A: High significance - Mitigation as part of development process not advised.			

4.	Local/Grade 3B: High significance - Could be mitigated and (part) retained as heritage register site	
5.	Generally protected A: High/medium significance - Should be mitigated before destruction	
6.	Generally protected B: Medium significance - Should be recorded before destruction	
7.	Generally protected C: Low significance - Requires no further recording before destruction	

## 2.2 Significance of the anticipated impact on heritage resources

All impacts identified during the HIA stage of the study will be classified in terms of their significance. Issues would be assessed in terms of the following criteria:

### Nature of the impact

A description of what causes the effect, what will be affected and how it will be affected.

### Extent

The physical **extent**, wherein it is indicated whether:

- 1 - The impact will be limited to the site;
- 2 - The impact will be limited to the local area;
- 3 - The impact will be limited to the region;
- 4 - The impact will be national; or
- 5 - The impact will be international.

### Duration

Here it should be indicated whether the lifespan of the impact will be:

- 1 - Of a very short duration (0–1 years);
- 2 - Of a short duration (2-5 years);
- 3 - Medium-term (5–15 years);
- 4 - Long term (where the impact will persist possibly beyond the operational life of the activity); or
- 5 - Permanent (where the impact will persist indefinitely).

### Magnitude (Intensity)

The magnitude of impact, quantified on a scale from 0-10, where a score is assigned:

- 0 - Small and will have no effect;
- 2 - Minor and will not result in an impact;
- 4 - Low and will cause a slight impact;
- 6 - Moderate and will result in processes continuing but in a modified way;
- 8 - High, (processes are altered to the extent that they temporarily cease); or
- 10 - Very high and results in complete destruction of patterns and permanent cessation of processes.

### Probability

This describes the likelihood of the impact actually occurring and is estimated on a scale where:

- 1 - Very improbable (probably will not happen);
- 2 - Improbable (some possibility, but low likelihood);
- 3 - Probable (distinct possibility);
- 4 - Highly probable (most likely); or
- 5 - Definite (impact will occur regardless of any prevention measures).

### Significance

The significance is determined through a synthesis of the characteristics described above (refer to the formula below) and can be assessed as low, medium or high:

$$S = (E+D+M) \times P; \text{ where}$$

S = Significance weighting



E = Extent  
 D = Duration  
 M = Magnitude  
 P = Probability

Significance of impact		
Points	Significant Weighting	Discussion
< 30 points		Where this impact would not have a direct influence on the decision to develop in the area.
31-60 points	Medium	Where the impact could influence the decision to develop in the area unless it is effectively mitigated.
> 60 points	High	Where the impact must have an influence on the decision process to develop in the area.

**Confidence**

This should relate to the level of confidence that the specialist has in establishing the nature and degree of impacts. It relates to the level and reliability of information, the nature and degree of consultation with I&AP's and the dynamic of the broader socio-political context.

- High, where the information is comprehensive and accurate, where there has been a high degree of consultation and the socio-political context is relatively stable.
- Medium, where the information is sufficient but is based mainly on secondary sources, where there has been a limited targeted consultation and socio-political context is fluid.
- Low, where the information is poor, a high degree of contestation is evident and there is a state of socio-political flux.

**Status**

- The status, which is described as either positive, negative or neutral.

**Reversibility**

- The degree to which the impact can be reversed.

**Mitigation**

- The degree to which the impact can be mitigated.

Nature:	Without mitigation	With mitigation
<b>Construction Phase</b>		
Probability		
Duration		
Extent		
Magnitude		
Significance		
Status (positive or negative)		
<b>Operation Phase</b>		
Probability		
Duration		
Extent		
Magnitude		
Significance		
Status (positive or negative)		
Reversibility		
Irreplaceable loss of resources?		
Can impacts be mitigated		

### 3. Mitigation measures

- *Mitigation: means to anticipate and prevent negative impacts and risks, then to minimise them, rehabilitate or repair impacts to the extent feasible.*

Impacts can be managed through one or a combination of the following mitigation measures:

- Avoidance
- Investigation (archaeological)
- Rehabilitation
- Interpretation
- Memorialisation
- Enhancement (positive impacts)

For the current study, the following mitigation measures are proposed, to be implemented only if any of the identified sites or features are to be impacted on by the proposed development activities:

- (1) Avoidance/Preserve: This is viewed to be the primary form of mitigation and applies where any type of development occurs within a formally protected or significant or sensitive heritage context and is likely to have a high negative impact. This measure often includes the change / alteration of development planning and therefore impact zones in order not to impact on resources. The site should be retained *in situ* and a buffer zone should be created around it, either temporary (by means of danger tape) or permanently (wire fence or built wall). Depending on the type of site, the buffer zone can vary from
  - 10 metres for a single grave, or a built structure, to
  - 50 metres where the boundaries are less obvious, e.g. a Late Iron Age site.
- (2) Archaeological investigation/Relocation of graves: This option can be implemented with additional design and construction inputs. This is appropriate where development occurs in a context of heritage significance and where the impact is such that it can be mitigated. Mitigation is to excavate the site by archaeological techniques, document the site (map and photograph) and analyse the recovered material to acceptable standards. This can only be done by a suitably qualified archaeologist.
  - This option should be implemented when it is impossible to avoid impacting on an identified site or feature.
  - This also applies for graves older than 60 years that are to be relocated. For graves younger than 60 years a permit from SAHRA is not required. However, all other legal requirements must be adhered to.
    - Impacts can be beneficial – e.g. mitigation contribute to knowledge
- (3) Rehabilitation: When features, e.g. buildings or other structures are to be re-used. Rehabilitation is considered in heritage management terms as an intervention typically involving the adding of a new heritage layer to enable a new sustainable use.
  - The heritage resource is degraded or in the process of degradation and would benefit from rehabilitation.
  - Where rehabilitation implies appropriate conservation interventions, i.e. adaptive reuse, repair and maintenance, consolidation and minimal loss of historical fabric.
    - Conservation measures would be to record the buildings/structures as they are (at a particular point in time). The records and recordings would then become the ‘artefacts’ to be preserved and managed as heritage features or (movable) objects.
    - This approach automatically also leads to the enhancement of the sites or features that are re-used.

- (4) Mitigation is also possible with additional design and construction inputs. Although linked to the previous measure (rehabilitation) a secondary though 'indirect' conservation measure would be to use the existing architectural 'vocabulary' of the structure as guideline for any new designs.
  - The following principle should be considered: **heritage informs design**.
    - This approach automatically also leads to the enhancement of the sites or features that are re-used.
- (5) No further action required: This is applicable only where sites or features have been rated to be of such low significance that it does not warrant further documentation, as it is viewed to be fully documented after inclusion in this report.
  - Site monitoring during development, by an ECO or the heritage specialist are often added to this recommendation in order to ensure that no undetected heritage/remains are destroyed.

#### 4. Relocation of graves

If the graves are younger than 60 years, an undertaker can be contracted to deal with the exhumation and reburial. This will include public participation, organising cemeteries, coffins, etc. They need permits and have their own requirements that must be adhered to.

If the graves are older than 60 years old or of undetermined age, an archaeologist must be in attendance to assist with the exhumation and documentation of the graves. This is a requirement by law.

Once it has been decided to relocate particular graves, the following steps should be taken:

- Notices of the intention to relocate the graves need to be put up at the burial site for a period of 60 days. This should contain information where communities and family members can contact the developer/archaeologist/public-relations officer/undertaker. All information pertaining to the identification of the graves needs to be documented for the application of a SAHRA permit. The notices need to be in at least 3 languages, English, and two other languages. This is a requirement by law.
- Notices of the intention needs to be placed in at least two local newspapers and have the same information as the above point. This is a requirement by law.
- Local radio stations can also be used to try contact family members. This is not required by law, but is helpful in trying to contact family members.
- During this time (60 days) a suitable cemetery need to be identified close to the development area or otherwise one specified by the family of the deceased.
- An open day for family members should be arranged after the period of 60 days so that they can gather to discuss the way forward, and to sort out any problems. The developer needs to take the families requirements into account. This is a requirement by law.
- Once the 60 days has passed and all the information from the family members have been received, a permit can be requested from SAHRA. This is a requirement by law.
- Once the permit has been received, the graves may be exhumed and relocated.
- All headstones must be relocated with the graves as well as any items found in the grave.


#### Information needed for the SAHRA permit application

- The permit application needs to be done by an archaeologist.
- A map of the area where the graves have been located.
- A survey report of the area prepared by an archaeologist.
- All the information on the families that have identified graves.
- If graves have not been identified and there are no headstones to indicate the grave, these are then unknown graves and should be handled as if they are older than 60 years. This information also needs to be given to SAHRA.
- A letter from the landowner giving permission to the developer to exhume and relocate the graves.
- A letter from the new cemetery confirming that the graves will be reburied there.
- Details of the farm name and number, magisterial district and GPS coordinates of the gravesite.

5. Inventory of identified cultural heritage sites

<b>NHRA Category</b>	<b>Structures older than 60 years - Section 34</b>
----------------------	--

<p><b>7.3.1. Type:</b> Built structures. <b>Farm:</b> Van Dyksput 214 IR. <b>Coordinates:</b> S 26,04055; E 28,88314</p> <p><b>Description</b></p> <p>Old station building. According to its style and the material used in its construction, this building probably dates to the 1940s. It is similar in style, layout and material as other station on the same line, e.g. Dryden and Argent.</p> <p>Unfortunately, the building is fenced off and has an alarm that goes off when anybody gets to near it. No access could be obtained.</p>
--



<b>Significance of site/feature</b>	Generally protected: High significance - Grade 4-A
<p><b>Reasoned opinion:</b> This site represents the remains of a technology and style of life that became redundant due to the cessation in demand of its original purpose. Such sites representing industrial heritage are usually few and far between and therefore the destruction of a single such site would have a proportionate high impact on the occurrences of similar features in the larger landscape.</p>	

<b>Impact assessment</b>
This site is located inside the development area and therefore there is a high possibility that it might be impacted on by the expansion of the scope of activities at the railway siding.

<b>Mitigation</b>
<p>(1) Avoidance/Preserve: Because of its location within the larger project development area, it would be possible to avoid this site as it actually occupies a small footprint;</p> <p>(2) Archaeological investigation: If the former is not possible, the site should be documented in full before destruction.</p>

<b>Significance of impact: before/after mitigation</b>					
Extent	Duration	Intensity	Probability	Significance	Weight
3		5	4	5	60
1		5	3	3	27

<b>Requirements</b>
Conservation by local authority. Sites should be mitigated before impact. Permit required from provincial heritage authority, as well as other institutions – see Section 4 of the Addendum.

<b>References</b>

## 6. Curriculum vitae

### Johan Abraham van Schalkwyk

#### Personal particulars

Date of birth: 14 April 1952  
Identity number: 520414 5099 08 4  
Marital status: Married; one daughter  
Nationality: South African

#### Current address: home

62 Coetzer Ave, Monument Park, Pretoria, 0181  
Mobile: 076 790 6777; E-mail: jvschalkwyk@mweb.co.za

#### Qualifications

1995 DLitt et Phil (Anthropology), University of South Africa  
1985 MA (Anthropology), University of Pretoria  
1981 BA (Hons), Anthropology, University of Pretoria  
1979 Post Graduate Diploma in Museology, University of Pretoria  
1978 BA (Hons), Archaeology, University of Pretoria  
1976 BA, University of Pretoria

#### Non-academic qualifications

12th HSRC-School in Research Methodology - July 1990  
Dept. of Education and Training Management Course - June 1992  
Social Assessment Professional Development Course - 1994  
Integrated Environmental Management Course, UCT - 1994

#### Professional experience

Private Practice  
2017 - current: Professional Heritage Consultant

#### National Museum of Cultural History

1992 - 2017: Senior researcher: Head of Department of Research. Manage an average of seven researchers in this department and supervise them in their research projects. Did various projects relating to Anthropology and Archaeology in Limpopo Province, Mpumalanga, North West Province and Gauteng. Headed the Museum's Section for Heritage Impact Assessments.  
1978 - 1991: Curator of the Anthropological Department of the Museum. Carried out extensive fieldwork in both anthropology and archaeology

#### Department of Archaeology, University of Pretoria

1976 - 1977: Assistant researcher responsible for excavations at various sites in Limpopo Province and Mpumalanga.

#### Awards and grants

1. Hanisch Book Prize for the best final year Archaeology student, University of Pretoria - 1976.
2. Special merit award, National Cultural History Museum - 1986.
3. Special merit award, National Cultural History Museum - 1991.
4. Grant by the Department of Arts, Culture, Science and Technology, to visit the various African countries to study museums, sites and cultural programmes - 1993.
5. Grant by the USA National Parks Service, to visit the United States of America to study museums, sites, tourism development, cultural programmes and impact assessment programmes - 1998.
6. Grant by the USA embassy, Pretoria, under the Bi-national Commission Exchange Support Fund, to visit cultural institutions in the USA and to attend a conference in Charleston - 2000.
7. Grant by the National Research Foundation to develop a model for community-based tourism - 2001.

8. Grant by the National Research Foundation to develop a model for community-based tourism - 2013. In association with RARI, Wits University.

**Publications**

Published more than 70 papers, mostly in scientifically accredited journals, but also as chapters in books.

**Conference Contributions**

Regularly presented papers at conferences, locally as well as internationally, on various research topics, ranging in scope from archaeology, anthropological, historical, cultural historical and tourism development.

**Heritage Impact Assessments**

Since 1992, I have done more than 2000 Phase 1 and Phase 2 impact assessments (archaeological, anthropological, historical and social) for various government departments and developers. Projects include environmental management frameworks, roads, pipeline-, and power line developments, dams, mining, water purification works, historical landscapes, refuse dumps and urban developments.

**Annexure 16.2.6: Biodiversity Management Plan**




**BIODIVERSITY MANAGEMENT PLAN FOR  
ARBOR RAILWAY SIDING OPERATED BY  
GIJIMA SUPPLY CHAIN MANAGEMENT  
SERVICES IN KANGALA DISTRICT  
MUNICIPALITY**



**ZEN**

*“Balancing human livelihoods  
with environmental sustainability”*

## REPORT INFORMATION

Report Title:	Biodiversity Management Plan for Arbor Railway Siding operated by Gijima Supply Chain (Pty) Ltd		
Report Reference:	BIO-REP-01_2016		
Report Status:	Draft		
Author (s):	Vuyokazi Maceduma April ( <i>Pri.Sc.Nat</i> )		
Client:	Myezo Environmental Management Services (Pty) Ltd on behalf of Gijima Supply Chain (Pty) Ltd		
<p>☎ <a href="tel:+27129987642">+27 12 998 7642</a></p> <p>☎ <a href="tel:+270129987641">+ 27 012 998 7641</a></p> <p>✉ <a href="mailto:sicelo@myezo.co.za">sicelo@myezo.co.za</a></p>			
Prepared By:	Zen Environmental Consultant		
<p>☎ <a href="tel:08247806130827587590">082 478 0613/082 758 7590</a></p> <p>✉ <a href="mailto:zen.environmental@outlook.com/mishapril@gmail.com">zen.environmental@outlook.com/mishapril@gmail.com</a></p>			
	Name:	Signature:	Date:
Reviewed & Approved By:	Chipo J. Mlinda-Muhomba		26/07/16

## DECLARATION OF INDEPENDENCE

I, **Maceduma Vuyokazi April**, in my capacity as a specialist consultant, hereby declare that I:-

- ✦ Act as an independent consultant;
- ✦ Do not have any financial interest in the undertaking of this project, other than remuneration for the work performed in terms of the National Environmental Management Act 107 of 1998;
- ✦ Have and will not have vested interest in the proposed activity nor will I engage myself in any conflicting interest associated with this project
- ✦ As a registered member of the South African Council for Natural Scientific Professions, I will undertake my profession in accordance with the Code of Conduct of the Council as well as other associates to which I am a member;
- ✦ I undertake to disclose and provide to the competent authority any material or information at my disposal regarding this project as required in terms of National Environmental Management Act 107 of 1998;
- ✦ Based on the information provided to me by the client and in addition to information obtained during the course of this study, I have presented the results and conclusion with regard to this project to the best of my professional ability;
- ✦ I reserve the right to modify aspects pertaining to this study should additional information become available through ongoing research and further work on this field;
- ✦ I undertake to have my work peer reviewed on a regular basis by a competent specialist in the field of study.



**Vuyokazi April (PrSci/Net)**

14/07/16

## EXECUTIVE SUMMARY

Zen Environmental Consultant, as an independent environmental and specialist consultants has been appointed by Myezo Environmental Management Services (Pty) Ltd on behalf of Gijima Supply Chain (Pty) Ltd to undertake and compile a Biodiversity Management Plan as part of the Environmental Management Plans compliance process for their operation at Arbor Railway Siding on Portion 1 of the Farm Vandykspunt 214 IR in Mpumalanga Province.

The management plan is aimed to indicate biodiversity important species and ecosystems within the operating area. The occurrence and diversity of flora and fauna species associated with the site, the ecological functionality and conditions that influence the area's ecosystems interactions will be detailed. And, the client with the help of this plan will be advised on what measures and mitigation to undertake while enabling a successful operation and biodiversity management within the site. This report presents the findings obtained following desktop research and field work undertaken within the study area.

Findings indicate that the area adjacent to the operating site is mainly used for residential, agriculture and mining activities that left it in a destitute form. With regards to flora and fauna, the study site is located in a Highveld part of Mpumalanga province which commonly known for its wetlands and grass plains with variety of flora species. The Grassland biome is the heavily impacted and disturbed biome in the country and its associated wetlands and rivers continually get affected as a result. However, within the Arbor Siding area availability of flora is restricted to alien invasive plants, thus the vegetation is transformed in the edges of the site. No critical flora species of conservation importance within the site was recorded. Furthermore, with exception with random encounters with fauna, no faunal species of importance was observed or recorded within the site as the site is highly disturbed to carry any faunal species unless that species is domesticated.

With exception of one transformed wetland and dam constructed to support the activity, there were no natural or functioning wetlands were observed and recorded within Arbor siding boundary.

Outside the boundaries of the study site there are thriving ecosystems such as wetlands and rivers located on the north of the site. These ecosystem supports variety of species such as Grass Owl. Arbor Siding activities only affect these ecosystems due to the uncontrolled stormwater drainage as a result it is recommended that the proponent put in place proper stormwater measures that could prevent it from draining into the nearest freshwater ecosystems.

# CONTENTS

DECLARATION OF INDEPENDENCE .....	I
EXECUTIVE SUMMARY .....	II
CONTENTS .....	III
1. INTRODUCTION .....	4
2. LOCATION OF THE ACTIVITY .....	4
3. RELEVANT LEGISLATION .....	5
4. LAND USE IN THE AREA.....	5
5. METHODOLOGY .....	5
5.1. DESKTOP STUDY.....	6
5.2. SITE SCREENING AND GROUND TROTHING .....	6
5.3. FIELD ASSESSMENT .....	6
6. SITE CHARACTERISTICS.....	6
7. FINDINGS OF THE STUDY .....	10
8. CONCLUSION AND RECOMMENDATIONS .....	12
9. REFERENCES .....	15
10. GLOSSARY .....	18

## LIST OF FIGURES

Figure 1: The study location Vandykspunt 214 1R and the study site Portion 1 (Arbor Siding).....	5
Figure 2: Entrance to Arbor Siding.....	7
Figure 3: View from the North side of the site.....	7
Figure 4: View from the west side of the site.....	8
Figure 5: View from the south side of the site.....	8
Figure 6: Coal loading operation underway.....	9
Figure 7: Coal storage stockpiles that are loaded into the train carriages using a front scoop caterpillar.....	9
Figure 8: Gijima Offices, parking area and weigh bridge area.....	10
Figure 9: Coal dust along R555 road.....	10
Figure 10: Control dam in site (Image ©MYEZO).....	11
Figure 11: Transformed wetland observed within Arbor siding boundary.....	11
Figure 12: Arbor Siding Biodiversity Sensitivity Map.....	12
Figure 13: Stormwater colbet from R555 used to drain stormwater.....	13
Figure 14: The drainage continues from the colbet into the sensitive area near the Arbor Siding operation area.....	13
Figure 15: Coal dust residue observed in stormwater drained on the area towards NFEPA recognised ecosystem in the area.....	14
Figure 16: Dried coal dust residue stormwater.....	14
Figure 17: The study area from the sensitive NFEPA ecosystem location.....	15
Figure 18: NFEPA recognised river and wetland in the area.....	15

## 1. INTRODUCTION

This assessment study was undertaken as part of compliance with the National Environmental Management Act, 1998 (Act 107 of 1998), as amended and the Environmental Impact Assessment Regulations of 2014.

The objective of this study was to cover the season flora and fauna species variation habiting and likely to occur within Vandykspunt 214 IR Portion 1 where Gijima Supply Services are operating a coal siding at Arbor Railway Sidings. The flora and fauna species that potentially occur and seen during the survey were recorded. Red data or Orange data species (both fauna and flora) that are known to occur on site were investigated. The current ecological status and conservation priority of vegetation on the site was also assessed.

To comply with the requirements of the Provincial Authorities, Departmental divisions and regional requirements, the Terms of Reference (ToR) for this study are:-

- ❖ To assess the current status of the habitat components and its conservation status
- ❖ To identify the floral species on site and to recommend steps to be taken should a Red list/ Orange list or protected species be found
- ❖ To identify the fauna species on the site and to recommend steps to be taken should a Red list/ Orange List species be found
- ❖ To highlight the potential impacts the development may have on the ecosystem components of the study area
- ❖ Provide management recommendation to mitigate negative impacts and enhance positive impacts of the proposed activity

## 2. LOCATION OF THE ACTIVITY

The coal handling and storage operation is currently taking place in Arbor Siding situated on Portion 1 of Vandykspunt 214 IR in Witbank, Nkangala District Municipality, Mpumalanga Province. The siding is located west of N12 and can be accessed through R555 to Ogies.




Figure 1: The study location Vandyksput 214 1R and the study site Portion 1 (Arbor Siding).

### 3. RELEVANT LEGISLATION

- Constitution of RSA 108 of 1996;
- National Environmental Management Act 107 of 1998, (NEMA);
- National Water Act 36 of 1998.(NWA);
- National Environmental Management: Biodiversity Act 10 of 2004 (NEMBA);
- Conservation of Agricultural Resources Act 43 of 1983 (CARA);
- Mineral and Petroleum Resources Development Act 28 of 2002 (MPRDA);
- Mpumalanga Province Biodiversity Act 6 of 1998 (MPBA);
- Mpumalanga Terrestrial Protected Areas Act 5 of 2005 (MTPAA); and
- MNCA 10 of 1998 (MNCA).

### 4. LAND USE IN THE AREA

Apart from the coal siding operating at the study location, the area is characterised by the following land use activities:-

1. Agriculture (Farming and Cultivation);
2. Operational Power Station;
3. Active mines; and
4. Human dwellings.

### 5. METHODOLOGY

The study consists of three components, viz:-

- a) A desktop review and analysis
- b) Site Screening and ground truthing

c) A field assessment

### **5.1.Desktop Study**

The available provincial biodiversity data sets, Red and Orange listed fauna and flora data, species conservation status data and relevant legislation and policies information were researched and included for constructive environmental impact assessment conclusion. Previously conducted studies for proposed activities of similar nature were reviewed and used as references. The specialist also liaised and communicated with relevant sectors whose mandate is to conserve and be custodians of biodiversity. Maps and any spatial data on biodiversity (where available) were used to determine the species occurrence, distribution and status.

### **5.2.Site screening and ground trothing**

The site visit was conducted on 18 November 2015 on Portions 1 of the Farm Vandykspunt 214 IR in Witbank, Mpumalanga Province. The visit was used to verify if the results yielded by the desktop research and other reference material significance. Macro and micro changes in the environment that has not yet documented were investigated during screening. This component entailed a visual assessment of the area, monitoring of species activities and other activities taking place within or adjacent to the project area.

### **5.3.Field Assessment**

This component was aimed at assessing terrestrial biodiversity by visual observations and recording of species occurrence. Flora and fauna observed during this component were recorded and the results were compared with the desktop reviews and used to conclude on the ecological sensitivity of the area. This particular assessment was done in conjunction with the site screening and groundthrothing on the 18 November 2015.

The site was visited and assessed to determine the various plant communities, fauna and ecosystems occurring on the site. All observed species were recorded. Faunal species were observed visually and the survey was done mostly on foot. Avi-fauna observed was then verified using the checklist obtained from the desktop studies and further identified using Sasol Birds of Southern Africa (Sinclair *et. al.*, 2002), South African Bird Atlas Phase 2 and Bird Life South Africa for avian species occurring in the area. Animals and small mammals were identified within the study site using sitings, spoor, tracts, signs and droppings as well as burrows and nesting sites on the grounds where possible.

National Freshwater Ecosystem Priority Areas (NFEPA) identified and recognized ecosystems occurrence, their functionalities were assessed and reported.

**All the observed biodiversity was identified, recorded and used to compile this report.**

## **6. SITE CHARACTERISTICS**

Arbor Siding is highly disturbed and transformed due to the coal handling and storage operation. The operations footprints in the site and adjacent areas to the site are highly identifiable.

The following visuals were taken at the site.





Figure 2: Entrance to Arbor Siding.



Figure 3: View from the North side of the site.



Figure 4: View from the west side of the site.



Figure 5: View from the south side of the site.



Figure 6: Coal loading operation underway.



Figure 7: Coal storage stockpiles that are loaded into the train carriages using a front scoop caterpillar.



Figure 8: Gijima Offices, parking area and weigh bridge area.



Figure 9: Coal dust along R555 road.

## 7. FINDINGS OF THE STUDY

With regards to flora and fauna, the study site is located in a Highveld part of Mpumalanga province which commonly known for its wetlands and grass plains with variety of flora species. The Grassland biome is the heavily impacted and disturbed biome in the country and its associated wetlands and rivers continually get affected as a result.

Findings show that the area adjacent to the operating site is mainly used for residential, agriculture and mining activities that left it in a destitute form. However, within the Arbor Siding area availability of flora is restricted to alien invasive plants, thus the vegetation is transformed in the edges of the site. No critical flora species of conservation importance within the site was recorded. Furthermore, with exception with random encounters with fauna, no faunal species of importance was observed or recorded within the site as the site is highly disturbed to carry any faunal species.

With exception of one transformed wetland and dam constructed to support the activity, there were no natural or functioning wetlands observed and recorded within Arbor siding boundary.



Figure 10: Control dam in site (Image ©MYEZO)



Figure 11: Transformed wetland observed within Arbor siding boundary.



Figure 12: Arbor Siding Biodiversity Sensitivity Map.

## 8. CONCLUSION AND RECOMMENDATIONS

The operational site is highly transformed and with exception of Eucalyptus species randomly occurring on the boundaries of the site and serve as screening method; the site is unable to carry and sustain any flora species as a habitat due to coal dust footprint. However, outside the boundaries of the study site on the east side there are thriving ecosystems such as wetlands and rivers located on the north of the site. These ecosystem supports variety of species such as Grass Owl. Arbor Siding activities only affect these ecosystems due to the uncontrolled stormwater as a result it is recommended that the proponent put in place proper stormwater measures that could prevent it from draining into the nearest freshwater ecosystems.

The following visuals were taken from the drainage coming on Arbor siding side towards the NFEPA ecosystem in the close vicinity to the operational site. This is outside Arbor Siding boundary; however, stormwater with coal dust residue was observed:-



Figure 13: Stormwater colbet from R555 used to drain stormwater.



Figure 14: The drainage continues from the colbet into the sensitive area near the Arbor Siding operation area.



Figure 15: Coal dust residue observed in stormwater drained on the area towards NFEPA recognised ecosystem in the area.



Figure 16: Dried coal dust residue stormwater.





Figure 17: The study area from the sensitive NFEPA ecosystem location.



Figure 18: NFEPA recognised river and wetland in the area.

## 9. REFERENCES

- Acocks, J.P., 1988. Veld types of South Africa. Mem. Bot. Soc. S. Afr 57. Department of Agriculture and Water supply. Pretoria.
- Brix, H. (1994). Use of constructed wetlands in water pollution control: historical development, present status, and future perspectives. *Water Science Technology* , 209-223.

- Bromilow, C. 2001. Problem Plants of South Africa : A guide to the identification and control of more than 300 invasive plants and other weeds. Briza publishers, South Africa
- Driver, A., Maze, K., Rouget, M., Lombard, A.T., Nel, J., Turpie, J.K., Cowling, R.M., Desmet, P., Goodman, P., Harris, J., Jonas, Z., Reyers, B., Sink, K. & Strauss, T. 2005. National Spatial Biodiversity Assessment 2004: priorities for biodiversity conservation in South Africa. *Strelitzia* 17. South African National Biodiversity Institute, Pretoria. 45pp
- Department of Water Affairs and Forestry. 2005. A practical field procedure for identification of wetlands and riparian areas. DWAF. South Africa
- Edwards, P.J., Abivardi, C. 1998. The value of biodiversity: Where ecology and economy blend. *Biological Conservation* 83(3). Pp 239-246
- Henderson, L. 2004. Alien weeds and invasive plants: A complete guide to declared weeds and invaders in South Africa. Plant Protection Research Institute Handbook no. 12. Agricultural Research Council. Pretoria
- IUCN. 2009. Red List of Threatened Species. IUCN Species Survival Commission, Cambridge Available: <http://www.iucnredlist.org/> (Accessed 17/03/2012).
- Kuntonen-van't Riet, J. 2007. Strategic review of the status of biodiversity management in the South African mining industry. Matrix + Consulting. South Africa
- Manning, J. 2010. Wild flowers of South Africa. Random Struik publishers. South Africa
- Maze, K., Driver, A., Brownlie, S. 2003. Mining and Biodiversity in South Africa: A discussion paper. In Driver A, Cowling, R.M., Maze, K. (2003) Planning for living landscapes: Perspective and lessons from South Africa. Washington DC: Centre for Applied Biodiversity Science and Conservation. BotSoc. South Africa
- Milton, S.J. 2004. Grasses as invasive aliens in South Africa. *South African Journal of Science* 100. Pp 69-75
- Mucina, L., Rutherford, M. C. & Powrie, L. W. 2005. Vegetation Map of South Africa, Lesotho and Swaziland. South African National Biodiversity Institute. ISBN 1-919976-22-1
- Raimondo, D., von Staden, L., Foden, W., Victor, J.E., Helme, N.A., Turner, R.C., Kamundi, D.A., Manyama, P.A. 2009. Red List of South African Plants. *Strelitzia* 25. South African National Biodiversity Institute. Pretoria
- Richardson, D.W., van Wilger, B.W. 2004. Invasive Alien Plants in South Africa: How well do we understand the ecological impacts. *South African Journal of Science* 100. Pp 45-52
- Rouget, M., Reyers, B., Jonas, Z., Desmet, P., Driver, A., Maze, K., Egoh, B., Cowling, R.M., Mucina, L. & Rutherford, M. 2004. South African National Spatial Biodiversity Assessment Technical Report. Volume 1: Terrestrial Component. South African National Biodiversity Institute, Pretoria.
- Sinclair, I., Hockey, P., Tarboton, W. 2002. Sasol Birds of Southern Africa. Struik publishers, South Africa
- Semlitsch, R.D. & Bodie, J.R. Biological Criteria for Buffer Zones around Wetlands and Riparian Habitats for Amphibians and Reptiles. *Conservation Biology* Volume 17 (5) pg 1219 – 1228.

Skinner, J., & Smithers, R. N. (1990). The mammals of the Southern African Sub region. Pretoria: University of Pretoria

Stuart, C., & Stuart, T. (1997). Field Guide to Mammals of Southern Africa. Cape Town : Struik Publishers.

Tainton, N. 2000. Pasture Management in South Africa. University of Natal Press, Pietermaritzburg. South Africa

van Oudtshoorn, F. 2002. Guide to grasses of Southern Africa. Briza publishers, South Africa

**Annexure 16.2-7: Stockpile Coal Handling Capacity Report**



STORAGE AREAS

Measured on 09-03-2018

Available Existing Storage Area

Storage Area

STORAGE VOLUME

As Measured on 09-03-2018 : 23 800 cu.m

Available Existing Storage Volume : 2 700 cu.m

Storage Volume : 20 850 cu.m

New Weigh

VOLUME : 47 350 cu.m

TONNAGE : 37 882 ton

Calculated by:

F.J. DE LANGE (Pr. Eng.)  
(ECSA No. 800102)

Google Earth

Image © 2018 DigitalGlobe  
© 2018 AtrigIS (Pty) Ltd.  
© 2018 Google

	SYS
Pt	Y
A	+11 624



200 m

