

Contract

**HERITAGE RESOURCES
IDENTIFICATION AND ASSESSMENT.**

Olifants River Water Resources

Development Project Phase 2

(ORWRDP II)

REVISED 2011-05-11

Research

§

Consulting

Services

Name and geographical location of the site(s) and/ or project: ORWRDP Phase 2B to 2F of the proposed pipelines and associated borrow pits in the Steelpoort and Olifants River Valleys respectively.

Property or farm name: Refer Appendix A

Magisterial district: Greater Sekhukhune; Waterberg and Capricorn District Municipalities

Province: Limpopo

Authors: WC Nienaber, M Hutten and A Meyer

- Business Enterprises at University of Pretoria (Pty) Ltd
- Forensic Anthropology Research Centre (FARC)
- University of Pretoria

Developer and consultant

This report was commissioned by:

Mr D Esterhuisen, Aurecon SA (Pty) Ltd and
Ndodana Consulting Engineers Joint Venture

Business Enterprises at University of Pretoria (Pty) Ltd

PO Box 14679
Hatfield 0028

T: +27 (12) 420 4245
F: +27 (12) 362 5270

University of Pretoria Main Campus
Prospect Street, Hatfield
Graduate Center, Entrance 1.82



Executive Summary

- The purpose of the study was the identification and assessment of affected heritage resources on the proposed alignment of the Olifants River Water Resources Development Project Phase 2B-F and 11 associated proposed borrow pits.
- The findings summarised:
 - i. No heritage resources were found to be affected by the proposed borrow pits.
 - ii. No heritage resources were found to be affected by the proposed Phase 2B alignment.
 - iii. Sites ORW 3, 6, 7, 8 and 22 are included in the report but are either not on any of the current proposed alignments, or were identified in the field and subsequently assessed to fall outside the legal definitions of what constitutes an affected heritage resource. No actions are required for these sites, apart from considering such locations where they fall on indicated alternative alignments when alternative alignments are investigated.
 - iv. Sites ORW 1, 2, 4, 10, 18, 19, 20, 24 and 26 are insignificant Late Iron Age Potshard scatters. In all cases these were assessed to be without heritage value due to the disturbed or compromised nature of the occurrences. These sites were deemed to have been sufficiently recorded by this report and no further actions are recommended. Only in the case of Site ORW 26, where it is associated with the grave at Site ORW 25 are recommendations for mitigation made if the alignment cannot be slightly changed to avoid impacts on the site and grave.
 - v. Sites ORW 5, 11, 12, 14, 15, 27, 28, 29 and 30 are ruins of abandoned homesteads affected by the different proposed alignments. These structures are of recent modern origin and are not significant heritage resources, however, it is known that the graves of young

children often occur in the floors of such houses and for this reason it is recommended that impacts on these structures be avoided where possible, or alternatively that a suitably accredited archaeologist monitor the construction activities at these sites to ensure that such graves be treated according to legislative requirements should they be discovered.

- vi. Sites ORW 9, 13, 16, 17, 21, 23 and 25 are graves and cemeteries. All graves are legally protected. In all cases it should be possible to avoid impacts by slight changes in alignment or by managing construction activities in the direct vicinity of the graves. Although grave relocation exists as a possible mitigation measure it is not advised due to previous social, cultural and political problems with grave relocation in this area.

ORW Site no.	GPS Location (Deg, min, sec)	Proposed Alignment	Site Type	Significance	Rating	Recommendations	Secondary Recommendations	Actions required
1	S24 54 47.2 E29 59 03.1	Phase 2C	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
2	S24 54 47.2 E29 59 07.3	Phase 2C	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
3	S24 53 19.1 E29 59 55.8	Not on current alignment	Not applicable	n/a	Not applicable	Not applicable		None
4	S24 53 19.1 E30 01 31.0	Phase 2C	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None

5	S24 51 06.5 E30 04 32.5	Phase 2C	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
6	S24 50 21.8 E30 05 26.6	Phase 2C	Not applicable	n/a	Not applicable	Not applicable		None
7	S24 50 14.4 E30 05 33.1	Phase 2C	Not applicable	n/a	Not applicable	Not applicable		None
8	S24 50 04.2 E30 05 41.8	Phase 2C	Not applicable	n/a	Not applicable	Not applicable		None
9	S24 45 08.1 E30 10 21.2	Phase 2C	3 Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
10	S24 44 38.6 E30 11 02.6	Phase 2C	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
11	S24 38 58.6 E30 10 56.9	Phase 2D	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
12	S24 38 49.5 E30 10 53.3	Phase 2D	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
13	S24 37 59.7 E30 10 39.2	Phase 2D	5 Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
14	S24 37 32.6 E30 10 15.4	Phase 2D	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction	If impact is unavoidable contract an accredited	Commence construction under supervision of an

						activities on site.	archaeologist on a watching brief	archaeologist
15	S24 37 29.1 E30 10 12.4	Phase 2D	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
16	S24 33 59.9 E30 09 25.0	Phase 2D	100+ Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
17	S24 32 17.3 E30 08 59.4	Phase 2D	250+ Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
18	S24 32 08.6 E30 08 56.0	Phase 2D	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
19	S24 31 59.8 E30 08 49.7	Phase 2D	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
20	S24 31 53.0 E30 08 53.8	Phase 2D	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
21	S24 29 30.5 E30 07 08.5	Phase 2E	12 Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
22	S24 28 52.9 E30 07 15.7	Not on current alignment	Graves	High/ Medium	Generally Protected A (Field Rating IV A)			Consider in conjunction with choosing alternatives to the proposed alignments

23	S24 25 56.8 E30 04 57.1	Phase 2F	200+ Graves	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
24	S24 25 24.2 E30 03 58.3	Phase 2F	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
25	S24 18 05.2 E29 49 29.2	Phase 2F	1 Grave	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site. Mitigation decision in conjunction with Site ORW 26	If impact is unavoidable: Grave Relocation in compliance with NHRA Sec 36.	Demarcation/fencing of grave site
26	S24 18 06.1 E29 49 28.8	Phase 2F	Late Iron Age - Potshard scatter	Low	Generally Protected C (Field Rating IVC)	Requires no further recording before destruction		None
27	S24 18 07.3 E29 49 26.3	Phase 2F	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
28	S24 18 29.7 E29 48 35.6	Phase 2F	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
29	S24 19 51.5 E29 46 20.5	Phase 2F	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist
30	S24 19 53.2 E29 46 17.8	Phase 2F	Possible graves under floors of Recent Modern homestead	High/ Medium	Generally Protected A (Field Rating IV A)	Avoid impact by changing alignment or managing construction activities on site.	If impact is unavoidable contract an accredited archaeologist on a watching brief	Commence construction under supervision of an archaeologist

Table of Contents

1.	Introduction.....	2
2.	Background to the Archaeological History of the area.....	4
2.1.	Literature review	4
2.2.	Archival research	10
2.3.	HIA reports on the directly affected area:.....	13
2.4.	HIA reports on the larger area:.....	15
3.	Description of the Property or Affected Environment.....	17
3.1.	ORWRDP Phase 2B.....	17
3.2.	ORWRDP Phase 2C.....	20
3.3.	ORWRDP Phase 2D	23
3.4.	ORWRDP Phase 2E.....	26
3.5.	ORWRDP Phase 2F.....	28
3.6.	ORWRDP Phase 2B-F associated borrow pits	31
3.6.1.	ORWRDP II Proposed Borrow Pit 1	31
3.6.2.	ORWRDP II Proposed Borrow Pit 2	33
3.6.3.	ORWRDP II Proposed Borrow Pit 3	35
3.6.4.	ORWRDP II Proposed Borrow Pit 4.....	37
3.6.5.	ORWRDP II Proposed Borrow Pit 5	39
3.6.6.	ORWRDP II Proposed Borrow Pit 6	41
3.6.7.	ORWRDP II Proposed Borrow Pit 7	43
3.6.8.	ORWRDP II Proposed Borrow Pit 8	45
3.6.9.	ORWRDP II Proposed Borrow Pit 9	47
3.6.10.	ORWRDP II Proposed Borrow Pit 10	49
3.6.11.	ORWRDP II Proposed Borrow Pit 11	51
4.	Survey methodology	53
5.	Description of Sites.....	55
5.1.	Site ORW 1 ORWRDP Phase 2C	55
5.2.	Site ORW 2 ORWRDP Phase 2C	59
5.3.	Site ORW 4 ORWRDP Phase 2C	63
5.4.	Site ORW 5 ORWRDP Phase 2C	66
5.5.	Site ORW 6 ORWRDP Phase 2C	70
5.6.	Site ORW 7 ORWRDP Phase 2C	70
5.7.	Site ORW 8 ORWRDP Phase 2C	70
5.8.	Site ORW 10 ORWRDP Phase 2C	71
5.9.	Site ORW 11 ORWRDP Phase 2D	76
5.10.	Site ORW 12 ORWRDP Phase 2D	80
5.11.	Site ORW 14 ORWRDP Phase 2D	84
5.12.	Site ORW 15 ORWRDP Phase 2D	88
5.13.	Site ORW 18 ORWRDP Phase 2D	92
5.14.	Site ORW 19 ORWRDP Phase 2D	96
5.15.	Site ORW 20 ORWRDP Phase 2D	99
5.16.	Site ORW 24 ORWRDP Phase 2F.....	102

5.17.	Site ORW 26 ORWRDP Phase 2F	106
5.18.	Site ORW 27 ORWRDP Phase 2F	110
5.19.	Site ORW 28 ORWRDP Phase 2F	114
5.20.	Site ORW 29 ORWRDP Phase 2F	119
5.21.	Site ORW 30 ORWRDP Phase 2F	124
6.	Burial Grounds and Graves.....	128
6.1.	Site ORW 3 ORWRDP (Not directly on current proposed alignment)	128
6.2.	Site ORW 9 ORWRDP Phase 2C	128
6.3.	Site ORW 13 ORWRDP Phase 2D	137
6.4.	Site ORW 16 ORWRDP Phase 2D	147
6.5.	Site ORW 17 ORWRDP Phase 2D	155
6.6.	Site ORW 21 ORWRDP Phase 2E	163
6.7.	Site ORW 22 ORWRDP	171
6.8.	Site ORW 23 ORWRDP Phase 2F	173
6.9.	6.9. Site ORW 25 ORWRDP Phase 2F.....	180
7.	Conclusions.....	188
	Bibliography	189
	Archival sources	191

1. INTRODUCTION

Background Information on the Project:

- This study is included in the Baseline Report is part of a re-assessment of the final alignments of infrastructure. An existing Record of Decision exists for phase's 2B-F for the water augmentation project.
- Phase 2 of the ORWRDP is a multi-purpose project incorporating both economic and social development objectives to cater for the water demands of commercial and social users. The project comprises a number of sub-phases and entails additional water resource infrastructure, pump stations and reservoirs, consisting of the De Hoop storage dam as Phase 2A which is presently under construction by DWA, and bulk transfer pipelines and pump stations as Phases 2B to 2H.
- Most of the pipeline is within the road reserve, but wherever infrastructure is outside existing servitudes on privately or state owned land, sub-divisions and servitude registrations would be necessary.
- The baseline HIA re-assesses the final alignments of the ORWRDP-2 infrastructure, which differs from the previously done Heritage Impact Assessment study during the Environmental Impact Assessment process. The activities will provide detailed and accurate information as a baseline for planning mitigation activities and in order to avoid damages to any heritage aspects.
- Legislative requirements: Baseline studies are required to re-assesses the final alignments of infrastructure and to secure baseline information for planning mitigation activities.

Developer – Trans-Caledon Tunnel Authority (TCTA) is the implementing agent on behalf of the Department of Water Affairs.

Contact Person:

Azwianewi Nelwamondo (TCTA Environmental Manager)

Tel: 012-683 1200

Fax: 012-683 1300

ANelwamondo@tcta.co.za

Consultant – Aurecon-Ndodana Joint Venture

Contact Person:

Deon Esterhuizen (Environmental team leader)

082 445 1781

deon@iliso.com

Owner - Department of Water Affairs

2. BACKGROUND TO THE ARCHAEOLOGICAL HISTORY OF THE AREA

2.1. Literature review

Stone Age

The earliest evidence of habitation in this area can be found on the farm Rietkloof, specifically on the site, Maleoskop. Stone tool assemblages include choppers (Oldowan), hand axes and cleavers (Acheulean) dating to the Early Stone Age (Boshoff, 2005). Middle Stone Age assemblages can be found on the farm Klipfonteinhoek in the Ohrigstad district. This site, called Bushman Rock Shelter, was first excavated in the 1960s by Eloff (1969) and Louw (1969). This site also yielded evidence of Later Stone Age tools as well as Early Iron Age ceramics (Klein, 1984; Plug, 1981; Plug, 1982). Late Stone Age assemblages in the area can mainly be attributed to the San hunter-gatherer communities. The San were nomadic by nature and did not have any permanent settlements, yet rock shelters are often associated with their seasonal occupation of an area. Evidence of these shelters can be found in areas such as Witbank, Ermelo, Baberton, Nelspruit, White River, Lydenburg and Ohrigstad, as well as along the Olifants River and the foothills of the Mpumalanga Drakensberg (Delius, 2007; Klein, 1984; Korsman, 1994; Mitchell, 2002; Plug, 1981; Plug, 1982; Schoonraad and Beaumont, 1971). These shelters often also contain rock art produced by the San as well as the later farming communities. Rock art sites are distributed throughout the larger area specifically in the Witbank, Lydenburg, White River, Nelspruit and Nsikazi districts (Delius, 2007).

Iron Age

Early Iron Age settlements from the Kwale branch of the Urewe tradition can be found in and around the affected area. Mzonjani is the earliest facies found in the area and dates to AD 450 to AD 750 (Huffman,

2007). The Mzonjani facies can be regarded as the first representation of Early Iron Age communities in the area (Mitchell, 2002). Huffman (1998) identifies two sites at Riverside in the Steelpoort area which yielded evidence of dung-lined storage pits indicating an early variant of the Central Cattle Pattern amongst the Mzonjani communities. These communities can also be linked to the early Sotho-Tswana (Huffman, 2007).

More Early to Middle Iron Age sites from the Kalundu tradition and the Happy Rest sub-branch can also be identified in the affected area (Huffman, 2007). These sites include the Doornkop facies dating from AD 750 to AD 1000 and the later Klingbeil facies dating to AD 1000 to AD 1200 (Huffman, 2007; Mitchell, 2002). Research on Middle Iron Age sites in this area is limited and only a few sites have been excavated (Huffman, 2007), one of the most famous sites being the Lydenburg head site (Whitelaw, 1996). Aerial surveying done by Mason in 1968, however, showed the presence of 1792 possible settlements in the Steelpoort, Sabi, Crocodile and Komati rivers drainage areas (Evers, 1975). Another aerial survey done by Evers in 1975 increased this estimate to around 5000 possible settlements (Evers, 1975).

Late Iron Age sites include sites from both the Kalundu and Urewe traditions. Only one facies from the Kalundu tradition is present in the area. This is the Letaba facies dating to AD 1650 - AD 1840 and forms part of the Happy Rest sub-branch (Huffman, 2007). The Olifants River marks the southern boundary for this facies, and it is only present in the most northern parts of the affected area.

From the Urewe tradition sites representing two facies of the Moloko branch can be identified in the affected area. The first is the Icon facies dating to AD 1300 to AD 1500 and the second is the Marateng facies dating to AD 1650 to AD 1840 (Huffman, 2007). The Marateng facies also covers the era of

Sotho-Tswana settlement, specifically the Pedi, in the area. Later Iron Age settlements dating to the historical period are ethnographically known to have been built on hilltops and were always enclosed by stone walling (Delius, 1983; Mönning, 1967). The southern most affected areas were inhabited not only by Sotho-Tswana, but also by the Nguni, specifically the Ndzundza Ndebele (Schoeman, 1997). The Ndzundza originally moved into the Steelpoort River source area and first settled at the site called KwaSimkulu in the 1630s (Nell, 2009). There are also three more sites associated with the northern expansion of the Ndzundzu known as Kwamaza, Esikhunjini, and KoNomtjarhelo dating to around the AD 1700 to AD 1900 (Nell, 2009; Schoeman, 1998a, Schoeman, 1998b).

Ethnography

The first semi-permanent inhabitants of the area were the predecessors of the group known today as the Pedi (Delius, 1983; Theal, 1964). The Pedi forms part of the larger group known as the Northern-Sotho, which incorporates a number of different tribes, each with their own chief (Mönning, 1967). Some of the larger groups were the Roka, Kwena, Tau, Pai, Kutswe, Pulana and the Maroteng (the latter of which was lead by Sekhukhune) (Delius, 1983; Mönning, 1967). The area on which the affected farms are located was originally inhabited by a group known as the Bakoni (Massie, 1905). The Bakoni was already settled in the area by the 1600s and large agricultural settlements were widely dispersed across the area (Wright, 2010). The Bakoni was therefore already settled into the area before the Pedi arrived. Subsequently, though, the Bakoni submitted to Pedi rule and was eventually incorporated into the Pedi Kingdom (Massie, 1905).

Oral tradition holds that the Maroteng entered the affected area (the area between the Olifants River and the Steelpoort River) after they broke away from the Kagatla who lived in and around what would

become Pretoria (Delius, 1983). Dates obtained from material remains suggest that this migration took place around 1650 (Delius, 1983, Massie, 1905). When the Maroteng entered the area it was already dominated by the Kwena/Morgatana (Mönning, 1967). Originally the Maroteng were subjugated by the Kwena/Morgatana (Mönning, 1967), however, by the start of the 19th century the Maroteng had risen to dominate the area between the Olifants and the Steelpoort Rivers as well all the tribes within it (Massie, 1905).

By the 1820s, the Pedi lost dominance over the area, following a dramatic population decline as a direct result of the Difiqane/Mfeqane (Delius, 1983; Mönning, 1967). The Pedi were almost completely destroyed by the Ndebele forces, who acted under the command of either Mzilikazi or Zwibe (Delius, 1983; Mönning, 1967; Theal, 1964). Sekwati, the only surviving Pedi royal heir, fled north after the attacks, but after a few years he again returned to the area to reclaim and rebuild it (Massie, 1905, Mönning, 1967).

It was at this point, while the Pedi were still recovering from the Difiqane/Mfeqane, that the Voortrekkers arrived in the area and formed the ZAR. Due to the weakened state of the Pedi, Sekwati signed over land to the ZAR in return for protection against the Swazi, the most powerful group in the area at the time (Delius, 1983). However, the Pedi did not see this as handing over ownership of the land, but only the right to use it (Delius, 1983; Theal, 1964). The throne of the Pedi moved to Sekhukhune after the death of Sekwati in 1861 (Massie, 1905; Mönning, 1967; Theal, 1964), and it was under Sekhukhune's leadership that the Pedi would become one of the most powerful groups in the area. Relations between the Pedi and the ZAR was strained since the 1850s, with the ZAR claiming raids were being ordered by the Pedi paramount Chief, whereas the Pedi, on the other hand, claimed that their land

was being stolen by the ZAR (Delius, 1983). This strained relationship finally erupted into war (1875) (Delius, 1983; Theal, 1964). Despite having initial success against the ZAR force, under President Burgers, the Pedi were finally defeated by the British in 1879 and Sekhukhune was captured. This saw the end of the Pedi as an independent kingdom (Delius, 1983; Theal, 1964; Massie, 1905). After the war, Mampuru and Nkopodi (also known as Ramoroko) assumed joint leadership of the Pedi, however, after Sekhukhune was released Mampuru refused to give up his role and had Sekhukhune murdered. Mampuru fled to the Ndebele chief, Nyabele, and was eventually captured by the ZAR and hanged (Delius, 1983; Massie, 1905, Mönning, 1967). This resulted in a long period of arguing about leadership between the different Pedi houses, until it was finally decided, by order of the ZAR, that the territory would be split and shared by the two ruling houses. Sekhukhune's son, Sekhukhune II, became the paramount Chief of the northern portions whereas Kgolane (who was awarded the seat of the paramount Chief by the ZAR) became Chief of the southern portions (Mönning, 1967). Sekhukhune II tried to reclaim the whole of the old Pedi territory during the confusion of the Anglo-Boer War, however, after the war the British enforced the ZAR division and ever since the Pedi have been divided between several factions (Massie, 1905) The Pedi became subjects of the British crown and they became subject to taxation and also to the administration of the Governor of the Transvaal, who was appointed paramount Chief of all the black communities in Transvaal (Mönning, 1967). With the incorporation of the *Land Act of 1913* and the *Bantu Land and Trust Act of 1936* provision was made for separate land reservations for, amongst others, the Pedi (Mönning, 1967). The *Bantu Administration Act of 1927* further enabled the Pedi to once again appoint chiefs and headmen, giving them control over administrative and civil/criminal matters (Mönning, 1967).

Historical period

The first Europeans entered the area in the 1830s during a period known as the Great Trek. These Voortrekkers were lead by Louis Trichart and moved through the area to Delagoa Bay, modern day Maputo (Berg, 1999; Bosman, 1977; Muller, 1985; Van Jaarsveld, 1985). After Trichart had left the area, another group lead by Andries Potgieter also arrived and founded the towns of Ohrigstad (1845) and later Lydenburg (1850) (Bosman, 1977). These were the first European settlements in the area; however, they were situated east of the Steelpoort River. As previously mentioned the area between the Olifants and Steelpoort Rivers were inhabited by the Pedi, and it would only be after the Sekhukhune Wars of 1875-1879 that the Pedi would be subjugated and their territory incorporated into the ZAR, which was already under British rule by 1879 (Bosman, 1977; Delius, 1983; Van Jaarsveld, 1985). The Sekhukhune Wars also saw the construction of Fort Burgers (today Burgesfort), Fort Weber, Fort Olifants, Fort Mamelube, Fort Faugh-A-Ballach, Fort Albert and with Fort Albert Ewdards and Seven Miles Post located just south of the affected area (Berg, 1999; Bosman, 1977; Delius, 1983; Van Jaarsveld, 1985) The invasion route used by the British in 1879 to attack Sekhukhune's capital was also just south of the affected area, with a small skirmish between the British and the Pedi soldiers occurring there (Berg, 1999). Despite the area being under Pedi control, there were a number of mission stations in the area belonging to the Berlin Missionary Society. The first mission station was build at Kchalatlolu (1861), followed by Bothsabelo (1865), Lobethal (1877), Arkonh (1877), Patametsane (1877) (Van der Merwe, 1975). After the fall of Sekhukhune's capital a missionary station at Thaba Mossegu (1880) was also built (Van der Merwe, 1975). This station is just south of the affected farms and may hold some historical value.

As for the First or Second Anglo-Boer Wars this area saw no major battles. In 1902, following the Second Anglo-Boer War, a conference was held at Schoonoord (on one of the affected farms) between

the African communities and the British Colonial Administration to discuss land redistribution (Delius, 2007). Nothing came of this conference and in 1950 the area was transformed into the Lebowa Homeland and was given self governing status in 1973 (Delius, 2007). In the late 1960s the Lebowa/Bokoni mine was built by Anglo-Gold in the area and is still operating today (Ntrama, 2006). Several small settlements or mining villages are also associated with the mine.

2.2. Archival research

Archival research seems to suggest that most of the affected farms were owned by black communities some of which were already set out for prospecting and mining by the government.

The first reference to the farm Schoonoord 462 can be found in 1885 when the supposed owner, Mr. William Fraser, enquires about compensation since he was unaware of the fact that most of the farm Schoonoord was already occupied by a black community (SS 1139 R6199/85). Following the Schoonoord conference, mentioned above, the farm was expropriated in 1902 (CS 181 15494/02) and finally in 1903 the title deed was transferred from Mr. Fraser to the government (CS 366 8533/03; LD 159 AG54144/02). This area was then handed over to the Native Commission (SNA 49 NA1722/02) and in 1906 Mr. Rathagane was appointed as Native Chief (SNA 310 NA595/06) after which Mr. D.R. Hunt was appointed Native Commissioner at Schoonoord in 1907 (LD 746 AG2610/04). In 1909 the first application for a prospecting permit was sent to the secretary of mines by Mr. T. Liversage to prospect on several farms in the area, one of which was Schoonoord (SNA 450 NA3983/09). It is uncertain whether a prospecting permit was in fact issued.

The only information available for Koppieskraal 475 was that it was first registered to a Mr. G.C. Meyer in 1891 (SS 3043 R12313/91) whereas the only information for the farm Diamand 422 indicates that it was reclaimed for settlement purposes in 1945 (HKN 1/1/146 28N2/11/3(3)).

The first entry found for the farm Middelpunt 420 dates to 1886 when a Mr. Steenkamp sent in a request to the government regarding two of his farms (SS 1169 R629/86). He requested that he keep his farm Maandagshoek in exchange for his other farm Middelpunt which at this time seems to have been set out by the government for possible mineral prospecting purposes. Prospecting on the farm Middelpunt 420 as well as the farms Brakfontein 464 and Klipfontein 465 commenced from 1937 (NTS 6849 46/319) until 1957 (NTS 6902 345/319(5)). Reference is also given to the housing of black communities on the farms Middelpunt and Klipfontein with the construction of boreholes and ‘Native’ Mission schools from the 1930s onwards (NTS 2823 247/302; NTS 7119 438/323; NTS 7107 241/323; NTS 1963 T20583). In 1964, however, the farm Middelpunt was opened for mining and in 1965 the Atok mines opened its doors also building family quarters on the farm for all its black employees (BAO 10155 D52/1608/68; BAO 2829 C32/3/2697).

The farm Maandagshoek then again appear in the records in 1896 when the superintendent of “*naturellezaken*”, Mr. D. W. Hoffmans requested the housing of ten black households on his farm Maandagshoek (SS 0 R2801/96). It also seems, however, that the Maandagshoek farm had some mineral value since Mr. Andries Lombaard found evidence of platinum for the first time in 1924 (Jacobs, 2006). This discovery initiated the explorations of the geologist, Hans Merensky, and it also saw the construction of the first smelter on the farm Klipfontein (Jacobs, 2006). In 1944/45 Maandagshoek farm

was, however, reclaimed for settlement purposes (HKN 1/1/94 26N2/11/3(5) and in 1965 a missionary hospital was built on the farm grounds (THD 4 10/2/99).

The farm Paschaskraal 466 also seems to have been set out for mining purposes from 1964 to 1970, although no other information is available for the earlier history of this farm (BAO 10157 D52/1608/143).

The farms Surbiton 115 and Twickenham 114 both also seem to have been occupied by black communities already since the early 20th century. The first reference given to the farm Surbiton dates to 1927 when ownership of the farm was transferred from the Transvaal Estate and Development Company Ltd. to the Minister of Native Affairs in trust for the Bapedi tribe who already stayed on the farm (URU 947 3545). The farm Twickenham also seems to have belonged to the Native Trust under which boreholes and schools were constructed in the 1940s to 1960s (BAO 1/2034 D48/1608/97/1; NTS 10963 T220563)

There is, unfortunately, no records for the farms Blauwbloemetjeskloof 428 and Umkoanestad 419, however these two farms are very closely situated to the above mentioned farms and therefore may also have been used for mining purposes or settlement for local black communities.

2.3. HIA reports on the directly affected area:

Huffman, T.N. & Schoeman, M.H. 2001. *Scoping Study for the Proposed Water Supply Pipeline to the Planned Twickenham Hackney Paschaskraal Platinum Mine*. An unpublished report by Archaeological Resources Management on file at SAHRA as: 2001-SAHRA-0097.

Küsel, U. 2003. *Cultural Resources Assessment of 14.7 km 132 kV Line for Twickenham Substation Steelpoort District*. An unpublished report by African Heritage Consultants CC on file at SAHRA as: 2003-SAHRA-0111.

Pistorius, J.C.C. 2004. *A Heritage Impact Assessment Study for the Proposed New Optimum Colliery on the Farm Schoonoord 164 IS*. An unpublished report on file at SAHRA as: 2004-SAHRA-0037.

Roodt, F. 2002. *Lebowa Platinum Mines: Atok Lepelle Open Cast Mine Merensky and Ug2 Reefs Limpopo Province*. An unpublished report by R & R Cultural Resource Consultants on file at SAHRA as: 2002-SAHRA-0107.

Roodt, F. 2002. *Lebowa Platinum Mines Ltd - Atok Section (LPM-A) New Tailings Dam Amendment to the Environmental Management Programme Report (EMPR-A)*. An unpublished report by R & R Cultural Resource Consultants on file at SAHRA as: 2002-SAHRA-0178.

Schoeman, M.H. & van Doornum, B. 2001. *Archaeological Assessment for the Twickenham Hackney Paschaskraal Platinum Mine, Northern Province*. An unpublished report by Archaeological Resources Management on file at SAHRA as: 2001-SAHRA-0089.

Van Schalkwyk, J.A. 2002. *A Survey of Cultural Resources for the Proposed New Twickenham-Paschaskraal-Hackney Mining Development, Sekhukhune District, Northern Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2002-SAHRA-0024.

Van Schalkwyk, J.A. 2002. *A Survey of Cultural Resource in the Construction Camp Site, Twickenham-Paschaskraal-Hackney Mining Development, Sekhukhune District, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2002-SAHRA-0046.

Van Schalkwyk, J.A. 2002. *A Survey of Cultural Resources for the Senior Construction Camp, Twickham-Paschaskraal-Hackney Mining Development, Sekhukhune District, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2002-SAHRA-0099.

Van Schalkwyk, J.A. 2002. *A Survey of Cultural Resources in the Proposed Host Areas of the Twickenham-Hackney-Paschaskraal-Mining Development Report*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2002-SAHRA-0010.

Van Schalkwyk, J.A. 2003. *Documentation of Historical Sites in the Twickenham-Hackney Mine Development, Sekhukhune District, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2003-SAHRA-0014.

Van Schalkwyk, J.A. 2003. *Documentation of Historical Sites in the Twickenham Platinum Mine Development, Sekhukhune District, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2003-SAHRA-0088.

Van Schalkwyk, J.A. & Moifatswane, S. 2002. *Documentation of a Historical Site on the Farm Surbiton, in the Twickenham-Paschaskraal-Hackney Mining Area, Sekhukhune District, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2002-SAHRA-0170.

2.4. HIA reports on the larger area:

Calabrese, J.A. & Quinney, P.S. 1998. *Archaeological Survey of Steelpoort Pumped Storage Scheme, Upper and Lower Reservoir Areas*. An unpublished report by Archaeological Resources Management on file at SAHRA as: 1998-SAHRA-0066.

Murimbika, M. 2005. *Olifants River Water Resources Development Project (ORWRDP) Environmental Impact Assessment (12/12/20/553) Infrastructure Components: Cultural Heritage Assessment, Specialist Study*. An unpublished report by Nzumbululo Heritage Solutions on file at SAHRA as: 2005-SAHRA-0094.

Roodt, F. 2006. *Mining Development on the Farm Maandagshoek 254 KT, Tubatse Municipal Area, Sekhukhune District*. An unpublished report by R & R Cultural Resource Consultants on file at SAHRA as: 2006-SAHRA-0083.

Van der Ryst, M. & Kruger, N. 2007. *Specialist Archaeological Report: Maandagshoek 254 KT*. An unpublished report by the University of South Africa on file at SAHRA as: 2007-SAHRA-0401.

Van Schalkwyk, J.A. 2000. *Preliminary Archaeological Impact Assessment for the Maandagshoek Amplats Platinum Project*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2000-SAHRA-0004.

Van Schalkwyk, J.A. 2001. *A Survey of Cultural Resources in Five Locations of the Steelpoort Area of Sekhukhuneland, Northern Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2001-SAHRA-0041.

Van Schalkwyk, J.A. 2004. *Archaeological/ Historical Significance of the Sekhukhune Valley*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2004-SAHRA-0167.

Van Schalkwyk, J.A. 2007. *Heritage Impact Scoping Report for the Planned Steelpoort Integration Project, Limpopo Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2007-SAHRA-0329.

Van Schalkwyk, J.A. 2007. *Heritage Impact Assessment for the Planned Steelpoort Pumped Storage Station, Lydenburg Municipal District, Mpumalanga Province*. An unpublished report by the National Cultural History Museum on file at SAHRA as: 2007-SAHRA-0035.

3. DESCRIPTION OF THE PROPERTY OR AFFECTED ENVIRONMENT

3.1. ORWRDP Phase 2B

3.1.1. Details of the area surveyed

3.1.1.1. Location Data

The proposed ORWRDP Phase 2B alignment starts on the Farm Pruissen and continues southwards next to the R518 road through a shallow poort to the west of Immelpan and Pruissen Hills. On the Farm Doornfontein the alignment veers south away from the R518 and follows a (undesignated) gravel road across the plain to Roodesloot Hill at the south-east from where it crosses the Rooisloot Stream following the D2858 secondary road. It passes south of Kromdraai Hill towards Immelpan railway siding still adjacent to the D2858 road. From there it follows the D885 road through the Or Quarry mining area and passes to the south of Leo and Springbok mines as indicated on the map. On the Farm Singapore it veers due south of the D885 road following the D2015 road from the junction. From here the alignment passes between the Grasvallei mine on the west and Ga-Mampuru Village on the east and continues through Hinlopen Village along the D2015 road to the junction with the extension of the D3600 road. From this junction it follows the D4356 road to the turn-off at the Flag Bosheilo Dam where it joins at the pump station.

The proposed alignment crosses the following farms:

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2B	Arabie 685 KS	RE	2B	Malgas 154 KS	RE/2
2B	Hindostan 680 KS	RE/1	2B	Malgas 154 KS	1
2B	Tambootieboom 686 KS	2	2B	Brakfontein 152 KS	5
2B	Roodewal 678 KS	1	2B	Brakfontein 152 KS	RE/3
2B	Roodewal 678 KS	RE	2B	Brakfontein 152 KS	9
2B	Gaasterland 677 KS	1	2B	Brakfontein 152 KS	2
2B	Gaasterland 677 KS	RE	2B	Brakfontein 152 KS	RE

2B/BP1	Hinloopen 647 KS	RE	2B	Brakfontein 152 KS	13
2B	Elandskraal 936 KS		2B	Brakfontein 152 KS	12
2B	Mutue Fides 648 KS		2B/BP2	Brakfontein 152 KS	RE/4
2B	Weltevreden 646 KS	1	2B	Brakfontein 152 KS	10
2B	Weltevreden 646 KS	3	2B	Brakfontein 152 KS	11
2B	Weltevreden 646 KS	RE/2	2B	Eenzaam 148 KS	RE
2B	Tygerpad 633 KS	1	2B	Eenzaam 148 KS	1
2B/BP4	Vooruitgang 634 KS	1	2B	Rietlaagte 149 KS	RE
2B	Vooruitgang 634 KS	RE	2B	Rietlaagte 149 KS	RE/2
2B	Restaurant 588 KS	RE/1	2B	Rietlaagte 149 KS	RE/1
2B	Restaurant 588 KS	RE	2B	Kalkvalley 151 KS	1
2B	Restaurant 588 KS	3	2B	Kalkvalley 153 KS	RE
2B	Foleys Rust 583 KS	RE	2B	Kromdraai 129 KS	1
2B/BP5	Klipfontein 587 KS	RE	2B	Kromdraai 129 KS	2
2B	Mokkafontein 584 KS	1	2B	Kromdraai 129 KS	RE
2B	Mokkafontein 584 KS	RE	2B	Roodebult 128 KS	RE
2B	Singapore 585 KS	RE/1	2B	Roodesloot 130 KS	RE
2B/BP3	Singapore 585 KS	RE	2B	Roodesloot 130 KS	2
2B	Singapore 585 KS	2	2B	Groothoek 99 KS	3
2B	Singapore 585 KS	3	2B	Doornfontein 98 KS	3
2B	Doornboom 586 KS	RE	2B	Doornfontein 98 KS	9
2B	Calais 563 KS	RE	2B	Doornfontein 98 KS	8
2B	Calais 563 KS	1	2B	Doornfontein 98 KS	1
2B	Hoogte 155 KS	4	2B	Pruissen 48 KS	RE
2B	Malgas 154 KS	RE	2B	Pruissen 48 KS	2
BP9	Mooihoek 225	1	BP10	Surbiton 115	RE
BP6	Doornbosh 294	5	BP7 & BP8	Derde Gelid 278	RE
BP11	Twyfelaar 119	RE			

3.1.1.2.Location Map

Figure 1 shows the proposed ORWRDP Phase 2B alignment.

3.1.1.3.Area surveyed

The area surveyed corresponds with the indicated alignment and encompasses a linear area 40m wide which is also indicated as the construction footprint of the proposed pipe line development.

3.2. ORWRDP Phase 2C

3.1.1 Details of the area surveyed

3.1.1.1 Location Data

The proposed Phase 2C alignment of the ORWRDP II starts at the De Hoop Dam (currently under construction) and from there follows the R555 road in a generally northerly direction. At the southern boundary of the Farm Aapjesboom at the R555, the alignment leaves the road and follows the Steelpoort River, somewhat to the west of the R555, to the portion boundary of Portions 366/1 and 366/2 at the R555 road, south east of Ga-Malekana Village. From here it again follows the R555. It passes between Mooimeisiesfontein Hill and Tweekop Hill as well as between Kennedy's Vale Hill and Ga-Mampuru Village. Still along the R555 road, it passes between Mokome Hill and Lavino Chrome Mine. Approximately 1,5km (along the R555 road) from Steelpoort Town it veers north west along an undesignated gravel road and bypasses the town to the north west thereof where it joins the Phase 2D alignment at a gravel road north of Steelpoort at the boundary between the Farm Vredelus and Portion 337/10 of the Farm Goudmyn.

The proposed alignment passes over the following farms:

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2C	De Hoop 886 KS	RE	2C	Kennedy's Vale 361 KT	19
2C	De Hoop 886 KS	1	2C	Kennedy's Vale 361 KT	22
2C	Aapjesboom 884 KS	RE	2C	Kennedy's Vale 361 KT	29
2C	Aapjesboom 884 KS	1	2C	Kennedy's Vale 361 KT	27
2C	Steelpoort Park 366 KT	2	2C	Kennedy's Vale 361 KT	8
2C	Steelpoort Park 366 KT	11	2C	Spitskop 333 KT	30
2C	Steelpoort Park 366 KT	1	2C	Spitskop 333 KT	11
2C	Belvedere 362 KT	33	2C	Spitskop 333 KT	3
2C	Belvedere 362 KT	34	2C	Spitskop 333 KT	2
2C	Belvedere 362 KT	21	2C	Spitskop 333 KT	1
2C	Belvedere 362 KT	17	2C	Annex Grootboom 335 KT	1
2C	Belvedere 362 KT	16	2C	Annex Grootboom 335 KT	RE

2C	Belvedere 362 KT	15	2C	Grootboom 336 KT	3
2C	Belvedere 362 KT	3	2C	Grootboom 336 KT	RE
2C	Belvedere 362 KT	14	2C	Grootboom 336 KT	2
2C	Belvedere 362 KT	2	2C	Grootboom 336 KT	1
2C	Belvedere 362 KT	25	2C	Grootboom 336 KT	4
2C	Belvedere 362 KT	22	2C	Goudmyn 337 KT	RE
2C	Belvedere 362 KT	6	2C	Goudmyn 337 KT	25
2C	Kennedy's Vale 361 KT	25	2C	Goudmyn 337 KT	10
2C	Kennedy's Vale 361 KT	28	2C	Goudmyn 337 KT	22
2C	Kennedy's Vale 361 KT	9	2C	Goudmyn 337 KT	28

3.1.1.2 Location Map

Figure 2 shows the proposed ORWRDP Phase 2C alignment.

3.1.1.3 Area surveyed

The area surveyed corresponds with the indicated alignment and encompasses a linear area 40m wide which is also indicated as the construction footprint of the proposed pipe line development.

3.3. ORWRDP Phase 2D

3.2.1 Details of the area surveyed

3.2.1.1 Location Data

From where it starts at the join with the Phase 2C alignment just north of Steelpoort Town, the ORWRDP Phase 2D proposed alignment proceeds northwards along an undesignated gravel road running at the foot of Doornbosh and Lekgobo Hills on the escarpment. It passes between Winterveld Mine and Doornbosh Village along this road and then veers north west at the northern boundary of the Farm Doornbosh to cross the Seduku and Moopetsi Streams on the Farm Hendriksplaats before passing to the west of the part of Driekop Village situated west of the R37 road. It passes through Mooihoek Poort parallel, but to the west of, the R37 road and crosses the D4169 road at Dilokong Chrome Mine before turning abruptly east to cross the R37 road and end just south of Motlolo Village.

The proposed alignment passes over the following farms:

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2D	Winterveld 293 KT		2D	Hendriksplaats 281 KT	RE
2D	Doornbosch 294 KT	2	2D	Derde Gelid 278 KT	RE
2D	Doornbosch 294 KT	4	2D	Derde Gelid 278 KT	2
2D	Doornbosch 294 KT	RE	2D	Derde Gelid 278 KT	1
2D	Doornbosch 294 KT	5	2D	Mooihoek 255 KT	2
2D	Doornbosch 294 KT	1	2D	Mooihoek 255 KT	RE
2D	Doornbosch 294 KT	6	2D	Mooihoek 255 KT	RE/1
2D	Apiesboomen 295 KT	RE			

3.2.1.2 Location Map

Figure 3 shows the proposed ORWRDP Phase 2D alignment.

3.2.1.3 Area surveyed

The area surveyed corresponds with the indicated alignment and encompasses a linear area 40m wide which is also indicated as the construction footprint of the proposed pipe line development.

Figure 3. ORWRDP Phase 2D alignment.



3.4. ORWRDP Phase 2E

3.3.1 Details of the area surveyed

3.3.1.1 Location Data

The proposed alignment of the ORWRDP Phase 2E repeats the alignment of ORWRDP Phase 2D from just south of Motlolo Village and from there it follows the R37 road north westwards, after the road had been crossed. Approximately 850m south east of the boundary between the Farms Groothoek and Twyfelaar at the R37 road the proposed alignment veers west-north-westwards from the R37 to pass to the south of the prominent hill on the Farm Twyfelaar. At the boundary of the Farm Clapham, the alignment turns due north following the farm boundary, to pass around the base of Matadi Hill on the north and east thereof. From the hill it follows an undesignated gravel road to intersect with the R37 road, after crossing the Tlopeng Stream, where it ends.

The proposed alignment passes over the following farms:

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2E	Groothoek 256 KT	RE	2E	Clapham 118 KT	RE
2E	Twyfelaar 119 KT	RE	2E	Forest Hill 117 KT	RE


3.3.1.2 Location Map

Figure 4 shows the proposed ORWRDP Phase 2E alignment.

3.3.1.3 Area surveyed

The area surveyed corresponds with the indicated alignment and encompasses a linear area 40m wide which is also indicated as the construction footprint of the proposed pipe line development.

Figure 4. ORWRDP Phase 2E alignment.



3.5. ORWRDP Phase 2F

3.4.1 Details of the area surveyed

3.4.1.1 Location Data

The proposed ORWRDP Phase 2F alignment starts on the R37 road directly west of the Makopi High School in Ga-Kgwete Village and follows the road in a north westerly direction. South west of Forest Hill it follows an undesignated gravel road in a westerly direction from the junction with the R37 to cross the Moopetsi River at the junction with the extension of the D4220 road and from there across the Motse River to the west and past the northern foot of Morapeng Hill still following the gravel road. On the Farm Twickenham it turns north west at a road junction with another undesignated gravel road. From here it follows this road past Gangadza Senior Primary School after which it veers away from the road to proceed parallel, but to the east thereof. This parallel alignment turns west north west on the Farm Klipfontein and proceeds to again join up at the boundary of the Farm Umkoanestad. From here the alignment follows the road for a short distance before veering due west at the northern boundary of the Farm Middelpunt from where it approximately follows this boundary to the Zeekoegat road where it turns south to cross the Olifants River and end on Portion 475/1 of the Farm Koppieskraal.

The proposed alignment passes over the following farms:

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2F	Surbiton 115 KT	RE	2F	Middelpunt 420 KS	RE
2F	Twickenham 114 KT	RE	2F	Diamand 422 KS	RE
2F	Paschaskraal 466 KS	1	2F	Schoonoord 462 KS	RE
2F	Klipfontein 465 KS	RE	2F	Blauwbloemetjieskloof 428 KS	RE
2F	Brakfontein 464 KS	RE	2F	Dal Josaphat 461 KS	RE
2F	Umkoanestad 419 KS	RE	2F	Locatie van M'Phatlele 457 KS / Koppieskraal 475 KS	RE

3.4.1.2 Location Map

Figure 5 shows the proposed ORWRDP Phase 2F alignment.

3.4.1.3 Area surveyed

The area surveyed corresponds with the indicated alignment and encompasses a linear area 40m wide which is also indicated as the construction footprint of the proposed pipe line development.

3.6. ORWRDP Phase 2B-F associated borrow pits

3.6.1. ORWRDP II Proposed Borrow Pit 1

4.6.1.1 Details of the area surveyed

The proposed ORWRDP II Borrow Pit 1 is associated with the proposed Phase 2B alignment and is located just north west of Hindlopen Village on the D2015 road close to the northern border of the Farm Elandskraal.

4.6.1.2 Location Data

Farm Elandskraal 936.

4.6.1.3 Location Map

Refer Figure 6 for locality map of Borrow Pit 1.

4.6.1.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 7 for a transect log plot indicating the survey.

Figure 6. Locality map of Borrow Pit 1.




Figure 7. Transect log plot indicating the survey.



3.6.2. *ORWRDP II Proposed Borrow Pit 2*

4.6.2.1 Details of the area surveyed

The proposed Borrow Pit 2 forms part of the Phase 2B alignment on the ORWRDP and is located north west of Immelpan siding on the D2658 road on Portion 152/4 of the Farm Brakfontein.

4.6.2.2 Location Data

Farm Brakfontein 152.

4.6.2.3 Location Map

Refer Figure 8 for locality map of Borrow Pit 2.

4.6.2.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 9 for a transect log plot indicating the survey.

Figure 8. Locality map of Borrow Pit 2.



Figure 9. Transect log plot indicating the survey.



3.6.3. *ORWRDP II Proposed Borrow Pit 3*

4.6.3.1 Details of the area surveyed

The proposed Borrow Pit 3 form part of the ORWRDP Phase 2B alignment and is located in the south east corner of the junction between the D885 and D2015 roads.

4.6.3.2 Location Data

Farm Singapore 585.

4.6.3.3 Location Map

Refer Figure 10 for locality map of Borrow Pit 3.


4.6.3.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 11 for a transect log plot indicating the survey.

Figure 10. Locality map of Borrow Pit 3.



Figure 11. Transect log plot indicating the survey.



3.6.4. ORWRDP II Proposed Borrow Pit 4

4.6.4.1 Details of the area surveyed

The proposed ORWRDP Borrow Pit 4 is not directly adjacent to any of the Phase alignments and is located on the D2659 road on the Farm Vooruitgaan 634 approximately 2.8 km north east of the junction between the D2659 and D2-15 roads.

4.6.4.2 Location Data

Farm Vooruitgaan 634.

4.6.4.3 Location Map

Refer Figure 12 for locality map of Borrow Pit 4.

4.6.4.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 13 for a transect log plot indicating the survey.

Figure 12. Locality map of Borrow Pit 4.





Figure 13. Transect log plot indicating the survey.



3.6.5. *ORWRDP II Proposed Borrow Pit 5*

4.6.5.1 Details of the area surveyed

The proposed Borrow Pit 5 is associated directly with the ORWRDP Phase 2B alignment and is located on the D2015 road just north of the farm boundary between the farms Klipfontein 587 and Restourant 588.

4.6.5.2 Location Data

Farm Klipfontein 587.

4.6.5.3 Location Map

Refer Figure 14 for locality map of Borrow Pit 5.


4.6.5.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 15 for a transect log plot indicating the survey.

Figure 14. Locality map of Borrow Pit 5.



Figure 15. Transect log plot indicating the survey.



3.6.6. ORWRDP II Proposed Borrow Pit 6

4.6.6.1 Details of the area surveyed

Proposed Borrow Pit 6 is part of the ORWRDP Phase 2D alignment and is located on an undesignated road where it crosses Portion 294/5 of the Farm Doornbosh north-north east of Lekgobo Hill.

4.6.6.2 Location Data

Farm Doornbosh 294.

4.6.6.3 Location Map

Refer Figure 16 for locality map of Borrow Pit 6.

4.6.6.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 17 for a transect log plot indicating the survey.

Figure 16. Locality map of Borrow Pit 6.



Figure 17. Transect log plot indicating the survey.



3.6.7. ORWRDP II Proposed Borrow Pit 7

4.6.7.1 Details of the area surveyed

The proposed ORWRDP Borrow Pit 7 is not directly adjacent to any of the proposed Phase alignments and is located in the south western corner of the Farm Derde Gelid 278 at the south western foot Derde Gelid Hill on the southern bank of the Mokgowane River.

4.6.7.2 Location Data

Farm Derde Gelid 278.

4.6.7.3 Location Map

Refer Figure 18 for locality map of Borrow Pit 7.

4.6.7.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 19 for a transect log plot indicating the survey.

Figure 18. Locality map of Borrow Pit 7.





Figure 19. Transect log plot indicating the survey.



3.6.8. *ORWRDP II Proposed Borrow Pit 8*

4.6.8.1 Details of the area surveyed

The proposed Borrow Pit 8 is not directly adjacent to any of the proposed ORWRDP Phase alignments and is located a short distance east south east of Borrow Pit 7 next to the R37 road.

4.6.8.2 Location Data

Farm Derde Gelid 278.

4.6.8.3 Location Map

Refer Figure 20 for locality map of Borrow Pit 8.


4.6.8.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 21 for a transect log plot indicating the survey.

Figure 20. Locality map of Borrow Pit 8.



Figure 21. Transect log plot indicating the survey.



3.6.9. ORWRDP II Proposed Borrow Pit 9

4.6.9.1 Details of the area surveyed

The proposed Borrow Pit 9 is associated with the ORWRDP Phase 2D alignment and is located just west of the R37 where the portion boundary between the Farm Mooihoek 225 and Portion 225/1 crosses the road in the Mooihoek Poort.

4.6.9.2 Location Data

Farm Mooihoek 225/1.

4.6.9.3 Location Map

Refer Figure 22 for locality map of Borrow Pit 9.


4.6.9.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 23 for a transect log plot indicating the survey.

Figure 22. Locality map of Borrow Pit 9.



Figure 23. Transect log plot indicating the survey.



3.6.10. ORWRDP II Proposed Borrow Pit 10

4.6.10.1 Details of the area surveyed

The proposed Borrow Pit 10 is associated with the ORWRDP Phase 2F alignment and is located at the Moopetsi River just before the confluence with the Motse River.

4.6.10.2 Location Data

Farm Surbiton 115.

4.6.10.3 Location Map

Refer Figure 24 for locality map of Borrow Pit 10.


4.6.10.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 25 for a transect log plot indicating the survey.

Figure 24. Locality map of Borrow Pit 10.



Figure 25. Transect log plot indicating the survey.



3.6.11. ORWRDP II Proposed Borrow Pit 11

4.6.11.1 Details of the area surveyed

The proposed Borrow Pit 11 is associated with the ORWRDP Phase 2F alignment and consists of a linear area, approximately 1.2km long, in the bed of the Thlopeng River at the north eastern foot of Clapham Hill.

4.6.11.2 Location Data

Farm Twyfelaar 119.

4.6.11.3 Location Maps

Refer Figure 26 for locality map of Borrow Pit 11.


4.6.11.4 Area surveyed

The area surveyed corresponds directly with the indicated proposed borrow pit area. Refer Figure 27 for a transect log plot indicating the survey.

Figure 26. Locality map of Borrow Pit 11.



Figure 27. Transect log plot indicating the survey.



4. SURVEY METHODOLOGY

The indicated proposed alignments were surveyed on foot by between three and four two man teams consisting of a suitably accredited archaeologist and an experienced field hand over a period of two weeks from 3 – 17 October 2010. The alignments were plotted on hand held GPS receivers and team members leap-frogged each other to cover the total alignment. The indicated construction impact is a 40m wide linear area along the alignment which mostly followed an existing road, or other existing infrastructure such as a power line or other pipeline. To ensure the coverage of the construction footprint team members employed a survey strategy of parallel transects where applicable and necessary. All transects were recorded as track logs and are enclosed as Appendix B.

No sampling was conducted. Where applicable cultural materials were collected from the surface and grouped for photography, but were left on site in all cases.

No restrictions to the study were encountered. In some areas the alignment route had previously been disturbed by natural processes and other infrastructure development. Where these disturbances were encountered they were taken to indicate possible exposed sub-surface indications of heritage resources in the area. On account of the season vegetation was almost non-existent and provided ideal conditions for observation.

For location and transect purposes, in addition to compasses and printed maps, Garmin MAP60sx hand held GPS receivers with GARMAP SAS Topo TMC base maps were used. No observations were recorded unless the instrument indicated accuracy higher than 4m. Location information was plotted and

manipulated with Garmin MAPSource version 6.16.2 and Arcview version 8.1 software. Photography was with CANON A30 digital cameras and images were managed using Microsoft Office 2007 Picture Manager.


5. DESCRIPTION OF SITES

5.1. Site ORW 1 ORWRDP Phase 2C

6.1.1 Location of site

S24 54 47.2 E29 59 03.1 – Refer Figure 28 for locality map, and Appendix B for survey transect logs.

Figure 28. Locality map for site ORW 1, 3 and 4.



6.1.2 Description of site

6.1.2.1 Type of site

- Potshard scatter

6.1.2.2 Site category

- Late Iron Age

6.1.2.3 Context

- Disturbed

6.1.2.4 Cultural affinities, approximate age and significant features of the site

6.1.2.5 Extent

- Approximately 30m in diameter, no directional alignment.

6.1.2.6 Depth and stratification of the site

- Surface scatter only, no associated deposits

6.1.2.7 Possible sources of information about past environments

- None

6.1.2.8 Photographs and diagrams

- Refer Figure 29.

6.1.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.1.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non diagnostic potsherds were found at the site (Fig. 30).

6.1.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.1.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.1.7 Recommendations

6.1.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.1.7.2 Proposals for protection or mitigation

- None.

6.1.7.3 Action/s required at the site

- None

Figure 29. Site ORW 1.





Figure 30. Artifacts at Site ORW 1.




5.2. Site ORW 2 ORWRDP Phase 2C

6.2.1 Location of site

S24 54 47.2 E29 59 07.3 – Refer Figure 31 for locality map, and Appendix B for survey transect logs.

Figure 31. Locality map for site ORW 2.



6.2.2 Description of site

6.2.2.1 Type of site

- Potshard scatter.

6.2.2.2 Site category

- Late Iron Age

6.2.2.3 Context

- Disturbed.

6.2.2.4 Cultural affinities, approximate age and significant features of the site

6.2.2.5 Extent

- Approximately 30m in diameter.

6.2.2.6 Depth and stratification of the site

- Surface occurrence only, no evidence for any deposits.

6.2.2.7 Possible sources of information about past environments

- None.

6.2.2.8 Photographs and diagrams

- Refer Figure 32.

6.2.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.2.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic potsherds were found at the site (Fig. 33).

6.2.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.2.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.2.7 Recommendations

6.2.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.2.7.2 Proposals for protection or mitigation

- None.

6.2.7.3 Action/s required at the site

- None

Figure 32. Site ORW 2.



Figure 33. Artifacts at Site ORW 2.



5.3. Site ORW 4 ORWRDP Phase 2C

6.3.1 Location of site

S24 53 19.1 E30 01 31.0 – Refer Figure 28 for locality map, and Appendix 2 for survey transect logs.

6.3.2 Description of site

6.3.2.1 Type of site

- Potshard scatter.

6.3.2.2 Site category

- Late Iron Age.

6.3.2.3 Context

- Primary but severely weathered.

6.3.2.4 Cultural affinities, approximate age and significant features of the site

6.3.2.5 Extent

- Low density scatter over an area of approximately 30m in circumference.

6.3.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.3.2.7 Possible sources of information about past environments

- None.

6.3.2.8 Photographs and diagrams

- Refer Figure 34 for a general view of the site.

6.3.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.3.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic ceramics (Fig. 35).

6.3.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.3.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.3.7 Recommendations

6.3.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.3.7.2 Proposals for protection or mitigation

- None.

6.3.7.3 Action/s required at the site

- None

Figure 34. Site ORW 4.




Figure 35. Artefacts at site ORW4.



5.4. Site ORW 5 ORWRDP Phase 2C

6.4.1 Location of site

S24 51 06.5 E30 04 32.5 – Refer Figure 36 for locality map, and Appendix 2 for survey transect logs.

Figure 36. Locality map for site ORW 5, 6, 7 and 8.



6.4.2 Description of site

6.4.2.1 Type of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.4.2.2 Site category

- Recent modern.

6.4.2.3 Context

- Primary.

6.4.2.4 Cultural affinities, approximate age and significant features of the site

6.4.2.5 Extent

- In total an area of approximately 40x40m is covered by the ruined homestead.

6.4.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.4.2.7 Photographs and diagrams

- Refer Figure 37 for site photograph.

6.4.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.4.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.4.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.4.6 Recommendations

6.4.6.1 Proposals for protection or mitigation


- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.
- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature

(nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.4.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 37. General photograph of Site ORW 5.



5.5. Site ORW 6 ORWRDP Phase 2C

This structure was initially recorded and subsequently assessed to fall outside of the provisions of the NHRA, i.e. younger than 60 years and with no indicated heritage value.

No recommendations for mitigation are applicable and no actions are required.

5.6. Site ORW 7 ORWRDP Phase 2C

This structure was initially recorded and subsequently assessed to fall outside of the provisions of the NHRA, i.e. younger than 60 years and with no indicated heritage value.

No recommendations for mitigation are applicable and no actions are required.

5.7. Site ORW 8 ORWRDP Phase 2C

This structure was initially recorded and subsequently assessed to fall outside of the provisions of the NHRA, i.e. younger than 60 years and with no indicated heritage value.

No recommendations for mitigation are applicable and no actions are required.

5.8. Site ORW 10 ORWRDP Phase 2C

6.8.1 Location of site

S24 44 38.6 E30 11 02.6 – Refer Figure 38 for locality map, and Appendix 2 for survey transect logs.

Figure 38. Locality map for site ORW 9 and 10.



6.8.2 Description of site

6.8.2.1 Type of site

- Potshard scatter

6.8.2.2 Site category

- Late Iron Age

6.8.2.3 Context

- Disturbed

6.8.2.4 Cultural affinities, approximate age and significant features of the site

6.8.2.5 Extent

- Approximately 80m in diameter, no directional alignment.

6.8.2.6 Depth and stratification of the site

- Due to the disturbance by previous ploughing the sub-terranean features of the site has been destroyed. Some indications of possible grain bin foundations and habitational structures were observed, but none are intact.

6.8.2.7 Possible sources of information about past environments

- None

6.8.2.8 Photographs and diagrams

- Refer Figure 39.

6.8.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.8.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non- diagnostic potsherds were found at the site (Fig. 40). Although some fragments showed possible decoration, this was not sufficient to ascribe the site to a particular ceramic facies or tradition.

6.8.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.8.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.8.7 Recommendations

6.8.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.8.7.2 Proposals for protection or mitigation

- None.

6.8.7.3 Action/s required at the site

- None

Figure 39. Site ORW 10.



Figure 40(a). Artefacts at Site ORW 10.



Figure 40(b). Artefacts at Site ORW 10.



5.9. Site ORW 11 ORWRDP Phase 2D

6.9.1 Location of site

S24 38 58.6 E30 10 56.9 – Refer Figure 41 for locality map, and Appendix 2 for survey transect logs.

Figure 41. Locality map for site ORW 11 and 12.



6.9.2 Description of site

6.9.2.1 Type of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.9.2.2 Site category

- Recent modern.

6.9.2.3 Context

- Primary.

6.9.2.4 Cultural affinities, approximate age and significant features of the site

6.9.2.5 Extent

- In total an area of approximately 50 m in diameter is covered by the ruined homestead.

6.9.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.9.2.7 Photographs and diagrams

- Refer Fig. 42 for site photograph.

6.9.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.9.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.9.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.9.6 Recommendations

6.9.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is,


therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.

- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.9.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 41. General photograph of Site ORW 11.



5.10.Site ORW 12 ORWRDP Phase 2D

6.10.1 Location of site

S24 38 49.5 E30 10 53.3 – Refer Figure 41 for locality map, and Appendix 2 for survey transect logs.

6.10.2 Description of site

6.10.2.1 Type of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.10.2.2 Site category

- Recent modern.

6.10.2.3 Context

- Primary.

6.10.2.4 Cultural affinities, approximate age and significant features of the site

6.10.2.5 Extent

- In total an area of approximately 50 m in diameter is covered by the ruined homestead.

6.10.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.10.2.7 Photographs and diagrams

- Refer Fig. 43 for site photograph.

6.10.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.10.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.10.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.10.6 Recommendations


6.10.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.
- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.10.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 43. General photograph of Site ORW 12.



6.11.2.2 Site category

- Recent modern.

6.11.2.3 Context

- Primary.

6.11.2.4 Cultural affinities, approximate age and significant features of the site

6.11.2.5 Extent

- In total an area of approximately 50 m in diameter is covered by the ruined homestead.

6.11.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.11.2.7 Photographs and diagrams

- Refer Fig. 45 for site photograph.

6.11.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.11.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.11.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.11.6 Recommendations

6.11.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in*

situ, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.

- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.11.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 45. General photograph of Site ORW 14.



5.12.Site ORW 15 ORWRDP Phase 2D

6.12.1 Location of site

S24 37 29.1 E30 10 12.4 – Refer Figure 44 for locality map, and Appendix 2 for survey transect logs.

6.12.2 Description of site

6.12.2.1 Type of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.12.2.2 Site category

- Recent modern.

6.12.2.3 Context

- Primary.

6.12.2.4 Cultural affinities, approximate age and significant features of the site

6.12.2.5 Extent

- In total an area of approximately 50 m in diameter is covered by the ruined homestead.

6.12.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.12.2.7 Photographs and diagrams

- Refer Fig. 46 for site photograph.

6.12.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.12.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.12.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.12.6 Recommendations


6.12.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.
- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.12.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 46. General photograph of Site ORW 15.




5.13.Site ORW 18 ORWRDP Phase 2D

6.13.1 Location of site

S24 32 08.6 E30 08 56.0 – Refer Figure 47 for locality map, and Appendix 2 for survey transect logs.

Figure 47. Locality map for Site ORW 17, 18, 19 and 20.



6.13.2 Description of site

6.13.2.1 Type of site

- Potshard scatter.

6.13.2.2 Site category

- Late Iron Age.

6.13.2.3 Context

- Primary – disturbed by ploughing.

6.13.2.4 Cultural affinities, approximate age and significant features of the site

6.13.2.5 Extent

- Low density scatter over an area of approximately 30m in diameter.

6.13.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.13.2.7 Possible sources of information about past environments

- None.

6.13.2.8 Photographs and diagrams

- Refer Figure 48 for a general view of the site.

6.13.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.13.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic ceramics (Fig. 49).

6.13.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.13.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.13.7 Recommendations

6.13.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.13.7.2 Proposals for protection or mitigation

- None.

6.13.7.3 Action/s required at the site

- None

Figure 48. Site ORW 18.





Figure 49. Artefacts at site ORW18.



5.14.Site ORW 19 ORWRDP Phase 2D

6.14.1 Location of site

S24 31 59.8 E30 08 49.7 – Refer Figure 47 for locality map, and Appendix 2 for survey transect logs.

6.14.2 Description of site

6.14.2.1 Type of site

- Potshard scatter.

6.14.2.2 Site category

- Late Iron Age.

6.14.2.3 Context

- Primary – disturbed by ploughing.

6.14.2.4 Cultural affinities, approximate age and significant features of the site

6.14.2.5 Extent

- Low density scatter over an area of approximately 30m in diameter.

6.14.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.14.2.7 Possible sources of information about past environments

- None.

6.14.2.8 Photographs and diagrams

- Refer Figure 50 for a general view of the site.

6.14.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.14.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic ceramics (Fig. 51). Some fragments of ceramic display graphite burnishing which might indicate an affinity with the Marateng facies.

6.14.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.14.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.14.7 Recommendations

6.14.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.14.7.2 Proposals for protection or mitigation

- None.

6.14.7.3 Action/s required at the site

- None

Figure 50. Site ORW 19.





Figure 51. Artefacts at site ORW 19.



5.15.Site ORW 20 ORWRDP Phase 2D

6.15.1 Location of site

S24 31 53.0 E30 08 53.8 – Refer Figure 47 for locality map, and Appendix 2 for survey transect logs.

6.15.2 Description of site

6.15.2.1 Type of site

- Potshard scatter.

6.15.2.2 Site category

- Late Iron Age.

6.15.2.3 Context

- Primary – disturbed by ploughing.

6.15.2.4 Cultural affinities, approximate age and significant features of the site

6.15.2.5 Extent

- Low density scatter over an area of approximately 30m in diameter.

6.15.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.15.2.7 Possible sources of information about past environments

- None.

6.15.2.8 Photographs and diagrams

- Refer Figure 52 for a general view of the site.

6.15.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.15.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic ceramics (Fig. 53).

6.15.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.15.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.15.7 Recommendations

6.15.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.15.7.2 Proposals for protection or mitigation

- None.

6.15.7.3 Action/s required at the site

- None

Figure 52. Site ORW 20.





Figure 53. Artefacts at site ORW 20.




5.16.Site ORW 24 ORWRDP Phase 2F

6.16.1 Location of site

S24 25 24.2 E30 03 58.3 – Refer Figure 54 for locality map, and Appendix 2 for survey transect logs.

Figure 54. Locality map: Site ORW 23 and 24.



6.16.2 Description of site

6.16.2.1 Type of site

- Potshard scatter.

6.16.2.2 Site category

- Late Iron Age.

6.16.2.3 Context

- Primary – disturbed by ploughing.

6.16.2.4 Cultural affinities, approximate age and significant features of the site

6.16.2.5 Extent

- Low density scatter over an area of approximately 30m in diameter.

6.16.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.16.2.7 Possible sources of information about past environments

- None.

6.16.2.8 Photographs and diagrams

- Refer Figure 55 for a general view of the site.

6.16.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.16.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

- Non-diagnostic ceramics (Fig. 56). Three of the potsherds identified were coloured/decorated with ochre and/or graphite and two more had decorations just underneath the lip of the vessel (Marateng – open bowls).

6.16.5 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value.

6.16.6 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.16.7 Recommendations

6.16.7.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.16.7.2 Proposals for protection or mitigation

- None.

6.16.7.3 Action/s required at the site

- None

Figure 55. Site ORW 24.





Figure 56. Artefacts at site ORW 24.




5.17.Site ORW 26 ORWRDP Phase 2F

6.17.1 Location of site

S24 18 06.1 E29 49 28.8 – Refer Figure 57 for locality map, and Appendix 2 for survey transect logs.

Figure 57. Locality map: Site ORW 25, 26 and 27.



6.17.2 Description of site

6.17.2.1 Type of site

- Potshard scatter.

6.17.2.2 Site category

- Late Iron Age.

6.17.2.3 Context

- Primary

6.17.2.4 Cultural affinities, approximate age and significant features of the site

6.17.2.5 Extent

- Low density scatter over an area of approximately 30m in diameter. Most of the site was open and cleared and the site was situated approximately 40m from the grave identified at site ORW 25. The site was also situated at the foot of the small hill.

6.17.2.6 Depth and stratification of the site

- Surface indications only, no indications of deposits of any depth.

6.17.2.7 Possible sources of information about past environments

- None.

6.17.2.8 Photographs and diagrams

- Refer Figure 58 for a general view of the site.

6.17.3 Threats or sources of risk and their impact on the heritage resources

- Construction activities.

6.17.4 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the site

6.17.5 Non-diagnostic ceramics (Fig. 59). Two of the potsherds identified were coloured/decorated with ochre (Marateng).

6.17.6 Statement of Significance (Heritage Value)

- Due to disturbed context and non-diagnostic ceramics the site has no heritage value; the association with the grave at Site ORW 25 should be integrated in the mitigation on the site.

6.17.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected C (Field Rating IV C): this site has been sufficiently recorded (in the Phase 1). It requires no further recording before destruction (generally Low significance).

6.17.8 Recommendations

6.17.8.1 Assessment of the potential impact of the development on the site, relative to sustainable social and economic benefits

- No possible benefit to be derived from the mitigation or conservation of this site.

6.17.8.2 Proposals for protection or mitigation

- In conjunction with the mitigation of grave Site ORW 25.

6.17.8.3 Action/s required at the site

- In conjunction with the actions at grave Site ORW 25.

Figure 58. Site ORW 26.





Figure 59. Artefacts at site ORW 26.



5.18.Site ORW 27 ORWRDP Phase 2F

6.18.1 Location of site

S24 18 07.3 E29 49 26.3 – Refer Figure 57 for locality map, and Appendix 2 for survey transect logs.

6.18.2 Description of site

6.18.2.1 Type of site

The remains and the foundations of a dilapidated structure were identified at this location. The remains consisted basically of collapsed and weathered mud-bricks of a hut structure on top of a hut floor. The hut structure was circular in shape and measured approximately 3m across. Other, more dilapidated, structures were also identified in this area. These structures served as home or as a homestead for their previous occupants. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.18.2.2 Site category

- Recent modern.

6.18.2.3 Context

- Primary.

6.18.2.4 Cultural affinities, approximate age and significant features of the site

6.18.2.5 Extent

- In total an area of approximately 50 m in diameter is covered by the ruined homestead.

6.18.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.18.2.7 Photographs and diagrams

- Refer Fig. 60 for site photograph.

6.18.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.18.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.18.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.18.6 Recommendations


6.18.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.
- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.18.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 60. General photograph of Site ORW 27.



5.19.Site ORW 28 ORWRDP Phase 2F

6.19.1 Location of site

S24 18 29.7 E29 48 35.6 – Refer Figure 61 for locality map, and Appendix 2 for survey transect logs.

Figure 61. Locality map for Site ORW 28.



6.19.2 Description of site

6.19.2.1 Type of site

The remains of the foundations of a small dilapidated structure were identified at this location. The site was situated right next to a ploughed field. The remains of the structure consisted basically of packed lines of rocks which were used in the foundations of these presumably temporary structures. Some of these rocks were removed and in other areas the foundations were damaged. The structure was square in shape and measured approximately 5m x 5m. It was most probably that this structure was only used as a

temporary base during agricultural activities (ploughing, planting & harvesting) due to the minimal materials left on the site and its close proximity to the ploughed field

6.19.2.2 Site category

- Recent modern.

6.19.2.3 Context

- Primary - disturbed.

6.19.2.4 Cultural affinities, approximate age and significant features of the site

6.19.2.5 Extent

- Single structure 5X5m in extent.

6.19.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.19.2.7 Photographs and diagrams

- Refer Fig. 62 for site photograph.

6.19.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.19.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.19.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.19.6 Recommendations

6.19.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is,


therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.

- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.19.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 62. General photograph of Site ORW 28.



5.20.Site ORW 29 ORWRDP Phase 2F

6.20.1 Location of site

S24 19 51.5 E29 46 20.5 – Refer Figure 63 for locality map, and Appendix 2 for survey transect logs.

Figure 63. Locality map for Site ORW 29 and 30.



6.20.2 Description of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains of these structures were situated approximately 15m from the gravel road. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures consisted of one or more rooms which were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. These structures served as home or as a homestead for their previous occupants. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.20.2.1 Type of site

6.20.2.2 Site category

- Recent modern.

6.20.2.3 Context

- Primary - disturbed.

6.20.2.4 Cultural affinities, approximate age and significant features of the site

6.20.2.5 Extent

- Approximately 30m in diameter.

6.20.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.20.2.7 Photographs and diagrams

- Refer Fig. 64 for site photograph.

6.20.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.20.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deems not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.20.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.20.6 Recommendations

6.20.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in*


situ, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.

- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.20.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 64. General photograph of Site ORW 29.



5.21.Site ORW 30 ORWRDP Phase 2F

6.21.1 Location of site

S24 19 53.2 E29 46 17.8 – Refer Figure 63 for locality map, and Appendix 2 for survey transect logs.

6.21.2 Description of site

The remains and the foundations of a cluster of dilapidated structures were identified at this location. The remains of these structures were situated approximately 20m from the gravel road. The remains consisted basically of packed lines of rocks which were used in the foundations of these structures on which mud-brick walls were built. These structures consisted of one or more rooms which were predominantly square or rectangular in shape and the rooms measured approximately 5m x 5m. These structures served as home or as a homestead for their previous occupants. A few metal artefacts such as wire and cans were observed amongst the remains of the structures.

6.21.2.1 Type of site

6.21.2.2 Site category

- Recent modern.

6.21.2.3 Context

- Primary - disturbed.

6.21.2.4 Cultural affinities, approximate age and significant features of the site

6.21.2.5 Extent

- Approximately 50m in diameter.

6.21.2.6 Depth and stratification of the site

- Single phase habitation with very sub-surface features.

6.21.2.7 Photographs and diagrams

- Refer Fig. 65 for site photograph.

6.21.3 Threats or sources of risk and their impact on the heritage resources

- Damage through proposed construction.

6.21.4 Statement of Significance (Heritage Value)

Through experience of similar sites and a knowledge of cultural customs and traditions it is known that stillborn babies and deceased infants occasionally were being buried within the occupational settlement. These children were sometimes buried underneath the floors and walls of houses and huts. These burials were not marked, but were known to the immediate family.

Customs and traditions like these were common in the rural African communities even up to the later parts of the 20th century. It is therefore not only possible, but rather likely that some of these structures may be on top of some of these infant remains.

Significance: Moderate significance. The structures themselves have little or no heritage value or significance due to their relevant recent origins from within the last 60 years. The structures, however should be avoided, but if this deem not to be possible, a watching brief is recommended due to the possibility of infant human remains underneath the remains of the structures.

6.21.5 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

6.21.6 Recommendations


6.21.6.1 Proposals for protection or mitigation

- If the structures can not be avoided during construction a suitably accredited archaeologist should be present when they are destroyed to ensure that no human remains are inadvertently discovered.
- If human remains are uncovered during the course of archaeological work this usually entails that excavations affecting the burial must be stopped. SAHRA should then be consulted and depending on the situation, the remains are either covered and left *in situ*, exposed (but not removed) and studied *in situ*, or fully excavated and studied with the consent and participation of the interested parties. It is, therefore, advisable that if it is foreseen that any archaeological research will uncover human remains an agreement with the interested parties and a permit for burials be obtained beforehand.
- For human remains inadvertently discovered in other situations, the legal requirement is that all activities affecting the burial must be stopped and that the discovery must be reported to the SAPS and SAHRA. The status of the remains is then ascertained. If it is found to be forensic in nature (nominally younger than 60 years and perceived to be the victim of crime or a person that have died of unnatural causes) recovery by the Provincial Forensic Pathology Services in conjunction with the SAPS is mandated. If the remains are of cultural, historical or archaeological origin recovery is usually facilitated by SAHRA by means of a Rescue Permit.

6.21.6.2 Action/s required at the site

- Appoint a suitably accredited archaeologist on a watching brief to monitor construction activities.

Figure 65. General photograph of Site ORW 30.



6. BURIAL GROUNDS AND GRAVES

6.1. Site ORW 3 ORWRDP (Not directly on current proposed alignment)

7.1.1 Location of burial grounds and graves

S24 53 19.1 E29 59 55.8 – Refer Figure 28 for locality map, and Appendix 2 for survey transect logs.

These graves were identified during field surveys, but were subsequently assessed to be outside of the affected alignment and will therefore not be impacted on by the proposed project.

6.2. Site ORW 9 ORWRDP Phase 2C

7.2.1 Location of burial grounds and graves

S24 45 08.1 E30 10 21.2 – Refer Figure 38 for locality map, and Appendix 2 for survey transect logs.

7.2.2 Description of burial grounds and graves

A cluster of three graves was identified here. The graves were approximately 20 meters from the tar road and were situated right next to the existing Lebalelo pipeline. The graves were placed next to each other and they were orientated from west to east. Two of the graves had cement slabs as dressings and cemented headstones placed at the western ends of the grave. The headstone of the one grave was partially damaged. The headstones and dressings had no inscriptions. The third grave had an informal mound of packed rock and soil as dressing. All three graves were in a neglected state and were damaged to some extent. No other structures or features were associated with these graves (Fig. 66).

7.2.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).
 - Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
- Persons of royal descent and traditional leaders.
- Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
- Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the

Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.
- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a

Municipality but in an area under a Traditional Authority, permission from said authority is required.

- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).
- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.2.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.2.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- No cultural material (“burial objects”) was observed in association with these graves.

7.2.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remain graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.2.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.2.8 Recommendations

7.2.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.

7.2.8.2 Proposals for protection or mitigation



- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.



- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.2.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation. Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 66. Graves at Site ORW 9.





6.3. Site ORW 13 ORWRDP Phase 2D

7.3.1 Location of burial grounds and graves

S24 37 59.7 E30 10 39.2 – Refer Figure 44 for locality map, and Appendix 2 for survey transect logs.

7.3.2 Description of burial grounds and graves

A cluster of five graves was identified here. Three of the graves were placed in a line next to each other and the other two graves were placed in another line next to each other in front of the first three graves. All of the graves were orientated from west to east. The first three graves had rectangular shaped brick and cement outlines which were filled with gravel and soil as grave dressings. Inscribed granite headstones were placed at the western ends of these graves. These graves were also crudely fenced in. One of the graves in the second line had a formal granite dressing with an inscribed granite headstone placed at the western end of the grave. The second grave had an informal mound of packed rocks and soil as dressing. The graves were well maintained and some grave goods (such as cups and pots) were present on the graves (Fig. 67).

7.3.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8

of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).

- Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
 - Persons of royal descent and traditional leaders.
 - Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
 - Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must

invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.

- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a Municipality but in an area under a Traditional Authority, permission from said authority is required.
- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.

- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).
- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.3.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.3.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some object of personal use, such as cups and pots (“burial objects”) were observed in association with these graves.

7.3.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remains graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.3.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.3.8 Recommendations

7.3.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.

7.3.8.2 Proposals for protection or mitigation



- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.
- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.


7.3.9 Action/s required at the site


- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation.

Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 67. Graves at Site ORW 13.








6.4. Site ORW 16 ORWRDP Phase 2D

7.4.1 Location of burial grounds and graves

S24 33 59.9 E30 09 25.0 – Refer Figure 68 for locality map, and Appendix 2 for survey transect logs.

Figure 68. Locality map for Site ORW 16.



7.4.2 Description of burial grounds and graves

A large cemetery with over 100 graves was identified at this location. A large area was fenced to serve as official graveyard for the surrounding communities. This fenced area extended right across the proposed route of the pipeline. This cemetery is still in an early stage of being utilized, with large areas still to be filled. Due to the inherent inaccuracy of GPS readings and large scale and relatively poor print quality of the printed maps it was difficult to say if the proposed pipeline missed all of the graves or

could possibly pass over some of them. It seemed however, that the proposed route of the pipeline passed over an area of the cemetery which was already filled with graves (Fig. 69).

7.4.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).
 - Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
- Persons of royal descent and traditional leaders.
- Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
- Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.
- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.

- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a Municipality but in an area under a Traditional Authority, permission from said authority is required.
- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).
- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.4.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.4.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some object of personal use, such as cups and pots (“burial objects”) were observed in association with these graves.

7.4.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remains graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.4.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.4.8 Recommendations

7.4.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.



7.4.8.2 Proposals for protection or mitigation

- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.
- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.4.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation. Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 69. Graves at Site ORW 16.



6.5. Site ORW 17 ORWRDP Phase 2D

7.5.1 Location of burial grounds and graves

S24 32 17.3 E30 08 59.4 – Refer Figure 47 for locality map, and Appendix 2 for survey transect logs.

7.5.2 Description of burial grounds and graves

Another large cemetery with over 250 graves was identified at this location. A large area was fenced to serve as official graveyard for the surrounding communities. This fenced area extended right across the proposed route of the pipeline. This cemetery is still in an early stage of being utilized, with large areas still to be filled. Due to the inherent inaccuracy GPS and relatively large scale and poor print quality of the printed maps it was difficult to say if the proposed pipeline missed all of the graves or could possibly pass over some of them. It seemed however, that the proposed route of the pipeline passed over an area of the cemetery which was already filled with graves (Fig. 70).

7.5.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).

- Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
 - Persons of royal descent and traditional leaders.
 - Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
 - Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of

documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.

- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.

- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a Municipality but in an area under a Traditional Authority, permission from said authority is required.
- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for

other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).

- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.5.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.5.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some object of personal use, such as cups and pots (“burial objects”) were observed in association with these graves.

7.5.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remains graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.5.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.5.8 Recommendations

7.5.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.

7.5.8.2 Proposals for protection or mitigation



- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.
- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.5.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation.

Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 70. Graves at Site ORW 17.




6.6. Site ORW 21 ORWRDP Phase 2E

7.6.1 Location of burial grounds and graves

S24 29 30.5 E30 07 08.5 – Refer Figure 71 for locality map, and Appendix 2 for survey transect logs.

Figure 71. Locality map for Site ORW 21 and 22.



7.6.2 Description of burial grounds and graves

A small informal cemetery with twelve graves was identified at this location. The informal cemetery was situated approximately 20m east of the gravel road in an open area in between the stands. The graves were placed in three unequal lines and all were orientated from east to west. Five of the graves had formal granite dressings and the rest of them had informal mounds of packed rocks and soil as dressings. The graves were well maintained and some of them had grave goods (such as cups and plates) placed on them (Fig. 72).

7.6.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).
 - Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
- Persons of royal descent and traditional leaders.
- Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
- Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the

Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.
- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a

Municipality but in an area under a Traditional Authority, permission from said authority is required.

- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).
- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.6.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.6.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some object of personal use, such as cups and pots (“burial objects”) were observed in association with these graves.

7.6.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remains graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.6.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.6.8 Recommendations

7.6.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.

7.6.8.2 Proposals for protection or mitigation


- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.

- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.6.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation. Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 72. Graves at Site ORW 21.



6.7. Site ORW 22 ORWRDP

7.7.1 Location of burial grounds and graves

S24 28 52.9 E30 07 15.7


This site is on one of the alternative alignments indicated (Refer Fig. 71) and is not affected by the current proposed alignment. It is included for the sake of consideration when alternatives are assessed.

7.7.2 Description of burial grounds and graves

A small informal cemetery with approximately twenty graves was identified at this location. The informal cemetery was situated approximately 15m east of the R37 tar road in an open area in between the stands and the road. The graves were placed in several unequal lines and some were orientated from east to west and others were orientated from north to south. Several of the graves had formal granite dressings and the rest of them had informal mounds of packed rocks and soil as dressings. The graves were well maintained and some of them had grave goods (such as cups and plates) placed on them.

(Fig. 73).

Figure 73. Graves at Site ORW 22.



6.8. Site ORW 23 ORWRDP Phase 2F

7.8.1 Location of burial grounds and graves

S24 25 56.8 E30 04 57.1 – Refer Figure 54 for locality map, and Appendix 2 for survey transect logs.

7.8.2 Description of burial grounds and graves

A large, fenced cemetery with over 200 graves was identified here. The cemetery was situated next to and on the western side of the R37 tar road. The cemetery's fence was approximately 20m from the tar road. The cemetery was being used by the surrounding communities. It seemed as if the proposed pipeline will be situated in the area between the tar road and the cemetery (Fig. 74).

7.8.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.
- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).
 - Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).

- Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
- Persons of royal descent and traditional leaders.
- Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
- Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for

exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.
- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.

- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a Municipality but in an area under a Traditional Authority, permission from said authority is required.
- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.
- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).

- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.8.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.8.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some object of personal use, such as cups and pots (“burial objects”) were observed in association with these graves.

7.8.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remains graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.8.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.8.8 Recommendations

7.8.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.


7.8.8.2 Proposals for protection or mitigation

- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.
- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.8.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation. Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirement during the process.

Figure 74. Graves at Site ORW 23.



6.9.



6.9. Site ORW 25 ORWRDP Phase 2F

7.9.1 Location of burial grounds and graves

S24 18 05.2 E29 49 29.2 – Refer Figure 57 for locality map, and Appendix 2 for survey transect logs.

7.9.2 Description of burial grounds and graves

A single grave was identified at this location. The grave was situated at the foot of a small hill. The grave was orientated from west to east and a large rock was placed upright at the western end to serve as headstone. The grave had a rectangular shaped cement slab as dressing. The cement slab was inscribed with the words:

“Ramakgahle
Ramosedi
Maphakhane
Rest
In
Peace”

The grave was well maintained and some glass bottle fragments were found behind the headstone and were probably part of the grave goods which were placed at the grave (Fig. 75).

This grave is directly associated with Site ORW 26.

7.9.3 Legal implications of graves

The NHRA identifies the following categories of human remains whether as incidentally discovered remains, or in burial grounds and graves:

- Human remains older than 100 years, which are defined as archaeological.

- “Victims of Conflict” that include:
 - Persons who died in the present territory of the Republic of South Africa as a direct result of any war or conflict (the act requires regulations to list these but none has been published to date) excluding those covered by the Commonwealth War Graves Act (Act 8 of 1992) (effectively persons who were citizens of Commonwealth Countries other than South Africa who died in South Africa after 4 August 1914).
 - Members of the forces of Great Britain and the former British Empire who died on active duty in the present territory of the Republic of South Africa before 4 August 1914.
 - Persons that were exiled from the present territory of the Republic of South Africa and died outside of South Africa during the Anglo-Boer War (1899-1902).
 - Certain persons who died in the “liberation struggle” (the act requires regulations to list such persons but none have been published to date) in the present territory of the Republic of South Africa and outside South Africa.
- Ancestral graves.
- Persons of royal descent and traditional leaders.
- Individuals indicated by the Minister of Arts and Culture in notices in the Government Gazette.
- Historical graves and burial grounds.

Graves are defined as the place of burial as well as the contents, headstone or any other marker and any other structure on, or associated with such a place.

Under the provisions of the NHRA a SAHRA permit is therefore required for any action affecting a burial ground or grave or human remains (including the handling and housing thereof) older than 100 years; that of a victim of conflict, a person of royal descent or a traditional leader and those from

historical and ancestral graves as well as any grave or burial ground older than 60 years which is situated outside a formal cemetery administered by a recognized local authority. In addition to the normal requirements for an archaeological excavation permit, the following requirements must be met in applications involving any of the above:

- The applicant must illustrate a concerted effort to trace and identify any person or community with an interest in the grave, burial ground or remains. This should be done by means of documentary and archival research, a process of public participation and social consultation and the placing of site and newspaper notices.
- If any interested parties are identified their permission for the exhumation of the remains or any action affecting the graves must be obtained and an agreement as to the requirements for exhumation, the research on and the re-internment of, or any other arrangement for the long term storage of the remains must be met.

If the grave or burial ground in question is that of a member of the military forces of a Commonwealth Country other than South Africa, permission must be obtained from the Commonwealth War Graves Commission.

The handling, storage and transport of human remains, whether they be of archaeological or recent origin, is further regulated by the Graves and Dead Bodies Ordinance (Ord 7 of 1925 (re-instituted by Proclamation 109 of 17 June 1994), the Exhumations Ordinance (Ord 12 of 1980) as well as either the Human Tissues Act (Act 65 of 1983 as Amended) or the National Health Act (Act 61 of 2003). With the promulgation of the Health Act not all of the sections of the Human Tissues Act were repealed, and since this process is ongoing these acts must be used in conjunction with each other. In addition, graves and human remains in municipal cemeteries are regulated by the applicable Municipal By-Laws.

For practical purposes the following is required to legally excavate and handle human remains:

- Notices advertising the proposed exhumation of graves must be placed in a local newspaper in English and one of the common additional official languages of the area. These notices must invite possible objections to the proposed exhumation. A period of two weeks must be allowed for comments.
- Site notices similar in content to the newspaper notices must be placed at the site and should remain in place for a period of 60 days.
- A concerted effort to identify and contact persons or groups with an interest in the graves must be undertaken through documentary and archival research, public participation and social consultation. The process must be documented and this record must accompany the application.
- If any interested parties are identified, their permission for the proposed action must be obtained in an agreement that states the preferred place of reburial or mode of long term retention of the remains and the cultural and/or religious requirements that must be met. The applicant must assist the group in question to meet the agreed requirements.
- If the grave is located in a National Park the requirements of the SANParks policy must be met.
- The permission of the Premier of the Province, or the delegated official, must be obtained.
- A permit from the Provincial Department of Health must be obtained.
- Permission of the Municipality from where the remains are exhumed and where it will be reburied must be obtained. The second is usually included in the process of obtaining new burial plots for re-internment. If the graves in question are not located in the jurisdiction of a Municipality but in an area under a Traditional Authority, permission from said authority is required.
- The permission of the landowner where the remains are to be exhumed as well as where the remains will be buried is required.

- If the agreement allows for the remains to be placed in a collection, the permission of the head of the institution that houses the collection must be obtained. If the agreement with the interested parties allows for the study of the remains before re-internment, this implies temporary storage which also requires the permission of the head of the institution involved.
- A SAHRA permit must be obtained for graves and remains listed above, in short for graves older than 100 years, older than 60 years if located outside the jurisdiction of a municipality and for other graves of cultural significance irrelevant of their age (Note that this may vary between provinces).
- Permission from the Commonwealth War Graves Commission must be obtained for any graves under their administration.
- The local South African Police Services must be notified of the exhumation seven days prior to the action.
- Only a certified funeral undertaker, or an institution with a similar legal status and facilities, is legally allowed to handle, transport and store human remains. South African medical schools legally have this status.

7.9.4 Threats or sources of risk and their impact on the burial grounds and graves

- The graves will be affected by the construction activities on the proposed alignment.

7.9.5 Description of the Artefacts, Faunal, Botanical or Other Finds and Features associated with the burial grounds and graves

- Some glass fragments, possibly indicating “burial objects” was observed in association with this grave.

7.9.6 Statement of Significance (Heritage Value)

- Although the graves might fall under any legislation that specifically indicates them as culturally significant, they remain graves and will have significance on local and family level.
- All graves are protected by legislation whether it is archaeological, heritage, or recent modern, and no actions affecting the graves may be undertaken without legislated permission.

7.9.7 Field Rating (Recommended grading or field significance) of the site:

While formal grading is the responsibility of the heritage resources authorities, this report includes Field Ratings for sites, to comply with section 38 of the national legislation.

- Generally Protected A (Field Rating IV A): this site should be mitigated before destruction (generally High/Medium significance);

7.9.8 Recommendations

7.9.8.1 Assessment of the potential impact of the development on these sites, relative to sustainable social and economic benefits.

- It is recognised that the need for water distribution in the area is high and this is considered relative to well established practice of grave relocation to recognised Municipal and other cemeteries.

7.9.8.2 Proposals for protection or mitigation

- The possibility of changing the alignment of the proposed pipeline should be considered as the most suitable measure.
- If an impact on the graves is unavoidable the full NHRA Sec 36 will come to bear. This is an extensive and expensive process and should only be considered as a last resort.

- If the grave is to be relocated this should be considered in conjunction with the actions for Site ORW 26.
- Other cases of proposed grave relocation in this region have met with serious social, political and cultural objections.

7.9.9 Action/s required at the site

- At the onset of construction all graves that might be affected should be clearly demarcated and if possible fenced off to protect them from any accidental damage, whether they are earmarked for relocation, or not.
- Should the decision be taken to propose the relocation of the affected graves, a suitably accredited and experienced service provider must be appointed to undertake the relocation. Please note that grave relocation is dependent on permission for the action by the close relatives and interested and affected parties from the community, and the requirement is that the developer must assist this community to fulfil their cultural and religious requirements during the process.

Figure 75. Grave at Site ORW 25.



7. CONCLUSIONS

From the literature review and archival sources it is clear that the area affected is rich in diverse and varied heritage resources dating from the Stone Age to historical times. Although several heritage resources were identified as part of this study none were assessed to be significant, apart from graves which occur near or on the proposed alignments surveyed. The reason for this is that the proposed alignments, for the most part, follow existing road, or other infrastructure (pipe or power lines) reserves. The nature of the development (water distribution) also requires it to proceed through mostly built-up and in some areas heavily disturbed areas. All of the archaeological sites is previously disturbed and only potshard scatters were observed to indicate their presence. Several recent modern homesteads, which fall outside of the scope identified as heritage resources because of their age were also identified. These are included to ensure that notice is taken of the fact that they might contain the graves of mainly young children in the floors of such houses in order to prevent the inadvertent discovery of such human remains when construction commences. Other graves identified can be mitigated by slightly changing the alignment of the proposed development, or by carefully managing the construction activities where these graves are near, and not directly on, the proposed alignment. Grave relocation is not deemed an appropriate measure in this case.

BIBLIOGRAPHY

- Berg, J.S. 1999. *Geskiedenis Atlas van Suid-Afrika: Die Vier Noordelike Provinsies*. Pretoria: J.J. Van Schaiks.
- Boshoff, W. 2005. *Summary report on Maleoskop on the Rietkloof farm in the district of Groblersdal*.
- Bosman, I.D. 1977. *Die Groot trek 1838-1854*. Geskiedenis van Suid-Afrika. Elsiesrivier: Nasionale Boekdrukkery.
- Delius, P. 1983. *The Land Belongs To Us: The Pedi Polity, the Boers and the British in the Nineteenth-century Transvaal*. Johannesburg: Ravan Press.
- Delius, P. 2007. *Mpumalanga. History and heritage*. University of KwaZulu-Natal: University of KwaZulu-Natal Press.
- Evers, T. M. 1975. Recent Iron Age research in the Eastern Transvaal, South Africa. *South African Archaeological Bulletin*. 30(119/120): 71-83.
- Eloff, J. F. 1969. Bushman Rock Shelter, Eastern Transvaal: Excavations 1967-1968. *South African Archaeological Bulletin* 24: 60.
- Huffman, T. N. 1998. The antiquity of lobola. *South African Archaeological Bulletin*. 53: 57-62.
- Huffman, T. N. 2007. *Handbook to the Iron Age: The archaeology of pre-colonial farming societies in southern Africa*. Scottsville: University of KwaZulu-Natal Press.
- Jacobs, M. 2006. Process Description and Abbreviated History of Anglo Platinum's Waterval Smelter. *Southern African Pyrometallurgy*. 17-23.
- Klein, R. G. 1984. Later Stone Age faunal samples from Heuningneskrans shelter (Transvaal) and Leopard's Hill Cave (Zambia). *South African Archaeological Bulletin* 39:109-116.
- Korsman, S. 1994. Two later Stone Age sites on the farm Honingklip in the Eastern Transvaal. *South African Archaeological Bulletin* 49:24-32.

- Louw, A. W. 1969. Bushman Rock Shelter, Ohrigstad, Eastern Transvaal, a preliminary investigation. *South African Archaeological Bulletin* 24: 39-57.
- Massie, R.H. 1905. *The Native Tribes of the Transvaal: Prepared for the general staff, war office.* London: Harrison and Sons.
- Mitchell, P. 2002. *The archaeology of southern Africa.* Cambridge: Cambridge University Press.
- Mönning, H.O. 1967. *The Pedi.* Pretoria: J.J. Van Schaik.
- Muller, C.F.J. 1985. *500 Jaar Suid-Afrikaans Geskiedenis.* Pretoria: Academica.
- Nell, C. 2009. An archaeozoology of the Ndzundza Ndebele in the Steelpoort River Valley, Mpumalanga, South Africa, c. 1700 AD tot 1883 AD. *South African Archaeological Bulletin.* 64(190): 184-192.
- Ntrama, O.Y. 2006. Replacement of the existing Merensky Reef operations at Lebowa Platinum Mines: an integrated business and operational readiness approach. *International Platinum Conference 'Platinum Surges Ahead'. The Southern African Institute of Mining and Metallurgy.* 295- 300.
- Plug, I. 1981. Some research results on the Late Pleistocene and Early Holocene deposits of Bushman Rock Shelter. Eastern Transvaal. *South African Archaeological Bulletin.* 133:14-21.
- Plug, I. 1982. Bone tools and shell, bone and ostrich eggshell beads from Bushman Rock Shelter (BRS), Eastern Transvaal. *South African Archaeological Bulletin.* 37(136): 57-62.
- Schoeman, M. H. 1997. *The Ndzundza archaeology of the Steelpoort River Valley.* An unpublished MA thesis. University of Witwatersrand.
- Schoeman, M. H. 1998a. Excavating Ndzundza Ndebele at Kwamaza. *South African Field Archaeology.* 7: 42-52.
- Schoeman, M. H. 1998b. Material culture “under the animal skin”: excavations at Esikhunjini, a Mfecane period Ndzundza Ndebele site. *South African Field Archaeology.* 7: 72-81.

Schoonraad, M. and Beaumont. 1971. The Welgelegen Shelter, Eastern Transvaal. Supplement to the *South African Journal of Science Special* number 2.

Theal, G.M. 1964. *History of South Africa from 1873 to 1884, vol. 10*. London: Allen and Unwin

Van der Merwe, D.W. 1975. *Die Geskiedenis van die Berlynse Sendingsgenoodskap in Transvaal, 1860-1900*. Unpublished MA thesis. University of Pretoria.

Van Jaarsveld, F. A. 1985. *From Van Riebeeck to Vorster, 1652-1974 : an introduction to the history of the Republic of South Africa*. Johannesburg: Perskor.

Whitelaw, G. 1996. Lydenburg revisited: another look at the Mpumalanga Early Iron Age sequence. *South African Archaeological Bulletin*. 51: 75-83.

Wright, J. 2010. Putting the Bakoni on the Historian's map. *African Studies*. 69(2): 229-233.

ARCHIVAL SOURCES

National Archives Depot, Pretoria: Transvaal Archives Depot, BAO 10155 D52/1608/68

National Archives Depot, Pretoria: Transvaal Archives Depot, BAO 2829 32/3/2697

National Archives Depot, Pretoria: Transvaal Archives Depot, BAO 10157 D52/1608/143

National Archives Depot, Pretoria: Transvaal Archives Depot, BAO 1/2034 D48/1608/97/1

National Archives Depot, Pretoria: Transvaal Archives Depot, CD 159 AG54144/02

National Archives Depot, Pretoria: Transvaal Archives Depot, CD 746 AG26/0/04

National Archives Depot, Pretoria: Transvaal Archives Depot, CS 181 15494/02

National Archives Depot, Pretoria: Transvaal Archives Depot, CS 366 8533/03

National Archives Depot, Pretoria: Transvaal Archives Depot, HKN 1/1/146 28N2/11/3(3)

National Archives Depot, Pretoria: Transvaal Archives Depot, HKN 1/1/94 26N2/11/3(5)

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 6849 46/319

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 692 345/319(5)

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 2823 247/302

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 7119 438/323

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 7107 241/323

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 1963 T20583

National Archives Depot, Pretoria: Transvaal Archives Depot, NTS 10963 T220563

National Archives Depot, Pretoria: Transvaal Archives Depot, SNA 310 NA595/06

National Archives Depot, Pretoria: Transvaal Archives Depot, SNA 450 NA3983/09

National Archives Depot, Pretoria: Transvaal Archives Depot, SS 1139 R6199/85

National Archives Depot, Pretoria: Transvaal Archives Depot, SS 3043 R123/3/91

National Archives Depot, Pretoria: Transvaal Archives Depot, SS 1169 R629/86

National Archives Depot, Pretoria: Transvaal Archives Depot, SS 0 R280/96

National Archives Depot, Pretoria: Transvaal Archives Depot, THD 4 10/2/99

National Archives Depot, Pretoria: Transvaal Archives Depot, URU 947 3545

APPENDIX A

Farm name and number

ROUTE DESCRIPTION	FARM NAME	PORTION	ROUTE DESCRIPTION	FARM NAME	PORTION
2B	Arabie 685 KS	RE	2C	Steelpoort Park 366 KT	1
2B	Hindostan 680 KS	RE/1	2C	Belvedere 362 KT	33
2B	Tambootieboom 686 KS	2	2C	Belvedere 362 KT	34
2B	Roodewal 678 KS	1	2C	Belvedere 362 KT	21
2B	Roodewal 678 KS	RE	2C	Belvedere 362 KT	17
2B	Gaasterland 677 KS	1	2C	Belvedere 362 KT	16
2B	Gaasterland 677 KS	RE	2C	Belvedere 362 KT	15
2B	Hinloopen 647 KS	RE	2C	Belvedere 362 KT	3
2B	Elandskraal 936 KS		2C	Belvedere 362 KT	14
2B	Mutue Fides 648 KS		2C	Belvedere 362 KT	2
2B	Weltevreden 646 KS	1	2C	Belvedere 362 KT	25
2B	Weltevreden 646 KS	3	2C	Belvedere 362 KT	22
2B	Weltevreden 646 KS	RE/2	2C	Belvedere 362 KT	6
2B	Tygerpad 633 KS	1	2C	Kennedy's Vale 361 KT	25
2B	Vooruitgang 634 KS	1	2C	Kennedy's Vale 361 KT	28
2B	Vooruitgang 634 KS	RE	2C	Kennedy's Vale 361 KT	9
2B	Restaurant 588 KS	RE/1	2C	Kennedy's Vale 361 KT	19
2B	Restaurant 588 KS	RE	2C	Kennedy's Vale 361 KT	22
2B	Restaurant 588 KS	3	2C	Kennedy's Vale 361 KT	29
2B	Foleys Rust 583 KS	RE	2C	Kennedy's Vale 361 KT	27
2B	Klipfontein 587 KS	RE	2C	Kennedy's Vale 361 KT	8
2B	Mokkafontein 584 KS	1	2C	Spitskop 333 KT	30
2B	Mokkafontein 584 KS	RE	2C	Spitskop 333 KT	11
2B	Singapore 585 KS	RE/1	2C	Spitskop 333 KT	3
2B	Singapore 585 KS	RE	2C	Spitskop 333 KT	2
2B	Singapore 585 KS	2	2C	Spitskop 333 KT	1
2B	Singapore 585 KS	3	2C	Annex Grootboom 335 KT	1
2B	Doornboom 586 KS	RE	2C	Annex Grootboom 335 KT	RE
2B	Calais 563 KS	RE	2C	Grootboom 336 KT	3
2B	Calais 563 KS	1	2C	Grootboom 336 KT	RE
2B	Hoogte 155 KS	4	2C	Grootboom 336 KT	2
2B	Malgas 154 KS	RE	2C	Grootboom 336 KT	1
2B	Malgas 154 KS	RE/2	2C	Grootboom 336 KT	4
2B	Malgas 154 KS	1	2C	Goudmyn 337 KT	RE
2B	Brakfontein 152 KS	5	2C	Goudmyn 337 KT	25
2B	Brakfontein 152 KS	RE/3	2C	Goudmyn 337 KT	10
2B	Brakfontein 152 KS	9	2C	Goudmyn 337 KT	22
2B	Brakfontein 152 KS	2	2C	Goudmyn 337 KT	28
2B	Brakfontein 152 KS	RE	2D	Winterveld 293 KT	

2B	Brakfontein 152 KS	13	2D	Doornbosch 294 KT	2
2B	Brakfontein 152 KS	12	2D	Doornbosch 294 KT	4
2B	Brakfontein 152 KS	RE/4	2D	Doornbosch 294 KT	RE
2B	Brakfontein 152 KS	10	2D	Doornbosch 294 KT	5
2B	Brakfontein 152 KS	11	2D	Doornbosch 294 KT	1
2B	Eenzaam 148 KS	RE	2D	Doornbosch 294 KT	6
2B	Eenzaam 148 KS	1	2D	Apiesboomen 295 KT	RE
2B	Rietlaagte 149 KS	RE	2D	Hendriksplaats 281 KT	RE
2B	Rietlaagte 149 KS	RE/2	2D	Derde Gelid 278 KT	RE
2B	Rietlaagte 149 KS	RE/1	2D	Derde Gelid 278 KT	2
2B	Kalkvalley 151 KS	1	2D	Derde Gelid 278 KT	1
2B	Kalkvalley 153 KS	RE	2D	Mooihoek 255 KT	2
2B	Kromdraai 129 KS	1	2D	Mooihoek 255 KT	RE
2B	Kromdraai 129 KS	2	2D	Mooihoek 255 KT	RE/1
2B	Kromdraai 129 KS	RE	2E	Groothoek 256 KT	RE
2B	Roodebult 128 KS	RE	2E	Twyfelaar 119 KT	RE
2B	Roodesloot 130 KS	RE	2E	Clapham 118 KT	RE
2B	Roodesloot 130 KS	2	2E	Forest Hill 117 KT	RE
2B	Groothoek 99 KS	3	2F	Surbiton 115 KT	RE
2B	Doornfontein 98 KS	3	2F	Twickenham 114 KT	RE
2B	Doornfontein 98 KS	9	2F	Paschaskraal 466 KS	1
2B	Doornfontein 98 KS	8	2F	Klipfontein 465 KS	RE
2B	Doornfontein 98 KS	1	2F	Brakfontein 464 KS	RE
2B	Pruissen 48 KS	RE	2F	Umkoanesstad 419 KS	RE
2B	Pruissen 48 KS	2	2F	Middelpunt 420 KS	RE
2C	De Hoop 886 KS	RE	2F	Diamand 422 KS	RE
2C	De Hoop 886 KS	1	2F	Schoonoord 462 KS	RE
2C	Aapjesboom 884 KS	RE	2F	Blauwbloemetjieskloof 428 KS	RE
2C	Aapjesboom 884 KS	1	2F	Dal Josaphat 461 KS	RE
2C	Steelpoort Park 366 KT	2	2F	Locatie van M'Phatlele 457 KS / Koppieskraal 475 KS	RE
2C	Steelpoort Park 366 KT	11			

APPENDIX B
Survey Transect Logs

ORWRDP Phase 2B






The image may not be displayed. Try to refresh the content or check with the author if the image is not visible.



The image may not be displayed. Try to refresh the content or delete and re-add the content to the page.





The image may not be displayed. Try to refresh the content or check with the service provider.



The image may not be displayed. Try to refresh the content or check with the author if the image is not visible.





The image may not be displayed. Try to refresh the content or check with the author if the image file is correct.



The image may not be displayed. Try to refresh the content or check with the service provider for the correct file name.







The image may not be displayed. Try to refresh the content or check with the service provider.



The image may not be displayed. Try to refresh the content or check with the service provider.