

NOTES :

ALL LEVELS AND DIMENSIONS TO BE CHECKED ON SITE BEFORE WORK COMMENCES. ANY DISCREPANCIES TO BE BROUGHT TO THE ATTENTION OF THE ENGINEER.

ALL FOUNDATIONS MUST BE INSPECTED BY THE ENGINEER BEFORE THE CONCRETE IS CAST

IF MIXING OF CONCRETE IS DONE BY CONTRACTOR ON SITE, THEN APPROPRIATE MIX DESIGN MUST BE USED AND CONCRETE CUBE TEST MUST BE CARRIED OUT.

COMPACTION OF ALL SPECIFIED GEO-FILL MATERIALS TO BE TESTED AND RESULTS ISSUED TO THE ENGINEER.


WHERE PROPPING IS REQUIRED, CONTRACTOR SHALL BE RESPONSIBLE FOR ERECTION, MAINTENANCE AND REMOVAL OF PROPS.

CONCRETE STRENGTH AT 28 DAYS
 BASES : 25MPa/10mm
 GROUND SLAB : 25MPa/10mm
 STRIPFOOTING : 25MPa/10mm

MIN. COVER TO REINFORCING :
 COLUMNS : 30mm COVER
 BASES : 40mm COVER
 STRIPFOOTING : 40mm COVER

ALL BRICKWORK/BLOCKWORK TO BE FULLY BONDED.
 SABS APPROVED BRICK/BLOCK FORCE TO BE USED AT EVERY THIRD COURSE.

DWG. NO.	REFERENCE DRAWINGS	
REVISION		
REV.	DATE	DESCRIPTION



CONSULTANT:

PREBEN NAIDOO & ASSOCIATES
 CONSULTING CIVIL AND STRUCTURAL ENGINEERS

350 Prince Alfred Street
 Pleinmaritzburg
 3201

P. O. BOX 539
 Luxmi
 Pleinmaritzburg
 3207

Tel. No. (+27 (0)33) 342 2705
 Fax No. (+27 (0)33) 342 6480
 e-mail address : preben@pnaengineers.co.za

COPYRIGHT : THIS DRAWING IS THE PROPERTY OF PREBEN NAIDOO & ASSOCIATES AND SHALL NOT BE COPIED OR USED WHOLLY OR IN PART WITHOUT PRIOR WRITTEN CONSENT FROM PREBEN NAIDOO & ASSOCIATES

DESIGN	APPROVED/CONSULTANT	DATE
P. Naidoo		08/13
DRAWN	DATE	
R. Paul		08/13
CHECKED	DATE	
P. Naidoo		08/13
CONSULTANT'S DRAWING NO.		
PO 1394		

PROJECT.	WHITBY LODGE
DRAWING TITLE	FOUNDATION LAYOUT
SCALES	AS SHOWN
DRAWING No.	PO 1394/001
REVISION	0